



This is a digital copy of a book that was preserved for generations on library shelves before it was carefully scanned by Google as part of a project to make the world's books discoverable online.

It has survived long enough for the copyright to expire and the book to enter the public domain. A public domain book is one that was never subject to copyright or whose legal copyright term has expired. Whether a book is in the public domain may vary country to country. Public domain books are our gateways to the past, representing a wealth of history, culture and knowledge that's often difficult to discover.

Marks, notations and other marginalia present in the original volume will appear in this file - a reminder of this book's long journey from the publisher to a library and finally to you.

Usage guidelines

Google is proud to partner with libraries to digitize public domain materials and make them widely accessible. Public domain books belong to the public and we are merely their custodians. Nevertheless, this work is expensive, so in order to keep providing this resource, we have taken steps to prevent abuse by commercial parties, including placing technical restrictions on automated querying.

We also ask that you:

- + *Make non-commercial use of the files* We designed Google Book Search for use by individuals, and we request that you use these files for personal, non-commercial purposes.
- + *Refrain from automated querying* Do not send automated queries of any sort to Google's system: If you are conducting research on machine translation, optical character recognition or other areas where access to a large amount of text is helpful, please contact us. We encourage the use of public domain materials for these purposes and may be able to help.
- + *Maintain attribution* The Google "watermark" you see on each file is essential for informing people about this project and helping them find additional materials through Google Book Search. Please do not remove it.
- + *Keep it legal* Whatever your use, remember that you are responsible for ensuring that what you are doing is legal. Do not assume that just because we believe a book is in the public domain for users in the United States, that the work is also in the public domain for users in other countries. Whether a book is still in copyright varies from country to country, and we can't offer guidance on whether any specific use of any specific book is allowed. Please do not assume that a book's appearance in Google Book Search means it can be used in any manner anywhere in the world. Copyright infringement liability can be quite severe.

About Google Book Search

Google's mission is to organize the world's information and to make it universally accessible and useful. Google Book Search helps readers discover the world's books while helping authors and publishers reach new audiences. You can search through the full text of this book on the web at <http://books.google.com/>

Archit.

TA


7

.16

v.34

B

914,880



The Gift of
Leonard B. Willeke
Architect

Property of
LEONARD WILLEKE.

International Correspondence Schools

I. C. S.

REFERENCE LIBRARY

A SERIES OF TEXTBOOKS PREPARED FOR THE STUDENTS OF THE
INTERNATIONAL CORRESPONDENCE SCHOOLS AND CONTAINING
IN PERMANENT FORM THE INSTRUCTION PAPERS,
EXAMINATION QUESTIONS, AND KEYS USED
IN THEIR VARIOUS COURSES

LOADS IN STRUCTURES
PROPERTIES OF SECTIONS
MATERIALS OF STRUCTURAL ENGINEERING
BEAMS AND GIRDERS
COLUMNS AND STRUTS
DETAILS OF CONSTRUCTION
GRAPHICAL ANALYSIS OF STRESSES

24- 119

SCRANTON
INTERNATIONAL TEXTBOOK COMPANY

Arch
IA
7
I 6
V. 34

Copyright, 1905. by INTERNATIONAL TEXTBOOK COMPANY.

Entered at Stationers' Hall, London.

Loads in Structures: Copyright, 1904, by INTERNATIONAL TEXTBOOK COMPANY.
Entered at Stationers' Hall, London.

Properties of Sections: Copyright, 1904, by INTERNATIONAL TEXTBOOK COMPANY.
Entered at Stationers' Hall, London.

Materials of Structural Engineering, Parts 1 and 2: Copyright, 1904, by INTERNATIONAL TEXTBOOK COMPANY. Entered at Stationers' Hall, London.

Materials of Structural Engineering, Part 3: Copyright, 1905, by INTERNATIONAL TEXTBOOK COMPANY. Entered at Stationers' Hall, London.

Beams and Girders, Part 1: Copyright, 1904, by INTERNATIONAL TEXTBOOK COMPANY. Entered at Stationers' Hall, London.

Beams and Girders, Parts 2 and 3: Copyright, 1905, by INTERNATIONAL TEXTBOOK COMPANY. Entered at Stationers' Hall, London.

Columns and Struts: Copyright, 1904, by INTERNATIONAL TEXTBOOK COMPANY.
Entered at Stationers' Hall, London.

Details of Construction: Copyright, 1905, by INTERNATIONAL TEXTBOOK COMPANY.
Entered at Stationers' Hall, London.

Graphical Analysis of Stresses: Copyright, 1904, by INTERNATIONAL TEXTBOOK COMPANY. Entered at Stationers' Hall, London.

All rights reserved.

2000
2001
2002
2003
2004
2005
2006
2007
2008
2009
2010
2011
2012
2013
2014
2015
2016
2017
2018
2019
2020
2021
2022
2023
2024
2025
2026
2027
2028
2029
2030
2031
2032
2033
2034
2035
2036
2037
2038
2039
2040
2041
2042
2043
2044
2045
2046
2047
2048
2049
2050
2051
2052
2053
2054
2055
2056
2057
2058
2059
2060
2061
2062
2063
2064
2065
2066
2067
2068
2069
2070
2071
2072
2073
2074
2075
2076
2077
2078
2079
2080
2081
2082
2083
2084
2085
2086
2087
2088
2089
2090
2091
2092
2093
2094
2095
2096
2097
2098
2099
2100
2101
2102
2103
2104
2105
2106
2107
2108
2109
2110
2111
2112
2113
2114
2115
2116
2117
2118
2119
2120
2121
2122
2123
2124
2125
2126
2127
2128
2129
2130
2131
2132
2133
2134
2135
2136
2137
2138
2139
2140
2141
2142
2143
2144
2145
2146
2147
2148
2149
2150
2151
2152
2153
2154
2155
2156
2157
2158
2159
2160
2161
2162
2163
2164
2165
2166
2167
2168
2169
2170
2171
2172
2173
2174
2175
2176
2177
2178
2179
2180
2181
2182
2183
2184
2185
2186
2187
2188
2189
2190
2191
2192
2193
2194
2195
2196
2197
2198
2199
2200
2201
2202
2203
2204
2205
2206
2207
2208
2209
2210
2211
2212
2213
2214
2215
2216
2217
2218
2219
2220
2221
2222
2223
2224
2225
2226
2227
2228
2229
2230
2231
2232
2233
2234
2235
2236
2237
2238
2239
2240
2241
2242
2243
2244
2245
2246
2247
2248
2249
2250
2251
2252
2253
2254
2255
2256
2257
2258
2259
2260
2261
2262
2263
2264
2265
2266
2267
2268
2269
2270
2271
2272
2273
2274
2275
2276
2277
2278
2279
2280
2281
2282
2283
2284
2285
2286
2287
2288
2289
2290
2291
2292
2293
2294
2295
2296
2297
2298
2299
2300
2301
2302
2303
2304
2305
2306
2307
2308
2309
2310
2311
2312
2313
2314
2315
2316
2317
2318
2319
2320
2321
2322
2323
2324
2325
2326
2327
2328
2329
2330
2331
2332
2333
2334
2335
2336
2337
2338
2339
2340
2341
2342
2343
2344
2345
2346
2347
2348
2349
2350
2351
2352
2353
2354
2355
2356
2357
2358
2359
2360
2361
2362
2363
2364
2365
2366
2367
2368
2369
2370
2371
2372
2373
2374
2375
2376
2377
2378
2379
2380
2381
2382
2383
2384
2385
2386
2387
2388
2389
2390
2391
2392
2393
2394
2395
2396
2397
2398
2399
2400
2401
2402
2403
2404
2405
2406
2407
2408
2409
2410
2411
2412
2413
2414
2415
2416
2417
2418
2419
2420
2421
2422
2423
2424
2425
2426
2427
2428
2429
2430
2431
2432
2433
2434
2435
2436
2437
2438
2439
2440
2441
2442
2443
2444
2445
2446
2447
2448
2449
2450
2451
2452
2453
2454
2455
2456
2457
2458
2459
2460
2461
2462
2463
2464
2465
2466
2467
2468
2469
2470
2471
2472
2473
2474
2475
2476
2477
2478
2479
2480
2481
2482
2483
2484
2485
2486
2487
2488
2489
2490
2491
2492
2493
2494
2495
2496
2497
2498
2499
2500
2501
2502
2503
2504
2505
2506
2507
2508
2509
2510
2511
2512
2513
2514
2515
2516
2517
2518
2519
2520
2521
2522
2523
2524
2525
2526
2527
2528
2529
2530
2531
2532
2533
2534
2535
2536
2537
2538
2539
2540
2541
2542
2543
2544
2545
2546
2547
2548
2549
2550
2551
2552
2553
2554
2555
2556
2557
2558
2559
2560
2561
2562
2563
2564
2565
2566
2567
2568
2569
2570
2571
2572
2573
2574
2575
2576
2577
2578
2579
2580
2581
2582
2583
2584
2585
2586
2587
2588
2589
2590
2591
2592
2593
2594
2595
2596
2597
2598
2599
2600
2601
2602
2603
2604
2605
2606
2607
2608
2609
2610
2611
2612
2613
2614
2615
2616
2617
2618
2619
2620
2621
2622
2623
2624
2625
2626
2627
2628
2629
2630
2631
2632
2633
2634
2635
2636
2637
2638
2639
2640
2641
2642
2643
2644
2645
2646
2647
2648
2649
2650
2651
2652
2653
2654
2655
2656
2657
2658
2659
2660
2661
2662
2663
2664
2665
2666
2667
2668
2669
2670
2671
2672
2673
2674
2675
2676
2677
2678
2679
2680
2681
26

PROPERTIES OF SECTIONS

MATERIALS OF STRUCTURAL ENGINEERING

iii

MATERIALS OF STRUCTURAL ENGINEERING

<i>Continued</i>	<i>Section</i>	<i>Page</i>
Characteristics of Timber	9	1
Strength Values	9	8
Factor of Safety	9	17

BEAMS AND GIRDERS

Elements of Beams	12	1
Moments of Forces	12	1
The Lever	12	7
Reactions	12	10
Stresses in Beams	12	17
Continuous Beams	12	37
Deflection of Beams	12	40
Wooden, Steel, and Reenforced Concrete		
Beams	13	1
Formula of General Application	13	1
Wooden Beams	13	3
General Notes Relative to Wooden Beams	13	4
Flitch-Plate Girders	13	6
Built-Up Wooden Beams	13	9
Details of Design	13	13
Steel Beams	13	21
Transverse Strength	13	22
Lateral Strength of Beams	13	34
Spacing of Tie-Rods	13	37
Bearing Plates	13	44
Reenforced Concrete Beams	13	47
Ransome System	13	57
Hennebique System	13	59
Method Used in Common Practice	13	60
The Kahn System of Reenforced Concrete	13	63
The Unit Concrete Steel Reenforcement .	13	70
Specification for Reenforced Concrete . .	13	74
Built-Up Girders	14	1
General Construction	14	1
Principles of Design	14	4
Practical Design	14	52

CONTENTS

v

BEAMS AND GIRDERS— <i>Continued</i>	Section	Page
Cambëred Girders	14	57
Analytic Method of Computing Stresses . .	14	57
Graphic Method of Determining Stresses .	14	61
Detail Design	14	63
Trussed Girders	14	66
The Howe Truss	14	67
The Pratt Truss	14	77
The Warren Truss	14	80
The Lattice Truss	14	83
Lateral Bracing	14	87
Details of Truss Construction	14	89
COLUMNS AND STRUTS		
Columns in General	15	3
Stress in Columns	15	3
Timber Columns and Posts	15	10
Short Columns	15	11
Long Columns	15	12
Method of Securing Posts in Buildings . .	15	20
Cast-Iron Columns	15	25
Formulas for Cast-Iron Columns	15	26
Design of Cast-Iron Columns	15	32
Design of Cast-Iron Brackets	15	40
Steel Columns	16	1
Classification of Steel Columns	16	1
Forms of Steel Columns	16	3
Formulas for Steel Columns	16	9
Columns With Eccentric Loads	16	17
Design of Steel Columns	16	31
DETAILS OF CONSTRUCTION		
Rivets and Pins	25	1
Riveted Connections	25	2
Rivets	25	2
Spacing of Rivets	25	7
Analysis of Riveted Joints	25	13
Pin Connections	25	32

DETAILS OF CONSTRUCTION— <i>Continued</i>	Section	Page
Comparison With Riveted Connections	25	32
Methods of Failure	25	33
Calculations for Resistance	25	33
Details of Design	25	47.
 GRAPHICAL ANALYSIS OF STRESSES		
Fundamental Principles of Graphical		
Analysis	26	4
Effects of a Force	26	4
The Composition of Forces	26	6
The Resolution of Forces	26	12
Equilibrium	26	14
Application of Graphical Analysis	26	37
Scope of Graphical Solutions	26	37
Diagrams	26	41
Determination of External Forces	26	46
Determination of Internal Stresses	26	63
Diagrams for Simple Frames	27	1
Howe Roof Truss	27	8
Scissors Roof Truss	27	14
Truss With Loads on Lower Chord	27	25
Queen-Post Truss	27	35
Diagrams for Complex Frames	27	40
Trusses With Joints Acted On By Three		
Unknown Forces	27	40
Fink Truss With Cambered Tie-Member	27	50
Wind and Snow Loads on Opposite Sides	27	56
Roof Trusses With Horizontal or Oblique		
Thrusts	27	65
Roof Trusses With Members Subjected to		
Transverse Stress	27	74

LOADS IN STRUCTURES

FLOOR, ROOF, AND WIND LOADS

DEAD LOAD

1. The weight of the material used in the permanent structure of a building produces loads on the floor systems, the columns, and the foundations. These loads are called the **dead loads** and include the weight of the structural framework, walls, floors, partitions, and roofs. In fact, the weight of every piece of material used in the construction of the building is included in the dead load.

Before the dead load can be computed, the weight of various materials must be known, and those in common use are given in the following tables. The units in which these weights are expressed are those most often employed in making estimates of loads in engineering calculations. Thus, Table I gives the weight, per cubic foot, of the materials usually measured by that unit, together with the weight, per cubic inch, of a few often measured in inches; while Table II gives the weights of such materials as are used in the construction of floors, roofs, ceilings, etc., where the quantities are generally expressed in square feet.

2. **Weight of Fireproof Floors.**—If fireproof floors are of standard construction, their weight may be determined from the weights given by the manufacturers of the particular type to be used; they may be found for most systems in the tables in *Fireproofing*. Where the fireproof-floor system is of special construction, that is, different from the standard commercial construction, a careful estimate of the dead load

For notice of copyright, see page immediately following the title page

TABLE I
WEIGHT OF MATERIALS

Name of Material	Average Weight	
	Pounds per Cu. In.	Pounds per Cu. Ft.
Aluminum096	166
<i>Asphalt pavement composition</i>		130
<i>Bluestone</i>		160
Brass302	523
<i>Brickwork, in lime mortar</i>		120
<i>Brickwork, in cement mortar</i>		130
Bronze319	552
<i>Cement, Portland</i>		80 to 100
<i>Cement, Rosendale</i>		56 to 60
<i>Concrete, in cement</i>		140
Copper, cast319	550
Earth, dry and loose		72 to 80
Earth, dry and moderately rammed		90 to 100
Gneiss, common		168
Gneiss, in loose piles		96
Granite		165 to 170
Gravel		117 to 125
<i>Iron, cast</i>260	450
<i>Iron, wrought</i>277	480
Lead, commercial cast412	712
<i>Limestone</i>		170
<i>Marble</i>		164
<i>Masonry, granite or limestone</i>		165
<i>Masonry, granite or limestone rubble</i>		150
<i>Masonry, granite or limestone dry rubble</i>		138
<i>Masonry, sandstone</i>		145
Mortar, hardened		90 to 100
Quartz, common pure		165
Sand, pure quartz, dry		90 to 106
<i>Sandstone, building, dry</i>		144 to 151
Slate		160 to 180
<i>Snow, fresh fallen</i>		5 to 12
<i>Steel, structural</i>283	490
Terra cotta		110
<i>Terra-cotta masonry work</i>		112
Tile		110 to 120

NOTE.—While it is not necessary for the student to memorize all of this table, it is well to keep in mind the weights of the materials printed in *Italics*.

TABLE II
WEIGHT OF MATERIALS

Name of Material	Average Weight per Square Foot Pounds
Corrugated galvanized iron No. 20, unboarded	2 $\frac{1}{4}$
Copper, 16-ounce, standing seam	1 $\frac{1}{4}$
Felt and asphalt, without sheathing	2
Glass, $\frac{1}{8}$ inch thick	1 $\frac{3}{4}$
Hemlock sheathing, 1 inch thick	2 $\frac{1}{2}$
Lead, about $\frac{1}{8}$ inch thick	6 to 8
Lath-and-plaster ceiling (ordinary)	6 to 8
Mackite, 1 inch thick, with plaster	10
Neponset roofing felt, 2 layers	$\frac{1}{2}$
Spruce sheathing, 1 inch thick	2
Slate, $\frac{3}{8}$ inch thick, 3 inches double lap	6 $\frac{3}{4}$
Slate, $\frac{1}{2}$ inch thick, 3 inches double lap	4 $\frac{1}{2}$
Shingles, 6 inches by 18 inches, one-third to weather	2
Skylight of glass, $\frac{3}{16}$ inch to $\frac{1}{4}$ inch, including frame	4 to 10
Slag roof, 4-ply	4
Tin, IX	$\frac{3}{4}$
Tiles, 10 $\frac{1}{2}$ inches by 6 $\frac{1}{4}$ inches by $\frac{5}{8}$ inch; 5 $\frac{1}{4}$ inches to weather (plain)	18
Tiles, 14 $\frac{1}{2}$ inches by 10 $\frac{1}{2}$ inches; 7 $\frac{1}{4}$ inches to weather (Spanish)	8 $\frac{1}{2}$
White-pine sheathing, 1 inch thick	2 $\frac{1}{2}$
Yellow-pine sheathing, 1 inch thick	4

per square foot of floor surface should be made. The volume of all materials that are measured by the cubic inch or cubic foot should be obtained by the rules and methods in *Geometry and Mensuration*, and the load obtained by multiplying by the unit weights of the materials found in Table I. The area covered by materials, such as flooring, sheathing,

roof covering, etc., that are measured by the square foot, should be computed and multiplied by the weight, per square foot, given in Table II, to obtain the load.

In making calculations for the dead load of floors where the section through the floor shows irregularities in thickness and consequently in volume and weight, it is necessary to consider the section through a panel, which is the space between two floor beams. The section of the floor is taken




FIG. 1

1 foot in depth, as designated at xy , Fig. 1, so that when the entire weight of the section has been obtained the average weight per square foot can be found by dividing by the panel distance, or the distance between the floor beams.

EXAMPLE.—What is the amount of dead load per square foot of floor surface on the floor system shown in Fig. 1?

SOLUTION.—The sectional area of the brick arch is practically equal to the product of the length of the arc on the center line ab by the thickness of the arch, which in this instance is 4 in. The length of the chord of the arc ab is 47½ in., while the rise is 5 in. From these dimensions the length of the arc on the center line ab may be found by substituting in the formula $l = \frac{4\sqrt{c^2 + 4h^2}}{3} - c$, given in *Geometry and Mensuration*, in which c equals the chord and h the rise of the arc, the value of l is found to equal

$$\frac{4\sqrt{(47.5 \times 47.5) + (4 \times 5 \times 5)} - 47.5}{3} = 48.8883 \text{ in.}$$

Then the sectional area of the brick arch equals $\frac{48.8883 \times 4}{144} = 1.358$ sq. ft. Since the calculation is for a portion of the floor system 1 ft. in depth or length, the area of the section of the arch also equals, numerically, the cubical contents, so that the weight of the brick arch 1 ft. wide is equal to 1.358 multiplied by 120, the weight per cubic foot of brickwork laid in lime mortar, obtained from Table I, or 162.96 lb.

The area of the section of the concrete is equal to the area of a rectangle, in this case 7 in. \times 47½ in., from which must be deducted the area of the segment of the circle included between the arc ced and the chord cd . In order to obtain the area of this segment calculate the radius of the arc ced by applying the formula $r = \frac{c^2 + 4h^2}{8h}$, given in *Geometry and Mensuration*. The quantities c and h represent, as before, the chord and the rise and are equal, respectively, to 47.5 in. and 4.875 in. Substituting these values in the formula,

$$r = \frac{(47.5 \times 47.5) + (4 \times 4.875 \times 4.875)}{8 \times 4.875} = 60.29 \text{ in.}$$

The area of the segment is equal to the area of the sector minus the area of the triangle formed by the chord and the radii, or, as designated in Fig. 2, the area of the shaded portion is equal to the area $cedo$ minus the area of the triangle cdo . The area of the sector may be found by the formula $a = \frac{lr}{2}$, given in *Geometry and Mensuration*, in which l equals the length of the arc and r the radius. The arc cd has a smaller rise than that of arc ab and will therefore be shorter. Its length, found by the formula just given, is 48.82 in. Inserting this value and that of the radius in the formula,

$$a = \frac{48.82 \times 60.29}{2} = 1,471.68 \text{ sq. in.}$$

The area of the triangle to be deducted from the sector is equal to one-half the product of the base and the altitude. From Figs. 1 and 2, the base equals 47.5 in. and the altitude equals the radius minus the rise of the arc, or $60.29 - 4.875 = 55.415$ in., and consequently the area of the triangle cdo , as designated in Fig. 2, is $\frac{47.5 \times 55.415}{2} = 1,316.1063$ sq. in. Since the area of the sector $cedo$ equals 1,471.68 sq. in. and the triangle cdo has an area of 1,316.1063 sq. in., the area of the segment ced equals the difference between these




FIG. 2

quantities, or 155.57 sq. in.; hence, the area of concrete is $(7 \times 47\frac{1}{2}) - 155.57 = 176.93$ sq. in. The weight, from Table 1, is 140 lb. per cu. ft; since the length of the concrete section is 1 ft., its weight equals $(176.93 \div 144) \times 140 = 172$ lb. The steel beam shown in Fig. 1 weighs 40 lb. per lineal ft. From these calculations, the entire weight of a panel section of the floor system for 1 ft. in length or per lineal foot may be itemized as follows:

Weight of brick arch	162.96 lb.
Weight of concrete	172.00 lb.
Weight of steel beam	40.00 lb.
Total	374.96 lb.

This amount is the dead load on 4 sq. ft., and hence the dead load per square foot is $374.96 \div 4 = 93.74$ lb. Ans.

3. Where the floor construction is of uniform weight and thickness throughout, as in mill construction, designated in Fig. 3, the calculations for the dead load can be made directly for 1 square foot of floor surface. The size of the girders or floor beams is seldom known before the dead load has been determined, so that it is necessary to assume their size




FIG. 3

and to add the weight of the assumed girders or beams in calculating the dead load. When considering the amount of dead weight supported by a beam or girder, it is customary to consider the same as made up of one-half the panel situated on either side of the beam. After the dead load has been found and the size of the girder accurately determined, the assumed weight can be checked by the actual weight.

EXAMPLE.—In Fig. 3, what is the total dead load on the girder *B*?

SOLUTION.—The weight of the materials per square foot may be obtained from Table II and be tabulated as follows:

Yellow-pine flooring, 1 in. thick	4 lb. per sq. ft.
Two layers of felt	$\frac{1}{2}$ lb. per sq. ft.
Rough spruce flooring, 3 in. thick	6 lb. per sq. ft.
Assume the weight of the girder	8 lb. per sq. ft.

Total dead load of floor surface $18\frac{1}{2}$ lb. per sq. ft.

The area of the floor carried by the girder is $6 \times 18 = 108$ sq. ft. Then, $108 \times 18\frac{1}{2} = 1,998$ lb., the entire dead load on the girder *B*. Ans.

4. Dead Load on Roof Trusses.—This includes the weight of the roof covering, sheathing, and the weight of the roof trusses. The weight of the roof covering and the sheathing may be calculated from the unit weights given in Table II. The weight of the roof trusses, or *principals*, as they are termed, is not known until they have been designed and must be assumed in the original calculation. The weight of roof trusses depends on the material of which they are constructed, the span, and the distance they are placed apart and also on the rise and the type of construction, though these two latter factors are neglected in the usual empirical formulas.

The approximate weight of wooden and iron or steel roof trusses may be determined by the following formula:

$$W = a D L \left(1 + \frac{L}{10} \right) \quad (1)$$

in which W = approximate weight of truss, in pounds;

a = constant, for wood .50, for iron or steel .75;

D = distance, in feet, from center to center of trusses;

L = span of the truss, in feet.

This formula may be expressed as follows:

Rule.—Multiply the constant for the material of which the truss is composed by the distance, in feet, from center to center of trusses by the span of the truss, in feet; the product of this result and 1 plus one-tenth of the span of the truss, in feet, is the approximate weight of the truss, in pounds.

5. After the weight of the principals, or roof trusses, has been determined by formula 1, it is usual, in order to find the panel loads, or weight created at the connections of the truss, to determine what weight per square foot of roof surface it is necessary to add to the weight of the covering in order to provide for the weight of the principals or trusses. This weight may be found by dividing W , as determined from formula 1, by the actual area on the slope of the roof supported by one truss, or, it may be determined directly from the following formula, which is evolved from formula 1 by dividing by $DL \sec x$; this expression represents twice the length of the slope multiplied by the distance from center to center of trusses. The value w , or the approximate weight of the truss in pounds per square foot of roof surface, can be obtained from the following formula:

$$w = \frac{a(10 + L)}{10 \sec x} \quad (2)$$

in which a and L have the same values as above and x equals the angle of rafter member with horizontal.

This may be stated in the form of a rule as follows:

Rule.—*Multiply the constant by 10 plus the span of the truss, in feet; divide this product by 10 times the secant of the angle that the rafter member makes with the horizontal, which gives the approximate weight of the truss, in pounds per square foot of roof surface.*

EXAMPLE.—Determine the weight, per square foot, that it is necessary to add to the weight of the roof covering to provide for the weight of the principals, when the steel trusses have a span of 72 feet and a rise of 18 feet.

SOLUTION.—The roof slope has a pitch of 6 in. for every foot horizontal and the angle x of the slope with the horizontal is found from Table VII to be $26^\circ 33'$. The $\sec x = \text{hypotenuse} \div \text{adjacent side}$ or $\sec x = \frac{\sqrt{36^2 + 18^2}}{36} = 1.118$. The hypotenuse in this case is identical with the roof slope, the length of which is found by the formula: $\text{hypotenuse}^2 = \left(\frac{\text{span}}{2}\right)^2 + \text{rise}^2 = 36^2 + 18^2$. The hypotenuse is therefore $\sqrt{36^2 + 18^2}$, which value has been inserted in the formula.

The secant x may also be found by means of the formula: $\sec x = \frac{1}{\cos x}$; $\cos 26^{\circ} 33'$ being .8945, $\sec x = \frac{1}{.8945} = 1.118$. Substituting the values of a , L , and $\sec x$ in formula 2.

$$w = \frac{.75 (10 + 72)}{10 \times 1.118} = 5.5 \text{ lb. Ans.}$$

From formula 2, the following table has been calculated. It gives the weight that it is necessary to add to a square

TABLE III
WEIGHT OF ROOF TRUSSES

$w = \frac{a (10 + L)}{10 \sec x} = \text{Form. 2}$	Span Feet	Pounds per Square Foot of Roof Surface			
Character of Truss		$\frac{1}{2}$ Pitch	$\frac{1}{3}$ Pitch	$\frac{1}{4}$ Pitch	$\frac{1}{8}$ Pitch
Wood	30	1.417	1.63	1.79	1.90
	35	1.588	1.87	2.01	2.13
	40	1.764	2.08	2.24	2.37
	45	1.941	2.29	2.46	2.61
	50	2.115	2.49	2.68	2.85
	55	2.293	2.70	2.91	3.08
	60	2.470	2.91	3.13	3.32
	65	2.646	3.12	3.35	3.56
	70	2.823	3.33	3.58	3.80
	75	2.999	3.54	3.80	4.03
Iron or steel	80	3.176	3.75	4.03	4.27
	30	2.117	2.45	2.69	2.85
	35	2.382	2.81	3.02	3.20
	40	2.647	3.12	3.35	3.56
	45	2.911	3.44	3.69	3.92
	50	3.176	3.74	4.02	4.28
	55	3.440	4.05	4.37	4.62
	60	3.705	4.37	4.70	4.98
	65	3.965	4.68	5.03	5.34
	70	4.235	5.00	5.37	5.70
	75	4.499	5.31	5.40	6.05
	80	4.764	5.63	6.05	6.41

foot of roof covering in order to provide, in the amount of the unit dead load, for the weight of the principals or trusses.

The term pitch used in Table III may have more than one interpretation; it may be the quotient $\frac{\text{rise}}{\text{span}}$ or $\frac{\text{rise}}{\frac{\text{span}}{2}}$.

Throughout this Course it will mean: $\frac{\text{rise}}{\text{span}}$. For instance, $\frac{1}{4}$ pitch means a rise one-fourth of the total span; $\frac{1}{6}$ pitch a rise one-sixth of the total span, etc.

EXAMPLES FOR PRACTICE

1. A $2'' \times 3''$ wrought-iron bar is $36\frac{1}{2}$ inches long. What is its weight? Ans. 60.66 lb.
2. The outside diameter of a cast-iron column is 10 inches, and the thickness of the material composing the column is $\frac{3}{4}$ inch. What is its weight per foot of length? Ans. 68 lb.
3. The wall of a brick building, laid in cement mortar, is 24 inches thick, 36 feet high, and 100 feet long; in it are located 20 window openings, 2 feet 6 inches wide by 6 feet high. What is the weight of this wall? Ans. 858,000 lb.
4. What is the weight of a structural steel angle $6'' \times 6'' \times \frac{1}{2}'' \times 20'$ long? Ans. 390.54 lb.
5. The roof of a building is made of No. 20 corrugated galvanized iron, laid on 1-inch spruce boarding. What is the weight of the roof covering per square foot? Ans. $4\frac{1}{4}$ lb.
6. What will be the difference in weight per square foot between a 4-ply slag roof, laid on 3-inch tongued-and-grooved yellow-pine planking, and a $\frac{3}{16}$ -inch slate roof laid on 2-inch hemlock sheathing, covered with Neponset roofing felt, two layers thick? Ans. $3\frac{3}{4}$ lb.
7. The span of a steel roof truss is 40 feet, and its rise 10 feet. Referring to Table III, what weight per square foot of roof surface should be assumed so as to allow for the weight of the principal or roof truss? Ans. 3.35 lb.

LIVE LOAD

6. Besides the dead load, which includes the weight of all the material used in the structure itself, there is a load due to the weight of people, machinery, and merchandise; this load is called the live load. The live load comprises people in the building, furniture, movable stocks of goods, small

safes, and varying weights of any character. Large safes and extremely heavy machinery require some special provision, usually embodied in the construction. Table IV gives the live loads per square foot, recommended as good practice in conservative building construction.

TABLE IV

Character of Building	Pounds
Dwellings	70
Offices	70
Hotels and apartment houses	70
Theaters	120
Churches	120
Ballrooms and drill halls	120
Factories	from 150 up
Warehouses	from 150 to 250 up

The load of 70 pounds will probably never be realized in dwellings; but inasmuch as a city house may, at times, be used for some purpose other than that of a dwelling, it is not generally advisable to use a lighter load. In the case of a country house, a hotel, or a building of like character, where economy demands it, and its actual use for a long time, for some fixed purpose, is almost certain, a live load of 40 pounds per square foot of floor surface is ample for all rooms not used for public assembly.

For rooms thus used, a live load of 80 pounds will be sufficient, experience having demonstrated that a floor cannot be crowded to more. If the desks and chairs are fixed, as in a schoolroom or church, a live load of more than 40 to 50 pounds will never be attained. Retail stores should have floors proportioned for a live load of 100 pounds and upwards. Wholesale stores, machine shops, etc., should have the floors proportioned for a live load of not less than 150 pounds per square foot. The floors of printing houses and binderies, especially where the accumulation of heavy stock, such as

bound volumes and calendered paper, is likely to occur, should be proportioned for a live load of at least 250 pounds per square foot. Special provision should be made in floor systems for heavy presses, trimmers, and cutters and the beams should be proportioned for twice the static load likely to occur from such machines.

The static load in factories seldom exceeds 40 to 50 pounds per square foot of floor surface, and, therefore, in the majority of cases, a live load of 100 pounds, including the effects of vibrations due to moving machinery, is ample. The conservative rule is, in general, to assume loads not less than the above, and to proportion the beams so as to avoid excessive deflection. Stiffness is as important a factor as strength.

7. Warehouse Floors.—In the design of warehouse floors, the character of the material to be stored should always be considered and the data should be obtained regarding the manner of storing, the bulk of the packages, and the weight of the load per square foot. With the view of furnishing reliable data to manufacturers, architects, and engineers, the Boston Manufacturers' Mutual Fire Insurance Company has prepared from its extensive experience the following table, which gives the greatest possible loads that can be placed on warehouse floors, with the usual system of loading, and the space that the merchandise occupies. Where the floor space and the cubical contents of the load are given in the table, the height of the load above the finished floor may be obtained by dividing the volume of the load by the floor area covered. For instance, the floor space occupied by white linen rags in a bale is 8.5 square feet, and the cubical contents are 39.5 cubic feet; then the height of the loading is $39.5 \div 8.5 = 4.65$ feet. It is unusual and hardly possible, in the absence of hoists, to place such materials on the floor more than one bale in thickness, and the same thing applies to merchandise in barrels on the side and end. Where no data other than the weight per cubic foot is given in the table, it signifies that the possible height of the load is only

limited by the height of the room, or the *headroom*, as it is called. With a live load of such merchandise, the floor system must be designed for the maximum load, which consists of the weight of the merchandise covering the entire floor area to a depth of not less than 6 feet.

The building ordinances of the principal American cities are particularly emphatic with reference to warehouse floors. For instance, the building laws of Greater New York stipulate that, in all warehouses, storehouses, factories, workshops, and stores where heavy materials are kept and stored, or machinery introduced, the weight that each floor will safely sustain upon each superficial foot, or upon each varying part of such floor, shall be estimated by the owner or occupant, or by a competent person employed by the owner or occupant.

Such estimate shall be reduced to writing or printed forms, stating the material, size, distance apart, and span of beams and girders, posts or columns to support floors, and its correctness shall be sworn to by the person making the same; it further being required that this estimate shall be filed in the office of the Department of Buildings.

But if the commissioners of buildings shall have cause to doubt the correctness of said estimate, they are empowered to revise and correct the same, and for the purpose of such revision the officers and employes of the Department of Buildings may enter any building and remove so much of any floor or other portion thereof as may be required to make necessary measurements and examination.

When the correct estimate of the weight that the floors in any such buildings will safely sustain has been ascertained as herein provided, the Department of Buildings shall approve the same. Thereupon the owner or occupant of said building, or any portion thereof, shall post a copy of such approved estimate in a conspicuous place on each story or varying parts of each story of the building to which it relates. No person shall place on any floor of any building any greater load than the safe load as correctly estimated and ascertained.

TABLE V
WEIGHTS OF MERCHANDISE FOR CALCULATING LIVE LOADS

Materials	Measurements		Approximate Weights	
	Floor Area Sq. Ft.	Contents Cu. Ft.	Total Pounds	Pounds per Cu. Ft.
Cotton, etc.	Bale	44.2	515	12
	Bale of compressed	21.6	550	25
	Bale of American Cotton Co.	11.0	263	24
	Bale of Planters Compress Co.	7.2	254	35
	Bale of jute	9.9	300	30
	Bale of jute lashings	10.5	450	43
	Bale of manila	10.9	280	26
	Bale of hemp	34.7	700	20
	Bale of sisal	17.0	400	24
Cotton goods	Bale of unbleached jeans	12.5	300	24
	Piece of duck	2.3	75	33
	Bale of brown sheetings	10.1	235	23
	Case of bleached sheetings	11.4	330	30
	Case of quilts	19.0	295	16
	Bale of print cloths	9.3	175	19
	Case of prints	13.4	420	31
	Bale of tickings	8.8	325	37
	Skein of cotton yarns			11
	Burlaps		130	30
	Jute bagging	5.3	100	24
Grain	Wheat in bags	4.2	165	39
	Wheat in bulk			44

Grain	Wheat in bulk						39
	Wheat in bulk, mean						41
	Flour in barrels on side	4.10	5.40	218	53		40
	Flour in barrels on end	3.10	7.10	218	70		31
	Corn in bags	3.60	3.60	112	31		31
	Corn meal in barrels	3.70	5.90	218	59		37
	Oats in bags	3.30	3.60	96	29		27
	Bale of hay	5.00	20.00	284	57		14
	Hay, Derrick compressed	1.75	5.25	125	72		24
	Straw	1.75	5.25	100	57		19
Paper	Tow	1.75	5.25	150	87		29
	Excelsior	1.75	5.25	100	57		19
	Calendered book						50
	Supercalendered book						69
	News paper						38
	Straw board						33
	Leather board						59
	Writing						64
	Wrapping						10
	Manila						37
Rags in bales	White linen	8.50	39.50	910	107		23
	White cotton	9.20	40.00	715	78		18
	Brown cotton	7.60	30.00	442	59		15
	Paper shavings	7.50	34.00	507	68		15
	Sacking	16.00	65.00	450	28		7
	Woolen	7.50	30.00	600	80		20
	Jute butts	2.80	11.00	400	143		36

TABLE V—(Continued)

Materials	Measurements		Approximate Weights		
	Floor Area Sq. Ft.	Contents Cu. Ft.	Total Pounds	Pounds per Sq. Ft.	Pounds per Cu. Ft.
Wool					
Bale, East India	3.0	12	340	113	28
Bale, Australian	5.8	20	385	66	15
Bale, South American	7.0	34	1,000	143	29
Bale, Oregon	6.0	33	482	79	15
Bale, California	7.5	33	550	73	17
Bag of wool	5.0	40	200	40	7
Sack of scoured wool					5
Woolen goods					
Case of flannels	5.5	12.7	220	40	17
Case of flannels, heavy	7.1	15.2	340	46	22
Case of dress goods	5.5	22	400	84	21
Case of cassimeres	10.5	28	550	52	20
Case of underwear	7.3	21	350	48	16
Case of blankets	10.3	35	350	34	11
Case of horse blankets	4.0	14	240	60	18
Miscellaneous					
Box of tin	2.7	.5	149	99	278
Box of glass					60
Crate of crockery	9.9	39.6	1,600	162	40
Cask of crockery	13.4	42.5	600	52	14
Coal, anthracite, broken					54
Coal, anthracite, moderately shaken					58
Coal, anthracite, solid					93
Coal, anthracite, heaped bushel					80
Coal, bituminous, solid					84

[illegible]

EXAMPLE.—What will be the entire live load coming on a large girder supporting a portion of a church floor, if the floor area to be supported is 600 square feet?

SOLUTION.—From the list given in Table IV, 120 lb. is usually considered safe for a live load in a church. Therefore, $600 \times 120 = 72,000$ lb., the total live load on the girder. Ans.

EXAMPLES FOR PRACTICE

1. What will be the entire live load on the floor of a church 50 feet by 120 feet? Ans. 720,000 lb.

2. What live load will a joist in a city dwelling be required to bear, the distance between centers being 14 inches, and the span of the joist 20 feet? Ans. 1,633 lb.

3. A steel beam, supporting a portion of the floor in an office building, sustains an area of 80 square feet. What will be the live load coming on the beam? Ans. 5,600 lb.

4. A warehouse used for the storage of South American wool is 40 feet wide and 80 feet long inside. The girders extend across the building and divide it lengthwise into 5 bays; provided the floor construction and the girders weigh 20 pounds per square foot of surface, what is the total dead and live load on each girder? Ans. 104,320 lb.

8. In proportioning the live loads on floors, the architectural engineer cannot always exercise his own judgment, for if the building is to be erected in a large city, the live load must comply with the building laws. As these are not uniform in the several cities the following table is given to show the stipulated live loads in the four largest cities in the United States:

TABLE VI

THE ALLOWABLE LIVE LOADS ON FLOORS IN DIFFERENT CITIES

Character of Building	Pounds per Square Foot			
	New York	Philadelphia	Chicago	Boston
Buildings for public assembly .	90	100	120	150
Buildings for ordinary stores, light manufacturing, and light storage	120	100	120	
Dwellings, apartment houses, hotels, tenement houses, or lodging houses	60	40	70	50
Office buildings, first floor . . .	150	100	100	100
Office buildings, above first floor	75	100	100	100
Public buildings, except schools				150
Roofs, pitch less than 20° . . .	50	25	30	25*
Roofs, pitch more than 20° . . .	30	25	30	25*
Schools or places of instruction	75			80
Stables or carriage houses less than 500 square feet in area . .	75	40		
Stables or carriage houses more than 500 square feet in area . .	75	100		
Stores for heavy materials, ware- houses, and factories	150		150	250
Sidewalks	300			

NOTE.—In this table the values given for roofs are not live loads, for a snow load can hardly be classified with live loads. The roof loads, in the last column, marked with the asterisk (*), do not include the wind load, and the building laws of Boston require that a proper allowance for the wind load exerting a pressure of 30 pounds per square foot of vertical surface shall be made in designing roofs.

SNOW AND WIND LOADS

9. In calculating the weight on roofs, there are two other loads always to be considered when obtaining the stresses on the various members of the truss; these are *snow* and *wind loads*. When the roof is comparatively flat, that is, when the rise of the roof is under 12 inches per foot of horizontal distance, the **snow load** is estimated at 12 pounds

per square foot; for roofs that have a steep slope, or a rise of more than 12 inches per foot of horizontal distance, it is good practice to assume the snow load to be 8 pounds per square foot. In northern climates, such as Canada, snow loads 50 per cent. greater than the above should be assumed.

10. Wind Pressure.—The wind pressure depends on the velocity with which the air is moving. United States Government tests have determined that the pressure per square foot on a vertical surface is approximately represented by the formula

$$p = .004 V^2 \quad (3)$$

in which p = pressure, in pounds per square foot, of vertical surface;

V = velocity of wind, in miles per hour.

This formula may be expressed in a rule thus:

Rule.—*The wind pressure, in pounds per square foot of vertical surface, is obtained by multiplying the square of the velocity of the wind, in miles per hour, by .004.*

The velocity of the wind varies from a pleasant breeze of 2 or 3 miles per hour to a violent hurricane or tornado of 100 or more miles per hour. Careful records, extending over a period of years, show that the velocity of the wind seldom attains 100 miles per hour; probably not more than once in the lifetime of the structure. In cyclonic storms, the velocity of the wind greatly exceeds 100 miles per hour, and structures cannot be built that will withstand their fury.

By applying formula 3, it will be found that a wind having a velocity of 100 miles per hour will exert a pressure of 40 pounds per square foot of vertical surface and this is the pressure usually assumed by conservative engineers in providing for the resistance to wind pressure on structures. However, where the surface is of great area, as the side of a large office building, a pressure of 30 pounds per square foot is considered ample; for, the average unit pressure on a large surface is never so great as the maximum unit pressure on a small surface.

11. Curved surfaces, such as would be presented by circular towers and stacks, and flat surfaces not in a vertical plane, as roofs, are subjected to less pressure than flat vertical surfaces. The pressure on a cylindrical surface is about one-half the pressure on a flat surface having the same width as the diameter of the cylinder and the same height.

12. On roofs the wind pressure is always assumed as acting normal (that is, perpendicular) to the slope. In Fig. 4, the outline abc of a roof is shown; the force d is normal to the slope ab , and represents the assumed pressure of the wind on the roof. The wind generally acts in a horizontal direction, as shown by the full arrow e . The reason for assuming the force d instead of e as the active wind pressure is for convenience in determining the stresses in the members of a roof frame or truss, which is explained in *Graphical Statics*. At present it may suffice to say that in order to estimate the effect of the force e , it is supposed to consist of two




FIG. 4




FIG. 5

components, one of which is the force d and the other a force acting upwards and in a direction parallel with the slope. The latter is not taken into consideration. The wind, blowing with a horizontal pressure of 40 pounds, strikes the roof at an angle; consequently, the pressure d , normal to the slope, is considerably less than 40 pounds, unless the slope of the

roof is very steep. Referring to Figs. 4 and 5, it is clear that the horizontal force e of the wind on the slope of the roof, shown in Fig. 4, is almost as intense as on a vertical surface; on the extremely flat roof in Fig. 5, however, the wind exerts hardly any force normal to the slope, because it strikes the slope at such an acute angle, and therefore has a tendency to slide along its surface. The more acute the angle between the lines e and d , the greater the pressure normal to the slope; whereas, the greater the angle, the less the pressure normal to the slope, until they approximate a right angle with each other, when the pressure on the roof may be disregarded. In the design of roof trusses a horizontal wind pressure of 40 pounds per square foot is usually assumed.

13. All necessary data for calculating the wind pressure on a roof are given in Table VII, but it may be interesting to the student to know how the results given therein are obtained, and therefore the following explanation is offered. The pressure normal to the slope is generally determined by what is known as *Hutton's formula*. This formula is trigonometric, and may be expressed as follows:

$$p = p' \sin x^{1.84 \cos x - 1} \quad (4)$$

in which p = pressure, in pounds per square foot, normal to slope of roof;

p' = wind pressure, in pounds per square foot, of vertical surface;

x = internal angle of roof with the horizontal.

This formula may be expressed as follows:

Rule.—*The pressure, in pounds per square foot, normal to the slope of the roof is equal to the product of the wind pressure, in pounds per square foot of vertical surface, and the sine of the angle that the roof slope makes with the horizontal, having an exponent of 1.84 times the cosine of the same angle, minus 1.*

For further explanation and application of the formula, assume a roof slope of 30° and the usual horizontal wind pressure of 40 pounds per square foot. The formula becomes, on substitution, $p = 40 \sin 30^{1.84 \cos 30 - 1}$, and

since $\sin 30^\circ$ equals .5000 and $\cos 30^\circ$ equals .86603, by further substitution $p = 40 \times .5000^{1.84 \times .86603 - 1}$, or $p = 40 \times .5000^{.5935}$. Referring to the logarithmic table given in *Logarithms*, the calculation for this last expression is as follows:

Log .5000 = 1.69897 and $1.69897 \times .5935 = - .1787$

Then $\log 40 = 1.60206$
 $ - .17870$
 $ \underline{1.42336}$

The number corresponding to this logarithm is 26.5 +, the value of p or the pressure in pounds per square foot normal to the slope of the roof.

The following table, which gives the normal wind pressure on roofs of different slopes, has been calculated for a horizontal wind pressure of 40 pounds per square foot:

TABLE VII
WIND PRESSURE NORMAL TO THE SLOPE OF ROOF

Rise	Angle of Slope With Horizontal	Pitch, Proportion of Rise to Span	Wind Pressure Normal to Slope Pounds per Sq. Ft.
4 inches per foot horizontal. .	18° 25'	$\frac{1}{8}$	16.8
6 inches per foot horizontal. .	26° 33'	$\frac{1}{4}$	23.7
8 inches per foot horizontal. .	33° 42'	$\frac{1}{3}$	29.1
12 inches per foot horizontal. .	45° 0'	$\frac{1}{2}$	36.1
16 inches per foot horizontal. .	53° 7'	$\frac{2}{3}$	38.7
18 inches per foot horizontal. .	56° 20'	$\frac{3}{4}$	39.3
24 inches per foot horizontal. .	63° 27'	1	40.0

14. A diagram of the formula for obtaining the wind pressure normal to the slope, such as shown in Fig. 6, is interesting and provides a convenient means of determining the amount of the pressure for any slope. This may be found by projecting the point which represents the upper end of the slope on the arc horizontally, until it intersects

the curve of normal pressure; the multiplier directly under this point multiplied by the assumed wind pressure on a vertical surface will give the normal pressure for the given




FIG. 6

slope. For instance, assume that it is desired to obtain the normal pressure on a roof whose slope forms an angle of 35°




FIG. 7

with the horizontal; mark off 35° on the arc and project this point horizontally until it intersects the curve of normal pressure, then note the value of the multiplier directly under

the point of intersection, which in this case is .75. Assuming a wind pressure of 40 pounds per square foot on a vertical surface, the normal pressure is found to be $40 \times .75 = 30$ pounds per square foot.

15. In order to more fully explain Table VII assume the conditions shown in Fig. 7. The rise in the slope ab is 6 inches for every 12 inches on the horizontal line ac ; for instance, at 4 feet from a on the horizontal line ac , the rise is four times 6 inches, or 2 feet, the angle included between the line of slope ab and the horizontal base line ac is $26^\circ 33'$, and the pressure normal to the slope, according to Table VII, is 23.7 pounds per square foot. Since the rise at the center is equal to one-half the length of one-half the span, the total rise is one-quarter of the span. Under these conditions, the pitch of the roof, that is, the ratio of the rise to the span, is $\frac{1}{4}$, and the roof is said to be $\frac{1}{4}$ *pitch*.

EXAMPLE.—(a) What will be the dead load per square foot of roof surface, on a roof with a 12-inch rise per foot horizontal, the span of the trusses being 50 feet, the roof covering 1-inch white-pine sheathing, 2 layers of Neponset roofing felt, and $\frac{1}{8}$ -inch slate 3-inch lap? (b) What will be the wind pressure per square foot normal to the slope? (c) If the roof trusses are placed 12 feet apart, what will be the entire dead load on one truss? Fig. 8 shows a plan with elevation and detail section of the roof.

SOLUTION.—(a) It is first necessary to obtain the length of the line of slope ab ; this is done by calculating the hypotenuse of the triangle, or by laying the figure out to scale and measuring. In this case it is found that ab measures about 35 ft. 4 in., equal to 35.33 ft. The area of the roof supported by one truss is $2 \times 35.33 \times 12 = 847.92$ sq. ft. By referring to Table III, it is seen that the approximate weight of a roof truss of $\frac{1}{4}$ pitch and with a span of 50 ft. is 3.176 lb. per sq. ft. of roof surface. Using the approximate value of 3.2 lb., the dead load per square foot of roof surface is, then, as follows:

Weight of supporting truss	3.2 lb. per sq. ft.
Weight of white-pine sheathing, 1 inch thick	2.5 lb. per sq. ft.
Weight of 2 layers of Neponset roofing felt .	.5 lb. per sq. ft.
Weight of slate ($\frac{1}{8}$ inch thick)	4.5 lb. per sq. ft.
Total	10.7 lb. per sq. ft.

The weight of the purlins supporting the sheathing has not been estimated in the above, it being safe in this case to assume that the

weight used for the principals, or trusses, is sufficient to cover this item. A snow and accidental load of 12 lb. per sq. ft. of roof surface should also be added to the dead load to get the entire vertical load on the roof.

(b) The wind pressure normal to the slope of this roof, according to Table VII for a $\frac{1}{2}$ -pitch roof is 36.1 lb., say 36 lb. per sq. ft. Ans.




FIG. 8

(c) The area of the roof supported by one truss is, as previously found, 847.92 sq. ft., and the dead load, 10.7 lb per sq. ft. Then, $847.92 \times 10.7 = 9,072.74$ lb. to be supported by one truss, not including the snow load. Ans.

16. Engineering, it must be remembered, is not an exact science, the results obtained depending more or less on the judgment and experience of the designer. When, for instance, the wind is blowing a hurricane, snow never lodges on a roof, the slates, shingles, and sheathing being

themselves exposed to sudden removal. If, therefore, the full wind pressure be assumed, the snow load may, in most cases, be neglected, especially if it is desired to build an economical roof. However, it is not well for the student to make such assumptions until his experience and judgment are sufficiently developed to enable him to make true deductions.

EXAMPLES FOR PRACTICE

1. With the wind blowing at a velocity of 36 miles per hour, what is the pressure, in pounds per square foot of vertical surface?

Ans. 5.18 lb.

2. The area of one slope of a $\frac{1}{2}$ -pitch roof is 800 square feet. What is the entire pressure on the slope of the roof, provided the maximum horizontal wind pressure is taken at 40 pounds per square foot?

Ans. 28,880 lb.

3. In a $\frac{1}{4}$ -pitch roof the trusses are 20 feet apart, and the length of the roof slope is 40 feet. What wind load is there on each roof truss, if the horizontal pressure is 40 pounds per square foot?

Ans. 18,960 lb.

4. The purlins supporting a $\frac{3}{4}$ -pitch roof are placed 6 feet apart, and the trusses are 12 feet from center to center. What is the maximum load due to the wind on each purlin, providing the greatest horizontal pressure is 40 pounds per square foot?

Ans. 2,830 lb.

5. The angle that the slope of a roof makes with the horizontal is 40° . Provided the wind exerts a pressure of 30 pounds per square foot of vertical surface, what is the pressure normal to the slope?

Ans. 25.50 lb.

ACCIDENTAL AND SUDDENLY APPLIED LOADS

17. Careful designers sometimes make allowance for the accidental load caused by a heavy body falling on the floor, or by a mass of snow dropping from one roof to another. The latter may usually be ignored, because it is taken care of in the factor of safety, within the limit of which every member in the structure is designed.

Members subjected to suddenly applied loads are seldom encountered in building construction, and still less frequently are members required to resist the effect of impact, or the blow imparted by a falling load. The beams supporting the mechanism at the heads of elevator shafts are at times

subjected not only to suddenly applied loads but also to falling loads; therefore, they should always be proportioned to withstand at least a suddenly applied load.

18. Where a load is placed suddenly on a beam, the stress produced is twice as great as if the same load had been at rest; that is, a beam to sustain a suddenly applied load should have twice the transverse strength required to sustain the same load at rest.

A falling load produces a much greater stress on a beam than a load suddenly applied, owing to the impact produced by the momentum of the falling body. It is usual in considering the effect of a falling load on a beam to determine the amount of a statical load that would produce the same results; the formula used to accomplish this is as follows:

$$W_1 = W \left(1 + \sqrt{\frac{2ah}{d}} + 1 \right) \quad (5)$$

in which W_1 = static load that would produce same stress in beam as falling load;

W = falling load;

h = height load falls, in inches;

d = deflection of beam, in inches;

a = constant.

The value of d may be determined as described in *Beams and Girders*, Part 1, while the value of a must be determined by the formula

$$a = \frac{1}{1 + .489 \frac{W_1}{W}} \quad (6)$$

in which W_1 = combined weight of beam and dead load that it supports;

W = amount of falling load, as before.

This may be expressed by a rule as follows:

Rule.—*The value of the constant is equal to 1 divided by the sum of 1 and .489 times the quotient obtained by dividing the combined weight of the beam and the dead load that it supports, by the falling load.*

19. Formula 5 may be stated as follows:

Rule.—*To the quotient of 2 times the constant times the distance the load falls, in inches, divided by the deflection of the beam in inches, add 1; the square root of this result is added to 1 and their sum multiplied by the falling load gives the static load that will produce the same strain in a beam as the falling load.*

EXAMPLE.—The drop test of a fireproof-floor system is to be made by letting a weight of 300 pounds fall through a distance of 3 feet. Provided the deflection of the floor beams under the falling load is $\frac{1}{8}$ inch and the weight of the beam with the dead load is 3,000 pounds, what static concentrated load is it necessary to figure on, that it may equal the falling load in its effect?

SOLUTION.—From formula 6, the value of a equals $\frac{1}{1 + .489 \frac{W_1}{W}}$,

or by substitution, $a = \frac{1}{1 + .489 \times \frac{3000}{300}} = .1698$.

The value of a having been found, the equivalent static load required by the example may be obtained from formula 5 where

$W_1 = W \left(1 + \sqrt{\frac{2 a h}{d} + 1} \right)$, or by substitution,

$$W_1 = 300 \left(1 + \sqrt{\frac{2 \times .1698 \times 36}{.125} + 1} \right) = 3,282 \text{ lb. Ans.}$$

EXAMPLES FOR PRACTICE

1. The static load from an elevator car on the steel beams at the head of the shaft is 4,000 pounds; what load should be figured on to compensate for the weight being suddenly applied in starting the car?
Ans. 8,000 lb.

2. The beams supporting a loading platform have a span of 20 feet and are frequently subjected to a load of 500 pounds falling a distance of 2 feet. Provided the deflection of the beam is $\frac{3}{16}$ inch, what static load will be equivalent to the effect of the falling load if the beam and the dead load on it weigh 1,000 pounds?
Ans. 6,210 lb.

THE DISPOSITION OF LOADS

20. In warehouses built especially for the storage of heavy merchandise, where the floors are likely at any time to be fully loaded, the beams, girders, columns, and foundations are always proportioned for the entire live and dead load on all floors. However, where the building exceeds four or five stories in height and is used for any other purpose than for storage, as, for instance, a modern office building, it is customary to assume that certain members, while proportioned for the entire dead load, carry only a certain percentage of the live loads.

In an office building, or similar structure, it is highly improbable that all the floors or all parts of the same floor will be fully loaded at the same time, and in view of this fact it is considered good practice, while proportioning the floor beams for the full live load, to calculate only 90 per cent. of the live load on the girders. It is usual to proportion the columns supporting the roof and the top floor for the full live load. The live loads on the columns, in each successive tier, from the floor above is reduced 5 per cent. until 50 per cent. of the live load is reached, when such reduced loads are used for all remaining floors to the basement. The economy obtained by this disposition of the live load is best observed from Table VIII, which gives the distribution of the assumed live loads on the columns in the several tiers of an eighteen-story office building.

While this system of graduating the live loads on the columns from floor to floor is generally practiced, the amount of reduction at each floor is a matter that depends on the judgment of the designer. The percentage of reduction is often fixed by the building laws of the city, with which the designer must comply. The reduction of 5 per cent. at each floor, the economy of which is shown in the table, is conservative and in most cases will be found to be in accordance with the building departments of the principal American cities.

TABLE VIII
SHOWING REDUCTIONS OF LIVE LOADS FROM FLOOR
TO FLOOR

Floors	Live Load in Lb. per Sq. Ft. on Each Floor	Live Load in Lb. per Sq. Ft. of Floor on Columns From Floor Above at 5% Reduction	Live Load in Lb. per Sq. Ft. of Floor on Columns From All Floors Above If No Reduction Were Made	Live Load in Lb. per Sq. Ft. of Floor on Columns From All Floors Above Increment of Reduction	Theoretical Percentage of Saving Instituted by the Reduction of 5% at Each Floor
	a	$a, a - .05a$	Σa	Σa_1	$\frac{\Sigma a - \Sigma a_1}{\Sigma a}$
Roof	20	20.00	20	20.00	
18	60	60.00	80	80.00	
17	60	57.00	140	137.00	2.1
16	60	54.15	200	191.15	4.4
15	60	51.44	260	242.59	6.7
14	60	48.87	320	291.46	8.9
13	60	46.43	380	337.89	11.1
12	60	44.11	440	382.00	13.2
11	60	41.90	500	423.90	15.2
10	60	39.80	560	463.70	17.2
9	60	37.81	620	501.51	19.1
8	60	35.92	680	537.43	21.0
7	60	34.12	740	571.55	22.8
6	60	32.41	800	603.96	24.5
5	60	30.79	860	634.75	26.2
4	60	30.00	920	664.75	27.7
3	60	30.00	980	694.75	29.1
2	60	30.00	1,040	724.75	30.3
1	60	30.00	1,100	754.75	31.4

21. In the design of the type of building known as **skeleton construction**, that is, one in which all floors and walls are supported on beams and girders that transmit the loads to columns and, in turn, are supported on ample

foundation footings, it is necessary to fix on the general arrangement, disposition, and approximate dimensions of the component parts before the dead load can be computed. After the calculations are made and the structural details are designed, the actual dead load should be checked to see whether it approximates the assumed load. If any considerable variation is found it can be provided for by increasing or diminishing the weight or thickness of the rolled steel shapes making up the structural members, the sizes of which have already been determined.

Where permanent partitions exist, they should always be figured in the dead load; and where they are directly above a beam or a girder, the member should be proportioned to sustain the additional weight without appreciable deflection. Where movable partitions occur or where there is a probability of the location of permanent partitions being changed, it is usual to add 20 pounds per square foot of floor surface to the dead load to take care of such contingencies.

The foundations of an office building should be proportioned for the entire dead load and none of the live load, the latter being provided for by making the unit pressure on the footings and piers well within the safe unit bearing value of the soil. In this way unequal settlement is prevented, as explained in *Foundations*.

PROPERTIES OF SECTIONS

CENTER OF GRAVITY

1. Introduction.—The calculations involved in the design of such built-up members of a building as steel columns and plate girders—members that are formed by the combination of several of the simple sections produced by the rolling mills—require a knowledge of certain mathematical properties of the simpler sections, together with the methods by which these properties may be calculated. In many cases, the exact determination of the required properties is based on complicated mathematical principles; there are, however, numerous formulas and practical methods by means of which the values for all sections used in ordinary practice may be determined, either exactly or with a degree of approximation sufficiently close for all practical purposes.

2. The center of gravity of a body, or of a system of bodies, is that point from which, if the body or system were suspended, it would be in equilibrium. If the body or system were suspended from any other point than the center of gravity, and in such a manner as to be free to turn about the point of suspension, the body would rotate until the center of gravity reached a position directly under the point of suspension.

3. Center of Gravity of Plane Figures.—If a plane figure has an *axis of symmetry*, this axis passes through its center of gravity. If the figure has two axes of symmetry, its center of gravity is at their point of intersection.

For notice of copyright, see page immediately following the title page

The *center of gravity of a triangle* lies on a line drawn from a vertex to the middle point of the opposite side, and at a distance from that side equal to one-third of the length of the line; or it is at the intersection of lines drawn from the vertexes to the middle of the opposite sides.

The perpendicular distance of the center of gravity of a triangle from the base is equal to one-third of the altitude.

The *center of gravity of a parallelogram* is at the intersection of its two diagonals; consequently, it is midway between its sides.

The *center of gravity of an irregular four-sided figure* may be found by first dividing it, by a diagonal, into two triangles and joining the centers of gravity of the triangles by a




FIG. 1

straight line; then, by means of the other diagonal, divide the figure into two other triangles, and join their centers of gravity by another straight line; the center of gravity of the figure is at the intersection of the lines joining the centers of gravity of the two sets of triangles.

Another method by which to locate the center of gravity of an irregular four-sided figure is illustrated in Fig. 1. Draw the diagonals *ac* and *bd*, and from their intersection *e*,

measure the distance to any vertex, as *ae*. From the opposite vertex, lay off this distance, as at *cf*. Then from *f*, draw a line to one of the other vertexes, as *fd*, and bisect this line as at *g*. Connect *g* and *b* and lay off one-third of its length from *g* at the point *h*. This point is the center of gravity of the figure.

The distance of the *center of gravity of the surface of a half circle* from the center is equal to the product of the radius multiplied by .424.

THE NEUTRAL AXIS

4. **Explanation of Neutral Axis.**—When a beam is subjected to a bending stress, the fibers on the concave side of the beam are shortened while those on the convex side are lengthened; hence, there is a compressive stress on the concave side of the beam and a tensile stress on the convex side. Therefore, there will be a plane near the center of the beam in which the fibers are neither lengthened nor shortened and in which there is no stress; this plane is termed the **neutral plane**, or **neutral surface**. A cantilever beam, or beam supported at one end, is shown in Fig. 2, having a load W applied at the end. In this case the upper side of the beam is lengthened and the lower side is shortened, while in a simple beam, or one having a support at each end, the reverse is the case. A line dc representing the intersection of the neutral plane $abcd$ with a cross-section of the beam is termed the **neutral axis**. This axis always passes through the center of gravity of the cross-section of the beam until the elastic limit is reached.




FIG. 2

LOCATION OF NEUTRAL AXIS

5. **Mechanical Method.**—It is evident, from Fig. 2, that the neutral axis is perpendicular to the direction in which the load acts on the beam; therefore, to find the neutral axis of a section with reference to a set of loads applied in a given direction, it is only necessary to pass a

line through the center of gravity perpendicular to the direction of the load.

A simple approximate method of locating the center of gravity and neutral axis of a section is shown in Fig. 3. Draw the outline of the section, either full size or to some




FIG. 3

convenient scale, on a piece of heavy cardboard. Cut out the section and balance it carefully over a knife edge, as shown in the figure; the line along which it rests on the edge of the knife is a line passing through the center of gravity, and by locating two such lines in different directions, the center of gravity will be found at their point of intersection.

6. Locating the Neutral Axis by Means of the Principle of Moments.—A convenient method of locating

the neutral axis is based on the principle that the moment of any figure, with respect to a given line as an axis or origin of moments, is equal to the sum of the




FIG. 4

moments of its separate parts with respect to the same axis. The moment of a figure about a given axis is the product of its area by the perpendicular distance from the center of gravity of the figure to the given axis. Thus, in Fig. 4, take

the line ab as the line of origin of moments. Divide the figure into the three rectangles m , m' , m'' . In accordance with the principles stated in Art. 3, the center of gravity of each of these rectangles is midway between its edges; the distances of the respective centers from the axis are, therefore, $1\frac{1}{2}$, 7, and $11\frac{1}{2}$ inches. The areas of the figures are, respectively, 3×3 or 9 square inches, 8×1 or 8 square inches, and 10×1 or 10 square inches. The moments of these areas about the axis ab are:

Section m	$9 \times 1\frac{1}{2}$	=	13.5
Section m'	8×7	=	56.0
Section m''	$10 \times 11\frac{1}{2}$	=	115.0
Total,			<u>184.5</u>

The area of the whole section is equal to $9 + 8 + 10 = 27$ square inches, the sum of the areas of the rectangles; the distance c of its neutral axis from the line of the origin of moments is, therefore, $184.5 \div 27 = 6.83$ inches, or nearly $6\frac{7}{8}$ inches.

It is not necessary that the line of the origin of moments should coincide with an edge of the figure, as in Fig. 4, since any other line parallel with the direction of the required neutral axis gives the same results; in most cases, however, it will be found more convenient to take the axis about which the moments are calculated on one of the extreme edges of the section.

Since the section shown in Fig. 4 is symmetrical with respect to an axis perpendicular to the neutral axis, it is evident that its center of gravity is on their intersection. If, however, there were no axis of symmetry, the center of gravity could have been located by taking a second line perpendicular to ab as an origin of moments and finding the neutral axis parallel to it. The intersection of this neutral axis with the one first found is the center of gravity of the section. In accordance with the principles illustrated in this example, we have the following rule:

Rule.—*To find the neutral axis of any section, first divide it into a number of simple parts, each of whose areas and centers*

the angles. From the same table it is also found that the area of the section of a $4'' \times 4'' \times \frac{1}{2}''$ angle is 3.75 square inches.

The area of the section of the flange plate is $\frac{3}{8} \times 12 = 4.5$ square inches, and of the web-plate, $\frac{3}{8} \times 16 = 6$ square inches; the area of the whole section is, therefore, $2 \times 3.75 + 4.5 + 6 = 18$ square inches.

The moments of the areas of the separate sections, with respect to the line $a b$, are as follows:

Flange plate,	$4.5 \times \frac{3}{16} =$.84
Two angles, $2 \times 3.75 \times 1\frac{1}{8} =$		11.70
Web-plate,	$6 \times 8\frac{3}{8} =$	50.25
Total,		<u>62.79</u>

The distance c from the top edge of the flange plate to the neutral axis $d e$ of the section is, therefore, $62.79 \div 18 = 3.48$ inches.

8. Graphical Method of Locating the Neutral Axis. Let it be required to determine the position of the neutral axis of the cast-iron beam section shown in Fig. 6. First, divide the depth of the section into any number of parts—as has been done in this case by the dotted lines $w' x$, $y z$, etc.—whose areas and centers of gravity can readily be found. Then compute the area and locate the center of gravity of each part. In Fig. 6, the area of the top slice is 12 square inches, the area of each of the slices in the web of the section is 3 square inches, and the area of the bottom flange is 28 square inches. Assume some scale whose unit of length represents 1 square inch; for example, in this case, let $\frac{1}{16}$ inch represent 1 square inch. Then, commencing at some point a , lay off on the line $a l$ lengths $a b$, $b c$, $c f$, etc., which represent the respective areas of the successive parts into which the section of the beam has been divided, beginning at the top part. Thus, with the scale of $\frac{1}{16}$ inch = 1 square inch, the line $a b$, which represents an area of 12 square inches, is $\frac{12}{16} = \frac{3}{4}$ inch long; each of the lines $b c$, $c f$, etc. is $\frac{3}{16}$ inch long; and the line $k l$ is $\frac{28}{16} = 1\frac{7}{4}$ inches long.

From the points a and l , draw lines at any convenient angle

to al intersecting at the point m . Then from the points b, c, f , etc., draw the lines bm, cm, fm , etc. Through the center




FIG. 6

of gravity of each of the parts of the section, draw indefinite lines parallel to al .

From the point n , where the line through the center of gravity of the top section intersects the line am , draw the line no parallel to the line bm until it intersects the line passing through the center of gravity of the second slice in the point o ; draw the line op parallel to cm ; pq parallel to fm ; qr parallel to gm ; rs parallel to hm ; st parallel to im ; tu parallel to jm ; and uv parallel to km .

From the point v , which is the point at the intersection of the line uv with the line drawn through the center of gravity of the last elementary section, draw the line vw parallel to ml ; then its intersection w with the line am is a point on the required neutral axis. If the line am is so short that the line vw fails to cut it, it may be extended indefinitely, as shown at mx' , so as to make it intersect with the line vw . Having found the point w , draw the horizontal line de through it. This line is the required neutral axis of the figure, and passes through its center of gravity.

This method of determining the position of the neutral axis and center of gravity may be applied to any irregular-shaped section, and in many cases may be found more convenient than the mathematical method.

When, as in Fig. 6, the section is made up of several regular parts whose centers of gravity can be readily located, it is not necessary to subdivide any one of these parts. Thus, the center of gravity of the web of the beam is located on the horizontal line through r , and its area is represented by the distance $b k$. We can therefore draw from n a line parallel to bm until it intersects the horizontal line through the center of gravity of the web member; then, from this point, draw a line parallel to km until it intersects the horizontal line through the lower section at the point v . The point v , as thus located, is identical with the point previously found when the web section was divided into the small parts, and the line drawn from v parallel to lm until it intersects am , locates the point w on the neutral axis, as before. If, however, the center of gravity of the web cannot be readily located, it is better to divide it into small parts, as in the first method.

THE MOMENT OF INERTIA

9. The term **moment of inertia** is a mathematical expression that depends on the distribution of either the material of a body or the area of a surface with respect to a given axis. In other words, the moment of inertia is a term that expresses the relative value of all of the infinitely small portions that make up the entire section of a beam or column. The portions of the area farthest from the neutral axis of a section are much more valuable in resisting stress than those portions adjacent to the axis, so that some value must be obtained that will express the efficiency of the entire section to resist transverse stress when compared with any other section. This value is called the moment of inertia. As applied to the area of a plane figure, the moment of inertia, with respect to an axis lying in the same plane, is numerically equal to the sum of the products obtained by multiplying each of the elementary areas of which the figure is composed by the square of its distance from the given axis.

By **elementary area** is meant an area smaller than any with which we are accustomed to deal in ordinary calculations; it is, therefore, impossible to find an exact expression for the moment of inertia of a figure by the methods of calculation in ordinary use. By means of calculus, however, exact formulas have been deduced, by which the moments of inertia of many of the simple geometrical forms, with respect to axes through their centers of gravity, have been found. There are also a number of approximate methods by which the moment of inertia of an irregular section, to which these formulas do not apply, may be found. Further, the moment of inertia of any section that can be divided into parts, the moments of each of which, with respect to an axis through its center of gravity, can be found, is easily calculated by one of the following principles.

COMPUTING THE MOMENT OF INERTIA

10. Analytical Method.—To illustrate a simple approximate method of computing the moment of inertia of a figure, consider the relation of the small I section shown in Fig. 7 to the axis de through its center of gravity. Divide the section




FIG. 7

into a number of little squares (in this case, each with an area of 1 square inch) and consider the distance of each square from the axis to be the distance from the axis to its center of gravity. The products of the area of each square, multiplied by the square of its distance from the axis, are as follows:

$$\text{Squares } a, 1 \times (5\frac{1}{2})^2 = \frac{121}{4}$$

$$\text{Squares } b, 1 \times (4\frac{1}{2})^2 = \frac{81}{4}$$

$$\text{Squares } c, 1 \times (3\frac{1}{2})^2 = \frac{49}{4}$$

$$\text{Squares } d, 1 \times (2\frac{1}{2})^2 = \frac{25}{4}$$

$$\text{Squares } e, 1 \times (1\frac{1}{2})^2 = \frac{9}{4}$$

$$\text{Squares } f, 1 \times (\frac{1}{2})^2 = \frac{1}{4}$$

Adding these products for all the squares, we have:

16 squares a ,	$\frac{121}{4} \times 16$	$= 484$
2 squares b ,	$\frac{81}{4} \times 2$	$= 40\frac{1}{2}$
2 squares c ,	$\frac{49}{4} \times 2$	$= 24\frac{1}{2}$
2 squares d ,	$\frac{25}{4} \times 2$	$= 12\frac{1}{2}$
2 squares e ,	$\frac{9}{4} \times 2$	$= 4\frac{1}{2}$
2 squares f ,	$\frac{1}{4} \times 2$	$= \frac{1}{2}$
Total,		$566\frac{1}{2}$

which is the sum of the products of each of the small areas multiplied by the square of its distance from the axis. This result, however, is only a rough approximation to the moment of inertia, owing to the fact that the assumed areas are so large. The actual value of the moment of inertia of the section, as will be shown subsequently, is $568\frac{1}{2}$.

11. Rules and Formulas for Moments of Inertia. In Table I exact formulas are given for computing the moment of inertia of such regular figures as are most often used in structural design; it also gives approximate formulas for computing this factor for common rolled sections. The tables of properties of rolled sections published by the rolling mills give accurate values of the moment of inertia of all the principal sections used in the construction of buildings, so that it is not generally necessary to make the calculations for these sections; the approximate formulas in Table I are, however, sometimes useful in making calculations when the tables published by the rolling mills are not at hand.

Rule.—*To find the moment of inertia, with respect to any axis of any figure whose moment of inertia, with respect to a parallel axis through its center of gravity, is known, add its moment of inertia, with respect to the axis through its center of gravity, to the product of its area multiplied by the square of the distance from its center of gravity to the required axis.*

This rule may be expressed by the formula

$$I' = I + a x^2 \quad (1)$$

in which I' = required moment of inertia;

I = moment of inertia of the section, with respect to the axis through its center of gravity and parallel to the given axis;

a = area of the figure;

x = distance from its center of gravity to the required axis.

The moment of inertia, with respect to an axis through its center of gravity, of any section that can be divided

into a number of parts, the moments of inertia of each of which, with respect to an axis through its center of gravity parallel to the given axis, is known, is equal to the sum of the moments of inertia of its parts with respect to the given axis. Since the moment of inertia of any figure, with respect to any axis, is expressed by the formula $I' = I + a x^2$, if we denote the sum of the moments of the separate figures making up a section, with respect to an axis through the center of gravity of that section, by $\Sigma I'$ (in which the Greek letter Σ , read *sigma*, means *sum of*), we have

$$I_s = \Sigma I' = \Sigma(I + a x^2) \quad (2)$$

which is a general formula often used to denote the moment of inertia I_s of any built-up section.

12. Graphical Methods of Computing Moments of Inertia.—There are several graphical methods of computing the moment of inertia, one of which is an extension of the graphical method of locating the center of gravity and neutral axis that was described in Art. 8 and illustrated by Fig. 6. Thus, let it be required to determine the moment of inertia, with respect to the axis $d e$, of the beam section shown in Fig. 6. Using the same scale as that to which the section was drawn, compute or measure the area of the figure enclosed by the lines $n o p q . . . v w n$; multiply this area by the area of the section—shown graphically by the length of the line $a l$ —and the product will be the moment of inertia of the section, with respect to the axis $d e$, through its center of gravity. For example, suppose that the section shown in Fig. 6 has been drawn to a scale of $\frac{1}{4}$ inch = 1 inch. Using this scale, and computing the area of the figure enclosed by the lines $n o p q . . . v w n$, we find it to be 43.36 square inches. The area of the section is 61 square inches; therefore, according to the rule, its moment, with respect to the axis $d e$, is $43.36 \times 61 = 2,644.96$.

For finding the moment of inertia, it is necessary to divide the section into a number of parts, for it is evident that the area of the figure enclosed by the lines $n r' v w n$ is considerably less than that of the figure $n o p q . . . v w n$,

obtained by dividing the web into the small sections and drawing the lines of the diagram for each.

The area of the figure $n o p q . . . v w n$ may be computed by extending the horizontal lines through o, p, q , etc., so as to divide it into a series of triangles and trapezoids. The dimensions of these can be readily measured, and their areas can be calculated by means of the principles of mensuration.

This method of computing the moment of inertia will be found convenient in the case of very irregular sections, to which the methods previously given can be applied only with considerable difficulty. The accuracy of the result will, in general, be greater when the section is drawn to a large scale and divided into a comparatively large number of parts.

EXAMPLE 1.—What is the moment of inertia of the section of a $10' \times 16''$ beam about an axis through its center of gravity parallel to its shorter side?

SOLUTION.—From Table I, the formula for the moment of inertia of a solid rectangle is $I = \frac{b d^3}{12}$. Substituting the given dimensions, we have

$$I = \frac{10 \times 16^3}{12} = 3,413\frac{1}{3}. \text{ Ans.}$$

EXAMPLE 2.—Using the formula given in Table I, compute the least moment of inertia of the section of a cast-iron column shown in Fig. 8.




FIG. 8

SOLUTION.—It can readily be seen that the least moment of inertia will be with reference to an axis parallel with the web. Hence, substituting in the formula, we have

$$I = \frac{2 s b^3 + h t^3}{12} \\ = \frac{2 \times 1 \times 8^3 + (8 \times 1^3)}{12} = 86. \text{ Ans.}$$

EXAMPLE 3.—Referring to the rules and formulas in Art. 11, compute the moment of inertia, with respect to the axis dc through its center of gravity, of the section shown in Fig. 7.

SOLUTION.—This section is made up of three rectangles, the moments of inertia of which, with respect to the given axis, can be found by means of formula 1. The moment of inertia of one of the flanges, with respect to an axis through its center of gravity parallel to dc is $I = \frac{8 \times 1^3}{12} = \frac{2}{3}$. The area of this figure is $8 \times 1 = 8$ sq. in.,

and the distance of its center of gravity from de is $5\frac{1}{2}$ in.; therefore, its moment of inertia, with respect to de , is $I' = \frac{8}{3} + 8 \times (5\frac{1}{2})^2 = 242\frac{2}{3}$. The axis through the center of gravity of the web section coincides with the axis de ; hence, the moment of inertia of this section, with respect to de , is

$$I'' = \frac{1 \times 10^3}{12} = 83\frac{1}{3}$$

Then, the moment of inertia I , of the whole section $= \Sigma I' = 242\frac{2}{3} + 242\frac{2}{3} + 83\frac{1}{3} = 568\frac{2}{3}$. Ans.

EXAMPLE 4.—What is the moment of inertia, with respect to the axis de , of the column section shown in Fig. 9?

SOLUTION.—The moment of inertia of one of the flange plates, with respect to an axis through its center of gravity, parallel to the axis de , is $12 \times (\frac{3}{8})^3 = .05$; the area of the

plate is $12 \times \frac{3}{8} = 4.5$ sq. in., and the distance of its center of gravity from the axis is $6\frac{3}{8}$ in. Therefore, the moment of inertia of the plate, with respect to the axis de , is $.05 + 4.5 \times (6\frac{3}{8})^2 = 172.33$. From Table V, the area of a $4'' \times 4'' \times \frac{1}{2}''$ angle

is 3.75 sq. in., and the distance of its center of gravity from the back of a flange is 1.18 in. The distance of the center of gravity of the angle from the axis de , in accordance with the dimensions given in the figure, is $6 - 1.18 = 4.82$ in. In accordance with the formula $\frac{2}{3}(a-c)^3 + ac^2 - \frac{(a-l)(c-l)^2}{3}$ given in Table II, for finding the

moment of inertia of an angle with equal legs, the moment of inertia of the $4'' \times 4'' \times \frac{1}{2}''$ angle, with respect to the axis through its center of gravity, is

$$\frac{.5(4 - 1.18)^3 + 4 \times 1.18^2 - (4 - .5)(1.18 - .5)^2}{3} = 5.54$$

The moment of inertia of the angle, with respect to de , is, therefore, $5.54 + 3.75 \times 4.82^2 = 92.65$. The center of gravity of the web-plate lies on the axis de ; therefore, the moment of inertia of the plate, with respect to de , is $\frac{\frac{3}{8} \times 12^3}{12} = 54$. The moment of inertia of the whole section, with respect to de , is, therefore, $2 \times 172.33 + 4 \times 92.65 + 54 = 769.26$. Ans.




FIG. 9

EXAMPLE 5.—What is the moment of inertia, with respect to the axis de , of the column section shown in Fig. 10?

SOLUTION.—The moment of inertia of one of the cover-plates, with respect to an axis through its center of gravity, parallel to de , is $\frac{12 \times (\frac{1}{2})^3}{12} = .125$;




FIG. 10

the area of the plate is $12 \times \frac{1}{2} = 6$ sq. in., and the distance of its center of gravity from de is $5\frac{1}{2}$ in.; therefore, its moment of inertia, with respect to de , is $I' = .125$

+ $6 \times (5\frac{1}{2})^2 = 165.5$. From Table IV, the area of a 10-in. 15-lb. channel is 4.46 sq. in., and its moment of inertia, with respect to an axis through its center of gravity, corresponding

in this case with the axis de , is 66.9; therefore, the moment of inertia of the whole section, with respect to de , is $2 \times 165.5 + 2 \times 66.9 = 464.8$. Ans.

EXAMPLES FOR PRACTICE

1. What is the moment of inertia of a hollow, square column section 12 inches outside and 10 inches inside? Ans. $894\frac{1}{3}$

2. Find the moment of inertia of a $4'' \times 6'' \times \frac{1}{2}''$ angle, with respect to an axis parallel to its long leg, using the formula given in Table II. Ans. 6.27

3. What is the moment of inertia, with respect to an axis parallel to the web, of a **Z** bar 5 inches in depth, $\frac{1}{2}$ inch thick, and having legs $3\frac{1}{2}$ inches in length? Use the formula given in Table II. Ans. 9.05

SECTION MODULUS

13. The section modulus of a section under transverse stress, or the stress to which a beam is subjected under a load which tends to bend it, is the moment about the neutral axis of such a portion of the section that if its area is multiplied by the extreme fiber stress, the resisting moment of this portion will equal the resisting moment of the variable stress in the actual section, from the neutral axis to the extreme fibers. By the term resisting moment is meant the value which expresses the resistance of the beam to the bending moment produced upon it by the loads which it supports. The resisting moment of any beam section is always equal to the section modulus multiplied by the extreme fiber stress, which is the strength value of










.

ELEMENTS

Sections	Area of Section A	Distance From Neutral Axis to Extremities of Section and c
	a^2	$c = \frac{a}{2}$
	a^2	$c = a$
	$a^2 - a_1^2$	$c = \frac{a}{2}$
	a^2	$c = \frac{a}{\sqrt{2}} = .707 a$
	$b d$	$c = \frac{d}{2}$
	$b d$	$c = d$
	$b d - b_1 d_1$	$c = \frac{d}{2}$
	$b d$	$c = \frac{b d}{\sqrt{b^2 + d^2}}$
	$b d$	$c = \frac{d \cos \alpha + b \sin \alpha}{2}$

SECTIONS

Moment of Inertia I	Section Modulus $S = \frac{I}{c}$	Radius of Gyration $r = \sqrt{\frac{I}{A}}$
$\frac{a^4}{12}$	$\frac{a^3}{6}$	$\frac{a}{\sqrt{12}} = .289 a$
$\frac{a^4}{3}$	$\frac{a^3}{3}$	$\frac{a}{\sqrt{3}} = .577 a$
$\frac{a^4 - a_1^4}{12}$	$\frac{a^3 - a_1^3}{6 a}$	$\sqrt{\frac{a^3 + a_1^3}{12}}$
$\frac{a^4}{12}$	$\frac{a^3}{6 \sqrt{2}} = .118 a^3$	$\frac{a}{\sqrt{12}} = .289 a$
$\frac{b d^3}{12}$	$\frac{b d^3}{6}$	$\frac{d}{\sqrt{12}} = .289 d$
$\frac{b d^3}{3}$	$\frac{b d^3}{3}$	$\frac{d}{\sqrt{3}} = .577 d$
$\frac{b d^3 - b_1 d_1^3}{12}$	$\frac{b d^3 - b_1 d_1^3}{6 d}$	$\sqrt{\frac{b d^3 - b_1 d_1^3}{12 (b d - b_1 d_1)}}$
$\frac{b^3 d^3}{6 (b^3 + d^3)}$	$\frac{b^3 d^3}{6 \sqrt{b^3 + d^3}}$	$\frac{b d}{\sqrt{6 (b^3 + d^3)}}$
$(d^3 \cos^3 a + b^3 \sin^3 a)$	$\frac{b d}{6} \left(\frac{d^3 \cos^3 a + b^3 \sin^3 a}{d \cos a + b \sin a} \right)$	$\sqrt{\frac{d^3 \cos^3 a + b^3 \sin^3 a}{12}}$

Sections	Area of Section A	Distance From Neutral Axis to Extremities of Section c and c_1
	a^2	$c = \frac{a}{2}$
	a^2	$c = a$
	$a^2 - a_1^2$	$c = \frac{a}{2}$
	a^2	$c = \frac{a}{\sqrt{2}} = .707 a$
	$b d$	$c = \frac{d}{2}$
	$b d$	$c = d$
	$b d - b_1 d_1$	$c = \frac{d}{2}$
	$b d$	$c = \frac{b d}{\sqrt{b^2 + d^2}}$
	$b d$	$c = \frac{d \cos \alpha + b \sin \alpha}{2}$

SECTIONS

Moment of Inertia I	Section Modulus $S = \frac{I}{c}$	Radius of Gyration $r = \sqrt{\frac{I}{A}}$
$\frac{a^4}{12}$	$\frac{a^3}{6}$	$\frac{a}{\sqrt{12}} = .289 a$
$\frac{a^4}{3}$	$\frac{a^3}{3}$	$\frac{a}{\sqrt{3}} = .577 a$
$\frac{a^4 - a_1^4}{12}$	$\frac{a^3 - a_1^3}{6 a}$	$\sqrt{\frac{a^4 + a_1^4}{12}}$
$\frac{a^4}{12}$	$\frac{a^3}{6 \sqrt{2}} = .118 a^3$	$\frac{a}{\sqrt{12}} = .289 a$
$\frac{b d^3}{12}$	$\frac{b d^3}{6}$	$\frac{d}{\sqrt{12}} = .289 d$
$\frac{b d^3}{3}$	$\frac{b d^3}{3}$	$\frac{d}{\sqrt{3}} = .577 d$
$\frac{b d^3 - b_1 d_1^3}{12}$	$\frac{b d^3 - b_1 d_1^3}{6 d}$	$\sqrt{\frac{b d^3 - b_1 d_1^3}{12 (b d - b_1 d_1)}}$
$\frac{b^3 d^3}{6 (b^3 + d^3)}$	$\frac{b^3 d^3}{6 \sqrt{b^3 + d^3}}$	$\frac{b d}{\sqrt{6 (b^3 + d^3)}}$
$\frac{d}{6} (d^3 \cos^3 a + b^3 \sin^3 a)$	$\frac{b d}{6} \left(\frac{d^3 \cos^3 a + b^3 \sin^3 a}{d \cos a + b \sin a} \right)$	$\sqrt{\frac{d^3 \cos^3 a + b^3 \sin^3 a}{12}}$



1. The first part of the document is a list of names and addresses.

2. The second part of the document is a list of names and addresses.

3. The third part of the document is a list of names and addresses.

the material of which the section is composed, per square inch of area; and the material is only subjected to this extreme stress at the outside edge of the section.

The value designated as the section modulus is more clearly explained by referring to Fig. 11, in which $ABCD$ shows a section of a rectangular beam. EF represents the neutral axis, which passes through the center of gravity, and GH is a line situated at the edge of the section and represents the position of the extreme fibers. Then $\frac{d}{2}$ is the distance from




FIG. 11

the extreme fibers to the neutral axis. The stress in the fibers on the neutral axis is zero, but it gradually increases until the edge of the section is reached, where it is maximum. Therefore, while the area is uniform, the stress varies with the distance of the fiber from the neutral axis.

Draw the diagonals AC and BD ; the shaded portions ABO and DCO represent the area that, if considered as having a uniform stress equal to the stress in the extreme fibers of the section, offers the same resistance as the entire section having the variable stress. Then the moment of this shaded portion about the neutral axis gives the section modulus of the beam. The combined area of the shaded portions is equal to $\frac{bd}{2}$, and the lever arm, which is the distance from the center of gravity of each section to the neutral axis, is $\frac{d}{3}$. The moment, therefore, is $\frac{bd}{2} \times \frac{d}{3} = \frac{bd^2}{6}$, and the section modulus for a rectangular beam may be expressed by the formula

$$S = \frac{bd^2}{6} \quad (3)$$

in which S = section modulus;

d = depth of beam, in inches;

b = breadth, or width, of beam, in inches.

14. In Fig. 12 is shown the graphical method of obtaining the section modulus for a T bar. The neutral axis is located at AB and the greatest distance from AB to the extreme fiber is c ; from a and b draw lines to the center of gravity of the section o . Below the neutral axis lay off the line CD parallel to the neutral axis AB and at a distance from it equal to c . Project the points d and e to d' and e' and




FIG. 12

from these points draw lines to o ; also project f and g to f' and g' and from these points draw lines to o . Then the shaded portions $hioj$, klm and aob represent areas that, if considered as having a uniform stress equal to that in the extreme fiber, will produce a stress equal to the total resisting stress, which is not uniform in the entire section. The moments of these areas about the neutral axis will give the section modulus of the section.

The same method may be applied to an irregular section, as illustrated in Fig. 13.

In this case the top and bottom edges of the section are equally distant from the neutral axis. Several points are projected from the surface of the section to the lines CD and EF and from these points lines are drawn to the point O on the neutral axis. Where the lines thus drawn intersect the horizontal lines drawn through the points in question, will be located points on the surface of the shaded portion.

The outline of the figure may then be drawn through the points thus located and the section determined. The moment of this section about the neutral axis gives the section




FIG. 13

modulus. In considering an irregular section, it is very necessary to apply the graphical method for determining the section modulus, as it is extremely difficult to evolve a convenient formula for obtaining it.

15. The section modulus for any section whose moment of inertia is known, is found by dividing the moment of inertia by the greatest distance of the neutral axis from the outside fibers of the section. This may be expressed by the formula

$$S = \frac{I}{c} \quad (4)$$

in which I = moment of inertia, with respect to the neutral axis;

S = section modulus;

c = distance from neutral axis to farthest edge of section.

EXAMPLE 1.—What will be the section modulus of a yellow-pine beam, 10 inches wide by 12 inches in depth?

SOLUTION.— $d = 12$ in., $b = 10$ in. Therefore, by applying formula 3, we have

$$S = \frac{b d^3}{6} = \frac{10 \times 12^3}{6} = \frac{1,440}{6} = 240. \text{ Ans.}$$

EXAMPLE 2.—What is the section modulus of the cast-iron lintel shown in Fig. 14?

SOLUTION.—From Table I, we have the formula $S = \frac{I}{d - c_1}$. As it

is necessary to have the area in order to determine the value of c_1 , in the above formula, this will be determined by the formula in the first column, or $A = bs + ht$. Substituting the values, we have $A = 8 \times \frac{3}{4} + 9\frac{1}{4} \times \frac{3}{4} = \frac{207}{16}$. Then substituting in the formula




FIG. 14

$$c_1 = \frac{d^2 t + s^2 (b - t)}{2 A}, \text{ gives}$$

$$c_1 = \frac{10^2 \times \frac{3}{4} + (\frac{3}{4})^2 (8 - \frac{3}{4})}{2 \times \frac{207}{16}} = 3.056 \text{ in.}$$

$$c = d - c_1 = 10 - 3.056 = 6.944 \text{ in.}$$

The moment of inertia is obtained from the formula

$$I = \frac{t c^3 + b c_1^3 - (b - t) (c_1 - s)^3}{3}$$

which gives

$$I = \frac{\frac{3}{4} \times 6.944^3 + 8 \times 3.056^3 - (8 - \frac{3}{4}) (3.056 - \frac{3}{4})^3}{3} = 130.181$$

$$\text{Then, } S = \frac{I}{d - c_1} = \frac{130.181}{6.944} = 18.747. \text{ Ans.}$$

EXAMPLES FOR PRACTICE

1. What is the section modulus of a trapezoidal section whose parallel sides are 6 and 9 inches and the distance between them is 6 inches? Ans. $249\frac{3}{4}$

2. Find the section modulus of a hollow, rectangular, cast-iron lintel that measures 10 inches by 12 inches outside and is $\frac{5}{8}$ inch thick. Ans. 89.026

3. The structural member of a skylight has the section of a cross, the vertical web of which is 5 inches in depth; the cross-bar extends $1\frac{1}{4}$ inches each side of the center line of the vertical bar and the center line of the horizontal bar bisects that of the vertical bar. Provided the thickness of the metal is $\frac{3}{8}$ inch, what will be the section modulus? Ans. 1.566

RADIUS OF GYRATION

16. In computing the strength of columns, frequent use is made of a property of a section that is numerically equal to the square root of the quotient of its moment of inertia, with respect to an axis through its center of gravity, divided by its area. This property is called the **radius of gyration** of the section, with respect to the given axis. It is usually expressed by the letter r , and its value, with respect to a given axis, for any section whose area A and moment of inertia I , with respect to the same axis, are known, is given by the formula

$$r = \sqrt{\frac{I}{A}} \quad (5)$$

The form in which the radius of gyration appears in most formulas for calculating the strength of columns is its square; hence, it is convenient to express the above relation by the formula

$$r^2 = \frac{I}{A} \quad (6)$$

which gives directly the value to be substituted in the column formulas. Formulas for computing the least radius of gyration and its square for the sections most often used in the design of structures, are given in Table I. The tables of the properties of rolled sections also give accurate values of r and r^2 for the sections used in the examples given in the following pages.

EXAMPLE.—Compute the square of the radius of gyration, with respect to the axis de , of the column section shown in Fig. 9.

SOLUTION.—By referring to example 4, Art. 12, the moment of inertia of the section is found to be $I = 737.06$, and the area of the section is $3 \times 4.5 + 4 \times 3.75 = 28.50$ sq. in. Substituting these values in formula 6, we have

$$r^2 = \frac{737.06}{28.50} = 25.86. \quad \text{Ans.}$$

EXAMPLES FOR PRACTICE

1. Find the radius of gyration of a round wooden column having a diameter of 12 inches. Ans. 3
2. What is the square of the least radius of gyration of the column section shown in Fig. 8? Ans. 3.583
3. Compute the radius of gyration of the section of a hollow cast-iron column, 8 inches by 12 inches outside and $\frac{3}{4}$ inch thick. Ans. 4.349

17. The diagram shown in Fig. 15 gives the width of flange, weight in pounds, per foot, and thickness of




FIG. 15

web for beams of the usual depths, these values being for standard beams of minimum weight.




FIG. 16

The following formulas, adopted by the Association of American Steel Manufacturers, are of value in determining the properties of I beams. (See Fig. 16.)

$$\text{Weight per foot} = \text{area} \times 3.4.$$

$$\text{Area} = td + 2s(b - t) + \frac{(b - t)^3}{12}.$$

$$\text{Section modulus} = S = \frac{2I}{d}.$$

$$\text{Slope of flange} = g = \frac{h - t}{b - t} = \frac{1}{6}$$

for standard beams.

I = moment of inertia, neutral axis ($I-I$) parallel to flange.

$I = \frac{1}{12} \left[b d^3 - \frac{1}{4g} (h^4 - l^4) \right]$, or $\frac{b d^3}{12} - \frac{h^4 - l^4}{8}$ for standard beams.

18. Fig. 17 shows the width of flange, thickness of web, and weight per foot for channel beams of the usual depths




FIG. 17

and, as in the diagram for I beams, these values are for channels of minimum weight.

The following formulas are given in connection with Fig. 18.
Weight per foot = area \times 3.4.

$$\text{Area} = t d + 2 s (b - t) + \frac{(b - t)^2}{6}.$$

$$\text{Section modulus} = S = \frac{2I}{d}.$$

$$\text{Slope of flange} = g = \frac{h - l}{2(b - t)}, \text{ or } \frac{1}{8}$$

for standard channels.

I = moment of inertia, neutral axis (1-1) parallel to flange.

$$I = \frac{1}{12} \left[b d^3 - \frac{1}{8g} (h^4 - l^4) \right], \text{ or } \frac{b d^3}{12} - \frac{h^4 - l^4}{16} \text{ for standard channels.}$$




FIG. 18

19. Table I gives formulas for computing the area, moment of inertia, section modulus, and radius of gyration of usual sections, also the distance from the neutral axis to the extremities of the section. These formulas are useful in obtaining the properties of sections that are not given in the table of properties for the several standard rolled sections.

20. Table II gives formulas for the moment of inertia of the standard rolled sections with respect to their different

axes, also the distance from the neutral axis to the back of the section; where a third axis is considered it gives the angle between the third axis and the vertical one.

The slope of the flanges of the I beams and channels is $\frac{1}{6}$, that is, $\frac{h-l}{b-t} = \frac{1}{6}$. In the formulas relating to the deck beam, e represents the area of the head.

21. Tables III to IX give the dimensions and properties of structural-steel shapes that conform to the American standards, adopted January, 1896. Such tables are found in most of the handbooks published by the different steel manufacturers. The first five columns give the dimensions, area, and weight of the section considered, and as all these sections are of structural steel, there is a fixed relation between the weight and area and one may be obtained from the other. The weight of 1 square inch of structural steel 1 foot long is 3.4 pounds; hence, the weight of 1 foot of any section is equal to its sectional area multiplied by 3.4, as stated in Arts. 17 and 18, in connection with the weight of I beams and channels.

The values for the section modulus, radius of gyration, and moment of inertia are required in finding the strength of the section under different conditions, and are used in calculating the strength of beams, girders, columns, and posts. The moment of inertia is particularly valuable because the section modulus and radius of gyration may be obtained from it, as explained in Arts. 15 and 16.

The uses of the coefficients of strength and coefficients of deflection are illustrated in the examples given in Art. 22.

The values in the columns headed F and F' are the safe uniformly distributed loads, in pounds, including the weight of the beam, for a beam 1 foot long; they have been computed for fiber stresses of 16,000 and 12,500 pounds per square inch, respectively. Hence, the safe load for any span is equal to the coefficient F or F' divided by the span, in feet.

The formulas from which these coefficients were obtained are $F = \frac{2}{3} \times 16,000 \times S$ and $F' = \frac{2}{3} \times 12,500 \times S$, in which S is the section modulus.

The values for N and N' , the coefficients of deflection for uniform and center loads, respectively, were obtained from the formulas $N = \frac{Wl^3}{76.8EI}$ and $N' = \frac{Wl^3}{48EI}$, in which W equals 1,000 pounds, l equals 12 inches, E equals 29,000,000; and I equals the moment of inertia about the axis 1-1. Therefore, these coefficients represent the deflection, in inches, of a beam 1 foot long having a load of 1,000 pounds. Multiplying the proper coefficient by the cube of the span, in feet, and by the number of 1,000-pound units in the given load, will give the deflection of a beam for any load and span.

Tables XI, XII, and XIII are useful in calculating the strength of these built-up sections when they are used as posts or struts in structural work. The angles given in these tables are not all standard, but the standard sections may be selected by referring to Tables V and VI.

22. The following examples illustrate the application of the tables giving the values for the properties of the several rolled sections.

In making the selection of the beams from the tables, it is customary to select the deepest beam having the least weight and the greatest section modulus. For instance, if a beam is required to have a section modulus of 30, and from the table it is observed that a 10-inch 40-pound beam has a section modulus of 31.7 and that a 12-inch 31.5-pound beam has a section modulus of 36, it is evident that it would be more economical to select the deeper, and consequently, the safer beam, thus saving a weight of 5 pounds per foot. As steel beams are sold usually by the pound price, such a saving would be great in a large order. This economical practice should always be employed when the several additional inches in the depth of the beam will not interfere with the required headroom in the architectural design.

EXAMPLE 1.—What is the deflection of a 20-inch 65-pound I beam that carries a center load of 28,000 pounds and has a span of 20 feet?

SOLUTION.—The amount of deflection is obtained by multiplying the coefficient of deflection for beams with center loads (column 15,

Table III) by the cube of the span, in feet, and the number of 1,000-lb. units in the load. Hence, the deflection equals

$$.00000106 \times 20^3 \times \frac{28,000}{1,000} = .237 \text{ in. Ans.}$$

EXAMPLE 2.—What size of I beam is required to support a uniform load of 800 pounds per foot over a span of 25 feet, considering a safe unit fiber stress of 16,000 pounds?

SOLUTION.—According to Art. 21, the safe uniformly distributed load for any span is equal to the coefficient F or F' divided by the span, in feet. By transposing the terms of the equation it is found that F or $F' = \text{load} \times \text{span}$. The coefficient required for the load in this case is $800 \times 25 \times 25 = 500,000$. From column 12, Table III, the coefficient of strength for a 15-in. 42-lb. beam is found to be 628,270. The weight of the beam is $42 \times 25 = 1,050$ lb., which requires a coefficient of $1,050 \times 25 = 26,250$; then $628,270 - 26,250$ gives a net coefficient of 602,020. Therefore, a 15-in. 42-lb. beam is the size required. If the load on the beam is concentrated at the center, the coefficient of strength required is twice as great. Ans.

EXAMPLE 3.—Two channels, placed back to back with webs vertical, form the support of an overhead mechanism for an elevator. The load is concentrated at the center of the channels and is equal to 10,000 pounds; provided the span of the channels is 8 feet and they are 7 inches in depth and weigh 14.75 pounds per foot, what will be the deflection?

SOLUTION.—The deflection is equal to the coefficient multiplied by the cube of the span and the number of 1,000-lb. units in the load. From column N' , Table IV, the coefficient of deflection for a 7-in. 14.75-lb. channel is .0000457. As there are two channels, each may be considered as supporting one-half of the load or 5,000 lb. Then the deflection will be equal to

$$.0000457 \times 8^3 \times \frac{5,000}{1,000} = .117 \text{ in. Ans.}$$

EXAMPLE 4.—What is the section modulus of a rectangular bar 3 inches by $\frac{3}{4}$ inch, using the moment of inertia obtained from Table X?

SOLUTION.—The section modulus is determined by the formula $S = \frac{I}{c}$, given in Art. 15, and from the table the moment of inertia is found to be 1.69. The neutral axis passes through the center of the rectangle and consequently the distance c is equal to $1\frac{1}{2}$ in. Substituting these values in the formula,

$$S = \frac{1.69}{1.5} = 1.127. \text{ Ans.}$$

EXAMPLES FOR PRACTICE

1. Two channels, placed back to back, are to be used to support a uniform load of 1,000 pounds per lineal foot over a span of 20 feet. Using a safe unit fiber stress of 16,000 pounds, what size channels will be the most economical for the purpose?

Ans. Two 12-in. 20½-lb. channels

2. What would be the deflection in the previous example?

Ans. .488 in.

3. What size of I beam should be used to support a center load of 10,000 pounds over a span of 12 feet, using a safe unit fiber stress of 16,000 pounds?

Ans. 10-in. 25-lb. I beam


4. An I beam to support a given load is required to have a section modulus of 30; what would be the size and weight of the most economical section?

Ans. 12-in. 31½-lb. I beam

5. From the fact that the available headroom is limited, it is necessary to use several 8-inch I beams placed side by side in order to support a uniformly distributed load of 20,000 pounds. The span of the beams is 20 feet. How many beams weighing 25.25 pounds are required to support this load, provided the allowable deflection is 1 inch, and a safe unit fiber stress of 16,000 pounds is used?

Ans. Three beams

TABLE III
PROPERTIES OF STANDARD I BEAMS



Depth of Beam Inches	Weight per Foot Pounds	Area of Section Square Inches	Thickness of Web Inches	Width of Flange Inches	Moment of Inertia, Axis 1-1 Inches	Section Modulus, Axis 1-1 Inches	Radius of Gyration, Axis 1-1 Inches	Radius of Gyration, Axis 2-2 Inches	Increase of Thick- ness of Web for Each Pound Increase in Weight, Inches	Coefficient of Strength	Coefficient of Deflection	Center Load
										For Fiber Stress of 16,000 Pounds per Square Inch for Buildings	Uniform Load	
										For Fiber Stress of 12,500 Pounds per Square Inch for Bridges		
2	5.50	1.63	.17	2.33	2.5	1.7	1.23	53	.098	17,650	.00031553	.00050006
3	6.50	1.91	.26	2.42	2.7	1.8	1.19	52		19,140	.00036827	.00046124
3	7.50	2.21	.30	2.52	2.9	1.9	1.15	52		20,710	.00036644	.00042630
4	7.50	2.21	.19	3.66	6.0	3.0	1.64	50	.074	24,830	.00013009	.00020815
4	8.50	2.50	.26	2.73	6.4	3.2	1.59	58		26,460	.00012209	.00019315
4	9.50	2.79	.34	2.81	6.7	3.4	1.54	58		28,110	.00011500	.00016400
4	10.50	3.09	.41	2.88	7.1	3.6	1.52	57		29,750	.00010868	.00017386
5	9.75	2.87	.21	3.00	12.1	4.8	2.05	46	.059	51,590	.00006417	.00010267
5	12.25	3.60	.16	3.15	13.6	5.4	1.94	43		58,100	.00005698	.00009117
5	14.75	4.34	.50	3.29	15.1	6.1	1.87	40		64,630	.00005122	.00008158
6	15.25	4.66	.55	3.43	16.6	6.8	1.80	38		71,160	.00004647	.00007348

7	15.00	4.42	.25	3.66	35.2	10.4	2.96	2.67	.78	.042	110.410	86.260	.00002142	.00001427
7	17.50	5.15	.35	3.76	39.2	11.2	2.76	2.94	.76		119.400	93.290	.00001980	.00001168
7	20.00	5.88	.46	3.87	42.2	12.1	2.63	3.24	.74		128.560	100.430	.00001839	.00001943
8	18.00	5.33	.27	4.00	56.9	14.2	3.27	3.78	.84	.037	151.660	118.490	.00001364	.00002183
8	20.25	5.96	.35	4.08	60.2	15.0	3.18	4.04	.82		160.510	125.400	.00001289	.00002062
8	22.75	6.69	.44	4.17	64.1	16.0	3.10	4.36	.81		170.970	133.570	.00001210	.00001936
8	25.25	7.43	.53	4.26	63.0	17.0	3.03	4.71	.80		181.430	141.740	.00001140	.00001825
9	21.00	6.31	.29	4.33	84.9	18.9	3.67	5.16	.90	.033	201.300	157.260	.00000914	.00001462
9	25.00	7.35	.41	4.45	91.9	20.4	3.54	5.65	.88		217.930	170.260	.00000844	.00001350
9	30.00	8.82	.57	4.61	101.9	22.6	3.40	6.42	.85		241.460	188.640	.00000762	.00001219
9	35.00	10.29	.73	4.77	111.8	24.8	3.30	7.31	.84		264.990	207.020	.00000694	.00001110
10	25.00	7.37	.31	4.66	122.1	24.4	4.07	6.89	.97	.029	260.470	203.500	.00000635	.00001017
10	30.00	8.82	.45	4.80	134.2	26.8	3.90	7.65	.93		286.250	223.630	.00000578	.00000925
10	35.00	10.29	.60	4.95	146.4	29.3	3.77	8.52	.91		312.390	244.050	.00000530	.00000848
10	40.00	11.76	.75	5.10	153.7	31.7	3.67	9.50	.90		338.530	264.480	.00000489	.00000782
12	31.50	9.26	.35	5.00	215.8	36.0	4.83	9.50	1.01	.025	383.670	299.740	.00000360	.00000575
12	35.00	10.29	.44	5.09	223.3	38.0	4.71	10.07	.99		405.800	317.030	.00000340	.00000544
12	40.00	11.76	.56	5.21	245.9	41.0	4.57	10.95	.96		437.170	341.540	.00000316	.00000505
15	42.00	12.48	.41	5.50	441.8	58.9	5.95	14.62	1.08	.020	628.270	490.840	.00000176	.00000281
15	45.00	13.24	.46	5.55	455.8	60.8	5.87	15.09	1.07		648.310	506.490	.00000170	.00000272
15	50.00	14.71	.56	5.65	433.4	64.5	5.73	16.04	1.04		687.530	537.130	.00000161	.00000257
15	55.00	16.18	.66	5.75	511.0	68.1	5.62	17.06	1.03		726.740	567.770	.00000152	.00000243
15	60.00	17.65	.76	5.84	538.6	71.8	5.52	18.17	1.01		765.960	598.410	.00000144	.00000231
18	55.00	15.93	.46	6.00	705.6	88.4	7.07	21.19	1.15	.016	942.880	736.620	.00000098	.00000156
18	60.00	17.65	.56	6.10	841.8	93.5	6.91	22.38	1.13		997.680	779.440	.00000092	.00000148
18	65.00	19.12	.64	6.18	831.5	97.9	6.79	23.47	1.11		1,044.740	816.200	.00000088	.00000141
18	70.00	20.59	.72	6.26	921.2	102.4	6.69	24.62	1.09		1,091.800	852.970	.00000084	.00000135
20	65.00	19.08	.50	6.25	1,160.5	117.0	7.83	27.86	1.21	.015	1,247.490	974.600	.00000066	.00000106
20	70.00	20.59	.58	6.33	1,210.8	122.0	7.70	29.04	1.19		1,301.110	1,016.490	.00000064	.00000102
20	75.00	22.06	.65	6.40	1,268.8	126.9	7.58	30.25	1.17		1,353.400	1,057.340	.00000061	.00000098
24	80.00	23.32	.50	7.00	2,087.2	173.9	9.46	42.86	1.36	.0123	1,855.310	1,449.460	.00000037	.00000060
24	85.00	25.00	.57	7.07	2,167.8	180.7	9.31	44.35	1.33		1,926.950	1,505.430	.00000036	.00000057
24	90.00	26.47	.63	7.13	2,238.4	186.5	9.20	45.70	1.31		1,989.700	1,554.450	.00000035	.00000056
24	95.00	27.94	.69	7.19	2,300.0	192.4	9.09	47.10	1.30		2,052.440	1,603.470	.00000034	.00000054
24	100.00	29.41	.75	7.25	2,379.6	198.3	8.99	48.55	1.28		2,115.190	1,652.490	.00000033	.00000052

TABLE IV
PROPERTIES OF STANDARD CHANNELS



1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17
Depth of Channel Inches	Weight per Foot Pounds	Area of Section Square Inches	Thickness of Web Inches	Width of Flange Inches	Moment of Inertia, Axis 1-1 Inches	Section Modulus, Axis 1-1 Inches	Radius of Gyration, Axis 1-1 Inches	Moment of Inertia, Axis 2-2 Inches	Section Modulus, Axis 2-2 Inches	Radius of Gyration, Axis 2-2 Inches	Distance of Center of Gravity from Outside of Web Inches	Increase of Thick- ness of Web for Each Pound Increase in Weight Inches	Coefficient of Strength For Fiber Stress of 16,000 Pounds per Square Inch for Buildings	Coefficient of Strength For Fiber Stress of 12,500 Pounds per Square Inch for Bridges	Uniform Load	Center Load
p		A	t	b	I	S	r	I	S	r'	x	i	F	F'	N	N'
3	4.00	1.19	.17	1.47	1.6	1.1	1.17	20	.21	.41	.44	.008	11,630	9,090	.0004743	.000589
3	5.00	1.47	.20	1.50	1.8	1.2	1.12	25	.24	.41	.44		13,140	10,270	.0004199	.000518
3	6.00	1.76	.25	1.60	2.1	1.4	1.08	31	.27	.42	.46		14,710	11,490	.0003751	.0004601
4	5.25	1.85	.18	1.58	3.8	1.9	1.56	32	.20	.45	.46	.074	20,230	15,800	.0002046	.0003173
4	6.25	1.84	.25	1.65	4.2	2.1	1.51	36	.22	.45	.46		22,270	17,400	.0001858	.0002993
4	7.25	2.13	.23	1.73	4.6	2.3	1.46	44	.25	.46	.46		24,360	19,030	.0001698	.0002717
5	6.50	1.95	.19	1.75	7.4	3.0	1.95	48	.28	.50	.40	.080	31,640	24,720	.0001046	.0001694
5	9.00	2.58	.22	1.80	8.9	3.5	1.83	64	.45	.40	.48		37,900	29,570	.0000875	.0001399
5	11.50	3.38	.28	2.04	10.4	4.2	1.75	82	.54	.40	.51		44,390	34,660	.0000740	.0001193

6	8.00	2.38	.20	1.92	13.0	4.3	2.34	.70	.50	.54	.52	.049	46.210	36.100	.0000597	.0000855
6	10.50	3.09	.32	2.04	15.1	5.0	2.21	.88	.57	.53	.50		53.750	42.000	.0000513	.0000821
6	13.00	3.82	.44	2.16	17.3	5.8	2.13	1.07	.65	.53	.52		61.600	48.120	.0000448	.0000717
6	15.50	4.56	.56	2.28	19.5	6.5	2.07	1.28	.74	.53	.55		69.440	54.250	.0000397	.0000636
7	9.75	2.85	.21	2.09	21.1	6.0	2.72	.98	.63	.59	.55	.042	64.270	50.210	.0000368	.0000588
7	12.25	3.60	.32	2.20	24.2	6.9	2.59	1.19	.71	.57	.53		73.650	57.540	.0000321	.0000514
7	14.75	4.34	.42	2.30	27.2	7.8	2.50	1.40	.79	.57	.53		82.740	64.690	.0000286	.0000457
7	17.25	5.07	.53	2.41	30.2	8.6	2.44	1.62	.87	.56	.55		91.950	71.840	.0000257	.0000411
7	19.75	5.81	.63	2.51	33.2	9.5	2.39	1.85	.96	.56	.58		101.100	78.990	.0000234	.0000374
8	11.25	3.35	.22	2.26	32.3	8.1	3.10	1.33	.79	.63	.58	.037	86.140	67.300	.0000240	.0000384
8	13.75	4.04	.31	2.35	36.0	9.0	2.98	1.55	.87	.62	.56		95.990	75.000	.0000216	.0000345
8	16.25	4.78	.40	2.44	39.9	10.0	2.89	1.78	.95	.61	.56		106.450	83.170	.0000194	.0000311
8	18.75	5.51	.49	2.53	43.8	11.0	2.82	2.01	1.02	.60	.57		116.910	91.340	.0000177	.0000283
8	21.25	6.25	.58	2.62	47.8	11.9	2.76	2.25	1.11	.60	.59		127.370	99.510	.0000162	.0000260
9	13.25	3.89	.23	2.43	47.3	10.5	3.49	1.77	.97	.67	.61	.033	112.170	87.630	.0000164	.0000262
9	15.00	4.41	.29	2.49	50.9	11.3	3.40	1.95	1.03	.66	.59		120.540	94.170	.0000153	.0000244
9	20.00	5.88	.45	2.65	60.8	13.5	3.21	2.45	1.19	.65	.58		144.070	112.550	.0000128	.0000204
9	25.00	7.35	.61	2.81	70.7	15.7	3.10	2.98	1.36	.64	.62		167.590	130.930	.0000110	.0000176
10	15.00	4.46	.24	2.60	66.9	13.4	3.87	2.30	1.17	.72	.64	.029	142.680	111.470	.0000116	.0000186
10	20.00	5.88	.38	2.74	78.7	15.7	3.66	2.85	1.34	.70	.61		167.940	131.210	.0000099	.0000158
10	25.00	7.35	.53	2.89	91.0	18.2	3.52	3.40	1.50	.68	.62		194.090	151.630	.0000085	.0000136
10	30.00	8.82	.68	3.04	103.2	20.6	3.42	3.99	1.67	.67	.65		220.230	172.060	.0000075	.0000120
10	35.00	10.29	.82	3.18	115.5	23.1	3.35	4.66	1.87	.67	.69		246.380	192.480	.0000067	.0000107
12	20.50	6.03	.28	2.94	128.1	21.4	4.61	3.91	1.75	.81	.70	.025	227.750	177.930	.0000061	.0000097
12	25.00	7.35	.39	3.05	144.0	24.0	4.43	4.53	1.91	.78	.68		256.000	200.000	.0000054	.0000086
12	30.00	8.82	.51	3.17	161.6	26.9	4.28	5.21	2.09	.77	.68		287.370	224.510	.0000048	.0000077
12	35.00	10.29	.64	3.30	179.3	29.9	4.17	5.90	2.27	.76	.69		318.750	249.020	.0000043	.0000069
12	40.00	11.76	.76	3.42	196.9	32.8	4.09	6.63	2.46	.75	.72		350.120	273.530	.0000039	.0000063
15	33.00	9.90	.40	3.40	312.6	41.7	5.62	8.23	3.16	.91	.79	.020	444.520	347.280	.0000025	.0000040
15	35.00	10.29	.43	3.43	319.9	42.7	5.57	8.48	3.22	.91	.79		455.030	355.500	.0000024	.0000039
15	40.00	11.76	.52	3.52	347.5	46.3	5.44	9.39	3.43	.89	.78		494.250	386.130	.0000022	.0000036
15	45.00	13.24	.62	3.62	375.1	50.0	5.32	10.29	3.63	.88	.79		533.470	416.770	.0000021	.0000033
15	50.00	14.71	.72	3.72	402.7	53.7	5.23	11.22	3.85	.87	.80		572.680	447.410	.0000019	.0000031
15	55.00	16.18	.82	3.82	430.2	57.4	5.16	12.19	4.07	.87	.82		611.900	478.050	.0000018	.0000029

TABLE V
PROPERTIES OF STANDARD ANGLES HAVING EQUAL LE



1	2	3	4	5	6	7	8	9	10	11	12
Dimensions Inches	Thickness Inches	Weight per Foot Pounds	Area of Section Square Inches	Distance of Center of Gravity From Back of Flange Inches	Moment of Inertia, Axis $I-I'$ Inches	Section Modulus, Axis $I-I'$ Inches	Radius of Gyration, Axis $I-I'$ Inches	Distance of Center of Gravity From External Apex, Inches	Least Moment of Gyration, Axis $X-X'$ Inches	Section Modulus, Axis $X-X'$ Inches	Least Radius of Gyration, Axis $X-X'$ Inches
$a \times a$	t		A	\bar{x}	I	S	r	x'	I'	S'	r'
1/8 x 1/8	1/8	.58	.17	.23	.009	.617	.22	.33	.004	.011	.004
1/4 x 1/4	1/4	.84	.25	.25	.012	.624	.22	.36	.005	.014	.005
3/8 x 3/8	3/8	1.16	.34	.32	.022	.631	.30	.42	.009	.021	.009
1/2 x 1/2	1/2	1.49	.44	.34	.037	.644	.30	.48	.016	.034	.016
5/8 x 5/8	5/8	1.82	.56	.36	.044	.649	.38	.51	.018	.035	.018
3/4 x 3/4	3/4	2.15	.68	.38	.061	.671	.38	.54	.025	.047	.025
7/8 x 7/8	7/8	2.48	.80	.40	.077	.691	.37	.57	.033	.057	.033
1 x 1	1	2.81	.92	.42	.090	.709	.36	.60	.040	.066	.040
1 1/8 x 1 1/8	1 1/8	3.14	1.04	.44	.108	.722	.47	.63	.051	.083	.051
1 1/4 x 1 1/4	1 1/4	3.47	1.16	.46	.111	.704	.46	.63	.045	.072	.045
1 3/8 x 1 3/8	1 3/8	3.80	1.28	.47	.124	.714	.45	.66	.058	.088	.058
1 1/2 x 1 1/2	1 1/2	4.13	1.40	.49	.136	.722	.44	.69	.070	.101	.070
1 3/4 x 1 3/4	1 3/4	4.46	1.52	.51	.149	.728	.44	.72	.082	.114	.082
2 x 2	2	4.79	1.64	.53	.161	.734	.43	.75	.094	.126	.094
2 1/8 x 2 1/8	2 1/8	5.12	1.76	.55	.174	.740	.42	.78	.106	.138	.106
2 1/4 x 2 1/4	2 1/4	5.45	1.88	.57	.187	.746	.41	.81	.118	.150	.118
2 3/8 x 2 3/8	2 3/8	5.78	2.00	.59	.199	.752	.40	.84	.130	.162	.130
2 1/2 x 2 1/2	2 1/2	6.11	2.12	.61	.212	.758	.39	.87	.142	.174	.142
2 7/8 x 2 7/8	2 7/8	6.44	2.24	.63	.224	.764	.38	.90	.154	.186	.154
3 x 3	3	6.77	2.36	.65	.236	.770	.37	.93	.166	.198	.166
3 1/8 x 3 1/8	3 1/8	7.10	2.48	.67	.248	.776	.36	.96	.178	.210	.178
3 1/4 x 3 1/4	3 1/4	7.43	2.60	.69	.260	.782	.35	.99	.190	.222	.190
3 3/8 x 3 3/8	3 3/8	7.76	2.72	.71	.272	.788	.34	.102	.202	.234	.202
3 1/2 x 3 1/2	3 1/2	8.09	2.84	.73	.284	.794	.33	.105	.214	.246	.214
3 7/8 x 3 7/8	3 7/8	8.42	2.96	.75	.296	.800	.32	.108	.226	.258	.226
4 x 4	4	8.75	3.08	.77	.308	.806	.31	.111	.238	.270	.238
4 1/8 x 4 1/8	4 1/8	9.08	3.20	.79	.320	.812	.30	.114	.250	.282	.250
4 1/4 x 4 1/4	4 1/4	9.41	3.32	.81	.332	.818	.29	.117	.262	.294	.262
4 3/8 x 4 3/8	4 3/8	9.74	3.44	.83	.344	.824	.28	.120	.274	.306	.274
4 1/2 x 4 1/2	4 1/2	10.07	3.56	.85	.356	.830	.27	.123	.286	.318	.286
4 7/8 x 4 7/8	4 7/8	10.40	3.68	.87	.368	.836	.26	.126	.298	.330	.298
5 x 5	5	10.73	3.80	.89	.380	.842	.25	.129	.310	.342	.310
5 1/8 x 5 1/8	5 1/8	11.06	3.92	.91	.392	.848	.24	.132	.322	.354	.322
5 1/4 x 5 1/4	5 1/4	11.39	4.04	.93	.404	.854	.23	.135	.334	.366	.334
5 3/8 x 5 3/8	5 3/8	11.72	4.16	.95	.416	.860	.22	.138	.346	.378	.346
5 1/2 x 5 1/2	5 1/2	12.05	4.28	.97	.428	.866	.21	.141	.358	.390	.358
5 7/8 x 5 7/8	5 7/8	12.38	4.40	.99	.440	.872	.20	.144	.370	.402	.370
6 x 6	6	12.71	4.52	.101	.452	.878	.19	.147	.382	.414	.382
6 1/8 x 6 1/8	6 1/8	13.04	4.64	.103	.464	.884	.18	.150	.394	.426	.394
6 1/4 x 6 1/4	6 1/4	13.37	4.76	.105	.476	.890	.17	.153	.406	.438	.406
6 3/8 x 6 3/8	6 3/8	13.70	4.88	.107	.488	.896	.16	.156	.418	.450	.418
6 1/2 x 6 1/2	6 1/2	14.03	5.00	.109	.500	.902	.15	.159	.430	.462	.430
6 7/8 x 6 7/8	6 7/8	14.36	5.12	.111	.512	.908	.14	.162	.442	.474	.442
7 x 7	7	14.69	5.24	.113	.524	.914	.13	.165	.454	.486	.454
7 1/8 x 7 1/8	7 1/8	15.02	5.36	.115	.536	.920	.12	.168	.466	.498	.466
7 1/4 x 7 1/4	7 1/4	15.35	5.48	.117	.548	.926	.11	.171	.478	.510	.478
7 3/8 x 7 3/8	7 3/8	15.68	5.60	.119	.560	.932	.10	.174	.490	.522	.490
7 1/2 x 7 1/2	7 1/2	16.01	5.72	.121	.572	.938	.09	.177	.502	.534	.502
7 7/8 x 7 7/8	7 7/8	16.34	5.84	.123	.584	.944	.08	.180	.514	.546	.514
8 x 8	8	16.67	5.96	.125	.596	.950	.07	.183	.526	.558	.526

TABLE V—(Continued)
PROPERTIES OF STANDARD ANGLES HAVING EQUAL LEGS



1	2	3	4	5	6	7	8	9	10	11	12
Dimensions Inches	Thickness Inches	Weight per Foot Pounds	Area of Section Square Inches	Distance of Center of Gravity From Back of Flange Inches	Moment of Inertia, Axis 1-1 Inches	Section Modulus, Axis 1-1 Inches	Radius of Gyration, Axis 1-1 Inches	Distance of Center of Gravity From External Apex Inches	Least Moment of Gyration, Axis 2-2 Inches	Section Modulus, Axis 2-2 Inches	Least Radius of Gyration, Axis 2-2 Inches
1	.125	4.9	1.44	.84	1.24	.58	.93	1.19	.50	.42	.59
1.25	.156	5.0	1.78	.87	1.51	.71	.92	1.22	.61	.50	.59
1.5	.188	7.2	2.11	.89	1.76	.83	.91	1.26	.72	.57	.58
1.75	.219	8.3	2.43	.91	1.99	.95	.91	1.29	.82	.64	.58
2	.25	9.4	2.75	.93	2.22	1.07	.90	1.32	.92	.70	.58
2.25	.281	10.4	3.06	.95	2.43	1.19	.89	1.35	1.02	.76	.58
2.5	.312	11.4	3.36	.98	2.62	1.30	.88	1.38	1.12	.81	.58
2.75	.344	12.4	3.65	1.00	2.81	1.40	.88	1.41	1.22	.88	.58
3	.375	13.4	3.94	1.02	3.00	1.50	.87	1.44	1.32	.95	.58
3.25	.406	14.4	4.23	1.04	3.19	1.60	.86	1.47	1.42	1.02	.58
3.5	.438	15.4	4.52	1.06	3.38	1.70	.85	1.50	1.52	1.10	.58
3.75	.469	16.4	4.81	1.08	3.57	1.80	.84	1.53	1.62	1.18	.58
4	.5	17.4	5.10	1.10	3.76	1.90	.83	1.56	1.72	1.26	.58
4.25	.531	18.4	5.39	1.12	3.95	2.00	.82	1.59	1.82	1.34	.58
4.5	.562	19.4	5.68	1.14	4.14	2.10	.81	1.62	1.92	1.42	.58
4.75	.594	20.4	5.97	1.16	4.33	2.20	.80	1.65	2.02	1.50	.58
5	.625	21.4	6.26	1.18	4.52	2.30	.79	1.68	2.12	1.58	.58
5.25	.656	22.4	6.55	1.20	4.71	2.40	.78	1.71	2.22	1.66	.58
5.5	.688	23.4	6.84	1.22	4.90	2.50	.77	1.74	2.32	1.74	.58
5.75	.719	24.4	7.13	1.24	5.09	2.60	.76	1.77	2.42	1.82	.58
6	.75	25.4	7.42	1.26	5.28	2.70	.75	1.80	2.52	1.90	.58
6.25	.781	26.4	7.71	1.28	5.47	2.80	.74	1.83	2.62	1.98	.58
6.5	.812	27.4	8.00	1.30	5.66	2.90	.73	1.86	2.72	2.06	.58
6.75	.844	28.4	8.29	1.32	5.85	3.00	.72	1.89	2.82	2.14	.58
7	.875	29.4	8.58	1.34	6.04	3.10	.71	1.92	2.92	2.22	.58
7.25	.906	30.4	8.87	1.36	6.23	3.20	.70	1.95	3.02	2.30	.58
7.5	.938	31.4	9.16	1.38	6.42	3.30	.69	1.98	3.12	2.38	.58
7.75	.969	32.4	9.45	1.40	6.61	3.40	.68	2.01	3.22	2.46	.58
8	1.0	33.4	9.74	1.42	6.80	3.50	.67	2.04	3.32	2.54	.58
8.25	1.031	34.4	10.03	1.44	6.99	3.60	.66	2.07	3.42	2.62	.58
8.5	1.062	35.4	10.32	1.46	7.18	3.70	.65	2.10	3.52	2.70	.58
8.75	1.094	36.4	10.61	1.48	7.37	3.80	.64	2.13	3.62	2.78	.58
9	1.125	37.4	10.90	1.50	7.56	3.90	.63	2.16	3.72	2.86	.58
9.25	1.156	38.4	11.19	1.52	7.75	4.00	.62	2.19	3.82	2.94	.58
9.5	1.188	39.4	11.48	1.54	7.94	4.10	.61	2.22	3.92	3.02	.58
9.75	1.219	40.4	11.77	1.56	8.13	4.20	.60	2.25	4.02	3.10	.58
10	1.25	41.4	12.06	1.58	8.32	4.30	.59	2.28	4.12	3.18	.58
10.25	1.281	42.4	12.35	1.60	8.51	4.40	.58	2.31	4.22	3.26	.58
10.5	1.312	43.4	12.64	1.62	8.70	4.50	.57	2.34	4.32	3.34	.58
10.75	1.344	44.4	12.93	1.64	8.89	4.60	.56	2.37	4.42	3.42	.58
11	1.375	45.4	13.22	1.66	9.08	4.70	.55	2.40	4.52	3.50	.58
11.25	1.406	46.4	13.51	1.68	9.27	4.80	.54	2.43	4.62	3.58	.58
11.5	1.438	47.4	13.80	1.70	9.46	4.90	.53	2.46	4.72	3.66	.58
11.75	1.469	48.4	14.09	1.72	9.65	5.00	.52	2.49	4.82	3.74	.58
12	1.5	49.4	14.38	1.74	9.84	5.10	.51	2.52	4.92	3.82	.58
12.25	1.531	50.4	14.67	1.76	10.03	5.20	.50	2.55	5.02	3.90	.58
12.5	1.562	51.4	14.96	1.78	10.22	5.30	.49	2.58	5.12	3.98	.58
12.75	1.594	52.4	15.25	1.80	10.41	5.40	.48	2.61	5.22	4.06	.58
13	1.625	53.4	15.54	1.82	10.60	5.50	.47	2.64	5.32	4.14	.58
13.25	1.656	54.4	15.83	1.84	10.79	5.60	.46	2.67	5.42	4.22	.58
13.5	1.688	55.4	16.12	1.86	10.98	5.70	.45	2.70	5.52	4.30	.58
13.75	1.719	56.4	16.41	1.88	11.17	5.80	.44	2.73	5.62	4.38	.58
14	1.75	57.4	16.70	1.90	11.36	5.90	.43	2.76	5.72	4.46	.58
14.25	1.781	58.4	16.99	1.92	11.55	6.00	.42	2.79	5.82	4.54	.58
14.5	1.812	59.4	17.28	1.94	11.74	6.10	.41	2.82	5.92	4.62	.58
14.75	1.844	60.4	17.57	1.96	11.93	6.20	.40	2.85	6.02	4.70	.58
15	1.875	61.4	17.86	1.98	12.12	6.30	.39	2.88	6.12	4.78	.58


TABLE VI
PROPERTIES OF STANDARD ANGLES HAVING UNEQUAL



1	2	3	4	5	6	7	8	9	10	11	12
Dimensions Inches	Thickness Inches	Weight per Foot Pounds	Area of Section Square Inches	Distance of Center of Gravity From Back of Longer Flange Inches	Moment of Inertia, Axis 1-1 Inches	Section Modulus, Axis 1-1 Inches	Radius of Gyration, Axis 1-1 Inches	Distance of Center of Gravity From Back of Shorter Flange, Inches	Moment of Inertia, Axis 2-2 Inches	Section Modulus, Axis 2-2 Inches	Radius of Gyration, Axis 2-2 Inches
$b \times a$	t		A	x	I	S	r	y	I'	S'	r'
2 1/2 x 3 1/2	1/2	2.2	.81	.51	.39	.30	.60	.76	.51	.39	.79
2 1/2 x 3 1/2	3/8	1.6	1.06	.54	.37	.25	.59	.79	.65	.38	.78
2 1/2 x 3 1/2	1/4	1.1	1.31	.56	.45	.31	.58	.81	.79	.47	.78
2 1/2 x 3 1/2	3/16	.8	1.55	.58	.51	.26	.58	.85	.91	.47	.77
2 1/2 x 3 1/2	1/8	.6	1.78	.60	.58	.21	.57	.88	1.03	.47	.76
2 1/2 x 3 1/2	3/32	.4	2.00	.63	.64	.16	.56	.90	1.14	.47	.75
2 1/2 x 3 1/2	1/32	.3	2.21	.65	.69	.11	.55	.90	1.24	.47	.75
3 x 3 1/2	1/2	4.5	1.31	.66	.74	.40	.75	.91	1.17	.56	.95
3 x 3 1/2	3/8	3.1	1.62	.68	.90	.29	.74	.93	1.42	.69	.94
3 x 3 1/2	1/4	2.2	1.92	.71	1.04	.24	.74	.96	1.66	.81	.93
3 x 3 1/2	3/16	1.6	2.21	.73	1.18	.20	.73	.98	1.88	.93	.92
3 x 3 1/2	1/8	1.1	2.50	.75	1.30	.17	.72	1.00	2.08	1.04	.91
3 x 3 1/2	3/32	.8	2.78	.77	1.42	.14	.72	1.02	2.28	1.15	.91
3 x 3 1/2	1/32	.6	3.05	.79	1.53	.10	.71	1.04	2.46	1.26	.90
3 1/2 x 3 1/2	1/2	6.0	1.44	.61	.78	.41	.74	1.11	1.80	.75	1.12
3 1/2 x 3 1/2	3/8	4.2	1.78	.64	.94	.30	.73	1.14	2.10	.93	1.11
3 1/2 x 3 1/2	1/4	2.9	2.11	.66	1.09	.25	.72	1.16	2.36	1.09	1.10
3 1/2 x 3 1/2	3/16	2.0	2.43	.68	1.23	.21	.71	1.18	2.61	1.26	1.09
3 1/2 x 3 1/2	1/8	1.4	2.75	.70	1.36	.18	.70	1.20	2.84	1.41	1.09
3 1/2 x 3 1/2	3/32	1.0	3.06	.73	1.49	.14	.70	1.23	3.05	1.56	1.08
3 1/2 x 3 1/2	1/32	.7	3.34	.75	1.61	.10	.69	1.25	3.25	1.71	1.07
3 1/2 x 3 1/2	3/64	.5	3.65	.77	1.73	.08	.69	1.27	3.43	1.85	1.06
3 1/2 x 3 1/2	1/64	.4	3.94	.79	1.83	.06	.68	1.29	3.60	1.99	1.06
3 1/2 x 3	1/2	6.6	1.93	.81	1.58	.72	.90	1.06	2.33	.95	1.10
3 1/2 x 3	3/8	4.5	2.30	.83	1.85	.50	.90	1.08	2.72	1.13	1.09
3 1/2 x 3	1/4	3.1	2.65	.85	2.09	.40	.89	1.10	3.10	1.29	1.08
3 1/2 x 3	3/16	2.2	3.00	.87	2.33	.33	.88	1.13	3.45	1.45	1.07
3 1/2 x 3	1/8	1.6	3.34	.90	2.55	.27	.87	1.15	3.79	1.61	1.07
3 1/2 x 3	3/32	1.1	3.67	.92	2.76	.22	.87	1.17	4.11	1.76	1.06
3 1/2 x 3	1/32	.8	4.00	.94	2.96	.18	.86	1.19	4.41	1.91	1.05
3 1/2 x 3	3/64	.6	4.31	.96	3.15	.14	.85	1.21	4.70	2.05	1.04
3 1/2 x 3	1/64	.4	4.62	.98	3.33	.11	.85	1.23	4.98	2.20	1.04
3 1/2 x 3	3/128	.3	4.92	1.00	3.50	.08	.84	1.25	5.24	2.33	1.03
4 x 3 1/2	1/2	7.1	2.09	.76	1.65	.73	.89	1.26	3.98	1.23	1.27
4 x 3 1/2	3/8	4.9	2.48	.78	1.92	.52	.88	1.28	4.36	1.46	1.26
4 x 3 1/2	1/4	3.3	2.87	.80	2.18	.40	.87	1.30	4.72	1.68	1.25
4 x 3 1/2	3/16	2.4	3.25	.83	2.42	.32	.86	1.33	5.05	1.89	1.25
4 x 3 1/2	1/8	1.7	3.62	.85	2.66	.25	.86	1.35	5.35	2.09	1.24
4 x 3 1/2	3/32	1.2	3.98	.87	2.87	.20	.85	1.37	5.63	2.30	1.23
4 x 3 1/2	1/32	.9	4.34	.89	3.08	.16	.84	1.39	5.90	2.49	1.22
4 x 3 1/2	3/64	.6	4.69	.92	3.28	.12	.84	1.42	6.13	2.68	1.22
4 x 3 1/2	1/64	.4	5.03	.94	3.47	.09	.83	1.44	6.35	2.87	1.21
4 x 3 1/2	3/128	.3	5.36	.96	3.66	.07	.83	1.46	6.55	3.05	1.20

TABLE VI—(Continued)

OPERTIES OF STANDARD ANGLES HAVING UNEQUAL LEGS



2	3	4	5	6	7	8	9	10	11	12	13	14
Thickness Inches	Weight per Foot Pounds	Area of Section Square Inches	Distance of Center of Gravity From Back of Longer Flange Inches	Moment of Inertia, Axis 1-1 Inches	Section Modulus, Axis 1-1 Inches	Radius of Gyration, Axis 1-1 Inches	Distance of Center of Gravity From Back of Shorter Flange, Inches	Moment of Inertia, Axis 2-2 Inches	Section Modulus, Axis 2-2 Inches	Radius of Gyration, Axis 2-2 Inches	Tangent of Angle	Least Radius of Gyration, Axis 2-2 Inches
t		A	x	I	S	r	x'	I'	S'	r'	a	r''
1/8	8.2	2.40	.68	1.75	.75	.85	1.68	6.26	1.89	1.61	.368	.66
1/4	9.7	2.86	.70	2.04	.89	.84	1.70	7.37	2.24	1.61	.364	.65
3/8	11.3	3.31	.73	2.32	1.02	.84	1.73	8.43	2.58	1.60	.361	.65
1/2	12.8	3.75	.75	2.58	1.15	.83	1.75	9.45	2.91	1.59	.357	.65
5/8	14.2	4.18	.77	2.83	1.27	.82	1.77	10.43	3.23	1.58	.353	.65
3/4	15.7	4.61	.80	3.06	1.39	.82	1.80	11.37	3.55	1.57	.349	.64
7/8	17.1	5.03	.82	3.29	1.51	.81	1.82	12.28	3.86	1.56	.345	.64
1	18.5	5.44	.84	3.51	1.62	.80	1.84	13.15	4.16	1.55	.340	.64
1 1/8	19.9	5.84	.86	3.71	1.74	.80	1.86	13.98	4.46	1.55	.336	.64
1 1/4	21.2	6.23	.88	3.91	1.85	.79	1.88	14.78	4.75	1.54	.331	.64
1 3/8	8.7	2.56	.84	2.72	1.02	1.03	1.59	6.60	1.94	1.61	.489	.77
1 1/2	10.4	3.05	.86	3.18	1.21	1.02	1.61	7.78	2.29	1.60	.485	.76
1 3/4	12.0	3.53	.88	3.63	1.39	1.01	1.63	8.90	2.64	1.59	.482	.76
1 7/8	13.6	4.00	.91	4.05	1.56	1.01	1.66	9.99	2.99	1.58	.479	.75
2	15.2	4.46	.93	4.45	1.73	1.00	1.68	11.03	3.32	1.57	.476	.75
2 1/8	16.7	4.92	.95	4.83	1.90	.99	1.70	12.03	3.65	1.56	.472	.75
2 1/4	18.3	5.37	.97	5.20	2.06	.98	1.72	12.99	3.97	1.56	.468	.75
2 3/8	19.8	5.81	1.00	5.55	2.22	.98	1.75	13.92	4.28	1.55	.464	.75
2 1/2	21.2	6.25	1.02	5.89	2.37	.97	1.77	14.81	4.58	1.54	.460	.75
2 3/4	22.7	6.67	1.04	6.21	2.52	.96	1.79	15.67	4.88	1.53	.455	.75
2 7/8	24.1	7.09	1.06	6.52	2.67	.96	1.81	16.49	5.17	1.53	.451	.75
3	11.6	3.42	.79	3.34	1.23	.99	2.04	12.86	3.24	1.94	.350	.77
3 1/8	13.5	3.96	.81	3.81	1.41	.98	2.06	14.76	3.75	1.93	.347	.76
3 1/4	15.3	4.50	.83	4.25	1.59	.97	2.08	16.59	4.24	1.92	.344	.76
3 3/8	17.1	5.03	.86	4.67	1.77	.96	2.11	18.37	4.72	1.91	.341	.75
3 1/2	18.9	5.55	.88	5.08	1.94	.96	2.13	20.08	5.19	1.90	.338	.75
3 3/4	20.6	6.06	.90	5.47	2.11	.95	2.15	21.74	5.65	1.89	.334	.75
3 7/8	22.3	6.56	.93	5.84	2.27	.94	2.18	23.34	6.10	1.89	.331	.75
4	24.0	7.06	.95	6.20	2.43	.94	2.20	24.89	6.55	1.88	.327	.75
4 1/8	25.7	7.55	.97	6.55	2.59	.93	2.22	26.39	6.98	1.87	.323	.75
4 1/4	27.3	8.03	.99	6.88	2.74	.93	2.24	27.84	7.41	1.86	.320	.75
4 3/8	28.9	8.50	1.01	7.21	2.90	.92	2.26	29.15	7.80	1.85	.317	.75
4 1/2	12.3	3.61	.94	4.90	1.60	1.17	1.94	13.47	3.32	1.93	.446	.88
4 3/4	14.2	4.18	.96	5.60	1.85	1.16	1.96	15.46	3.83	1.92	.443	.87
4 7/8	16.2	4.75	.99	6.27	2.08	1.15	1.99	17.40	4.33	1.91	.440	.87
5	18.1	5.31	1.01	6.91	2.31	1.14	2.01	19.26	4.83	1.90	.438	.87
5 1/8	19.9	5.86	1.03	7.52	2.54	1.13	2.03	21.07	5.31	1.90	.434	.86
5 1/4	21.8	6.40	1.06	8.11	2.76	1.13	2.06	22.82	5.78	1.89	.431	.86
5 3/8	23.6	6.94	1.08	8.68	2.97	1.12	2.08	24.51	6.25	1.88	.428	.86
5 1/2	25.4	7.46	1.10	9.23	3.18	1.11	2.10	26.15	6.70	1.87	.425	.86
5 3/4	27.2	7.99	1.12	9.75	3.39	1.11	2.12	27.73	7.15	1.86	.421	.86
5 7/8	28.9	8.50	1.14	10.26	3.59	1.10	2.14	29.26	7.59	1.86	.418	.86
6	30.6	9.00	1.17	10.75	3.79	1.09	2.17	30.75	8.02	1.85	.414	.86


TABLE VII
PROPERTIES OF Z BARS



1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17
Depth of Bar Inches	Length of Legs Inches	Thickness of Web and Legs Inches	Weight per Foot Pounds	Area of Section Square Inches	Moment of Inertia, Axis 1-1 Inches	Section Modulus, Axis 1-1 Inches	Radius of Gyration, Axis 1-1 Inches	Moment of Inertia, Axis 2-2 Inches	Section Modulus, Axis 2-2 Inches	Radius of Gyration, Axis 2-2 Inches	Tangent of Angle °	Least Radius of Gyration, Axis 3-3 Inches	Coefficient of Strength For Fiber Stress of 16,000 Pounds per Square Inch	Coefficient of Strength For Fiber Stress of 12,500 Pounds per Square Inch	Coefficient of Deflection Uniform Load	Center Load
3 1/4	12 1/4	3/16	12.4	4.16	5.26	3.43	1.12	5.68	2.30	1.17	.951	.54	36,000	28,000	.000148	.000236
3 1/8	12 1/8	3/16	12.5	4.16	4.90	3.06	1.12	4.85	1.99	1.15	.905	.53	32,000	25,500	.000160	.000271
3 1/8	12 1/8	3/16	11.4	3.86	4.57	2.96	1.17	4.75	1.86	1.10	.875	.55	31,000	24,800	.000170	.000272
3 1/8	12 1/8	3/16	10.7	3.64	4.27	2.57	1.16	4.24	1.57	1.12	.900	.54	27,400	21,400	.000201	.000322
3 1/8	12 1/8	3/16	9.7	2.86	3.85	2.36	1.21	3.64	1.40	1.21	1.000	.55	25,400	19,800	.000213	.000341
3 1/8	12 1/8	3/16	8.9	1.97	2.87	1.92	1.21	2.81	1.10	1.19	.966	.55	20,400	16,000	.000276	.000432

4	$\frac{3}{16}$	$\frac{1}{2}$	8.2	2.41	6.28	3.14	1.62	4.23	1.44	1.33	.778	.67	33,500	26,200	.000123	.000198
4 $\frac{1}{2}$	$\frac{3}{16}$	$\frac{1}{2}$	10.3	3.03	7.94	3.91	1.62	5.46	1.84	1.34	.788	.68	41,700	32,600	.000098	.000156
4 $\frac{1}{2}$	$\frac{3}{16}$	$\frac{1}{2}$	12.4	3.66	9.63	4.67	1.62	6.77	2.26	1.36	.798	.69	49,800	38,900	.000081	.000129
4	$\frac{3}{16}$	$\frac{1}{2}$	13.8	4.05	9.66	4.83	1.54	6.73	2.37	1.29	.794	.66	51,500	40,200	.000080	.000129
4 $\frac{1}{2}$	$\frac{3}{16}$	$\frac{1}{2}$	15.8	4.66	11.18	5.50	1.55	7.96	2.77	1.31	.804	.67	58,700	45,900	.000069	.000111
4 $\frac{1}{2}$	$\frac{3}{16}$	$\frac{1}{2}$	17.9	5.27	12.74	6.18	1.55	9.26	3.19	1.32	.814	.68	65,900	51,500	.000061	.000097
4	$\frac{3}{16}$	$\frac{1}{2}$	18.9	5.55	12.11	6.05	1.48	8.73	3.18	1.25	.808	.65	64,600	50,500	.000064	.000103
4 $\frac{1}{2}$	$\frac{3}{16}$	$\frac{1}{2}$	20.9	6.14	13.52	6.65	1.48	9.95	3.58	1.27	.818	.67	71,000	55,500	.000057	.000092
4 $\frac{1}{2}$	$\frac{3}{16}$	$\frac{1}{2}$	23.0	6.75	14.97	7.26	1.49	11.24	4.00	1.29	.828	.68	77,400	60,500	.000052	.000083
5	$\frac{3}{16}$	$\frac{1}{2}$	11.6	3.40	13.36	5.34	1.98	6.18	2.00	1.35	.611	.75	57,000	44,500	.000058	.000093
5 $\frac{1}{2}$	$\frac{3}{16}$	$\frac{1}{2}$	13.9	4.10	16.18	6.39	1.99	7.65	2.45	1.37	.619	.76	68,200	53,300	.000048	.000077
5 $\frac{1}{2}$	$\frac{3}{16}$	$\frac{1}{2}$	16.4	4.81	19.07	7.44	1.99	9.20	2.92	1.38	.628	.76	79,400	62,000	.000041	.000065
5	$\frac{3}{16}$	$\frac{1}{2}$	17.9	5.25	19.19	7.68	1.91	9.05	3.02	1.31	.616	.74	81,900	64,000	.000040	.000065
5 $\frac{1}{2}$	$\frac{3}{16}$	$\frac{1}{2}$	20.2	5.94	21.83	8.62	1.92	10.51	3.47	1.33	.623	.75	92,000	71,900	.000036	.000057
5 $\frac{1}{2}$	$\frac{3}{16}$	$\frac{1}{2}$	22.6	6.64	24.53	9.57	1.92	12.06	3.94	1.35	.631	.76	102,100	79,800	.000032	.000051
5	$\frac{3}{16}$	$\frac{1}{2}$	23.7	6.96	23.68	9.47	1.84	11.37	3.91	1.28	.619	.73	101,000	78,900	.000033	.000052
5 $\frac{1}{2}$	$\frac{3}{16}$	$\frac{1}{2}$	26.0	7.64	26.16	10.34	1.85	12.83	4.37	1.30	.626	.74	110,200	86,100	.000030	.000047
5 $\frac{1}{2}$	$\frac{3}{16}$	$\frac{1}{2}$	28.3	8.33	28.70	11.20	1.86	14.37	4.84	1.31	.633	.76	119,500	93,300	.000027	.000043
6	$\frac{3}{16}$	$\frac{1}{2}$	15.6	4.59	25.32	8.44	2.35	9.11	2.75	1.41	.519	.83	90,000	70,300	.000031	.000049
6 $\frac{1}{2}$	$\frac{3}{16}$	$\frac{1}{2}$	18.3	5.39	29.80	9.83	2.35	10.94	3.27	1.43	.526	.83	104,900	81,900	.000026	.000042
6 $\frac{1}{2}$	$\frac{3}{16}$	$\frac{1}{2}$	21.0	6.19	34.36	11.22	2.36	12.87	3.81	1.44	.532	.84	119,700	93,500	.000023	.000036
6	$\frac{3}{16}$	$\frac{1}{2}$	22.7	6.68	34.64	11.55	2.28	12.59	3.91	1.37	.520	.81	123,200	96,200	.000022	.000036
6 $\frac{1}{2}$	$\frac{3}{16}$	$\frac{1}{2}$	25.4	7.46	38.87	12.82	2.28	14.41	4.44	1.39	.526	.82	136,800	106,800	.000020	.000032
6 $\frac{1}{2}$	$\frac{3}{16}$	$\frac{1}{2}$	28.1	8.25	43.18	14.10	2.29	16.34	4.98	1.41	.532	.84	150,400	117,500	.000018	.000029
6	$\frac{3}{16}$	$\frac{1}{2}$	29.3	8.63	42.12	14.04	2.21	15.44	4.94	1.34	.519	.81	149,800	117,000	.000018	.000029
6 $\frac{1}{2}$	$\frac{3}{16}$	$\frac{1}{2}$	31.9	9.39	46.13	15.22	2.22	17.27	5.47	1.36	.525	.82	162,300	126,800	.000017	.000027
6 $\frac{1}{2}$	$\frac{3}{16}$	$\frac{1}{2}$	34.6	10.17	50.22	16.40	2.22	19.18	6.02	1.37	.530	.83	174,900	136,700	.000015	.000025
7 $\frac{1}{2}$	3	$\frac{1}{2}$	16.3	4.78	38.19	10.18	2.83	5.59	1.99	1.08	.29	.72	108,600	84,800	.000020	.000033
8	3	$\frac{1}{2}$	16.9	4.97	44.64	11.16	3.00	5.60	1.99	1.06	.27	.72	119,000	93,000	.000017	.000028
10	3	$\frac{1}{2}$	19.4	5.72	76.87	15.37	3.67	5.60	1.99	.99	.19	.71	163,900	128,100	.000010	.000016

TABLE VIII--PROPERTIES OF T BARS




EQUAL LEGS									
Width of Flange, Inches	Depth of Bar, Inches	Thickness of Flange, Inches	Thickness of Stem, Inches	Weight per Foot, Pounds	Area of Section, Square Inches	Distance of Center of Gravity from Outside of Flange, Inches	Moment of Inertia, Axis $x-x$, Inches ⁴	Section Modulus, Axis $x-x$, Inches ³	Radius of Gyration, Axis $x-x$, Inches
b	d	t	t to m'	t to t'	A	x	I	S	r
1	1	1 to 1	1 to 1	1.99	2.9	.30	.02	.02	.30
1	1	1 to 1	1 to 1	1.99	4.1	.33	.04	.02	.32
1	1	1 to 1	1 to 1	1.99	4.5	.33	.05	.02	.32
1	1	1 to 1	1 to 1	1.99	4.7	.36	.06	.02	.33
1	1	1 to 1	1 to 1	1.99	5.4	.36	.08	.02	.33
2	2	1 to 1	1 to 1	3.7	1.05	.59	.37	.36	.40
2	2	1 to 1	1 to 1	4.3	1.26	.61	.43	.31	.40
2	2	1 to 1	1 to 1	4.1	1.19	.63	.51	.32	.45
2	2	1 to 1	1 to 1	4.9	1.45	.67	.64	.32	.47
2	2	1 to 1	1 to 1	5.5	1.60	.73	.87	.49	.49
3	3	1 to 1	1 to 1	6.6	1.95	.86	1.58	.74	.50
3	3	1 to 1	1 to 1	7.8	2.27	.88	1.82	.86	.50
3	3	1 to 1	1 to 1	9.3	2.74	.99	3.10	1.33	1.08
UNEQUAL LEGS									
1 1/2	1 1/2	1/2 to 1	1/2 to 1	1.49	.44	.29	.04	.05	.29
2 1/2	2 1/2	1/2 to 1	1/2 to 1	2.9	.84	.30	.08	.09	.31
COEFFICIENT OF STRENGTH									
				For Fiber Stress of 16,000 Pounds per Square Inch		For Fiber Stress of 12,500 Pounds per Square Inch			
				F		F'			
1	1	1 to 1	1 to 1	380	380	370	370	13,140	10,360
1	1	1 to 1	1 to 1	440	440	440	440	13,140	10,360
1	1	1 to 1	1 to 1	490	490	490	490	13,140	10,360
1	1	1 to 1	1 to 1	530	530	530	530	13,140	10,360
1	1	1 to 1	1 to 1	590	590	590	590	13,140	10,360
2	2	1 to 1	1 to 1	2,770	2,770	2,160	2,160	13,140	10,360
2	2	1 to 1	1 to 1	3,330	3,330	2,600	2,600	13,140	10,360
2	2	1 to 1	1 to 1	3,440	3,440	2,690	2,690	13,140	10,360
2	2	1 to 1	1 to 1	4,300	4,300	3,360	3,360	13,140	10,360
2	2	1 to 1	1 to 1	5,350	5,350	4,100	4,100	13,140	10,360
3	3	1 to 1	1 to 1	7,850	7,850	6,140	6,140	13,140	10,360
3	3	1 to 1	1 to 1	9,180	9,180	7,180	7,180	13,140	10,360

TABLE IX
PROPERTIES AND PRINCIPAL DIMENSIONS OF STANDARD
T RAILS




1	2	3	4	5	6	7	8	9
Weight per Yard Pounds	Area Square Inches	h Inches	d Inches	b Inches	t Inches	r Inches	Axis I-I	
							Moment of Inertia	Section Modulus
							I	S
8	.78	1½	1½	1½	¾	.75	.23	.31
12	1.18	1¾	1¾	1¾	1¼	.92	.55	.58
16	1.57	2½	2½	1¾	¾	1.10	1.13	.99
20	2.00	2¾	2¾	1¾	¾	1.2	1.5	1.2
25	2.5	2¾	2¾	1¾	¾	1.4	2.4	1.7
30	2.9	3¼	3	1¾	¾	1.5	3.7	2.4
35	3.4	3¾	3¼	1¾	¾	1.5	4.3	2.8
40	3.9	3¾	3¼	1¾	¾	1.7	6.0	3.4
45	4.4	3¾	3¼	1¾	¾	1.8	7.6	3.9
50	4.9	3¾	3¼	2	¾	1.9	10.1	5.1
55	5.4	4¼	4¼	2¼	¾	2.0	12.2	5.9
60	5.9	4¼	4¼	2	¾	2.1	14.7	6.7
65	6.4	4¼	4¼	2¼	¾	2.1	17.0	7.4
70	6.9	4¼	4¼	2¼	¾	2.2	20.0	8.4
75	7.4	4¼	4¼	2¼	¾	2.3	23.0	9.1
80	7.8	5	5	2½	¾	2.4	26.7	10.1
85	8.3	5¼	5¼	2¾	¾	2.5	30.5	11.2
90	8.8	5¼	5¼	2¾	¾	2.6	35.2	12.6
100	9.8	5¾	5¾	2¾	¾	2.8	44.4	15.0
150	14.7	6	6	4	1	3.0	69.3	22.9

TABLE X
MOMENT OF INERTIA OF RECTANGULAR SECTIONS



Depth in Inches	Width of Rectangle in Inches						
	$\frac{1}{8}$	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{5}{8}$	$\frac{3}{4}$	$\frac{7}{8}$
2	.17	.21	.25	.29	.33	.38	.42
3	.56	.70	.84	.98	1.13	1.27	1.41
4	1.33	1.67	2.00	2.33	2.67	3.00	3.33
5	2.60	3.26	3.91	4.56	5.21	5.86	6.51
6	4.50	5.63	6.75	7.88	9.00	10.13	11.25
7	7.15	8.93	10.72	12.51	14.29	16.08	17.86
8	10.67	13.33	16.00	18.67	21.33	24.00	26.67
9	15.19	18.98	22.78	26.58	30.38	34.17	37.97
10	20.83	26.04	31.25	36.46	41.67	46.87	52.08
11	27.73	34.66	41.59	48.53	55.46	62.39	69.32
12	36.00	45.00	54.00	63.00	72.00	81.00	90.00
13	45.77	57.21	68.66	80.10	91.54	102.98	114.43
14	57.17	71.46	85.75	100.04	114.33	128.63	142.92
15	70.31	87.89	105.47	123.05	140.63	158.20	175.78
16	85.33	106.67	128.00	149.33	170.67	192.00	213.33
17	102.35	127.94	153.53	179.12	204.71	230.30	255.89
18	121.50	151.88	182.25	212.63	243.00	273.38	303.75
19	142.90	178.62	214.34	250.07	285.79	321.52	357.24
20	166.67	208.33	250.00	291.67	333.33	375.00	416.67
21	192.94	241.17	289.41	337.64	385.88	434.11	482.34
22	221.83	277.29	332.75	388.21	443.67	499.13	554.58
23	253.48	316.85	380.22	443.59	506.96	570.33	633.70
24	288.00	360.00	432.00	504.00	576.00	648.00	720.00
25	325.52	406.90	488.28	569.66	651.04	732.42	813.80
26	366.17	457.71	549.25	640.79	732.33	823.88	915.42
27	410.06	512.58	615.09	717.61	820.13	922.64	1,025.16
28	457.33	571.67	686.00	800.33	914.67	1,029.00	1,143.33
29	508.10	635.13	762.16	889.18	1,016.21	1,143.23	1,270.26
30	562.50	703.13	843.75	984.38	1,125.00	1,265.63	1,406.25
32	682.67	853.33	1,024.00	1,194.67	1,365.33	1,536.00	1,706.67
34	818.83	1,023.54	1,228.25	1,432.96	1,637.67	1,842.38	2,047.08
36	972.00	1,215.00	1,458.00	1,701.00	1,944.00	2,187.00	2,430.00
38	1,143.17	1,428.96	1,714.75	2,000.54	2,286.33	2,572.13	2,857.92
40	1,333.33	1,666.67	2,000.00	2,333.33	2,666.67	3,000.00	3,333.33
42	1,543.50	1,929.38	2,315.25	2,701.13	3,087.00	3,472.88	3,858.75
44	1,774.67	2,218.33	2,662.00	3,105.67	3,549.33	3,993.00	4,436.67
46	2,027.83	2,534.79	3,041.75	3,548.71	4,055.67	4,562.63	5,069.58
48	2,304.00	2,880.00	3,456.00	4,032.00	4,608.00	5,184.00	5,760.00
50	2,604.17	3,255.21	3,906.25	4,557.29	5,208.33	5,859.38	6,510.42
52	2,929.33	3,661.67	4,394.00	5,126.33	5,858.67	6,591.00	7,323.33
54	3,280.50	4,100.63	4,920.75	5,740.88	6,561.00	7,381.13	8,201.25
56	3,658.67	4,573.33	5,488.00	6,402.67	7,317.33	8,232.00	9,146.67
58	4,064.83	5,081.04	6,097.25	7,113.46	8,129.67	9,145.87	10,162.08
60	4,500.00	5,625.00	6,750.00	7,875.00	9,000.00	10,125.00	11,250.00

TABLE X—(Continued)
MOMENT OF INERTIA OF RECTANGULAR SECTIONS




Depth in Inches	Width of Rectangle in Inches					
	$\frac{1}{8}$	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{5}{8}$	1
2	.46	.50	.54	.58	.63	.67
3	1.55	1.69	1.83	1.97	2.11	2.25
4	3.67	4.00	4.33	4.67	5.00	5.33
5	7.16	7.81	8.46	9.11	9.77	10.42
6	12.38	13.50	14.63	15.75	16.88	18.00
7	19.65	21.44	23.22	25.01	26.80	28.58
8	29.33	32.00	34.67	37.33	40.00	42.67
9	41.77	45.56	49.36	53.16	56.95	60.75
10	57.29	62.50	67.71	72.92	78.13	83.33
11	76.26	83.19	90.12	97.05	103.98	110.92
12	99.00	108.00	117.00	126.00	135.00	144.00
13	125.87	137.31	148.75	160.20	171.64	183.08
14	157.21	171.50	185.79	200.08	214.38	228.67
15	193.36	210.94	228.52	246.09	263.67	281.25
16	234.67	256.00	277.33	298.67	320.00	341.33
17	281.47	307.06	332.65	358.24	383.83	409.42
18	334.13	364.50	394.88	425.25	455.63	486.00
19	392.96	428.69	464.41	500.14	535.86	571.58
20	458.33	500.00	541.67	583.33	625.00	666.67
21	530.58	578.81	627.05	675.28	723.52	771.75
22	610.04	665.50	720.96	776.42	831.87	887.33
23	697.07	760.44	823.81	887.18	950.55	1,013.92
24	792.00	864.00	936.00	1,008.00	1,080.00	1,152.00
25	895.18	976.56	1,057.94	1,139.32	1,220.70	1,302.08
26	1,006.96	1,098.50	1,190.04	1,281.58	1,373.13	1,464.67
27	1,127.67	1,230.19	1,332.70	1,435.22	1,537.73	1,640.25
28	1,257.67	1,372.00	1,486.33	1,600.67	1,715.00	1,829.33
29	1,397.29	1,524.31	1,651.34	1,778.36	1,905.39	2,032.42
30	1,546.88	1,687.50	1,828.13	1,968.75	2,109.38	2,250.00
32	1,877.33	2,048.00	2,218.67	2,389.33	2,560.00	2,730.67
34	2,251.79	2,456.50	2,661.21	2,865.92	3,070.63	3,275.33
36	2,673.00	2,916.00	3,159.00	3,402.00	3,645.00	3,888.00
38	3,143.71	3,429.50	3,715.29	4,001.08	4,286.88	4,572.67
40	3,666.67	4,000.00	4,333.33	4,666.67	5,000.00	5,333.33
42	4,244.63	4,630.50	5,016.38	5,402.25	5,788.13	6,174.00
44	4,880.33	5,324.00	5,767.67	6,211.33	6,655.00	7,098.67
46	5,576.54	6,083.50	6,590.46	7,097.42	7,604.38	8,111.33
48	6,336.00	6,912.00	7,488.00	8,064.00	8,640.00	9,216.00
50	7,161.46	7,812.50	8,463.54	9,114.58	9,765.63	10,416.67
52	8,055.67	8,788.00	9,520.33	10,252.67	10,985.00	11,717.33
54	9,021.38	9,841.50	10,661.63	11,481.75	12,301.88	13,122.00
56	10,061.33	10,976.00	11,890.67	12,805.33	13,720.00	14,634.67
58	11,178.29	12,194.50	13,210.71	14,226.92	15,243.12	16,259.33
60	12,375.00	13,500.00	14,625.00	15,750.00	16,875.00	18,000.00

TABLE XII—(Continued)

RADII OF GYRATION FOR TWO ANGLES, HAVING
UNEQUAL LEGS, PLACED BACK TO BACK


Dimensions Inches	Thickness Inches	Area of Two Angles Square Inches	Radii of Gyration					
			r_0	r_1	r_2	r_3	r_4	r_5
4 × 3	$\frac{3}{16}$	4.18	1.27	1.17	1.25	1.30	1.34	1.44
4 × 3	$\frac{9}{16}$	7.24	1.24	1.21	1.30	1.34	1.39	1.49
4 × 3	$\frac{13}{16}$	10.05	1.21	1.25	1.35	1.40	1.45	1.55
4 × 3 $\frac{1}{2}$	$\frac{5}{16}$	4.49	1.26	1.42	1.50	1.55	1.59	1.69
4 × 3 $\frac{1}{2}$	$\frac{13}{16}$	7.00	1.23	1.44	1.53	1.58	1.63	1.72
4 × 3 $\frac{1}{2}$	$\frac{5}{8}$	8.59	1.22	1.46	1.55	1.60	1.65	1.75
4 $\frac{1}{2}$ × 3	$\frac{3}{16}$	5.34	1.44	1.14	1.22	1.27	1.31	1.41
4 $\frac{1}{2}$ × 3	$\frac{13}{16}$	7.00	1.42	1.15	1.24	1.29	1.34	1.44
4 $\frac{1}{2}$ × 3	$\frac{5}{8}$	8.59	1.40	1.18	1.27	1.31	1.36	1.46
5 × 3	$\frac{5}{16}$	4.80	1.61	1.09	1.17	1.22	1.26	1.36
5 × 3	$\frac{9}{16}$	8.37	1.58	1.13	1.22	1.26	1.31	1.41
5 × 3	$\frac{13}{16}$	11.68	1.55	1.17	1.27	1.32	1.37	1.47
5 × 3 $\frac{1}{2}$	$\frac{3}{16}$	6.09	1.60	1.34	1.42	1.46	1.51	1.60
5 × 3 $\frac{1}{2}$	$\frac{5}{16}$	9.84	1.56	1.37	1.46	1.51	1.56	1.66
5 × 3 $\frac{1}{2}$	$\frac{7}{16}$	13.34	1.53	1.42	1.51	1.56	1.61	1.71
5 × 4	$\frac{3}{16}$	6.47	1.59	1.58	1.66	1.71	1.75	1.85
5 × 4	$\frac{13}{16}$	8.50	1.57	1.60	1.68	1.73	1.78	1.87
5 × 4	$\frac{5}{8}$	10.47	1.55	1.62	1.71	1.75	1.80	1.90
6 × 3 $\frac{1}{2}$	$\frac{3}{16}$	6.84	1.94	1.26	1.34	1.39	1.43	1.53
6 × 3 $\frac{1}{2}$	$\frac{5}{16}$	11.09	1.90	1.30	1.39	1.43	1.48	1.58
6 × 3 $\frac{1}{2}$	$\frac{7}{16}$	15.09	1.87	1.34	1.44	1.49	1.53	1.64
6 × 4	$\frac{3}{16}$	7.22	1.93	1.50	1.58	1.62	1.67	1.76
6 × 4	$\frac{5}{16}$	11.72	1.90	1.53	1.62	1.67	1.71	1.81
6 × 4	$\frac{7}{16}$	15.97	1.86	1.58	1.67	1.71	1.76	1.86
7 × 3 $\frac{1}{2}$	$\frac{7}{16}$	8.80	2.26	1.16	1.29	1.33	1.38	1.47
7 × 3 $\frac{1}{2}$	$\frac{13}{16}$	10.00	2.25	1.22	1.30	1.35	1.39	1.48
7 × 3 $\frac{1}{2}$	$\frac{5}{8}$	12.34	2.24	1.24	1.32	1.37	1.42	1.51
7 × 3 $\frac{1}{2}$	$\frac{13}{16}$	15.74	2.21	1.27	1.36	1.41	1.46	1.56
7 × 3 $\frac{1}{2}$	1	19.00	2.19	1.31	1.40	1.45	1.50	1.60

TABLE XIII
OF GYRATION FOR TWO ANGLES, HAVING UNEQUAL LEGS,
PLACED BACK TO BACK



Inches	Thickness Inches	Area of Two Angles Square Inches	Radii of Gyration					
			r ₁	r ₂	r ₃	r ₄	r ₅	r ₆
$\frac{3}{8}$	$\frac{3}{8}$	1.20	.41	.92	1.01	1.06	1.11	1.22
$\frac{3}{8}$	$\frac{3}{8}$	2.25	.38	.95	1.05	1.10	1.15	1.26
$\frac{1}{2}$	$\frac{3}{8}$	1.24	.44	.90	.99	1.05	1.09	1.20
$\frac{1}{2}$	$\frac{3}{8}$	2.34	.42	.93	1.09	1.14	1.19	1.29
$\frac{1}{2}$	$\frac{1}{2}$	1.34	.33	1.21	1.31	1.36	1.41	1.51
$\frac{1}{2}$	$\frac{1}{2}$	2.53	.32	1.25	1.35	1.40	1.45	1.56
$\frac{1}{2}$	$\frac{3}{8}$	1.43	.42	1.17	1.26	1.31	1.36	1.47
$\frac{1}{2}$	$\frac{3}{8}$	2.72	.40	1.20	1.30	1.35	1.40	1.51
$\frac{3}{8}$	$\frac{1}{2}$	1.52	.51	1.13	1.23	1.27	1.32	1.43
$\frac{3}{8}$	$\frac{1}{2}$	2.00	.50	1.14	1.24	1.29	1.34	1.44
	$\frac{1}{2}$	1.62	.60	1.10	1.19	1.24	1.29	1.39
	$\frac{3}{8}$	3.09	.58	1.13	1.23	1.28	1.33	1.43
	$\frac{1}{2}$	4.00	.56	1.15	1.25	1.30	1.35	1.46
$\frac{1}{2}$	$\frac{1}{2}$	1.52	.41	1.31	1.40	1.45	1.50	1.60
$\frac{1}{2}$	$\frac{5}{8}$	2.46	.40	1.33	1.43	1.48	1.53	1.63
$\frac{1}{2}$	$\frac{7}{8}$	3.34	.39	1.36	1.45	1.51	1.56	1.66
	$\frac{3}{8}$	1.80	.58	1.37	1.46	1.51	1.56	1.66
	$\frac{5}{8}$	2.93	.57	1.39	1.48	1.53	1.58	1.68
	$\frac{7}{8}$	3.99	.55	1.41	1.51	1.56	1.61	1.71
$2\frac{1}{2}$	$\frac{1}{4}$	2.63	.75	1.31	1.40	1.45	1.50	1.60
$2\frac{1}{2}$	$\frac{3}{8}$	3.84	.74	1.33	1.42	1.47	1.52	1.63
$2\frac{1}{2}$	$\frac{1}{2}$	5.55	.72	1.37	1.46	1.51	1.56	1.66
$2\frac{1}{2}$	$\frac{3}{4}$	2.88	.74	1.58	1.67	1.72	1.76	1.86
$2\frac{1}{2}$	$\frac{1}{2}$	5.50	.70	1.62	1.72	1.77	1.81	1.92
$2\frac{1}{2}$	$\frac{3}{4}$	7.30	.69	1.66	1.75	1.80	1.86	1.96
3	$\frac{1}{2}$	3.87	.90	1.52	1.61	1.66	1.71	1.80
3	$\frac{3}{4}$	6.68	.87	1.57	1.66	1.71	1.76	1.86
3	$\frac{1}{2}$	9.24	.85	1.61	1.71	1.76	1.81	1.91


TABLE XII—(Continued)
RADI OF GYRATION FOR TWO ANGLES, HAVING
UNEQUAL LEGS, PLACED BACK TO BACK



Dimensions Inches	Thickness Inches	Area of Two Angles Square Inches	Radii of Gyration					
			r ₀	r ₁	r ₂	r ₃	r ₄	r ₅
4 × 3	$\frac{3}{16}$	4.18	1.27	1.17	1.25	1.30	1.34	1.44
4 × 3	$\frac{9}{16}$	7.24	1.24	1.21	1.30	1.34	1.39	1.49
4 × 3	$\frac{13}{16}$	10.05	1.21	1.25	1.35	1.40	1.45	1.55
4 × 3 $\frac{1}{2}$	$\frac{5}{16}$	4.49	1.26	1.42	1.50	1.55	1.59	1.69
4 × 3 $\frac{1}{2}$	$\frac{1}{2}$	7.00	1.23	1.44	1.53	1.58	1.63	1.72
4 × 3 $\frac{1}{2}$	$\frac{3}{8}$	8.59	1.22	1.46	1.55	1.60	1.65	1.75
4 $\frac{1}{2}$ × 3	$\frac{3}{8}$	5.34	1.44	1.14	1.22	1.27	1.31	1.41
4 $\frac{1}{2}$ × 3	$\frac{1}{2}$	7.00	1.42	1.15	1.24	1.29	1.34	1.44
4 $\frac{1}{2}$ × 3	$\frac{3}{8}$	8.59	1.40	1.18	1.27	1.31	1.36	1.46
5 × 3	$\frac{3}{16}$	4.80	1.61	1.09	1.17	1.22	1.26	1.36
5 × 3	$\frac{9}{16}$	8.37	1.58	1.13	1.22	1.26	1.31	1.41
5 × 3	$\frac{13}{16}$	11.68	1.55	1.17	1.27	1.32	1.37	1.47
5 × 3 $\frac{1}{2}$	$\frac{3}{8}$	6.09	1.60	1.34	1.42	1.46	1.51	1.60
5 × 3 $\frac{1}{2}$	$\frac{1}{2}$	9.84	1.56	1.37	1.46	1.51	1.56	1.66
5 × 3 $\frac{1}{2}$	$\frac{7}{8}$	13.34	1.53	1.42	1.51	1.56	1.61	1.71
5 × 4	$\frac{3}{8}$	6.47	1.59	1.58	1.66	1.71	1.75	1.85
5 × 4	$\frac{1}{2}$	8.50	1.57	1.60	1.68	1.73	1.78	1.87
5 × 4	$\frac{3}{4}$	10.47	1.55	1.62	1.71	1.75	1.80	1.90
6 × 3 $\frac{1}{2}$	$\frac{3}{8}$	6.84	1.94	1.26	1.34	1.39	1.43	1.53
6 × 3 $\frac{1}{2}$	$\frac{1}{2}$	11.09	1.90	1.30	1.39	1.43	1.48	1.58
6 × 3 $\frac{1}{2}$	$\frac{7}{8}$	15.09	1.87	1.34	1.44	1.49	1.53	1.64
6 × 4	$\frac{3}{8}$	7.22	1.93	1.50	1.58	1.62	1.67	1.76
6 × 4	$\frac{1}{2}$	11.72	1.90	1.53	1.62	1.67	1.71	1.81
6 × 4	$\frac{3}{4}$	15.97	1.86	1.58	1.67	1.71	1.76	1.86
7 × 3 $\frac{1}{2}$	$\frac{7}{16}$	8.80	2.26	1.16	1.29	1.33	1.38	1.47
7 × 3 $\frac{1}{2}$	$\frac{1}{2}$	10.00	2.25	1.22	1.30	1.35	1.39	1.48
7 × 3 $\frac{1}{2}$	$\frac{3}{4}$	12.34	2.24	1.24	1.32	1.37	1.42	1.51
7 × 3 $\frac{1}{2}$	$\frac{13}{16}$	15.74	2.21	1.27	1.36	1.41	1.46	1.56
7 × 3 $\frac{1}{2}$	1	19.00	2.19	1.31	1.40	1.45	1.50	1.60

TABLE XIII


OF GYRATION FOR TWO ANGLES, HAVING UNEQUAL LEGS,
PLACED BACK TO BACK



Dimensions	Thickness Inches	Area of Two Angles Square Inches	Radii of Gyration					
			r ₁	r ₂	r ₃	r ₄	r ₅	r ₆
1 1/8	3/8	1.20	.41	.92	1.01	1.06	1.11	1.22
1 1/8	3/8	2.25	.38	.95	1.05	1.10	1.15	1.26
1 1/2	3/8	1.24	.44	.90	.99	1.05	1.09	1.20
1 1/2	3/8	2.34	.42	.93	1.09	1.14	1.19	1.29
1 3/4	3/8	1.34	.33	1.21	1.31	1.36	1.41	1.51
1 3/4	3/8	2.53	.32	1.25	1.35	1.40	1.45	1.56
1 3/4	3/8	1.43	.42	1.17	1.26	1.31	1.36	1.47
1 3/4	3/8	2.72	.40	1.20	1.30	1.35	1.40	1.51
1 3/4	3/8	1.52	.51	1.13	1.23	1.27	1.32	1.43
1 3/4	1/2	2.00	.50	1.14	1.24	1.29	1.34	1.44
2	3/8	1.62	.60	1.10	1.19	1.24	1.29	1.39
2	3/8	3.09	.58	1.13	1.23	1.28	1.33	1.43
2	1/2	4.00	.56	1.15	1.25	1.30	1.35	1.46
1 1/2	3/8	1.52	.41	1.31	1.40	1.45	1.50	1.60
1 1/2	5/8	2.46	.40	1.33	1.43	1.48	1.53	1.63
1 1/2	7/8	3.34	.39	1.36	1.45	1.51	1.56	1.66
2	3/8	1.80	.58	1.37	1.46	1.51	1.56	1.66
2	5/8	2.93	.57	1.39	1.48	1.53	1.58	1.68
2	7/8	3.99	.55	1.41	1.51	1.56	1.61	1.71
< 2 1/2	1/2	2.63	.75	1.31	1.40	1.45	1.50	1.60
< 2 1/2	3/8	3.84	.74	1.33	1.42	1.47	1.52	1.63
< 2 1/2	5/8	5.55	.72	1.37	1.46	1.51	1.56	1.66
x 2 1/2	1/2	2.88	.74	1.58	1.67	1.72	1.76	1.86
x 2 1/2	1/2	5.50	.70	1.62	1.72	1.77	1.81	1.92
x 2 1/2	1 1/2	7.30	.69	1.66	1.75	1.80	1.86	1.96
x 3	5/8	3.87	.90	1.52	1.61	1.66	1.71	1.80
x 3	7/8	6.68	.87	1.57	1.66	1.71	1.76	1.86
x 3	1 1/2	9.24	.85	1.61	1.71	1.76	1.81	1.91

TABLE XIII—(Continued)

RADII OF GYRATION FOR TWO ANGLES, HAVING UNEQUAL LI
PLACED BACK TO BACK



Dimensions Inches	Thickness Inches	Area of Two Angles Square Inches	Radii of Gyration				
			r_0	r_1	r_2	r_3	r_4
4 × 3	$\frac{3}{16}$	4.18	.89	1.79	1.88	1.93	1.97
4 × 3	$\frac{9}{16}$	7.24	.86	1.83	1.93	1.97	2.02
4 × 3	$\frac{13}{16}$	10.05	.83	1.88	1.97	2.02	2.08
4 × 3½	$\frac{3}{16}$	4.49	1.07	1.73	1.81	1.86	1.91
4 × 3½	$\frac{1}{2}$	7.00	1.04	1.76	1.85	1.89	1.94
4 × 3½	$\frac{5}{8}$	8.59	1.02	1.78	1.87	1.92	1.97
4½ × 3	$\frac{3}{8}$	5.34	.86	2.07	2.16	2.21	2.26
4½ × 3	$\frac{1}{2}$	7.00	.85	2.09	2.18	2.23	2.28
4½ × 3	$\frac{5}{8}$	8.59	.83	2.11	2.21	2.26	2.31
5 × 3	$\frac{3}{16}$	4.80	.85	2.33	2.42	2.47	2.52
5 × 3	$\frac{9}{16}$	8.37	.82	2.37	2.47	2.52	2.57
5 × 3	$\frac{13}{16}$	11.68	.80	2.42	2.52	2.57	2.62
5 × 3½	$\frac{3}{8}$	6.09	1.02	2.27	2.36	2.41	2.45
5 × 3½	$\frac{5}{8}$	9.84	.99	2.31	2.40	2.45	2.50
5 × 3½	$\frac{7}{8}$	13.34	.96	2.36	2.45	2.50	2.55
5 × 4	$\frac{3}{8}$	6.47	1.20	2.20	2.29	2.34	2.38
5 × 4	$\frac{1}{2}$	8.50	1.18	2.22	2.31	2.36	2.41
5 × 4	$\frac{5}{8}$	10.47	1.17	2.24	2.33	2.38	2.43
6 × 3½	$\frac{3}{8}$	6.84	.99	2.81	2.90	2.95	3.00
6 × 3½	$\frac{5}{8}$	11.09	.96	2.86	2.95	3.00	3.05
6 × 3½	$\frac{7}{8}$	15.09	.93	2.90	3.00	3.05	3.10
6 × 4	$\frac{3}{8}$	7.22	1.17	2.74	2.83	2.87	2.92
6 × 4	$\frac{5}{8}$	11.72	1.13	2.78	2.87	2.92	2.97
6 × 4	$\frac{7}{8}$	15.97	1.11	2.82	2.92	2.97	3.02
7 × 3½	$\frac{7}{16}$	8.80	.95	3.37	3.47	3.52	3.56
7 × 3½	$\frac{1}{2}$	10.00	.94	3.39	3.48	3.53	3.58
7 × 3½	$\frac{5}{8}$	12.34	.93	3.40	3.50	3.55	3.60
7 × 3½	$\frac{13}{16}$	15.64	.91	3.45	3.54	3.59	3.64
7 × 3½	1	19.00	.89	3.48	3.58	3.63	3.68

MATERIALS OF STRUCTURAL ENGINEERING

(PART 1)

FOUNDATION SOILS

EXAMINATION OF SOILS

1. Methods of Investigation.—Before any permanent structure is founded upon the earth, an accurate knowledge of the character of the soil at and below the foundation line should be obtained by examination. If the building is to be placed in a well-settled locality, this information may possibly be obtained from the history of the adjacent excavations; although, unless the geological formation of the ground is regular and uniform, this should not be relied on. If the building is to be placed in an unsettled locality, or if, in a settled locality, it is to be of greater weight than the adjoining buildings, maps of the geological formation, if available, should be consulted and may furnish valuable information as to the probable bearing capacity of the soils. If the building is an important one and doubt exists as to the capacity of the soil to sustain its weight, borings should be made for some distance below the bottom of the footings in order to determine the character of the underlying strata. These borings can be made by methods similar to those used in the driving of an ordinary pipe well, from which samples of the material passed through can be obtained as the pipe is driven down.

For notice of copyright, see page immediately following the title page

Tests may also be made by driving a gas pipe, say 2 inches or more in diameter, with a maul or hammer, and withdrawing the pipe from time to time to obtain samples of the material passed through. If the pipe passes through gravel or hard material, difficulty will be experienced in extracting the material after the pipe is withdrawn. This is at best a crude method and should not be used if accurate results are desired.

A better method of making this test is to sink a pipe and use an auger to bring up the material. A common wood auger with levers 2 or 3 feet long, turned by two men, will bring up samples that may be sufficient to determine the nature of the soil, but such samples cannot be taken as indicating the compactness of the soil, as the driving of the pipe compresses the material inside of it and the auger subsequently disturbs it. The same thing is true of the samples taken from a driven well, as the material inside the pipe is first compressed and then taken out with an auger, or, if the material is hard, broken up with a bit or chisel, and then removed with a sand pump.

In making tests with pipes, too great care cannot be exercised in arriving at conclusions regarding the character of the underlying material.

The soil may also be tested by digging an ordinary well 4 to 6 feet in diameter, curbing it with wood as the excavation proceeds. This method will permit accurate conclusions to be formed as to the character of the material in its natural position. If the ground is wet, it will be necessary to make the curbing water-tight and to remove the water.

If the site of the proposed structure is in a locality of apparently recent geological formation, such as the bottom lands in the valleys, more care must be exercised in obtaining the required information than is necessary in localities having an older geological history. In land formed of alluvial deposits a wide variation may be found between two contiguous sites. The difference may have been caused by changes in the river currents and channels due to floods or other natural causes, which may cause gravel to be

deposited in considerable layers in one spot and soft material in an adjoining spot. In alluvial soils, deep borings should always be made, as a shallow excavation or test well may disclose gravel that is of variable thickness and may be underlain with softer and yielding material. If the gravel is thick enough, it may be advisable not to go below it, but in any event the actual knowledge of the conditions should be ascertained before decision as to the character of the foundations is made.

2. Determination of Bearing Capacity.—After a full knowledge of the nature of the soil has been obtained, if the material is compressible and spread foundations are to be used, a test of the actual bearing capacity of the soil should be made by loading a platform of certain area and measuring accurately the settlements under increasing loads.

In testing the bearing capacity of the soil on which the New York State Capitol at Albany was erected, a measured load was applied to a square foot and also to a square yard. For the first test a timber mast 12 inches square, held in a vertical position by guys, was fitted with a cross-frame to hold the weights. A hole 3 feet deep was dug in the blue clay at the bottom of the foundation. The hole was 18 inches square at the top and 14 inches square at the bottom. Small stakes were driven in the ground on lines radiating from the center of the hole. The tops of the stakes were brought exactly to the same level so that any change in the surface of the ground adjacent to the hole could readily be detected by means of a straightedge. The foot of the mast was placed in the hole and the weights applied. No change in the surface of the adjacent ground was observed until the load reached 5.9 tons per square foot, when an uplift of the surrounding earth was observed in the form of a ring with an irregular rounded surface. Similar experiments were made by applying the load to a square yard, with essentially the same result. The loads were allowed to remain some time and the settlements observed.

Before building the Congressional Library at Washington, similar experiments were made with a frame, which rested

upon four corner posts, each a foot square. The frame could therefore be moved from place to place upon wheels and a number of tests were made on different parts of the site.

3. Experimental Precautions.—In making experimental tests, it is necessary to take extraordinary precautions to avoid obtaining erroneous results, and more particularly is extra care necessary if the bearing area tested is a small one, as slight errors either way may vitiate the correctness of the finding.

In placing posts on the ground, such as 12" × 12" timbers, great care is necessary to see that they are evenly and gently placed upon the surface to be tested; and if only a square foot is tested, allowance must be made for the greater resistance to displacement which the surrounding ground offers to a small area, as compared with a larger area. It is likewise well to consider that the employment of a square testing area gives four cutting edges, a condition likely to produce a greater and more rapid settlement than the parallel edges of a footing course.

CHARACTERISTICS OF FOUNDATION SOILS

4. The capacity of the earth to support superimposed loads without lateral displacement or crushing depends on the character of the soil, which may vary from solid rock through all intermediate stages to a soft or semifluid condition, as mud, silt, or marshy matter. Rock furnishes the most stable foundation. Gravel, which is composed of waterworn pieces of rock, is the next best. Hard dry sand, wet sand if confined, dry clay, wet clay, silt, and marshy matter decrease in bearing capacity approximately in the order named.

5. Rock.—The ultimate crushing strength of rock can only be determined from tests made on cubes of it in the testing machine, or, if the variety is well known, from the history of the stone. The ultimate strength of the rock varies from about 15 tons, the crushing strength of cemented gravel in the case of decayed rock and some of the softest

varieties, up to about 1,800 tons per square foot for the hardest rocks. In making tests of cubes of rock for the ultimate strength, in order to secure accurate results, the beds must be truly parallel and reduced to a true plane.

The safe bearing value of rock is considered to be not less than about one-tenth the ultimate crushing strength of the cubes. Under ordinary conditions it may safely be said that all rock, except that of the softest and most friable character, will safely sustain any load that may be placed upon it by a building of ordinary character, the area of the foundations being determined by the safe stresses that may be placed on the material forming the foundation courses of the superstructure. In ordinary practice, the safe bearing value of sound rock is taken from 14 to 20 tons per square foot.

6. Gravel.—Broken rock from which the earthy substance has been worn away by the action of water, or *detritus of rock*, as it is called, composes gravel. If gravel is found in a compact mass and in layers or strata of considerable thickness, it forms a most excellent foundation, compression within the safe limits of loading being so small that it can be neglected as a factor in design. In founding a building upon gravel, care must be taken to see that the stratum is of sufficient thickness and that the material underneath it is not such that it would be displaced by the load coming upon the strata above it. If a bed of gravel overlays a dry material, such as clay or sandy clay, it can be regarded as an excellent foundation; but if the clay is wet, a test of the ultimate bearing capacity should be made. The safe bearing loads upon gravel are usually taken from 6 to 10 tons per square foot on hard cemented gravel and from 4 to 6 tons per square foot on loose and sandy gravel, although the lower limit is considered the safer one to use under ordinary circumstances.

Strata, or sometimes merely pockets, of gravel are frequently found between layers of alluvial mud in land that has been formed through the action of water. In building

upon such soil, care must be taken that the gravel is not merely a local deposit, and soundings should be made over the whole site before the foundation is designed.

7. Sand.—Sandy soils vary from fine sand to coarse gravel. Dry sand is incompressible, and if beyond the danger of scour or of being carried away by running water is one of the best foundations obtainable. Where foundations are built upon sand, it is necessary to make sure provision that water will not remove it from underneath the footing courses. Dry sand when confined may be considered as having the same safe load as hard cemented gravel; but no rule can be laid down for the safe load of wet sand.

8. Clay.—Soils that are composed of clay vary greatly in hardness and bearing capacity, and range from slate or shale to soft, wet, or semiliquid clay. The bearing capacity of clays may roughly be said to vary directly in proportion to the water contained in them. It is therefore evident that their bearing capacity may be improved by draining them and thereby removing the water. Hard clay, such as slate or shale, will support the same load as rock of equal hardness, while soft, wet clay will squeeze out laterally when any pressure, such as ordinarily occurs in building, is placed upon it. Wet clay is at best a dangerous material for foundations, because it has a tendency to squeeze out around the edges of the footings, or, if it is not soft enough for this, settlement of the building takes place by the load pressing the water out of the clay and thereby reducing its volume.

In making an excavation below the water-line, clay may be found quite hard when first uncovered, but as it has a great capacity for absorbing water, it may swell up and increase in volume and become unfit for a foundation that would permit of no settlement.

If coarse sand or gravel is found mixed with the clay its bearing capacity is increased in the same proportion as these materials are mixed with it. It must be remembered, however, that clay is an unctuous material, that is, of a fatty or

greasy nature, and acts as a lubricant between the coarser particles, and therefore sand and gravel mixed with a very slight proportion of clay, if the material is wet, has a much smaller bearing capacity than the sand and gravel without the clay, but if the material is dry the bearing capacity is very much greater than if it is wet.

The city of Chicago is underlaid very largely with a stratum of clay of variable thickness, and the Building Laws there make the following restrictions: If the soil is a layer of pure clay at least 15 feet thick, without a mixture of any foreign substance, excepting gravel, it shall not be loaded more than at the rate of 3,500 pounds per square foot. If the soil is dry and thoroughly compressed, it may be loaded not to exceed 4,500 pounds per square foot. If the soil is a mixture of clay and sand, it shall not be loaded more than at the rate of 3,000 pounds per square foot. With the loads authorized by the Building Department of Chicago, the settlement of a building, due to the compression of the soil, amounts to from 3 inches to 5 inches.

From the experimental tests made on the soil at the State Capitol at Albany, it was found that the ultimate bearing capacity of the clay soil was less than 6 tons per square foot, and the building was designed to impose a load of 2 tons per square foot. This soil contained from 60 to 90 per cent. of alumina clay, the remainder being fine silicious sand. It was also found to contain from 27 to 43 per cent., usually about 40 per cent., of water, and samples of it weighed from 81 to 101 pounds per cubic foot.

In the soil underlying the Congressional Library at Washington, the ultimate bearing capacity of the soil, which was yellow clay mixed with sand, was $13\frac{1}{2}$ tons per square foot, and the building was designed to impose a pressure of $2\frac{1}{2}$ tons per square foot on this material.

Hard, stiff clay, when dry, may be estimated to have a safe bearing capacity of from 4 to 6 tons, but if it is allowed to become wet, its resistance is greatly decreased and it is probably not good for more than $1\frac{1}{2}$ to 2 tons; even then the compression and consequent settlement may be such as will

make it necessary to design all the footings so that the settlement on each will be the same, and a consideration of the safe capacity of such soil to properly bear the weight of the structure put upon it leads directly to the question of the design of foundations for which settlement has to be provided.

Where subsequent settlement of the foundations might cause cracks in the superstructure, the footing of a heavier part of the building, such as a tower, for instance, is temporarily loaded, the load being removed as the superstructure is built. In the Chicago Auditorium, a large tower rises 94 feet above the main building, and as a precaution against the heavy concentrated weight of the tower cracking the adjoining wall, a direct load, approximately equal to the weight of the finished tower, was placed upon the tower footings, and gradually removed as the walls were carried up.

In Chicago, when piles are not resorted to and the building is founded upon the compressible soil, the wall piers are built detached and are carefully calculated for the dead load that comes upon them. The live load is either omitted entirely or a very small proportion of it is used.

The great difficulty in designing a building to meet such conditions of supporting ground is that of accurately proportioning the foundations where the interior columns carry but little dead load, as, for instance, the interior columns in a store or other building having an open interior. In the case of office buildings, the dead load being a considerable part of the total load, the problem is easy of solution, but in store buildings it is a problem requiring great judgment to reach a satisfactory conclusion.

In designing foundations for which a settlement must be allowed, great care must be taken to have the center of resistance under the center of gravity of the load, as, with a yielding material, the overloading of one side or one edge may cause an undue compression of that side or edge and thereby tilt the footings with disastrous consequences to the superstructure. For compressible soil, it is necessary to spread the foundation over a large area, so as to have a small

load per square foot of surface. This is usually accomplished by means of I beams bearing on or embedded in a concrete slab or plate, but in buildings of no great importance this spreading of the footing is often done by means of timbers. When timbers are used, however, it is absolutely necessary that they be below the permanent water-line, as otherwise they will decay; it is also necessary that the bending stresses on the timbers be kept within very small limits, as otherwise the deflection of the timber under load will cause settlement.

9. Mud, Silt, Marsh, or Semiliquid Soils.—With soils of this character, it is necessary either to drive piles to a hard substratum, if it can be found, or to sink caissons to the hard material below, the method to be pursued usually depending on the importance of the building and the value of the land. With ordinary buildings, the pile foundation is undoubtedly the simplest and the cheapest method, but in New York city, in the lower part of the island, it is found necessary to go down to the bed rock, and in the most recent important structures there pneumatic caissons have been sunk to bed rock and afterwards filled with concrete, so arranged as to form a continuous retaining wall around the building. The material inside of this retaining wall is excavated and the space utilized for various purposes, such as basements, subbasements, and office or store purposes, the light, heat, and air being furnished by mechanical means.

Rankin gives the following formula for ascertaining the unit bearing capacity P_u of soft soil:

$$P_u = w h \left(\frac{1 + \sin \alpha}{1 - \sin \alpha} \right)$$

in which w = weight of soil, in pounds per cubic foot;

h = depth of marsh, in feet;

α = angle of repose of the soil.

For example, if α equals 5° , the supporting power of the soil is $1.19 w h$ per unit of area; if α equals 10° , it is $1.42 w h$; and if α equals 15° , it is $1.69 w h$. The weight of mud, silt, and quicksand varies from about 100 to 130 pounds per cubic foot.

The city of New Orleans is underlaid with alluvial soil, that is, a soil deposited by water, and experiments there made on quicksand would indicate that with a load of $\frac{1}{2}$ ton to 1 ton per square foot, the settlement would not be excessive.

In designing the foundation for any building, the particular character of the building, its cost, and permanence must determine the character of the footings. If the foundation is of soft material, the possibility of adjacent excavations wrecking the building must be carefully considered. If it is necessary to establish the foundation of a building on soft, yielding material, either too soft for a grillage or spread foundation, piles must usually be driven. If, also, the character of the building is such that it cannot be designed to insure equal settlement of all its pieces or parts, and a firm bearing soil cannot be found within convenient distance, piles long enough to sustain the load coming upon them should be driven into the ground. The piles can be used only in soils that are permanently saturated with water, as, if exposed to alternate wetting and drying, or if all the piling is not thoroughly immersed, fungus soon destroys the wood, and the building resting on the piles must fail.

10. Quicksand.—The term **quicksand** is applied to any silicious material so saturated with water that it will flow more or less easily when its natural condition of equilibrium is destroyed by excavating pits, trenches, shafts, or tunnels. Quicksand may be found on the surface, underlaid by firm material, or it may be found in a stratum of greater or less thickness, confined by firm strata both above and below. If the quicksand is on the surface, and underlaid by a hard material, it is no more difficult to deal with than water, but when found between strata of harder material at considerable depth, great difficulty will be ordinarily experienced in working in it, for the reason that as the depth below the surface increases, the pressure increases and the flow of the liquid or semiliquid materials allows the stratum on top of it to settle, bringing great pressure on the sides of the caissons, sheet piling, or cribbing, either crushing it or throwing it out of

line. The material falling on top of the quicksand increases the amount of material to be excavated and usually adds very greatly to the cost of the foundation of the structure.

Owing to the fact that quicksand flows and runs so readily, the greatest precaution must be exercised in working in this soil adjacent to the foundations of a building or structure. Instances have been known where the undue removal of sand and water, while boring a hole for a direct plunger elevator, imperiled the adjacent foundations by removing some of the stratum from beneath the footings with the detritus from the hole. It is likewise a necessary precaution to have all sewers and drain lines running near footings and on a lower level, and that are built in soils partaking of the nature of quicksand, so carefully constructed and inspected that there can be no possibility of bleeding the foundation stratum.

11. If quicksand is encountered in building construction, the only successful method of dealing with it is to use sheet piling in the excavation, keeping it in position by horizontal bars and bracing. The piling must be of sufficient thickness to withstand the bending strains due to the pressure of the quicksand. These piles should be tongued and grooved or connected with loose slip tongues. If the excavation can be carried on at the same time with the driving, it is possible to drive the piling with a heavy maul, or, if the material is soft enough, it may be driven with a maul before the excavation is made. If the material is of a clayey nature, and the excavation can not be carried along as the piling is driven, it may be impossible to drive it any distance with the maul. In such cases, a portable steam pile driver, which fits on the head of the pile, built on the same lines as a steam rock drill, may be used to advantage. By means of this driver, the piles may be driven to a considerable depth before the excavation is made, and as the material is thrown out of the trench or pit, shores can be put in place and the trenches carried down for some distance without any displacement of the adjacent material unless it is so thin that it will slip down under the piles and come up into the trench, in which case, if the

amount of material coming into the trench is considerable, the whole temporary structure must collapse because of the displacement of the material behind it. In such cases, several methods of founding may be followed. One is the freezing process, in which the earth adjacent to the excavation is frozen hard by means of brine from a portable refrigerating plant, which is circulated through pipes that are sunk into the ground around the sides of the proposed excavation. After the ground is frozen, the excavation can be carried on as with other hard material.

Another method is by sinking either pneumatic or open caissons through the material. If the material is very soft and fluid, the pneumatic caisson must be employed. Open caissons of hollow brick or concrete, or iron cylinders, or timber-lined shafts can be sunk to great depths through soft material and ultimately filled with concrete and masonry. In sinking these open caissons, the material is excavated from the inside and weights are built or placed upon the caissons, causing them to sink. If brick or concrete cylinders are used, the bottom must rest on a timber or iron curb with a cutting edge.

Pneumatic caissons usually consist of a strong grillage of timber, laid diagonally and crosswise, strongly bolted together, beneath which a strong cutting edge of timber, sheathed with iron, is provided. The height of this cutting edge is sufficient to permit the work to be carried on beneath the under side of the caisson. An air pressure sufficient to prevent the material from running in around the cutting edge is maintained in this open space. As the material is excavated from beneath it, the caisson sinks. The excavated material is taken out in buckets through the air lock. As the caisson sinks, the masonry is built upon it until the cutting edge finally reaches the hard material, after which the space between the cutting edge and the under side of the timber platform is filled with concrete.

Another method of dealing with quicksand is to solidify it by liquid cement by means of pipes sunk into the ground. Liquid hydraulic cement is forced down through one pipe

and suction is maintained in the other; by this means the cement is drawn from the supply pipe over to the exhaust pipe and the intervening material is saturated with it. By changing the position of the pipes often enough, a stratum or area of quicksand saturated with cement can be produced, which, upon hardening, forms an artificial stone.

12. Culm.—It is frequently necessary in the anthracite regions to build at least temporary structures upon culm or refuse from mines. This material is composed of fine particles of coal and slate, being exceedingly springy or elastic when in beds of considerable thickness and is a dangerous material upon which to build. This is especially true when it is not thoroughly confined or the building is so situated that its foundations are not well within the slope of repose, or slope which the material naturally assumes when dumped or piled loosely. Another great danger in building upon culm and similar materials exists in the liability of the material to be washed away by heavy rains, fire-streams, or leaky mains. Under no condition should culm be subjected to a greater pressure than $\frac{1}{2}$ to $\frac{3}{4}$ ton per square foot.

13. Foundations Over Mines, Etc.—Large buildings have been destroyed by the failure of the principal piers built over long-disused cisterns or vaults, which in the course of time have been forgotten and filled over. A principal pier in one instance did not break through the covering of the cistern until the building was far along in its construction, so that the failure of the pier precipitated the destruction of almost the entire building.

In the hard-coal section of this country, cities of importance are frequently undermined by galleries or veins which have been worked, and these are often near the surface. When heavy buildings are erected in such localities, the position of the building with reference to these mine workings must be investigated; then, if the roof of the working does not seem to offer adequate strength, some means of support must be provided. The working, if abandoned, may be filled, or a better method would be to extend piers through to the solid floor.

One great danger exists in such localities from the fact that surface water is likely to run along the hard-pan or shaly roof of the working, and thence down through fissures in some abandoned working. In such an instance a tunnel will frequently be formed by the action of the subterranean stream, and where a heavy foundation is placed above, damaging settlement is likely to occur which may possibly cause the failure of the building.

BEARING VALUE OF FOUNDATION SOILS

14. There is some difference of opinion regarding the safe bearing value of foundation soils, due probably to the difficulty of arriving at any experimental results that will have a general application. Conservative engineering practice, however, dictates that the greatest unit pressure on the different foundation soils shall not exceed the values given in the following table:

TABLE I
SAFE BEARING VALUES OF DIFFERENT FOUNDATION SOILS

Materials	Tons per Square Foot
Granite rock formation	30
Limestone, compact beds	25
Sandstone, compact beds	20
Shale formation, or soft friable rock	8 to 10
Gravel and sand, compact	6 to 10
Gravel, dry and coarse, packed and confined	6
Gravel and sand, mixed with dry clay	4 to 6
Clay, absolutely dry and in thick beds	4
Clay, moderately dry and in thick beds	3
Clay, soft (similar to Chicago clay)	1 to 1½
Sand, compact, well-cemented, and confined	4
Sand, clean and dry, in natural beds and confined	2
Earth, solid, dry, and in natural beds	4

BUILDING LAWS REGARDING FOUNDATION SOILS

15. The observance of the revised building laws of the several cities is considered good engineering practice, for they are usually the results of careful investigations and records of long experience. The following, quoted from the New York Building Law, is interesting and gives bearing values that are well within the safe limits.

Where no test of the sustaining power of the soil is made, different soils, excluding mud, at the bottom of the footings shall be deemed to safely sustain the following loads to the superficial foot, namely:

Soft clay, 1 ton per square foot.

Ordinary clay and sand together, in layers, wet and springy, 2 tons per square foot.

Loam, clay, or fine sand, firm and dry, 3 tons per square foot.

Very firm, coarse sand, stiff gravel, or hard clay, 4 tons per square foot, or as otherwise determined by the Commissioner of Buildings having jurisdiction.

Where a test is made of the sustaining power of the soil, the Commissioner of Buildings shall be notified so that he may be present in person or by representative. The record of the test shall be filed in the Department of Buildings.

When a doubt arises as to the safe sustaining power of the earth upon which a building is to be erected, the Department of Buildings may order borings to be made, or direct the sustaining power of the soil to be tested by and at the expense of the owner of the proposed building.

MATERIALS OF STRUCTURAL ENGINEERING

(PART 2)

MASONRY

INTRODUCTION

1. The materials of masonry construction include stone, brick, terra cotta, and the cementing materials—cement, lime, and sand—used in the manufacture of the mortars. That an intelligent working knowledge of these materials may be had, it is necessary to know something of the elements that compose them.

Though an extensive knowledge of chemistry and geology would be valuable to the structural engineer, his practice involves only an elementary knowledge of these subjects. This acquaintance is necessary, however, in order that he may know the chemical and physical nature of the materials with which he builds. Therefore, the first portion of this Section is devoted to a brief description of the principal elements of nature that combine to constitute stones and minerals, and following this is given a condensed geological description that will furnish an insight into the physical formation of the rocks from which building stones are obtained.

2. **Elements and Compounds.**—Every substance or mass of matter is either an *element*, a *compound*, or a *mixture*.

Any substance that can be decomposed or divided into separate substances is called a **compound**. For example, if an electric current is passed through water, the water slowly

For notice of copyright, see page immediately following the title page

disappears and two gases are formed. These gases are entirely unlike, and neither resembles the water from which it was produced. Likewise, lime can be divided into two other substances, calcium and oxygen.

There are substances, however, like iron, gold, sulphur, and arsenic, that have never been decomposed into other substances. These are called **elements**.

In referring to an element, it is customary to simply use the *symbol*, which is usually the first letter of the name. Thus, *H* stands for hydrogen, *C* for carbon, etc.

CHEMICAL ELEMENTS

3. About seventy elements have been found in the earth, but of these, fourteen in various combinations form nearly the entire crust of the earth. These elements, named in the approximate order of their importance, are oxygen, silicon, aluminum, iron, calcium, magnesium, potassium, sodium, carbon, hydrogen, phosphorus, sulphur, chlorine, and manganese, to which may be added nitrogen, for though it does not enter into the rocks to a great extent, it forms about 79 per cent. of the air.

As all these elements are ready to form combinations with others, they are seldom found uncombined and there is a constant tendency to change, the old combinations being broken up and new combinations being formed. One of the most active of the elements in this respect is oxygen.

4. Chemical Combination.—When two or more elements are brought into contact under favorable circumstances, they will combine and form a substance unlike either of the elements. For example, hydrogen, an exceedingly light gas, will burn in the air with a light blue flame. This burning is a form of chemical combination, in which the hydrogen unites with another gas, the oxygen of the air, and forms water, a substance with which we are all familiar.

Chemical combination produces heat; chemical separation, on the other hand, absorbs heat. Thus, if carbon and oxygen are brought together at high temperature, they will

combine and form carbon dioxide; hydrogen and oxygen combine to form water; hydrogen, nitrogen, and oxygen, when combined in certain proportions, form nitric acid; a given volume of nitrogen and three times that volume of hydrogen combine and form ammonia, a gas that differs greatly from both nitrogen and hydrogen. In each of these combinations a certain amount of heat is produced; to separate the elements again an amount of heat will be absorbed exactly equal to that produced by their combination.

5. It is supposed that the *molecules* of most elements, such as hydrogen or oxygen, are composed of two *atoms*. A *molecule* is the physical unit, or the smallest portion which, so long as the substance is chemically unchanged, keeps together without complete separation of its parts, while an *atom* is the chemical unit, or the smallest mass of an element that can exist. It is further supposed, by chemists, that equal volumes of all gases, whether simple or compound, contain the same number of molecules; thus, a cubic foot of hydrogen, a cubic foot of air, a cubic foot of steam, contain the same number of molecules.

Suppose, now, that a cubic foot of hydrogen gas is allowed to come into contact with a cubic foot of chlorine gas; if the mixture is exposed to heat or light, the gases combine. The process of combination is explained as follows: There is a certain attraction or affinity between the hydrogen and the chlorine atoms. Under the influence of heat or light, this attraction becomes so strong that the two atoms composing the molecule of hydrogen are torn apart. Likewise, the atoms composing a molecule of chlorine separate. Each atom of chlorine seizes upon an atom of hydrogen and forms a molecule of an entirely new gas, viz., hydrochloric acid gas. Since each atom of chlorine takes one atom of hydrogen, it is plain that the number of molecules of each gas must be the same. In other words, a cubic foot of chlorine requires a cubic foot of hydrogen to combine with it; these gases cannot be made to combine in any other proportion. For example, if 3 cubic feet of

chlorine were placed in contact with 2 cubic feet of hydrogen, 4 cubic feet of hydrochloric acid gas would be formed, and the extra cubic foot would still remain chlorine. The symbol for hydrochloric gas is HCl .

Suppose, now, that hydrogen and oxygen are placed in contact and heated; they will combine and form steam (or water). But it will be found that each atom of oxygen seizes two atoms of hydrogen to form a molecule of water, and, therefore, the volume of hydrogen must be double the volume of the oxygen with which it combines. This is shown by the symbol for water, H_2O ; that is, two parts or atoms of hydrogen to one of oxygen. Similarly, the symbol for ammonia is NH_3 ; that is, three parts of hydrogen to one of nitrogen. Again, hydrogen and carbon form a compound; each atom of carbon seizes four atoms of hydrogen and forms a molecule of marsh gas; the symbol for marsh gas is therefore CH_4 .

The symbol of any compound indicates how the atoms of the elements combine to form the compound. Thus, the symbol H_2O shows that two atoms of hydrogen and one of oxygen unite to form a molecule of water. The symbol H_2SO_4 (sulphuric acid) shows that a molecule of the sulphuric acid contains two atoms of hydrogen, one of sulphur, and four of oxygen.

6. Combination by Weight.—A cubic foot of hydrogen combines with just 1 cubic foot of chlorine. On weighing each gas, it is found that the cubic foot of chlorine weighs 35.5 times as much as the cubic foot of hydrogen. A cubic foot of oxygen weighs 16 times as much as a cubic foot of hydrogen.

As like volumes of gases contain equal numbers of molecules, and oxygen and hydrogen molecules contain two atoms each, like volumes of the two gases must contain equal numbers of atoms. Now, since the former weighs 16 times as much as the latter, it follows that an atom of oxygen weighs 16 times as much as an atom of hydrogen. Similarly, an atom of chlorine weighs 35.5 times as much as an atom of

hydrogen. This ratio between the weight of an atom of any element and the weight of an atom of hydrogen is called the **atomic weight**, or the **chemical equivalent**, of the element. The atomic weight of any element (or compound) may be found by dividing the weight of a given volume, say a cubic foot, of the element, when in a gaseous state, by the weight of a cubic foot of hydrogen. The atomic weight is, therefore, about the same thing as specific gravity, hydrogen being the base of comparison instead of water or air. Elements combine with other elements or parts of compounds in proportion to their atomic weight, or some simple multiple of it.

7. The atomic weights of some of the elements considered in this Section are as follows:

Hydrogen, <i>H</i>	1.0
Oxygen, <i>O</i>	16.0
Nitrogen, <i>N</i>	14.0
Carbon, <i>C</i>	12.0
Sulphur, <i>S</i>	32.0
Chlorine, <i>Cl</i>	35.5

By the aid of these atomic weights, the composition of any substance, by weight, can be found when its symbol is known. For example, take water, *H₂O*; multiply the number of atoms of each element by the atomic weight of the atom. Thus,

$$2 \times 1 = 2 \text{ parts, by weight, of hydrogen}$$
$$1 \times 16 = 16 \text{ parts, by weight, of oxygen}$$
$$\underline{\hspace{1.5cm}} \\ 18 \text{ parts, by weight, of water}$$

Water, then, is composed of $\frac{2}{18} = 11.11$ per cent. of hydrogen, and $\frac{16}{18} = 88.89$ per cent. of oxygen.

As another example, take carbon dioxide, *CO₂*. We have

1 atom of *C* × atomic weight, 12 = 12 parts, by weight, of *C*

2 atoms of *O* × atomic weight, 16 = 32 parts, by weight, of *O*

$\underline{\hspace{1.5cm}}$
44 parts, by weight, of *CO₂*

Hence, *CO₂* contains $\frac{12}{44} = 27.27$ per cent. of carbon and $\frac{32}{44} = 72.73$ per cent. of oxygen. From these examples it is

plain that the atomic weight of water is 18, and of carbon dioxide 44.

8. Mixtures.—Two or more elementary substances may be mixed together and yet not combine to form a new substance; they are then said to form a **mixture**. The mixture has the properties of the elements composing it. The most familiar example of a mixture is ordinary air, which is composed of 23 parts, by weight, of oxygen and 77 parts, by weight, of nitrogen. The two gases are not combined chemically; they are simply mixed.

9. Specific Gravity.—This value is the ratio of the weight of a given substance to that of a standard substance. For solids and liquids, the standard is pure water at a temperature of 62° F.; while for gas, the standard is usually hydrogen gas, though sometimes air. Frequently, however, the specific gravity of gases is measured with water as a standard.

The weight of a cubic foot of pure water at 62° F. is 62.355 pounds; so that in order to find the weight per cubic foot of any substance, the specific gravity of the substance is multiplied by 62.355; while to find the specific gravity of a substance, its weight per cubic foot is multiplied by the reciprocal of 62.355 or .016037. To ascertain the weight per cubic inch of a substance, its specific gravity is multiplied by .036085. With each element, briefly treated in the following description, are given the chemical symbols and the specific gravity. The values given for the gaseous elements are based on hydrogen as the standard, while those for solids have pure water at 62° F. for the basis of the value.

GASEOUS ELEMENTS

10. Oxygen, *O*, specific gravity 16, is a transparent, colorless, odorless gas. The word *oxygen* is derived from two Greek words that literally mean sour generator, or acid former, as it was formerly believed that oxygen was a constituent of all acids. The chemist Davy, however, showed that hydrogen and not oxygen was necessary for an acid.

Oxygen is found in both a combined and a free state. In the air it is mixed, but not combined, with nitrogen in the proportions of about 23 per cent. of oxygen and 77 per cent. of nitrogen. It is an important constituent of all animal and vegetable substances, and is contained in all mineral substances. In granite, slate, clay, limestone, and other rocks, except coal, the quantity of oxygen is nearly 50 per cent. It combines with all other elements except fluorine, which is a gaseous element never found uncombined. Water dissolves about 4 per cent. of oxygen; about 47 per cent. of the earth's crust is composed of it, while it constitutes about 86 per cent. of the water. Decay and the ordinary forms of decomposition are simply the result of oxidation.

11. Hydrogen, *H*, specific gravity 1, is the lightest of all known substances. As one of the two elements constituting water, it is found everywhere present in the crust of the earth. In combination with water, many minerals form the group of hydrous minerals. It exists in combination everywhere, as a constituent of water, of all plants and animals, and in numerous minerals, abundantly in coal, petroleum, bitumen, and in a lesser degree in rocks. The amount of water chemically combined in the rocks or mechanically held in the crevices is estimated to many times exceed the amount of water in the oceans.

Hydrogen, in combination with carbon, forms the *hydrocarbons* that are found in the rocks that contain the remains of animal and plant life, such as the rocks from which petroleum and natural gas are obtained.

Hydrogen, combined with the minerals, forms but .21 per cent. of the crust of the earth. The amount of it present in the air and water, however, increases the importance of this element.

12. Chlorine, *C*, specific gravity 35.5, is a nearly transparent gas, of a greenish-yellow color. Combined with magnesium, potassium, or sodium, it forms the chloride of which common salt is the most familiar example. It is never found in a free state. Chlorine is one of the strongest

oxidizing agents. It has a great affinity for hydrogen and most metals, of which it forms chlorides. Its most abundant compounds are chlorides, of which sodium chloride, $NaCl$, and magnesium chloride, $MgCl_2$, are the most common and widely distributed. Sodium and magnesium chlorides are found in sea-water, and all soils of the earth contain some sodium chloride.

Chlorine forms about .01 per cent. of the crust of the earth, but about 2 per cent. of the oceans.

SOLID ELEMENTS

13. Silicon, Si , specific gravity 2.49, is never found in a free state but is found chiefly in the form of the oxide, SiO_2 , commonly called *silica* or *silicon dioxide*, and also in combination with oxygen and several of the common metals, particularly with sodium, potassium, aluminum, and calcium, in the form of *silicates*, which are combinations of silicon with oxygen and other elements, as, for instance, feldspar, which is a complex silicate of aluminum and potassium. Silicon in one or the other of these forms is found in nearly all the rocks of the earth. In sandstone, it constitutes the greater part of the rock, while in coal it is only present in small quantities.

Next to oxygen, silicon is the most abundant element. Some extensive mountain ranges consist almost entirely of silicon dioxide, SiO_2 , in the forms known as *quartz* and *quartzite*. Other ranges are made up of silicates that are compounds formed by the combination of silicon dioxide and bases; that is, the greater number of rocks of the earth's surface are combinations of complex silicates, limestone, $CaCO_3$, being the only important exception. The clay of valleys, river beds, etc. also contains silicon in large quantities, while the sand found so abundantly on the seashore is mostly silicon dioxide, or pulverized quartz.

While it is difficult to decompose the oxide in such a way as to obtain the element, under proper conditions the silicon can be obtained in the form of crystals that are of a gray color and are harder than glass, although they are only a chemical curiosity. Crystalline silica is found as quartz,

rock crystal, and sand in variously colored varieties, and the amorphous (not crystalline) forms of flint, chalcedony, opal, and others. The specific gravity of quartz is about 2.6. It is very hard but not so hard as ruby, corundum, Al_2O_3 , and diamond. All forms of silica are more or less soluble in alkali by prolonged heating, but crystalline quartz is the least attacked. Silicon will not burn or dissolve in any acids except a mixture of nitric and hydrofluoric acids.

About 27 per cent. of the crust of the earth is composed of silicon, and therefore about 74 per cent. of the rocks are composed of oxygen and silicon.

14. Aluminum, Al , specific gravity 2.6, is a light, silver-white metal that is never found uncombined; its compounds are mostly silicates. It is the most abundant and widely distributed of all metals. Combined with oxygen it forms the oxide of aluminum, or *alumina*, Al_2O_3 . Aluminum is commonly found in combination with both oxygen and silicon and forms the group of minerals known as the silicates of alumina. Alumina is found in all rock formations, except limestone, and in nearly 200 minerals. Corundum, Al_2O_3 , is the richest of its ores. Emery is a mixture of the oxides of aluminum and iron.

The compounds of aluminum are difficult of reduction. The ruby and sapphire are Al_2O_3 , colored by impurities. About 8 per cent. of the crust of the earth is composed of aluminum and about 80 per cent. of the crust of the earth is composed of oxygen, silicon, and aluminum. The greater part of the clay soil and rocks is composed of these three elements.

15. Iron (*ferrum*), Fe , specific gravity 7.8, is rarely found in an uncombined state, but is usually found as an oxide. It is widely disseminated throughout the earth's crust, of which it constitutes about 5 per cent., and its presence is shown in the red and yellow colors in the soil and rocks.

Iron has a great affinity for oxygen and, combined with it, forms what is commonly known as *rust*, which is the hydrated

oxide of iron. It commonly exists in the soil in the form of the highest oxide and gives it the red and yellow color, but in the presence of an excess of organic matter, the ferric oxide is reduced to ferrous carbonate, and its red or yellow color is destroyed. The clay of swamps is always bluish, but if this clay is burned to brick the organic matter is destroyed and the iron peroxidized colors the brick red.

16. Calcium, Ca , specific gravity 1.578, is a brass-yellow lustrous metal that is never found in an uncombined state. In combination it is very widely distributed and is found in enormous quantities. It is found principally as *carbonate*, $CaCO_3$; in the form of limestone, marble, and chalk, as *sulphate*, $CaSO_4$; in the form of gypsum, as *phosphate*, Ca_3PO_4 . Calcium combined with carbon dioxide, CO_2 , and with another molecule of oxygen forms *calcite*, $CaCO_3$, which is present in some marbles and most limestones. Calcium is slightly soluble in water, and in solution forms the source from which fish, shell fish, and reef-building corals derive the materials from which to build their shells, cells, etc. Calcium in combination with sulphur and oxygen forms *gypsum*, $CaSO_4 + 2H_2O$.

Calcium enters into the composition of many of the complex silicates, and therefore forms a constituent of many of the rocks. In the form of carbonate, such as chalk and the various limestones, it forms an enormous rock mass in different parts of the earth. In some districts the sulphate or gypsum is found in considerable quantities. The chief varieties of native calcium carbonate, or carbonate of lime, are the amorphous forms, chalk, and the various kinds of limestone, the crystalline forms of marble, and the well-crystallized forms of calcite, or Iceland spar, and aragonite. Nearly 4 per cent. of the crust of the earth is composed of calcium.

17. Magnesium, Mg , specific gravity 1.7, is a less abundant element than calcium, but is almost invariably associated with it. It is a silver-white metal with a high luster, and is never found in a free state. Magnesium carbonate

is found as *magnesite*, $MgCO_3$, but usually occurs with calcium carbonate in dolomite and magnesian limestones. The sulphate and carbonate may be found in many natural waters. As silicate, magnesium enters into the composition of numerous minerals, as soapstone, serpentine, and meerschauum, while asbestos, hornblende, and many other silicates, contain this element. Magnesium forms about $2\frac{1}{2}$ per cent. of the crust of the earth.

18. Potassium (*kalium*), K , specific gravity .875, is a white metal with a bright, metallic luster. It is so light as to float on water. It is a constituent of many minerals, particularly feldspar, which is a complex silicate of aluminum and potassium. It is never found in a free state, but is present as a silicate in the older Plutonic rocks, which are rocks formed from molten material at a great depth and pressure and including the granites, and in a small quantity in most soils. It is also present in sea-water. Potassium forms about $2\frac{1}{2}$ per cent. of the crust of the earth.

19. Sodium (*natrium*), Na , specific gravity .973, is abundant, very widely distributed, and found in large quantities, principally as *sodium chloride*. It is found in a number of silicates and enters into the composition of an enormous number of rocks, being present in traces almost everywhere. It is a silver-white metal with a bright metallic luster, with a very light pink tinge, and is so light as to float on water. Sodium forms about $2\frac{1}{2}$ per cent. of the crust of the earth.

20. Carbon, C , specific gravity 3.52, is commonly found in combination with oxygen. In an uncombined state it is found in the form of diamond and graphite. It also forms part of the tissue of all animals and plants, and when these tissues decay or burn the carbon unites with oxygen to form *carbon dioxide*, CO_2 , which in combination with other elements forms the carbonates of which calcite (calcium carbonate) is an example.

Carbon is the central element of organic nature; every living thing contains it as an essential constituent. The number of compounds that it forms is almost infinite, and they

present such peculiarities that they are commonly treated under the head of "organic chemistry."

Carbon is present in a number of rocks, having been placed there by the agency of organic life, as in coal, where it has been taken from the air, and in limestone, where it has been taken from the water. .22 per cent. of carbon is estimated to be in the crust of the earth. The *diamond* is pure crystallized carbon.

21. Phosphorus, *P*, specific gravity 1.84 to 2.01, is a yellowish, translucent, crystalline, waxy solid that is never found in a free state because of its affinity for oxygen and other elements. Combined with oxygen it forms the phosphates, of which phosphate of lime is the most common. Its compounds are quite abundant and widely diffused, the principal one being calcium phosphate, which occurs in certain minerals as *phosphorite* and *apatite*.

Phosphorus, in minute quantities, enters into the bones and tissues of many animals and the tissues of many plants. It constitutes but about .1 per cent. of the crust of the earth.

22. Sulphur, *S*, specific gravity 7.086, is found particularly in the neighborhood of volcanoes. It occurs also as sulphide, in combination with many metals, as in *iron pyrites*, FeS_2 , *copper pyrites*, $FeCuS_2$, etc. As sulphate, it occurs in combination with metals and oxygen, as *calcium sulphate*, or *gypsum*, $CaSO_4 + 2H_2O$.

Sulphur is found in the tissues of many animals and plants, and is found in the rocks in small quantities. It forms but about .03 per cent. of the crust of the earth.

23. Manganese, *Mn*, specific gravity 7.14 to 7.20, is said to be the hardest of metals. It is brittle, almost infusible, and looks like cast iron. It is easily oxidized in the air and dissolves in diluted acids. It forms alloys and imparts valuable properties to steel, perhaps by combining with such impurities as sulphur and phosphorus, but this is uncertain. Manganese is widely disseminated and its presence is often shown by black and purple stains on the surface of the rocks. It forms less than 1 per cent. of the crust of the earth.

COMMON MINERALS

24. The elements, when they unite, follow definite laws and produce definite results, uniting themselves in regular proportions, forming molecules, which, if free to act under favorable conditions, often assume regular geometrical forms or crystals. These combinations produce *minerals*, which (with the exception of mercury) may be defined as homogeneous solids of definite chemical composition, found in nature, but not of apparent organic origin.

A mineral may be composed of a single element, such as gold, silver, copper, lead, etc., or it may be made up of two or more elements chemically combined, as is usually the case. These elements may be only slightly bound together, as in the case of sulphide of mercury, which may be disunited by the action of heat, or they may be so firmly united and their chemical affinity so strong that, like silica, they may resist almost any effort to separate them. Therefore, some minerals are enduring and others are unstable, and while the chemical composition is definite, it is subject to change whenever the conditions are favorable. These changes are the cause of the decay and crumbling of rocks.

Minerals are frequently formed under conditions that do not permit sufficient room for the perfect development of the crystals; therefore, the perfect crystal is rare. When the crystal is not perfect, though the internal structure shows a crystal formation, the mineral is termed *crystalline*.

Some minerals, like diamonds and quartz, are exceedingly hard, while others, like graphite or black lead, are soft. Some are brittle and others are plastic. Most of the minerals are crystalline, though sometimes built up in irregular shapes, to which is applied the term *amorphous*, which means not crystalline.

The minerals that make up the greater part of the earth's crust, named approximately in the order of their importance, are:

- | | |
|---|-------------------------------------|
| 1. Quartz. | 6. The pyroxene group. |
| 2. The group of feldspars. | 7. The group of iron minerals. |
| 3. The group including calcite, dolomite, and siderite. | 8. Gypsum. |
| 4. The group of micas. | 9. Salt. |
| 5. The amphibole group. | 10. Ice and its liquid form, water. |

25. Quartz.—Quartz (*silica*, SiO_2) is the most abundant mineral in the crust of the earth. In color it varies from a transparent rock crystal to a jet-black glassy mass. It is often colorless, though sometimes topaz-yellow, amethystine, rose, smoky, and other tints occur, also quartz of various shades of red, yellow, green, blue, or brown are found. In some varieties, the colors are in bands, stripes, or clouds, of all degrees of transparency to opaque, of a vitreous luster, with brilliant crystals, sometimes dull and often waxy.

The common mineral impurities of quartz are chlorite, rutile, asbestos, actinolite, tourmaline, hematite, and limonite. Hematite, or the red oxide of iron, is usually the red coloring matter; limonite, another oxide of iron, is the yellow coloring matter. Chlorite and actinolite give the green color, and an oxide of silicate of nickel an apple-green tint. Manganese gives an amethystine color, and carbonaceous matter, such as color marsh waters, the smoky-brown shades. Quartz crystals often contain liquid in cavities, either water, petroleum, or liquid carbon dioxide. Clear quartz is sometimes speckled with scales of mica or rendered opaline by means of asbestos. Flint or chert are often colored by mixture with the materials of the enclosing rock.

Quartz is sometimes amorphous, but usually crystalline, and is often found in perfect crystals; the varieties of the latter include agate, amethyst, and jasper. Quartz is light in weight, brittle, and so hard that it cannot be scratched with a knife. Its chemical composition is strongly fixed and silica, or quartz, once formed, remains as silica throughout all the changes to which rocks are ordinarily subjected. By reason of its hardness and chemical strength, quartz may

give a great durability to rock. There is no common mineral that resists destruction so well.

Quartz is found in various forms and colors, but may be distinguished by the lack of true cleavage, by hardness, infusibility before the blowpipe, and insolubility with the common acids.

It is found nearly everywhere on the earth's surface, but is particularly abundant in granite rocks, sandstone, and most of the soils. Wherever found, it is fresh, pure silica, and in this it differs from many of the common minerals, which are so liable to decay.

The varieties of quartz may be classified as *vitreous*, distinguished by their glassy fracture; *chalcedonic*, having a subvitreous or waxy luster and generally translucent; *jaspery cryptocrystalline*, having little or no luster, and opaque. The vitreous varieties comprise rock crystal, amethyst, rose quartz, false topaz, smoky quartz, prase, aventurine quartz, and ferruginous quartz. The chalcedonic varieties comprise chalcedony, chrysoprase, carnelian, sard, agate, onyx, cat's-eye, flint, rhomb spar, chert, and plasma. The jaspery varieties comprise jasper, bloodstone, Lydian stone, touchstone, basanite, besides other varieties arising from the structure.

26. Feldspar Group.—The name *feldspar* is given to all silicates of alumina with some other elements, such as magnesium, potassium, and calcium. Each species differs slightly from the other in chemical composition and mineral form. The two most common divisions are **orthoclase** and **plagioclase**. The former name signifies that the mineral has the lines of cleavage at right angles to each other, while the latter designation means that there are two prominent lines of cleavage oblique in direction.

Feldspar is variable in color, light in weight, and almost as hard as quartz. While quartz may be distinguished by its lack of cleavage, feldspar has distinct cleavage planes. Feldspar is always crystalline, though good crystals are not common. It is not as soluble as the nearly insoluble quartz,

but when exposed to the weather it begins to change and crumble and in time changes from a clear, hard, glassy mineral to a dull, opaque substance that can be scratched with a knife, and finally becomes a powdery white clay known as *kaolin*, from which fine chinaware is made. In changing to kaolin, some of the original sodium, calcium, or potassium enters into combination with other elements, producing a soluble salt that can be removed by solution in water; therefore, when exposed to the weather, rocks that contain feldspar decay and crumble.

27. Calcite Group.—The mineral in the calcite group is carbonate of lime, $CaCO_3$, and though commonly white, may be any color. It is usually crystalline but frequently amorphous. It is easily scratched with a knife, light in weight, and cleaves readily in two or three directions. Its principal varieties are Iceland spar, dog-tooth spar, satin spar, and limestone (a general name for a massive calcite as well as for massive dolomite), as well as granular or crystalline limestone, which includes all the fine marbles, compact limestone, chalk, hydraulic limestone, oolite, pisolite, argentine, etc.

Calcite is the main constituent of limestone and is one of the most abundant of the common minerals. It is present in nearly all waters on or in the earth, and is being constantly formed by the destruction of minerals that contain calcium. Its presence in water makes it possible for many animals and some plants to take it from solution and build it into their skeletons or substance, from the remains of which great beds of limestone are deposited in the sea.

Calcite, not being chemically strong, is not a durable substance, and hence rocks made of it do not resist the weather well.

28. Dolomite, or Magnesian Limestone.—Dolomite is calcium magnesium carbonate, $CaMgCO_3$, and its usual colors are white, or white tinged with yellow, red, green, brown, and sometimes black. Iron and manganese are often present, replacing part of the magnesium or calcium.

Iron-bearing varieties become brown on exposure, and magnesia-bearing varieties, black.

The principal kinds of dolomite are the white, crystalline, granular, and the white, massive varieties, of which the former resembles granular limestone and the latter is extensively used as a marble. The latter species include pearl spar, rhomb spar, and brown spar. Dolomite resembles calcite in that it burns to quicklime but is somewhat more resistant. It forms great beds of magnesian or dolomitic limestone, which is closely associated with calcite.

29. Siderite, or Spathic Iron.—Spathic iron, iron carbonate, or chalybite, FeO, C or $FeO + CO_2$, often contains some manganese oxide or magnesia and lime replacing some of the *iron protoxide*, FeO . The iron, on exposure to air, becomes *hydrous sesquioxide*, that is, an iron oxide having three parts oxygen to two parts of iron, and gives the siderite a brown or brownish-yellow color. The crystallized or foliated variety is called *spathic* or *sparry iron* because the mineral has the aspect of a spar or crystallized mineral. The cleavage of siderite resembles calcite, calcinite, and dolomite.

The argillaceous variety occurs in nodular or lumpy forms and is called clay ironstone, and is abundant in coal measures.

Siderite occurs in rocks of various ages and often accompanies other ores. Large deposits exist in gneiss and mica schist, clay, slate, also in some limestone and in the coal formations, principally in the form of clay ironstone.

30. Mica Group.—Mica is a general name applied to a large number of minerals that are complex silicates of aluminum and some other metals, as potassium, lithium, and magnesium. There are numerous species of mica, depending on differences in chemical composition. The one characteristic feature of them all, however, is the cleavage, which is such that the mineral splits readily into thin elastic plates.

Micas vary in color from light brown to deep black, and are very soft. They decay readily, forming soluble and insoluble products, the soluble part passing off in the water, the

insoluble parts usually remaining as clayey remnants. Some micas are not so easily decayed, however, and are frequently found in the soil, on the beach, and in beds that have been made from the decay of other rocks.

Mica is common in lava, granites, and many other rocks. The common mica is called *muscovite*, which varies in color from white to green, yellow, and brownish shades, rarely rose red or reddish violet. Mica possesses a pearly luster and is transparent or translucent. It is a constituent of granite, gneiss, and mica schist.

31. Amphibole and Pyroxene Groups.—The minerals of these groups possess distinct chemical and crystalline characteristics, which can be distinguished in the crystal, but which resemble each other so closely that they cannot readily be distinguished by the naked eye. *Hornblende* is the common representative of the amphibole group and *augite*, of the pyroxene group.

These minerals are found in many of the lavas and granitic rocks and are commonly dark-colored with jet-black grains. They are complex silicates, and iron is often present. They easily decay, forming reddish or yellowish stains of iron rust as the iron becomes an oxide. Much of the iron coloring matter of the soil is formed by their disintegration.

32. Ores of Iron.—In addition to siderite, which is a carbonate of iron, several oxides of iron and the sulphide of iron are quite common. Of the oxides, the most common is *magnetite*, Fe_3O_4 , a black mineral, frequently crystalline, and found in many of the volcanic rocks, in ore beds, and elsewhere. When magnetite rusts, it forms *hematite*, Fe_2O_3 , which is the commonest of the iron ores, and forms the red coloring matter of the rocks. When hematite is further oxidized, it becomes *limonite*, $2Fe_2O_3 \cdot 3H_2O$. The sulphide of iron or pyrites, FeS_2 , is found in many of the rocks in the form of cubical or other crystals, and is of a brownish-yellow color and commonly known as *fool's gold*.

33. Gypsum (Hydrous Calcium Sulphate).—Gypsum, $CaSO_4 + 2H_2O$, is sulphate of lime, and is formed by the

decomposition of lime-bearing minerals or by alteration of the carbonate of lime by the sulphate. It is soluble in water. Gypsum, in appearance, resembles calcite somewhat and has a cleavage nearly as perfect as that of some of the micas, but the cleavage plates are not elastic. While present all through the crust of the earth gypsum is not abundant. It is rarely found in large quantities, and when it is thus found it is mined for plaster of Paris. Its principal varieties are selenite, radiated and fibrous gypsum, and alabaster.

34. Salt, or Halite.—Salt is *chloride of sodium*, NaCl . Chlorine, which is one of the strongest of the oxidizing agents, has such strong affinities that it never occurs in a free state. Its most abundant compound is sodium chloride, which is very soluble. The salt in the ocean has been originally derived from the rocks reaching it in solution.

35. Ice.—Ice is a substance that plays a very important part in the changes that occur in the earth's crust. Water in freezing and producing ice expands with great force; this expansion is one of the most destructive agents in nature, and one with which the engineer has frequently to combat.

FORMATION AND CHARACTERISTICS OF ROCKS

36. Definition.—The term **rock** is commonly defined as a hard mass of mineral matter, composed of one or more kinds of minerals, having, as a rule, no definite external form and liable to vary considerably in chemical composition. According to geology, however, rock includes all the consolidated materials forming the crust of the earth, such as sand, gravel, and clay, as well as the fragmental or detrital beds that have been derived from it.

37. Classification.—Rocks are divided into two principal kinds, according to their structure and origin, namely, *stratified* and *unstratified*. **Stratified rocks** are more or less consolidated sediments and are therefore aqueous in origin and earthy in structure. **Unstratified rocks** have

been more or less fused and are therefore igneous in origin and either crystalline or glassy in structure.

The rocks of the earth's crust owe their formation to five different causes:

1. The solidification of molten rock, as, for instance, the lavas.

2. The chemical precipitation from water, as illustrated by the beds of salt.

3. The action of animals or plants, as exemplified in the case of coral or coal strata.

4. The mechanical destruction of other rocks, as in the sand and clay beds.

5. The alteration or metamorphism of one of these classes of rocks, as exemplified in the case of marble.

Rocks that owe their formation to the first cause are termed *igneous*. Rocks that owe their formation to the second, third, and fourth causes are termed *sedimentary* or *stratified*; the fifth class is termed *metamorphic*.

UNSTRATIFIED, OR IGNEOUS, ROCKS

38. Unstratified, or igneous, rocks can be distinguished by the absence of true stratification or the lamination by sorting of material, by the absence of fossils, by crystalline or glassy texture in place of an earthy texture, and by their mode of occurrence, all of which characteristics are due to their mode of origin. The igneous rocks have consolidated from a state of fusion or semifusion instead of being deposited as sediments. Their original fused condition is shown by the crystalline or glassy texture, and by their occurrence in fissures, which shows that they were injected in a molten state; also by their effects, due to their heated condition, on the stratified rocks with which they come in contact.

Igneous rocks occur in three principal positions: underlying stratified rock and appearing on the surface in large masses, particularly in the mountain regions; in vertical sheets intersecting the stratified rocks or other igneous rocks;

in streams or sheets overlying the stratified rocks or sometimes between the strata, sometimes as veins connected with the underlying masses of igneous rocks. They occupy but a small portion of the surface of the earth, estimated to be about one-tenth of the land surface, but underneath the stratified rocks they are supposed to form the great mass of the earth.

Igneous rocks are classified into two groups: the *Plutonics*, or the *granitics*, and the *volcanics*, or the true *eruptives*. The **Plutonics** are coarse-grained and occur only in great masses either underlying the stratified rocks or appearing on the surface over wide areas, especially in the axes of mountain ranges. Usually, the **granitics** have not been erupted at all, although they often form the reservoirs from which the eruptive rocks are derived. The **volcanic**, or **eruptive**, rocks are fine-grained, sometimes glassy, and are found in sheets injected among the strata or as streams and sheets outpoured on the surface. The term *trappean* has been applied to the eruptive rocks that are injected among the stratified rocks.

These rocks may be briefly summarized as the *granitic*, which occur beneath, the *trappean*, which are injected among, and the *volcanic*, which are outpoured on, the stratified rocks.

39. Granitic, or Plutonic, Rocks.—The granitic groups are found in great masses and never in sheets or streams. They are very coarse-grained in texture and have a mottled or speckled appearance, due to the crystals of which they are formed being of considerable sizes and of various colors aggregated. These crystals mainly consist of quartz, feldspar, mica, and hornblende. The quartz crystals are bluish, glassy, transparent spots. The feldspar crystals are opaque, whitish, greenish, or rose-colored crystals with fluted surfaces. The hornblende crystals are usually black spots. The mica may be distinguished by its thin, scaly structure, the color of which is pearly or black. The term *granitic* has been applied to this group because granite is its best type; in fact, all these rocks are commonly

called *granite* by those unfamiliar with mineralogy. Thus, true granite consists of quartz, feldspar, and mica, with hornblende and talc sometimes appearing as impurities. Syenite is feldspar and hornblende frequently associated with quartz, mica, etc.

Igneous rocks, whether Plutonic or volcanic, are divisible into two subgroups: the *acidic rocks* and the *basic rocks*. In the *acidic rocks*, quartz and potash feldspar (orthoclase) predominate; in the *basic rocks*, hornblende or augite and soda lime feldspar (plagioclase) predominate. The acidic rocks are light-colored and not so dense as the basic group; the basic rocks are darker and heavier than the acidic group. These two groups, while sometimes sharply defined, frequently grade into each other. Granite is the best type of the acidics, and diorite, particularly gabbro and diabase, of the basics.

40. Trappean, or Intrusive, Rocks.—This group of rocks is intermediate between the Plutonics and the volcanics. They occur in sheets intruded among the strata, particularly of the older rocks. They are finer grained than the Plutonics and more crystalline than the volcanics, presumably because they cooled more rapidly than the Plutonics and less rapidly than the volcanics.

The trappean rocks are also divisible into acidics and basics. *Felsite* and *porphyry* are among the acidics, and *diorite* and *diabase* are among the basics. *Diorite* and *diabase*, when occurring among the intrusive rocks, are finer grained than the massive varieties. *Felsite* is a fine-grained, light-grayish rock, consisting essentially of orthoclase and quartz. *Porphyry* consists of a fine-grained, feldspar, ground mass, with large crystals of feldspar disseminated through it. Any rock is said to be porphyritic, however, if it consists of a fine-grained ground mass with large crystals of any kind disseminated through it, as porphyritic diorite and porphyritic granite.

41. Volcanic, or Eruptive, Rocks.—The volcanic, or eruptive, rocks are distinguished from the Plutonic and

trappean by their texture and mode of occurrence. In texture they are characterized by a crystalline structure, though some of the fine-grained varieties are microcrystalline and are in a more or less uncrystalline or glassy base or cement, showing that the fused mass has cooled too quickly to permit of complete crystallization. Frequently these rocks are in a wholly glassy condition.

These rocks are also divisible into the acidic and the basic. Trachyte may be taken as a type of the acidics. It is a light-colored rock and rough to the touch, consisting essentially of orthoclase with more or less quartz. When the quartz grains are conspicuous it becomes *rhyolite*. Phonolite is a dense variety, of light grayish color, that splits into slabs on weathering and has a metallic ring under the hammer. Obsidian and pumice are glassy scoriaceous (that is, of cinder or slaglike foundation) varieties of trachyte. Basalt is a type of the basics. It is a very dark, almost black, heavy rock, with an almost invisible fine-grained texture, and consists of plagioclase with augite, olivine, and magnetite. Dolerite has a similar composition, but has a more distinctly crystalline texture and is therefore dark grayish in color.

42. The volcanic or eruptive rocks have been formed in two ways: through the craters of volcanoes, in which the fused mass comes up through the opening and flows off in streams or is thrown out as cinders and ashes; or, it comes up through great fissures in the crust of the earth, frequently hundreds of miles long, and spreads as extensive sheets. These two methods of formation may be called *crater eruption* and *fissure eruption*. The greater part of the rocks on the surface of the earth is due to the latter method.

The fissure eruptions may be subdivided into three classes: *dikes*, *overflow sheets*, and *intercalary beds*.

Dikes are vertical sheets, filling great fissures in other igneous or stratified rocks and are the most common of all methods of occurrence of eruptives and intrusive rocks.

Overflow sheets are masses of lava that have come up, in liquid form, through great fissures and spread out on the

surface as extensive sheets. These sheets are often out-poured one on the other until they reach a total thickness of 2,000 to 3,000 feet. Some of these lava floods are of great thickness and extent. The whole of Southern California, Northwestern Nevada, and a great part of Oregon, Washington, and Idaho, and part of Montana and British Columbia, are covered with these lava floods, which are supposed to have come up in fissures in the Cascade and Blue Mountains, and spread as sheets covering the whole intervening space. The most extensive overflow sheets are usually basalt. The basic lavas, like basalt, were very liquid and spread out in thin sheets, while the acidic lavas were stiffly viscous and were squeezed out in dome shape.

Intercalary beds are sheets of rock found between strata. As such they may have been poured out on the bed of the sea or lake, and afterwards covered with sediment, or they may have broken through the strata for a certain distance and then have spread between the separated strata.

SEDIMENTARY AND METAMORPHIC ROCKS

43. Sedimentary.—Some rocks disintegrate through mechanical or chemical agencies more readily than others. For instance, in granite, the quartz will waste very slowly and then only as it is dissolved, for it will not be altered chemically; the feldspar and hornblende, being more complex, are less durable and soon commence to change, finally becoming the clay from which some of the elements go off in solution; the quartz grains, left without cementing material, fall out and the granite crumbles. From the original minerals of this rock, three different products result: soluble salts, fine clayey fragments, and larger grains of pure quartz. What is true of granite is also true, in a certain degree, of all rocks.

44. According to the way in which these mineral products are gathered into layers or strata, they may be classified into three groups of sedimentary rocks: the *fragmental*, or *clastic*; the *chemical precipitates*; the *organic*. The chemical

precipitates and some of the fragmental and organic rocks are of aqueous formation. Nearly all are stratified and some of each group are truly sedimentary.

45. Fragmental, or clastic, rocks are composed of distinct fragments of other rocks, gathered into layers by means of wind, ice, water, or volcanic eruption. Sandstones are formed of particles of sand that have been gathered into beds by one of these agencies and consolidated. Strata in which the material is transported by wind must necessarily be composed of fine grains or dust; ice, water, and volcanoes can transport particles of any size. The size of the particles transported by the wind or water will be determined by the velocity with which they are moved; therefore, by the varying action of these transporting agencies, the fragments are assorted into layers, according to their size, the coarsest being moved only by the stronger currents, while the finer particles settle in quiet air or water, giving rise to banding or stratification. This is also true of rocks transported by means of volcanic action, the larger pieces falling first and the finer particles or ash being carried great distances.

46. The pebbly rocks formed at the base of a cliff may be transported by water and rounded, forming pebbly or granite beds which, when consolidated into hard rock, become known as a **conglomerate**. The matrix is usually sand that contains a cement which binds the fragments together and consolidates the rock. Among the various kinds of conglomerate rock are limestone conglomerates, shale conglomerates, quartz-pebbly conglomerates, granite-pebbly conglomerates, etc. There are also volcanic conglomerates, composed of larger fragments of volcanic pumice and ash.

47. The **sandstones** may be coarse in texture, according to the size of the conglomerate, or very fine in grain, almost like clay, as exemplified in bluestone. Sandstones are usually composed of grains of quartz. There are also shale sands, magnetite sands, and garnetiferous sands.

Sandstones have been given different names, depending on the cement that consolidates the sand grains. *Argillaceous*

sandstone is applied to rock that has a clayey cement. If the grain is fine it is sometimes called an *arenaceous clay*. In *calcareous sandstone*, the cementing material is lime. If the cementing material is of iron, the rock is *ferruginous*, as in the brown and red sandstone. In *siliceous sandstone*, the cementing material is silica. In some sandstones, there are many small angular fragments giving the rock the character of a grit, which is used for grindstones. Sandstone rocks that split easily in every direction are called *freestones*. Sometimes, owing to the presence of many mica flakes, sandstone cleaves readily in only one direction and it is then said to be *shaly* or *micaceous sandstone*.

48. The clay rocks are so constructed that they frequently split into layers. Such rock is called a *shale*, the cleavage depending on many minute flat particles of mineral, often mica. Near the coral islands, the grinding action of the waves on the beach often wears the coral into fine clay, which, in settling to the bottom, forms a limy mud, afterwards becoming transformed into limestone. There are many other kinds of clay rocks, such as the *kaolin clay*, formed by the decay of feldspar; and *fireclay*, which has lost its alkalies by having them extracted by the plants that grew upon it, leaving the clay so free of alkali that it resists the action of fire. There are also sandy or *arenaceous clays*, containing considerable fine sand, and *carbonaceous clays* that contain fragments of plants.

49. Chemically precipitated rocks are interesting but not important. Chemical precipitation, however, has much to do with the destruction of rocks.

Water passing through rocks often takes a mineral in solution from one place and places it in another; this is one of the ways in which rocks are cemented. The water often produces chemical reactions and sometimes completely changes entire beds of rock, as, for instance, certain limestones have been changed to magnesian limestone or dolomite, while others have been changed to iron beds by the precipitation of siderite or some other salt of iron from

some solution of iron in water. Other limestones have been changed to gypsum.

Pure rain water exerts very little power as a solvent in the dissolving of most minerals, but from decaying vegetation and from the air it derives impurities, including carbonic-acid gas, or it may encounter alkaline substances that are easily dissolved. These impurities transform the water, in some cases, into a weak acid, and in other cases, into a weak alkali, in which condition it may attack the minerals directly.

50. Organic rocks comprise calcareous, silicious, and phosphate rocks, and plant deposits.

1. *Calcareous Rocks*.—The greater part of the limestone beds of the earth have been formed through the agency of animals. In the oceans, there are reefs built of coral fragments, which are made of carbonate of lime that the coral animals have abstracted from the ocean water. On a great part of the ocean floor, an ooze or limestone mud is now forming deposits like the chalk, which originated in a similar manner. In past geological ages, a species of animal, now very rare in the ocean, built limestone beds that are known as *crinoidal limestone*. Limestones are composed of carbonate of lime, sometimes accompanied by numerous impurities that color them. When clay is present in large quantities, the rock is called an argillaceous limestone, which grades into a calcareous clay rock. They usually contain many fossil fragments of shells or corals.

2. *Silicious Rocks*.—These rocks, of animal origin, are not common. **Infusorial earth** is composed of the skeletons of microscopic animals and is found in shallow lakes and beneath some of the swamps. **Diatomaceous earth** is a silicious rock, geologically, containing large numbers of silicious cells of a plant belonging to the group of diatoms.

3. *Phosphate Rocks*.—In some places in the United States, particularly near Charleston, S. C., and Florida, and in certain sections of Tennessee, the bones of marine and land animals of great size have accumulated into bone beds.

MATERIALS OF

8 These rocks are phosphate of lime. They are known as phosphate rocks and are used to form the phosphoric acid of fertilizers. These phosphate rocks have no value for structural purposes.

4. *Plant Deposits.*—Vegetation takes carbon from the air and mineral substances from the water. With these substances they form their structure, which, on decaying, are returned in large part to the air of the earth. In swamps, where decay is retarded, the plant remains may accumulate in beds of peat which may later on become transformed into coal or mineral fuel, which is mostly composed of carbon. Peat, lignite or brown coal, bituminous coal, anthracite, and graphite are successive transformations of organic matter.

51. There are other forms of rock that are directly or indirectly of organic origin, while nearly all the sedimentary strata have some sedimentary animal or plant remains. Flint and chert are dense, hard layers of nodules of silica, some of which have been formed by silicious animals, although most of them appear to be of chemical origin.

52. Oolite is usually a limestone, although occasionally it is an iron or even a silicious rock. It is made up of minute grains resembling bunches of fish eggs, whence its name. Each of the rounded layers of nodules of silica, some layers like an onion. Oolite may be formed in three ways: by the action of lower forms of plant life, which build up the grains; by chemical deposit in water at the surface, as in the geyser origin of the Yellowstone; and by a chemical change, which causes a rock of a different origin to assume the conditions of an oolite. Oolite grains are now accumulating on many shores, as those of Florida and the Great Salt Lake.

Sedimentary rocks, particularly those that owe their origin to mechanical and organic agencies, are of the great importance to man, as they furnish him with most of building stones. At present sedimentary rocks are found all over the globe, on land and in the sea. More than one-half of the earth's crust that is visible is made of sedimentary strata.

53. Metamorphic Rocks.—These rocks are an intermediate series between the stratified and unstratified rocks. They are stratified, banded, or foliated rocks, but crystalline in texture, like the igneous rocks, and are usually destitute of fossils. This banding, however, is quite different from stratification, for it is an arrangement of crystalline minerals, while in sedimentary rocks it is usually a banding of fragments arranged according to size or color, etc. The metamorphic strata result from complex changes of other rocks, in which the elements are often made to combine in a new manner. Given the same assemblage of elements, the effects of metamorphism will produce the same result; thus, a schist may be formed from either a shale or a lava.

Metamorphic rocks are supposed to have been formed from sediments, like stratified rocks, but to have been subsequently changed by (1) heat, (2) water, (3) alkali, (4) pressure, (5) crushing. To produce metamorphism by heat alone, that is, dry heat, requires a temperature of 2,500° to 3,000° F., but in the presence of water an incipient change begins at 400° F., while complete hydrothermal fusion takes place at 800°. If any alkaline carbonate be present in the water, these effects occur at a still lower temperature. Pressure is necessary because without it it is impossible to have even such moderate heat in the presence of water.

Metamorphic rocks may grade into stratified rocks on the one hand and into igneous rocks on the other. They cover a large area; the older rocks especially, are found along the axes of great mountain chains. The whole of Labrador, the larger portion of Canada, the whole eastern slope of the Appalachian system, and also the axes of the Colorado and Sierra ranges consist of them. In Canada, they are supposed to be 40,000 to 50,000 feet thick. They are very much crumbled.

54. Metamorphism is nearly always associated with great thickness and crumbling. Some rocks, such as the igneous, were originally solid; many, such as the fragmental and organic, were unconsolidated. Metamorphism solidifies these

rocks and in some places changes them entirely. As a result of these changes, the strata are so altered that their original condition cannot be told at a glance. Sandstone becomes a dense quartz rock, called *quartzite*, in which the sand grains may be no longer visible to the eye. A peat bog may be changed to anthracite or even to graphite. A dense, apparently structureless, limestone, may become transformed to a white or variegated marble composed of many crystals of calcite, or a clay stratum may be metamorphosed into a slate, in which the dense rock becomes harder, although at the same time an ability to split easily in one direction is introduced. This is called *slaty cleavage* and is one of the features of metamorphism. The cleavage is developed because of many plates of micaceous material formed in the rock as a result of heat or the mashing together of the whole rock mass in a direction at right angles to the cleavage plane. In this change one of the conditions is great pressure, and as the minerals develop they grow in a plane at right angles to the direction of the pressure because this is the plane of the least resistance, and because of the many cleavage planes of the newly formed micaceous material, slate splits easily along these lines.

55. Metamorphism of slate rock continued further would develop other minerals and would soon be altered in character and become a *schist*, in which the various minerals are arranged in bands having a cleavage no less marked than that of slate. A schist will split into layers much less easily and uniformly than the slate. Schist is known by various names, depending on the minerals present, such as mica schist, hornblende schist, chlorite schist, etc. All these rocks are characterized by the banding and the ease of splitting, which is due to the schistose structure arising from the banding of the minerals along these planes. As in the case of slate, these bands are at right angles to the direction of the pressure that was present during the metamorphism.

A final metamorphic change is one in which the original condition is hidden. The last stage before actual melting

takes place produces **gneiss**, which resembles granite, except that it has its minerals more or less perfectly banded, while granite is massive and without layers. In granite and gneiss, the minerals are frequently the same in kind and in general formation.

56. Where metamorphism has taken place in sedimentary rocks, the changes are sometimes so pronounced that the stratification is destroyed and the original nature of the rocks is so changed that it is impossible to tell whether they were originally sedimentary or igneous. Metamorphic rocks are found in the earth's crust in three positions: first, near some mass of intruded igneous rock; second, in the core of mountains deep below the original surface; third, among the most ancient rocks, particularly the Archæan, which are the lowest and the oldest of all the rocks. In the latter place the metamorphic rocks occur in great masses.

It was formerly believed that metamorphic rocks were part of the original crust of the earth and represented the most ancient strata, but this belief has been proved erroneous and it can now be shown that the rocks that have been very much altered belong to later ages and are transformations of sediments belonging to the same general age as deposits of shales, limestone, and sandstone in adjoining regions.

JOINTS AND FISSURES IN ROCKS

57. All rocks—igneous, sedimentary, and metamorphic—are divided into separable blocks of different sizes and shapes by cracks in various directions; these cracks are called **joints**. In stratified rocks one of the division planes is between the strata and the other two nearly at right angles to this. The different kinds of rocks have blocks of characteristic shapes and sizes. In sandstone, for instance, the blocks are usually very large and roughly prismatic; in limestone, they are usually very regularly cubic; in shale, oblong rhomboidal; in slate, small and sharply rhombic; in granite, sometimes large and roughly cubic, sometimes scaling in concentric shells producing domes; in eruptives, of many shapes, such

as roughly cubic, roughly spherical columnar, etc. These joints are supposed to have been formed by the shrinkage of the rocks; in stratified rocks, in consolidating from sediments; in igneous or metamorphic rocks, in cooling from a state of fusion or semifusion. In stratified rocks, the joints are usually confined to the stratum, though some of the larger joints (*master joints*) run through several strata.

Fissures are undoubtedly formed by the movements of the earth's crust. Joints are cracks in the individual strata, while fissures are fractures of the earth's crust extending through many formations and continuing for great distances. Owing to the great horizontal pressure, due to the shrinkage of the crust of the earth, the crust is sometimes thrown into ridges and hollows, thereby producing enormous fractures parallel to the axis of bending; thus mountain ranges are produced parallel to mountain ranges, while sometimes a system is at right angles to the main system.

Great fissures occur in systems, usually parallel to the axis of elevation or length, and frequently extend for hundreds of miles, and are miles deep. When filled, at the moment of formation, with fused matter from below, they form *dikes*, and all great dikes and igneous overflows have been through such fissures. If these fissures are not filled at once with fused matter, but are afterwards slowly filled with mineral matter, they form *fissure veins*.

PHYSICAL PROPERTIES OF BUILDING STONE

58. The structural manner in which the constituent parts of the rocks are grouped together bears a greater relation to the value or quality of the rock than the character of the minerals composing it; or in other words, the **physical characteristics** may be, and frequently are, more important than the chemical qualities.

59. Density.—The weight, strength, and absorptive properties of stone are dependent on the **density**. Thus, among rocks having the same mineral composition but

differing as to structure, generally the strongest will be the densest, and the heaviest will be the least absorptive.

60. Hardness.—The manner in which the mineral constituents of a rock are cemented to each other and the individual hardness of such mineral constituents determine the hardness of the rock as a structure. The minerals composing a rock may be hard but the rock itself as a structure will be soft if the particles do not strongly adhere to one another. Thus, some of the softest sandstones are composed of quartz, which is a hard mineral, but the grains are so weakly cemented together that the stone as a whole is soft.

61. Structure.—The structure of a rock depends on the form, size, and arrangement of its component minerals. All rocks may be approximately classified as *crystalline*, *vitreous* or *glassy*, and *fragmental*. Granite and crystalline limestone may be taken as types of the crystalline group; obsidian and pitchstone may be taken as types of the vitreous group; while the sandstones are types of the fragmental group.

62. Though all rocks have some common structural characteristics, certain peculiarities are found only in single types of rock. If the structure can be recognized by the unaided eye, the rock is said to have a *macroscopic structure*, and such rocks may be said to be granular, massive, polished, stratified, porphyritic, and concretionary.

The term *granular*, as its name implies, is applied to rocks built up of distinct grains of crystalline, or fragmental and water-worn character.

The term *massive*, or *unstratified*, is applied to rocks that are not arranged in any definite form in layers, or strata, but have the constituent parts mingled together, as in diabase and granite.

The term *polished*, or *schistose*, is applied to rocks that have their constituents arranged in definite planes nearly parallel to each other.

The term *stratified* is applied to rocks composed of parallel layers or beds, as is frequently seen in limestone and

sandstone. When the strata are thin and fine, the rock structure is said to be scaly or laminated.

The term *porphyritic* is applied to rocks that consist of a ground mass of fine or compact and evenly crystallized material, with larger crystals of feldspar scattered through it. A granite fragment has a porphyritic structure, but it is difficult to distinguish owing to the similarity of color existing between the crystals and the ground mass. In such rocks as the felsites, it is quite noticeable. In the porphyries of Eastern Massachusetts, the ground mass is of a black or no color and very compact and dense, while the large white crystal feldspars are in marked contrast.

The porphyritic structure is so noticeable that any rocks possessing this characteristic in a marked degree are commonly termed *porphyries* without regard to the mineral composition. The word *porphyry* is now commonly applied as an adjective, because any rock may possess this structure, whatever may be its origin or composition.

The term *concretionary* is applied to rocks composed of concretions or rounded particles built up by the collections of mineral matter around a center forming a rounded mass of concentric layers like the coating of an onion. When the concretions are small, like the roe of a fish, the structure is called *oolitic*, or if large like a pea, the structure is called *pisolitic*. The Bedford, Ind., limestones are examples of the oolitic type. The concretionary structure is rarely found in crystalline rocks.

63. Aggregation of Particles.—The hardness of the rock depends largely on the aggregation of the particles; therefore, the working qualities of the rock are fixed by the character of this aggregation. If the grains are loosely coherent in a rock composed of hard minerals it may work readily, while a rock consisting of softer materials may be worked with difficulty because the particles tenaciously adhere to each other.

The durability of a stone is, to a great extent, a matter of texture. If the grains adhere closely, the stone will be less

absorbent and less durable than one in which the adhesion is not so great; as in the friable and loose-textured rocks.

The kind of fracture shown by a rock is determined by the fineness or the coarseness of the grain and the relation of the particles to themselves or their state of aggregation. Such rocks as flint, obsidian, and some varieties of limestone have a compact fine grain and show, on fracture, a concave or convex shell-like face of conchoidal form, and are difficult to dress. Other stones show, on fracture, a jagged surface or split along certain planes, all dependent on the aggregation of the particles.

64. Rift and Grain.—Rocks that do not possess rift and grain cannot be worked into rectangular form without great difficulty, unless they are of a very soft nature, but with these qualities the hardest rocks can be readily worked; for instance, the South Dakota quartzite, which is one of the hardest rocks known, can be as easily broken into pieces for paving as a soft sandstone or a granite.

The **rift** of a rock is a line of cleavage parallel to the bed and is visible in such rocks as mica schist, gneiss, and other sedimentary rocks. It is along these lines that the rock can be readily split. Rift, however, is commonly found in massive rocks, although it is not so easily discerned as in the examples cited. The **grain** of a rock is always at right angles to the plane of the rift or bed.

65. Color.—The chemical properties of a rock, as a rule, determine its **color**. The color of granites, however, is affected by the action of the light on the feldspars, which when clear and glassy, absorb the light, making the rock apparently darker than when the feldspars are white and opaque and reflect the light.

Iron, the principal coloring matter in rocks, may be found in chemical composition with other minerals or in such simpler compounds as the sulphides and carbonates, or as an oxide distributed throughout the mass of rock. The brownish or reddish hues are due to the free oxides of iron while the bluish or grayish hues are caused by the carbonates

or the sulphides. The absence of iron in any of its forms is usually indicated by the white, or nearly white, color of the rock. The permanency of the color of the rock depends on the form in which the iron is found. Oxidation is likely to result if it is in the form of a sulphide, carbonate, or other protoxide compound. Therefore, stone containing these forms of iron is apt to fade and turn yellowish and stain on exposure. The sesquioxide, being in the last stages of oxidation, can undergo no further change from oxidation and is therefore a permanent color; hence, the decidedly red color may be considered permanent. The blue and the black colors of marbles and limestones are largely caused by the presence of carbonaceous matter, usually of vegetable origin.

SILICIOUS STONES

66. The granitic group of igneous rocks is richest in silica and therefore its members are known as **silicious stones**. Of this class, granite, syenite, gneiss, greenstone, and trap and the harder varieties of sandstone are most commonly used for structural purposes.

67. These stones compose the **primary rocks**, which are those rocks supposed to have been formed from the slow cooling of the incandescent earth. The granites are also unstratified, eruptive rocks, and underlie the stratified rocks. They are composed of an aggregation or assemblage of crystals of feldspar, quartz, and mica, the principal impurities being hornblende and talc: Quartz (pure silica, SiO_2) has a hardness of 7; feldspar (silica and aluminum, together with potash), a hardness of 6; hornblende, a hardness of from 5 to 6; the small scales of mica, a hardness of 3.

The colors of granite are white, grayish white, yellowish, reddish, rose, flesh color, or deep red, but rarely green. It is distinguished by its even and brilliant fracture, its pearly luster, and its outline, which is seldom regular, but in which may be recognized rectangles and parallelograms.

Granite varies in quality according to the proportions of its components and their method of aggregation. Stone

of the greatest durability and hardness contains a greater proportion of quartz and a less proportion of feldspar and mica. Hornblende renders the stone tough and heavy. Feldspar renders it lighter in color, easier to cut, and more susceptible to decomposition by the solution of potash contained in it. Mica renders it friable.

The granites are among the most valuable of the building stones and are extensively used in important works. They can be readily quarried and by reason of the lack of grain in the stone, blocks can be obtained of any size. On account of its great hardness, granite is difficult to work and therefore very costly to use if the stone is required to be cut. It weighs about 166 pounds per cubic foot.

Granite is found in the eastern part of the United States, in Canada, in many parts of the Alleghany and Rocky Mountains, and, as a rule, wherever the later rock formations and the underlying beds have been left exposed. It is generally classified into gray and red. Gray granite is found throughout New England, the border states, and in Virginia. Red granite is composed of red orthoclase (aluminum potassium silicates), bluish quartz, and a little hornblende, with very little mica. It is hard and takes a fine polish. It is found on the Bay of Fundy, in the islands on the St. Lawrence River, Virginia, Lake Superior, Maine, and many points in the Rocky Mountains.

68. Syenite.—This stone derives its name from Syene in Egypt. It consists of feldspar and hornblende, frequently associated with mica and quartz; is of a granular texture closely resembling granite; and is hard and tough, somewhat coarse-grained, and will not take a polish. It is one of the most durable of the granitic rocks when its feldspar constituent is not too readily decomposed by the removal of its potash when open to the weather. For this reason it should be carefully tested before it is used.

69. Gneiss and Mica Slate.—These are similar to granite in composition but differ from it in being stratified. Granite, syenite, and gneiss resemble one another so closely

that they are all frequently called granite by those not familiar with their characteristics.

Gneiss is not as valuable a stone as granite on account of its stratification, which will not permit it to be split in any direction. It is, however, a good building material and often answers as well as granite.

70. Greenstone, Trap, and Basalt.—These stones are igneous, unstratified rocks, consisting of hornblende and feldspar. The term *trap* has been suggested as a generic name for these rocks. The greenstone is not as coarse-grained as granite, and in the trap and basalt the granular structure is not apparent. The greenstone and trap break into blocks and the basalt into columns of prismatic form. They are found in veins and dikes and injected among the stratified rock of all ages.

These rocks vary in color, from nearly white in some varieties of greenstone, to nearly black, as in basalt, the difference of color being determined by variation in the proportions of hornblende, which gives a dark color, and feldspar, which gives a light color. The green is due to chromium. These stones, while making very durable building material, cannot be obtained in large blocks and are difficult to cut. Trap rock forms one of the best aggregates for use in making concrete.

SEDIMENTARY STONES

71. Sandstones.—Such material as sandstone consists of fragmentary rocks, composed mostly of grains of silica (or quartz), cemented together by a deposition of silica, carbonate of lime, oxide of lime, and aluminous matter. Sandstone is a stratified rock and belongs to the later geological periods.

If the cementing material is silica, the rock is very durable, but difficult to work. Iron oxide in the cementing material, consisting of carbonate of lime, and clayey matter, gives the stone a reddish or brownish color. Lime renders the stone particularly liable to disintegration when exposed

to an atmosphere containing gases, or when used for foundations where the soil is impregnated with acid water. The presence of clay or the oxide of iron is also deleterious.

Sandstones are variable in character, some being nearly as valuable as granite, while others are practically useless for permanent construction. The best stone is characterized by small grains with a small proportion of cementing material, and when broken has a bright, clear, sharp fracture. It is usually found in thick beds and shows slight evidences of stratification. Water can readily penetrate between the layers of this stone; therefore, in foundations it should be laid on its natural bed so that the penetration of moisture and possible disintegration by freezing may be prevented as far as it may be possible.

Sandstone of good quality possesses strength and durability and can be readily cut and dressed, which qualities make it one of the most frequently used of our common building stones. When the grains are extremely small, it is termed a "freestone" because of the ease with which it can be quarried, cut, and dressed.

Sandstones vary much in color: The Ohio and Nova Scotia varieties are yellowish and cream color and sometimes nearly white; the Missouri sandstone is of a yellowish drab color and possesses durability; the Portland, Conn., Newark, N. J., Marquette, Mich., and Bass Island, in Lake Superior, sandstones are of a dark brownish-red color, which is due to the presence of iron, and are termed *brownstones*. The Potsdam, N. Y., red sandstone is durable, hard, highly silicious, and of a reddish color. The Hummelstown, Pa., sandstone has a brownish color.

72. Soapstone.—This stone is the silicate of magnesia and is found in many places in the United States. It possesses valuable qualities where a stone capable of resisting high temperature is required.

73. Argillaceous Stone.—Stones of this nature are generally weak and soft and are not durable when exposed to the weather. They are therefore of little value as building

stones. Clay slate is a sedimentary argillaceous rock, fine-grained, compact, and of a laminated structure. Its colors are usually dark purple, blue, and light green. The best varieties of clay slate are used for roofing and flagging.

CALCAREOUS STONES

74. Calcareous stones are composed largely of lime; therefore, limestones and marbles are the most familiar examples. Limestone is a carbonate of lime and effervesces when attacked by acids that are stronger than the carbonic acid in its composition, the weaker acid being rejected and new lime salts being formed. The carbonic acid can also be expelled by heat, in which case the product is caustic lime, commonly termed *quicklime*, which is uncombined lime. All varieties of calcareous stone are found in the United States. Extensive deposits are found in a line parallel with the Atlantic Coast; another deposit underlies the Middle States. The marbles are mostly confined to the mountainous districts, while the common limestones are frequently found in immense strata that have been deposited on the bed of an ancient ocean.

75. Limestones.—These common building stones are of various qualities, some being hard and strong while others are soft and friable. There are two sorts, the granular and the compact, from either of which excellent stones may be obtained. As they are usually easily worked, they are among the lowest-priced dressed stones in the building.

76. Marble.—Metamorphosed limestone gives masonry material known as **marble**, which is easily dressed to a smooth surface and polished. The granular varieties are generally superior to the compact for building purposes. The impure carbonates of lime are sometimes of great value as marble. The magnesian limestones, or the dolomites, are usually of excellent quality.

White marble is found in the Laurentian rocks, Canada, but much of that used in the Northern Atlantic States is obtained from the Green Mountains, which extend through

Vermont, Western Massachusetts, Western Connecticut, and Southeastern New York. Quarries exist at Granden, Rutland, Danby, Dorset, and Manchester, in Vermont; at Lanesborough, Lee, Stockbridge, Great Barrington, and Sheffield, in Massachusetts; at Canaan, in Connecticut; and at Pleasantville and Tuckahoe, in New York. The snowflake marble is obtained from the Pleasantville quarries, and a fine grade of statuary marble from Rutland, Vt. From this place toward the south, the marbles become coarser and harder and more suitable for building purposes. Dolomitic marbles are found in the southeastern part of New York and in Delaware. White dolomite marble is found in Maryland.

The colored marbles used in building construction are of several varieties and are found in Vermont, Connecticut, New York, Pennsylvania, and Tennessee. Brecciated marbles, that is, those in which the conglomerate fragments are angular instead of water-worn, are found in Vermont on the shores of Lake Champlain, and a dove-colored marble with greenish veins is found at Rutland. Black marbles are found at Shoreham, Conn., and Williamsport, Pa. Black Trenton limestone is found at Glen Falls, N. Y. The Warwick marble, found in Orange County, N. Y., is beautifully colored with carmine, with white veins. The Knoxville marble is of a reddish-brown color with lines of blue. Tennessee marble is brown and white mottled. The foreign marbles are largely imported from Italy, Spain, and Belgium. The Bardiglio of Italy is of a gray color shaded with black; the Siena of Spain is a pale yellow color; the Lisbon of Portugal a pale reddish color; and the Belgian, of Belgium, is black. Verde antique is composed of bands of serpentine and white marble.

77. Chalk.—Soft limestone in which the minute shells composing it have not been entirely destroyed by the pressure to which it has been subjected in early geological times is called chalk. It is not suitable for constructive purposes but is very useful in making lime and cement.

78. Quicklime.—This material is obtained by *calcination* from various limestones and is the basis of common mortar; the act, or operation, of calcination is the expelling, by heat, of some white substance by which the stone or the cementing material is broken down and reduced to a friable state. Limestones are necessary in the manufacture of iron, as they afford an alkaline base that unites chemically with the silica, alumina, and other impurities of the ores and allows the metal to separate into a state of approximate purity.

79. Gypsum, alabaster, or plaster of Paris is a sulphate of lime containing the water of crystallization. The term “plaster of Paris” is due to the fact that large deposits of this stone underlie the city of Paris. This natural sulphate of lime, when raised to a high temperature, loses its water of crystallization and is then ground into a fine powder. This becomes the plaster of Paris of commerce, which is used for molds, ornaments, and casts, as well as in wall plaster and staff. Gypsum is found in many parts of the United States, great quantities being found in the state of New York.

MANUFACTURED STONES

80. The artificial stones include *brick, firebrick, concrete,* and *terra cotta*. While there are several ornamental stones manufactured, they have little structural significance, and only brick, firebrick, and concrete, which are entirely materials of construction, will be discussed in this Section. Terra cotta is much used in modern construction to obtain decorative and architectural effect, but its chief structural use is in the construction of fireproof floors, partitions, and coverings.

81. Bricks.—As is generally known, **bricks** are made of burnt clay and are used extensively in all classes of building operations of permanency. They can be cheaply made, readily handled, and formed into structures of almost any desired form. Brick, if properly made, burned hard, and

laid up with Portland cement mortar, is one of the most durable building materials in use.

The clay of which the common brick is made consists principally of silicate of alumina, but usually also contains lime, magnesia, and oxide of iron; the oxide of iron gives the brick strength and hardness; silicate of lime renders the clay easily fusible and causes the brick to become distorted in the burning. Uncombined silica is beneficial, if there is not too much of it, as it preserves the shape of the brick at high temperature. If it is in excess, however, it renders the brick weak and brittle, because it destroys cohesion; 20 to 25 per cent. of silica makes a good proportion.

Bricks are made by hand and machine, the machine-made ones usually being the denser. They are burnt for about 2 weeks, first at a moderate heat, until all the moisture has been expelled, and then at a slowly increasing temperature until, at the end of 24 hours, the "arch bricks" attain a white heat, when the temperature is slightly lowered, but a constant high temperature is kept up until the end of the allotted time, after which the openings in the kiln are closed, the fire is drawn, and the kiln is allowed to cool very slowly. There are various kinds of kilns, some temporary and some permanent; the permanent kilns are the best and most economical.

Three kinds of bricks are usually taken from the kilns: those forming the top and sides of the arches in which the fire is placed are overburned and partly vitrified; the lower bricks in the arch are usually overburned on one end and underburned on the other and are called **arch bricks**; they are hard, brittle, and have little strength. Bricks from the interior of the pile are usually of the best quality in the kiln and are termed **body bricks**, sometimes **hard** or **cherry bricks**. Bricks from the exterior of the kiln are usually underburned and are called **soft** or **salmon bricks**. Salmon bricks are too soft for use in important places, as they are deficient in strength and will not resist the weather.

Bricks of good quality should be of regular shape with parallel surfaces, plane faces, and sharp square edges, of

uniform texture, and should be burned hard. They should be thoroughly sound, free from cracks, and should ring clearly when struck a sharp blow. They will fail under a compressive stress of about 3,000 pounds per square inch; soft bricks will not resist more than about one-tenth of this stress. Pressed bricks will bear about twice as much as good hard bricks. Hard, well-burned brick should not absorb more than 6 per cent. of its weight in water. Brickwork in masses will crush under a very much smaller load than a single brick, presumably because of the combined stresses due to bending, etc. The Watertown Arsenal tests of brick piers are worth careful study.

82. Firebrick.—Firebrick is usually made of a very pure clay with clean sand, or sometimes of pure silica cemented with a small proportion of clay. The clay should be silicate of alumina. Oxide of iron in the clay is very injurious, and if it reaches 6 per cent. the brick is not suitable for the purpose. Specifications for firebrick should require that the oxide of iron shall be less than this amount, and that the aggregate of lime, soda, potash, and magnesia shall be less than 3 per cent. The sulphide of iron or pyrites has a harmful effect on the fireclay, and brick containing it should not be accepted. An excess of silica in the brick makes it refractory in extremely high temperatures. Where the brick has to resist the action of metallic oxides, which would have a tendency to unite with silica, alumina should be in excess.

83. Concrete.—This name is given to any mixture of gravel, slag, cinders, or broken stone with cement and sand. The best concrete for heavy structural purposes has for its base broken stone or slag, while gravel and cinders are used for such work as filling in fireproof construction and for the foundation of cement pavements. An excellent concrete is made of cement and sand with a mixture of broken stone and gravel.

The broken stone, slag, cinders, or gravel forming the base of the concrete is known as the *aggregate*, while the

cementing material, composed of the cement and sand, is known as the *matrix*. The combination of the aggregate and the matrix forms, when the cement has attained its final set, an artificial conglomerate rock that is superior in strength and durability to many of the natural rocks or stones used for building purposes. The purpose of the aggregate is to provide strength and solidity to the mass and to make up the bulk as cheaply as possible, so that the amount of the cement mortar, which is the expensive material, may be reduced to a minimum. The matrix holds the aggregate together by its adhesion, and in a complete concrete must fill all *voids*, as the spaces that would exist between the parts of the aggregate are called.

In mixing concrete, water should be judiciously used, for the mixture should be pulverulent, or nearly so, rather than wet. An excess of water tends to weaken the concrete and prevents the proper distribution of the matrix throughout the mass of the aggregate.

Concrete should be put in place in layers of from 6 to 10 inches in depth and should be tamped until the moisture begins to appear on the top of the layer. In placing concrete, layer upon layer, the upper surface of the bed should be free from dirt and dust and moderately wet.

84. Stone and Gravel Concrete.—When concrete is composed of broken stone and gravel as a base, the stone, or gravel, and sand must be sharp and thoroughly clean in order that the concrete may attain its maximum strength. Sand containing loam, dirt, or dust, which will soil the hands when rubbed, should not be used in the manufacture of concrete where dependence must be placed on it for structural stability.

The proportion of parts for the ingredients composing stone and gravel concrete depend entirely on the purpose or use for which the material is required. In many instances, a *poor concrete*, that is, one in which a small quantity of cement is used in proportion to the stone, gravel, and sand, will fulfil the requirements and promote economy, while it is

MATERIALS OF

requently imperative that a *rich concrete* be used, or one in which considerable cement is employed in the mixture.

For structural work requiring strength and durability, engineers favor a mixture consisting of one part of Portland cement, two parts of sand, and five parts of broken stone that will pass through a 2- or 2½-inch ring. An excellent concrete is also made by using 5½ cubic feet of cement, 7 cubic feet of sand, and 27 cubic feet of broken stone. These proportions are just sufficient to make 1 cubic yard of concrete.

When gravel is used in making the concrete it assists in filling the voids and consequently decreases the amount of cement mortar required. Good proportions for concrete of this character consist of one part of Portland cement, two parts of sand, three parts of gravel, and four parts of broken stone. This formula, which is easily remembered, has been used by the engineer corps of the United States army in the construction of foundations. Rosendale or natural-rock cements may be substituted for Portland, if desired. Concrete composed of one part of sand and four parts of chips or cement to two parts of sand and four parts of broken stone is specified by many architects and was used in the construction of the East River Bridge. The mass of the foundation for the Statue of Liberty in New York harbor was made of two parts of Rosendale cement, two parts of sand, and seven parts of broken trap stone. The modulus of elasticity of good stone concrete is about 700,000 pounds, while of neat cement it is approximately 3,000,000 pounds. The unit adhesive strength of stone concrete to rough iron or steel is about 600 pounds, while the adhesion of cement to brick or stone, in pounds per square inch, is approximately 15.

85. Cinder Concrete.—This material has fire-resisting qualities superior to stone concrete, owing to the fact that its mass is more porous and that the air spaces confined within are non-conductors and also because the cinders are more refractory than the broken stone commonly

in stone concrete. Besides, it adapts itself more quickly to sudden changes in temperature and therefore is not as liable to crack, split, or disintegrate when rapidly cooled by streams of water used in the extinguishing of a fire.

Cinder concrete is light in weight, compared with stone concrete, and is used extensively for fireproof-floor construction both as a filling material and as a structural element of the construction, though the laying of any material in which the matrix is Portland cement should not be conducted when the thermometer is below 28° or 30° F. Cinder concrete, in case of necessity, can be laid at a much lower temperature, especially if it is being used in poor construction where the centers are so open as to allow the surplus water to drain away before freezing can take place in the body of the concrete.

86. Experience teaches that the rapid and complete destruction of iron or steel when in contact with damp ashes or cinders is certain. Even cast-iron pipes, which are less liable to corrosion than steel, running through cinder banks, oxidize rapidly and in a short time are unfit for use. It is only natural, therefore, that on this account cinders as aggregate for concrete should be looked on with some disfavor by those who contemplate using that material in conjunction with steel or iron.

The active agents producing corrosion are water, carbonic acid, and sulphuric acid. The water and carbonic acid occur in the atmosphere, and if allowed to come in contact with the bare metal will cause corrosion. Where the metal is embedded in the concrete, however, there is little chance for this to occur, and no more opportunity is offered by the use of cinder concrete than in that in which the principal ingredient is stone, the cement in any case being the protective material.

That cement will protect iron and steel from corrosion indefinitely is well known from observation and experiments; and if it protects the metal against the action of moisture and carbonic acid, it is reasonable to suppose that, if the cinders are embedded in a sufficient matrix of cement mortar,

there will be no action on the metal due to the sulphuric acid, or to sulphur as sulphide, in the cinders. Sufficient matrix in order to completely protect bare iron or steel, can only be had in complete cinder concrete, which is obtained by the proportions of 1 part of sand, 2.75 parts of cement, and 4.75 parts of cinders. Such a concrete is not so good a fire- and water-resisting material as that made of 1 part of sand, 2 parts of cement, and 5 parts of cinders, and is not as practicable, for it is heavier, and is not in accordance with the building ordinances, as usually framed in the principal cities.

Though the usual concrete in the proportion of 1, 2, and 5, will not entirely protect bare iron or steel, and some oxidation will take place more or less rapidly, depending on the absence or presence of moisture, it is hardly likely that the corrosion will be serious with the iron or steel used in the ordinarily dry atmosphere between the floors of a building. The concrete, however, contains considerable moisture when it is first laid, and an initial corrosion is likely to take place before the concrete has dried out. In order to avoid this initial corrosion, which is serious, for when it once starts it is liable to continue owing to chemical action and reaction, the iron or steel should be painted with some good paint, preferably one free from oils that are likely to be affected by acids and alkalies. Some paint of the asphaltum variety would probably be best.

Since meager concrete in the proportion of 1, 2, and 5 fails to entirely protect bare iron or steel, it is good practice, where possible, to cover the metal with a thin coat or layer of cement mortar of 1 part of Portland cement and 2.75 parts of sand, and then follow with the concrete. If this is done, the concrete will not come in contact with the metal, and the steel or iron will be fully protected from corrosion, which, though slight and probably locally confined, is likely to be instituted from the several causes previously cited.

FIRE-STONES

87. **Fire-stones** are stones capable of resisting the action of great heat without fusing, exfoliating, or cracking. Lime and magnesia, except in the form of silicates, are prejudicial to the quality of fire-stones; potash, also, is very injurious because it increases the fusibility of the stone, which, on melting, causes the formation of a fusible glass. Quartz and mica alone or in combination make the most refractory stones. Mica, slate, and gneiss make an excellent combination. Gneiss is particularly refractory when it contains a considerable portion of arenaceous quartz; that is, quartz in which the particles partake of the nature of sand.

Limestones do not stand well in the presence of high temperatures, as they sometimes explode, owing to the rapid expulsion of the carbonic-acid gas.

Granitic and other primary rocks usually contain some water, which, in the presence of fire, causes them to crack and sometimes explode.

Sandstones, if somewhat porous, uncrystallized, and free from feldspar, are the most refractory of the common building stones.

Firebrick is perhaps the most fire-resisting material now known, while common hard-burned brick is more refractory than any of the building stones.

Concrete made of Portland cement and stone is a fire-resisting medium of only fair value.

DURABILITY OF BUILDING STONE

88. In the structural use of building stones, it is seldom that the full safe strength of the stone is required to resist the stresses imposed, and consequently the range of choice is not limited by this consideration so much as by the factor of *durability*. While in architectural work color is of great importance, for on it the architect depends to a large extent for the success of his design, it is exceptional in purely structural work for the color of the stone to be a deciding factor.

The **durability** of a building stone depends not only on the physical and chemical formation of the stone, but to a considerable extent on the climate in which the structure is to be built and also the method employed in quarrying the material. Where a selection is to be made of two stones equally durable and structurally fit for their purpose, the economic consideration influences the choice. The cost of structural building stones is regulated by the difficulties of quarrying, the refractory nature of the stone in finishing, and the distance it must be transported.

89. Physical Structure.—The most durable building stones are generally of a compact and uniform texture and show a clean fracture free from earthy or soluble mineral matter. Stones showing lamination or layers are not likely to prove as durable as those of a more homogeneous structure, especially when laid with the laminations perpendicular to the bed of the wall, or on *edge*.

Non-porosity is not always a quality synonymous with durability, for many stones that absorb moisture also permit of its rapid evaporation; such stones are likely to prove more durable than those that absorb less moisture and part with it more reluctantly.

Stones showing a streaked appearance and lack of uniformity in color are usually composed of several minerals of various degrees of hardness, and in some instances one of them may be slightly soluble. Such stones are not likely to weather well, for the softer or more soluble mineral will be corroded and washed away, leaving the harder substance to protrude. When the less durable substance is in small pockets or spots, the stone will, on long exposure, be pitted; while if the softer mineral is in streaks or veins the material will be grooved, fissured, or channeled.

Small fossils or shells embedded in the substance of a building stone have usually a deleterious influence on its durability and weathering qualities. Such fossils and shells are calcareous in nature and generally soft and partially soluble under atmospheric influences.

90. Climate and Environment.—Building stones of the most durable character are required in climates where the diurnal changes in temperature are great and where there is much moisture in the atmosphere. The structure of a stone consists of minute particles that are surrounded by a matrix that forms the cementing material of the mass or are closely attached to each other by cohesion. In either case, changes in temperature cause these particles to expand and contract with considerable force, thus loosening particles from the matrix or from each other, causing deterioration and the ultimate destruction of the rock. The freezing of water in the pores of the stone or in the crevices and the spaces between the laminations in stratified stones, is the primary cause of the rapid destruction of some building stones. Water in freezing expands about one-tenth of its bulk and is said to exert a pressure of about 150 tons per square foot, which is sufficient, under favorable conditions, to split and rend the strongest rocks. The freezing of moisture within the pores of the stone is very deleterious to the stability of its structure, especially if there is not contained in the rock reserve pore space sufficient to accommodate the increased bulk of the water when frozen.

When water freezes in the crevices or spaces between the laminations, its action is that of an adjustable wedge tending to split the rock and widening the crevice more and more with each repetition of the freezing process. By this means, stones of laminated or stratified structure are particularly liable to disfigurement, when laid on edge by *exfoliation* or the scaling of the surface. In the large cities, it is not uncommon to observe balusters and carved details partially destroyed from this cause. The damages from the freezing of water in the spaces and crevices between the laminations is not as great when the stone is laid on its bed as when laid on edge, because there is not the same opportunity for the space lying in a horizontal plane to collect the moisture and also because the pressure on the stone from the superimposed masonry nullifies, to some extent, the wedging or bursting action of the freezing water.

The severest atmosphere on building stone is one that frequently and for long periods contains great quantities of suspended moisture in the shape of fogs and is also subjected, by environment, to much smoke and gas from the bituminous coals of manufactories. Such atmospheres are likely to contain carbonic-acid gas and sulphurous fumes, which have an appreciable effect on limestones and marbles. The actions from these sources affecting the durability of building stones are especially marked where the atmosphere is extremely moist.

91. Effect of Quarrying and Finishing.—Before stones are used in an important structure they must be thoroughly seasoned. When detached from the rock, stone is generally saturated with quarry water. It should, therefore, be exposed for some months, preferably under cover, to allow this water to evaporate. If the stone is not seasoned before it is placed in the wall of the structure, it is likely to remain peculiarly damp, and the excess of moisture, in freezing, will influence the durability of the material.

The use of heavy explosives for detaching dimensioned stone is detrimental to the quality of durability, from the fact that the severe concussion is likely to jar the particles and partially destroy their cementation and cohesion, producing incipient cracks and flaws that make the face of the stone more permeable to moisture and thus facilitating the deterioration of the stone by freezing and chemical action. For the same reasons stones sawed to size are more durable than those hammered and broken; and stones taken from the quarry by channeling or cutting are preferable to those procured by wedging.

92. Effect of Fire.—The fierce conflagrations that occur in the large cities frequently subject the stone walls of structures to intense heat. While stone is an excellent non-conductor, it is not as a rule as durable, when subjected to intense heat, as brick.

The severest test to which a stone can be subjected in a fire is for it to be heated intensely and then cooled by the

sudden application of water from the fire-hose. This rapid change of temperature causes the exterior heated layer of the stone to contract more rapidly than the mass, and from many stones under this condition, large pieces will crack and break off; the process being several times repeated results in the entire destruction of the stone.

The silicious sandstones are the least destructible by fire, while the granites and conglomerates are probably the most affected by intense heat and the sudden cooling incident to the application of water. Limestones are very refractory in temperatures less than $1,000^{\circ}$, and at this temperature are not liable to deterioration by sudden cooling, though above this temperature, they may be reduced to quicklime, which crumbles and falls away after a few weeks' exposure to the air.

STRENGTH OF STONES AND MASONRY

93. The resistance of stones to stress varies greatly, and the strength of masonry depends not only on the material of which it is composed but on the manner in which these materials are handled; that is, on the workmanship. Stones that are the densest usually possess the greatest resistance, and masonry composed of squared stones with close joints is the strongest.

Many tables, based on the results of tests, give the strength values of building stones, but they differ widely, the discrepancy being due to the following causes:

1. Samples are taken from different quarries or from different parts of the same quarry.
2. The pieces of stone used for testing are not uniformly seasoned.
3. Test pieces are of different sizes.
4. They are not uniformly dressed or finished.
5. Variations exist in the method of placing the test specimens in the machine.

Frequently stones quarried from different parts of the same bed will show 20 or 30 per cent. difference in their crushing resistance, and stones that have been quarried some

time and exposed will show a different resistance from those lately detached. The larger the test piece, the greater will be the unit stress developed, for small cubes do not develop as great a unit resistance as large ones, and within certain limits the unit stress that test cubes of the same material will sustain varies directly as the cube of the sides.

The method of finishing the test pieces and the accuracy and fineness with which the sides are dressed have much to do with the results of the test. Specimens that have been sawed to shape test higher than those that have been finished with a tool or chisel. Microscopic examination of the surface finished with a chisel reveals numerous minute cracks, caused by the excessive jars, that tend to reduce the crushing strength by starting fractures. The fineness of the surface finish also affects the result, from the fact that when the bearing surfaces are rough, transverse stresses that tend to disrupt the specimen are created.

94. It is well determined that from lack of homogeneousness or uniformity of texture, building stones and masonry of the same material have variable strength values. This uncertainty regarding the exact strength of masonry materials, together with their usually rapid deterioration, necessitates the use of a high factor of safety, so that in all work of this class minimum safety factors ranging from 10 to 20 are employed. When, therefore, the average strength values of commercial masonry materials are known and a high factor of safety is used, the basis on which the design is made is assuredly safe.

95. The average strength values for masonry materials, which are sufficiently conservative for good engineering practice, are given in the following tables:

TABLE I
STRENGTH OF BUILDING STONES AND MASONRY

Materials		Weight per Cubic Foot Pounds	Compressive Strength Pounds per Square Inch	Tensile Strength Pounds per Square Inch	Transverse Strength Pounds per Square Inch
Granite,	Colorado	166	15,000		
	Connecticut	166	14,000		1,500
	Massachusetts	165	16,000		
	Maine	165	15,000		
	Minnesota	166	25,000		
	New York	166	16,000	600	1,800
	New Hampshire	166	12,000		
Sandstone,	bluestone	160	15,000	1,400	2,700
	Connecticut, Middletown . . .	148	7,000	590	1,000
	Massachusetts {				
	Longmeadow, brown . . .	142	10,000	450	
	Longmeadow, red . . .				
		149	12,000	450	
	New York {				
	Hudson River Little Falls, brown . . .		12,000		
Limestone,	Ohio	130	8,000	100	479
	Pennsylvania, Hummelstown, brown		12,000		
	New York {				
	Kingston	168	12,000		
	Garrison Station	164	18,000	Average	Average
	Indiana, Bedford, oolitic . . .	146	8,000	1,000	1,500
	Michigan, Marquette	146	8,000		
	Pennsylvania, Conshohocken . .		15,000		
Marble,	Pennsylvania, Montgomery County		11,000		
	Massachusetts, Lee, dolomite . .		22,800	Average	Average
	New York, Pleasantville, dolomite		22,000	700	1,200
	Italian	168	12,000		
	Vermont	167	10,000		
	Slate	160-180	10,000	10,000	5,000
Rubble, in lime mortar		150	500		

TABLE II
STRENGTH OF BRICKS, BRICKWORK, AND RUBBLE

Materials	Weight per Cubic Foot Pounds	Compressive Strength Pounds per Square Inch	Tensile Strength Pounds per Square Inch	Transverse Strength Pounds per Square Inch
Bricks, soft, inferior	100	1,000	40	
good, common	120	10,000	200	600
best, hard	125	12,000	400	800
paving	130	5,000		
Philadelphia, pressed	150	6,000	200	600
Brickwork, common, in lime mortar	120	1,000	50	
stretchers, in cement and lime	125	1,500	100	
best, hard in cement mortar	130	2,000	300	
Terra cotta	110	5,000		
Terra-cotta work	112	2,000		
Rubble	150	500		

TABLE III
STRENGTH OF CEMENTS, MORTARS, AND CONCRETE

Materials	Weight per Cubic Foot Pounds	Compressive Strength Pounds per Square Inch	Tensile Strength Pounds per Square Inch	Transverse Strength Pounds per Square Inch
Neat cement, Portland, 1 month old		2,000	300	400
Portland, 1 year old		3,000	550	800
natural rock, 1 month old		1,200	150	200
natural rock, 1 year old		2,000	400	400
lime	59	600		200
plaster of Paris	79	600	70	
Concrete, Portland cement, 1 month old		1,000	200	100
Portland cement, 1 year old	120-140	2,000	400	150
natural cement, 1 month old	120-140	500	100	75
natural cement, 1 year old				
Mortar, lime	98	400	50	125
natural cement and lime	100	600	75	200
natural cement	102	1,000	145	102
Portland cement	109	2,000	300	700
plastering	86	400		

TABLE IV
ALLOWABLE UNIT STRESSES FOR MASONRY MATERIALS

Description of Material		Compressive Strength Pounds per Square Inch	Transverse Strength Pounds per Square Inch
Capstones, Templets, Monoliths,	bluestone	700	300
	granite	700	180
	limestone	500	150
	marble	400	120
	sandstone, other than bluestone . .	350	100
	slate	700	400
Squared-Stone Masonry,	bluestone	350	
	granite	350	
	limestone	250	
	sandstone, other than bluestone . .	175	
Rubble,	laid in Portland cement mortar . .	150	20
	laid in natural cement mortar . . .	120	
	laid in lime-and-cement mortar . .	100	
	laid in lime mortar	80	
Brickwork,	laid in Portland cement; cement 1, sand 3	250	50
	laid in natural cement; cement 1, sand 3	150	40
	laid in lime and cement; cement 1, lime 1, sand 1	125	30
	laid in lime; lime 1, sand 4	100	15
	Portland cement; cement 1, sand 2, stone 4	200	30
Concrete,	Portland cement; cement 1, sand 2, stone 5	150	20
	natural cement; cement 1, sand 2, stone 4	125	16
	natural cement; cement 1, sand 2, stone 5	100	10

96. The values given in Tables I, II, and III are the average ultimate and breaking loads for the different materials. They are the results of tests made at different times on specimens prepared for the purpose. It will be noticed that the strength values of squared masonry are not given, and though conservative practice recommends that masonry of squared stone may be considered as having an ultimate strength equal to four-tenths of the strength of the stone, this is only an assumption that has not been substantiated by tests. The scarcity of reliable tests on masonry piers and walls is due to the fact that in order to obtain accurate results of the test, specimens must be of full-size dimensions and when thus built their strength is so great as to resist the ultimate power of the testing machine.

97. In using the values given in Tables I, II, and III, factors of safety of not less than 10 for compression and 15 and 20 for tension and transverse stress, respectively, should be employed. The usual practice in structural and architectural engineering is to use the allowable unit values for masonry and masonry materials given in Table IV. These values are considered good practice, and, in most materials, correspond with values recommended by the building laws of several cities.

SELECTION OF BUILDING STONES

98. In the building of important masonry structures, it is of primary importance that the stone employed shall be of sufficient strength and durability. Probably nothing in engineering construction is so neglected as the inspection of the building stone that is to be used.

Where it is necessary to employ great quantities of building stone in important situations, with reference to the stability of the structure, an inspection of the quarry from which the stone is to be obtained should be made. Besides, it should be the effort of the person who is to decide on the merits of the stone to inspect some building or structure that has been erected of the same material for a considerable length of time.

It is well, however, not to depend wholly on either inspection at the quarry or at the building but to subject the stone to laboratory tests, when it should be tested both chemically and physically as well as subjected to microscopic inspection.

99. The inspection at the quarry, when conservatively made, will frequently reveal the durability of the stone as well as its uniformity. Exposed quarry faces will sometimes show the weathering properties of the stone, besides its liability to disintegration through moisture and running water containing deleterious acids and alkalies. Such inspection will also determine whether there is sufficient stone of a uniform texture and color in sight to supply the amount of material required for the work. By quarry inspection likewise, the several grades of stone are known, and in first-class work it is imperative that the best grade or run of the quarry be insisted on. Frequently, the third-grade stone is employed in the structure, and on showing deterioration and poor weathering qualities causes otherwise excellent building stone, when of first-class cuttings, to be condemned.

100. By the inspection of stone that is in place in a building or structure for a considerable length of time, an excellent idea may be had of its durability as to structure, color, and weathering properties. If, after years of exposure in the severe atmosphere of an industrial city situated in a temperate zone, the building stone shows no disintegration or exfoliation and has retained its original luster and color, but for the soil of dust and smoke stains, due to its environments, it certainly can be considered of the best structural value for building purposes.

101. While the quarry and building inspections of stone are of the utmost practical importance, they should, wherever possible, be augmented by laboratory tests; in fact, these tests are absolutely necessary. When the stone to be used is from a new quarry, the characteristics of the product are little known. The laboratory tests usually consist of chemical analysis, microscopic examinations, and physical tests.

The *chemical analysis* determines both qualitatively and quantitatively the chemical constituents of the stone. Examined qualitatively, the mineral elements and chemical combinations of composing the stone, together with the impurities and original matter, are determined; while the quantitative analysis shows the proportion of the different elements and chemical combinations. When the chemical composition of a stone is in this way determined, conclusions can usually, though not always, be drawn as to the quality of durability and the weathering properties of the stone.

The *microscopic examination* of building stone is of even more importance and is less expensive to conduct than the chemical analysis, for by it is revealed the structure of the stone. By the microscope may be observed whether the stone is igneous, metamorphic, or unaltered sedimentary rock. It also shows the size and shape of the particles or crystals composing the stone, their relative closeness, and the character and compactness of the cementing material holding them together. Usually the mineral constituents of the stone may be determined likewise by microscopic examination and frequently their proportions may be estimated, together with the percentage of impurities contained in the stone. Likewise by the microscope may be detected any flaws in the structure, such as cracks, cavities, incipient fractures, and gas bubbles.

The *physical tests* of stone are of great practical value in determining its strength and durability. When the strength values of a building stone are not known, it is frequently necessary to make tests in order to determine the crushing and transverse unit stress of the material, for though the unit crushing strength of building stone is usually greatly in excess of that required, the transverse strength is frequently barely sufficient to sustain the load when a fair factor of safety is allowed. An estimation of the durability of a building stone may be deduced from data collected from physical tests made to ascertain the specific gravity, porosity, and weight of the stone and from such tests as will demonstrate the effects of extreme heat and cold and the actions

of carbonic and sulphurous acids. In making these last tests, the object is to impose on the stone, as nearly as possible, conditions that in a few hours' time will approach the effect produced by climatic changes and vitiated atmosphere through a lapse of years.

MORTARS

CHARACTERISTICS OF MATERIALS

102. Mortars for structural purposes are composed of lime or cement and sand mixed to the proper consistency with water. When lime and sand are used, the mixture is known as *lime mortar*; when the mixture is of cement and sand, it is designated as *cement mortar*. Frequently in building work, lime mortar is mixed with cement mortar, when the term *lime-and-cement mortar* is used. Small percentages of other materials, such as salt, sugar, brick, and volcanic dust, are sometimes mixed with mortar in order to accomplish specific purposes, such as the prevention of freezing, hastening of setting, increasing of strength, and the creating of hydraulic properties, though with doubtful effectiveness. In mixing mortar, it is usual to designate the amount of such ingredients by a notation, such as 1 to 1, 1 to 2, or 1 to 3, which signifies that the mortar is composed of one part of cement or lime to one, two, or three parts of sand, respectively. The first number of the notation always indicates the amount of cement, which for convenience is taken at unity. In proportioning the mixture, the parts of the ingredients are generally measured by volume and just sufficient water supplied to work the mortar to the proper consistency.

103. Sand.—This material is an important part of all mortar mixtures, for in lime mortar it prevents excessive shrinkage and adds crushing resistance and tenacity, while in cement mortar it is principally used for economic reasons and to provide additional resistance to crushing, though it decreases tenacity of cement.

It is important that sand for mortars shall be clean and sharp. *Clean sand* when rubbed between the fingers will not soil them, but sand containing impurities will leave an earthy stain. When clean sand is dampened and squeezed in the palm of the hand, on the release of the pressure, it will fall apart, while if it contains soil, clay, or earthy substance, the particles will be held together by being cemented by the impurities. Sand for structural purposes should be *sharp*; that is, the grains should be cubical and angular rather than globular or rounded. The sharpness is best tested by rubbing or rolling the sand between the hands and if there is a distinct grating sound, it indicates that the sand grains are angular. Sand that is sharp and angular lies closer together and offers more surface of adhesion for the cement composing the matrix of the mortar.

Much importance has unwarrantedly been placed on the size of the grains of sand for structural purposes. Very fine sand and sand so coarse as to contain grains larger than the joints of masonry should not be used. A sand containing a mixed size of grain is the most economical and the best for structural purposes. When the usual specification is complied with, namely, that the sand shall be sifted through a screen having a mesh $\frac{1}{8}$ inch square, grains of not more than $\frac{1}{16}$ inch on a side will be passed, and sand of such size gives excellent results.

The usual sources from which building sand is obtained are the seashore, the river bank, and sand deposits or pockets. The first, which is known as *sea sand*, is usually objected to on account of the salt that it contains and should not be used where the appearance of the work is a factor unless it is well washed. The second, which is termed *river sand*, is generally composed of rounded particles rather than angular and may be either clean or dirty. The third, or *pit sand*, is usually sharp, though it is likely to contain clayey and earthy substances, which destroy its cleanliness.

104. Lime.—By calcining or burning calcium carbonate or limestone at a high temperature, **quicklime** or

commercial lime is produced. In the process of burning, the water that the stone contains is driven off, together with carbonic-acid gas or carbon dioxide. Lime has a great affinity for water and should be used soon after being made, as it is likely to become *air-slaked*, when it is unfit for use in making lime mortar. When lime is brought in contact with water, it takes it up rapidly, swelling and generating considerable heat, the lime falling apart and producing a fine white powder; this process is known as *slaking*. When more water is added to this powder, a *lime paste* is formed, which by the addition of sand produces lime mortar. The best limes slake vigorously and completely, the *lime flour*, or precipitate, being fine and free from refractory lumps and cores. The presence of such unslaked fragments indicates that the limestone was not pure or that the process of calcination was imperfect.

In slaking lime, a volume of water equal to two or three times the volume of the lime is used. The entire amount of water necessary for slaking should be used at one time, as it is deleterious to turn in cold water after the lime has commenced to slake.

105. Cement.—Commercial cements used for making mortar for structural purposes may be classified as *Portland* and *natural-rock cements*. The difference in their manufacture consists more essentially in the method of procuring the raw material rather than in the process of preparation. The name **Portland cement** is given to any cement that is manufactured from the several necessary materials carefully gathered and proportioned, while the term **natural**, or **natural-rock, cement** is given to those cements that are manufactured direct from a natural rock containing the necessary ingredients.

Portland cement is obtained by mixing lime or marl with clay in the proper proportion. The mixture is made into balls, or nodules, which are calcined in a furnace and ground to a fine powder. The natural-rock cements are manufactured from a natural rock that contains lime, alumina, and silica.

Rocks containing the proper materials for making these cements are of a mixed limestone and clayey nature. These rocks are calcined at a high temperature approaching vitrification and are broken, pulverized, and finally ground to form the commercial cement. Both Portland and natural-rock cements are *hydraulic*, that is, will set under water, and are consequently invariably used for work in damp situations and below the water-line.

When cement is brought in contact with water, it hardens rapidly even when air is not present. This hardening or *setting*, as it is called, is caused by a chemical reaction that takes place and forms with the water of crystallization double silicates of lime and alumina. Some cements set more rapidly than others and cements that take an initial set in from 5 to 30 minutes, or even 1 hour after mixing, are known as *quick-setting cements*, while those that require from several hours to a day or longer, in order for the initial set to take place, are known as *slow-setting cements*.

Usually natural-rock cements set in less time than the Portland cements; besides they are lighter in weight and do not obtain the same degree of strength in as short a time after mixing. A barrel of natural-rock cement weighs about 300 pounds, while Portland cements are usually one-third heavier.

Portland cement is considered, in many respects, superior to natural-rock cements for structural purposes, yet in this country great quantities of natural cement have been used for the most important engineering work and have been found, after years of service, to have been exceedingly durable, attaining great strength.

The natural-rock cements are found and manufactured in New York, Pennsylvania, Maryland, Virginia, and Kentucky, as well as in several of the western states. The principal brands are many. Those having an extended reputation are known as Rosendale, Louisville, Cumberland, James River, and Round Top. The Portland cements that are used in this country are both domestic and imported. Some of the principal domestic Portland cements are known as the

Vulcanite and Alpha, manufactured in New Jersey; the Dexter, Lehigh, Atlas, and Whitehall, manufactured in Pennsylvania. The imported cements come from Germany, France, and England. Lagerdorfer German cement is used to some extent, it being a strong, finely ground, and uniform material. Vicat cement, which is imported from France, is a high-priced cement and owes its use in this country to the fact that it is not as likely to stain fine ashlar work as some of the domestic cements. English Portland cement is also used to some extent, though it is doubtful whether it possesses any qualifications of excellency over the best American Portland cements. The distinction that the New York building laws make with regard to brands of cements sold under the general nomenclature of Portland and natural is interesting, though it does not determine actually whether the cement is Portland or natural.

The requirements of the building laws are as follows:

“Cement classified as Portland cement shall be considered to mean such cement as will, when tested neat, after 1 day set in air, be capable of sustaining, without rupture, a tensile stress of 120 pounds per square inch, and after 1 day in air and 6 days in water be capable of sustaining, without rupture, a tensile stress of at least 300 pounds per square inch.

“Cements other than Portland cement shall be considered to mean such cement that when tested neat, after 1 day set in air, be capable of sustaining, without rupture, a tensile stress of at least 120 pounds per square inch.”

The building laws continue to state that the test shall be made under the supervision of the Commissioner of Buildings, and that those tests shall be made at such a time as he shall deem advisable. They also require that records of the tests shall be kept for public information.

106. Lime Mortar.—Common mortar of quicklime and sand, though formerly used for all classes of work, is now supplanted by cement mortar for the better class of structural work. In mixing lime mortar, the lime is

thoroughly slaked to a powder and wetted to a paste when the sand is mixed and thoroughly incorporated with the paste by working and kneading. While lime on exposure to the atmosphere will become air-slaked and unfit for use, the slaked lime, when mixed with sand, is not so impaired and it is usually considered beneficial to mix up large batches of the mortar some time before using it, when it only requires tempering with water and some working to be ready for immediate use.

Sand is mixed with lime to form lime mortar in the proportions of one part of lime to from three to six parts of sand. With rich limes, that is, those that slake freely and completely, the proportion of three parts of sand to one of lime is not sufficient, and four parts of sand makes a better mixture. The proportion of six parts of sand to one of lime is never used except in the poorest work, and in fact the building ordinances of the several cities require that mortar shall be made of one part of lime and not more than four parts of sand, the lime to be in all cases thoroughly burnt, of good quality, and properly slaked before it is mixed with the sand.

Lime mortar sets by the drying out of the mortar and by a chemical action produced through the absorption of carbon dioxide, or carbonic-acid gas, from the air. By taking up this gas, the slaked lime is again converted to calcium carbonate, which surrounds each particle of sand, thus converting the mortar into artificial stone. Since the absorption of carbon dioxide is necessary, in order that lime mortar may harden, this mortar will not set in water and should not be used in foundation work below the water-line or in extremely damp situations. Lime mortar used in the interior of very thick walls has been known to remain soft for years; consequently, it cannot be used in concrete.

Though lime mortar will not harden in wet situations, the process of crystallization caused by the absorption of carbon dioxide in the air is facilitated by keeping the work damp for a short time after laying. For this reason, brickwork should not be laid in very hot or dry weather unless the bricks are thoroughly soaked in water.

When lime mortar does not retain sufficient moisture to properly promote the chemical action of hardening, it forms a chalky mass that is easily pulverized between the fingers, showing that it has lost most of its properties of adhesion and cohesion.

107. Cement Mortar.—Mortar composed of either Portland or natural-rock cement is being used extensively for all structural purposes, owing to the reduction in the price of these cements, and their excellent quality.

In this mortar, only cement and sand are used with just sufficient water to mix it to a mealy consistency; an excess of water is detrimental to its qualities of strength. The usual proportions of sand and cement, when natural-rock cements are used, are one part of cement and one or two parts of sand, the usual practice being to use the latter proportion. In mixing cement mortar with Portland cement, it is customary to mix the sand and cement in the proportion of 1 to 3, for this mixture is considered equal in strength and durability to a mixture of one part of sand and two parts of natural-rock cement.

The New York building laws specify that cement mortar shall be made of cement and sand in the proportion of one part of cement and three parts of sand and shall be used immediately after being mixed. The cement and sand are to be measured and thoroughly mixed before adding water. They also stipulate that the cements must be finely ground and free from lumps. The usual practice in making cement mortar is to mix the sand and cement together dry, measuring the parts by volume, adding the water as required in order to reduce the mixture to work consistently, care being exercised in supplying the water that the amount added is not excessive.

Owing to the fact that cement mortar sets rapidly, it should never be mixed, except immediately before being used; and after a batch of cement mortar has once taken its initial set no attempt should be made to retemper it, but the whole mass should be discarded. The natural-rock cement

mortars set more quickly than Portland cement mortars, but with care can be conveniently used in any class of work. Both natural-rock and Portland cement mortars have hydraulic properties and set rapidly and completely under water. This property of hydraulicity is not destroyed by the addition of lime in the proportion of not more than one part of lime to two of cement. Because of the hydraulic properties of cement mortar and on account of the great strength that it attains when it sets in water, this mortar should always be used for masonry in damp situations or for foundations that are likely to be immersed in water. The usual cement mortars are durable even when submerged in sea-water.

One barrel of cement to two barrels of sand will make about 8 cubic feet of cement mortar and will lay 1 cubic yard of brickwork or rubble, while one barrel of cement and three barrels of sand will make about 12 cubic yards of mortar, which will lay $1\frac{1}{2}$ cubic yards of ordinary masonry, or provide sufficient matrix for $1\frac{1}{2}$ cubic yards of concrete. The quantity of water that is required in mixing cement mortar varies considerably with the temperature and with the dryness of the materials. Ordinarily, one-third of a barrel of water mixed with one barrel of cement, will make two-thirds of a barrel of stiff paste.

In making cement mortar, sometimes the cement is mixed to a paste with the water and the sand added, but the usual practice is to mix the cement and sand dry and to introduce sufficient water in order to work it to a mealy and pasty condition. In the manufacture of all cement mortar, the sand and cement must be thoroughly mixed, as otherwise the substance will not have a uniform texture and its mass will incorporate spots of dry cement, and frequently there will be pockets of sand without the matrix of cement.

There is much difference of opinion as to the advisability of using cement mortar in freezing weather. Undoubtedly, the best practice is to suspend all masonry operations when the thermometer is below freezing, but when necessary, however, cement mortar may be used in temperatures several degrees below freezing. It is well, however, in laying work

with cement mortar in freezing weather to heat the sand, brick, and stone, if possible, and to use hot water in mixing. With ordinary precautions and by covering the work when operations are suspended at night, cement mortar may be used in low temperatures with safety. The frost may have some action on the exterior edges of the joints, but the action will not penetrate to the interior of the wall.

Some authorities recommend the introduction of salt in cement mortar when it is used in freezing weather. This practice is not to be recommended, however, for the salt retards the setting and is liable to stain the masonry or brickwork.

108. Cement-and-Lime Mortar.—Frequently mortar for building work is composed of a mixture of both cement and lime with sand. The lime introduced with cement in mortar makes the material more tractable by increasing the plasticity of the mortar, and thus facilitates the work of laying the masonry or brickwork. It also retards the setting, which is frequently requisite, and lowers the freezing point of the mortar. Besides, it does not shrink, like lime mortar, in setting and is therefore desirable in laying the backing of ashlar walls. Its use also promotes economy, for lime is much less costly than cement.

The proportion of the ingredients used in mixing this mortar varies considerably with the class of work and the judgment of the designer. For brick backing, piers, and walls, one part of Portland cement, two parts of good, fresh, wood-burned lime, and three parts of clean, sharp sand will give satisfaction. When this mixture is to be used for ashlar facing one part of Vicat Portland cement, two parts of good, fresh, wood-burned lime, and three parts of clean, sharp sand, mixed together as soon as prepared, have been found to give excellent results. Frequently only a small percentage of lime is added to the cement mortar to give it plasticity, and in this instance the specifications usually require that the mortar shall be composed of one part of Portland cement, three parts of clean, sharp sand, and just sufficient lime to make the mortar pasty. Lime-and-cement

mortar is admirably adapted to the construction of brick arches used in fireproof-floor construction.

The New York building laws stipulate that cement-and-lime mortar mixed shall be made of one part of lime, one part of cement, and not more than three parts of sand to each.

In mixing lime-and-cement mortar, the slaked lime is mixed in bulk with the sand and the cement added, after tempering it with water, immediately before being required. The lime mortar and the cement mortar made in this way must be thoroughly incorporated by working, though this must be done rapidly before the cement has had time to set.

109. Comparison of Lime and Cement Mortars.—It is interesting to compare lime and cement mortars so as to see wherein one is more advantageous than the other. The points in favor of lime are: its cheapness; the large quantity of mortar that can be made from a given quantity of lime; the fact that if, before use, it is kept damp, it remains good indefinitely; and the ease and simplicity of mixing. Against its use may be mentioned these points: in damp situations, it will not harden; in the interior of walls of any considerable thickness, it hardens (if at all) but very slowly; and it is much weaker than cement.

Among the advantages of cement mortar are: its hydraulic quality, in virtue of which it hardens even quicker in water than in air; its greater adhesive power; its rapidity of setting; and the great ultimate strength that it attains. The points against it are: the extra care required in mixing and handling; and its greater cost, which is, of course, the controlling factor. Summing up, it is evident that cement is greatly preferable to lime, and the quality of masonry laid with it is so much superior as to more than counterbalance the difference in cost over lime mortar.

Cement mortar possesses an advantage over lime mortar, in that in setting it does not shrink. Because of this property, and because of the fact that cement mortar sets rapidly, walls can be laid up in cement mortar much more rapidly than they can in lime mortar and with greater safety.

A mixture of cement and lime mortars is frequently used, and is a considerable improvement on ordinary lime mortar, in that, if the quality of lime is not greater than one-fourth or one-fifth that of the cement, the strength will be practically that of cement mortar, and the mixture will set quickly in damp places, while the cost will be materially less than that of cement mortar.

It may be interesting to compare the relative cost of masonry laid in lime and in cement mortar. For this purpose the following figures are given, which, being obtained from a very reliable source, will undoubtedly be found quite accurate. To work from a common basis, the estimates are made per 1,000 brick, and per perch of rubble masonry, all laid in 1-to-3 mortar. The quantities given, of course, remain constant, while the prices vary according to local rates. These figures represent actual cost.

BRICKWORK IN LIME MORTAR	
1,000 brick	\$6.00
3 bushels lump lime, at \$.2575
½ load (½ cubic yard) sand, at \$1.5075
Bricklayer, 7 hours, at \$.35	2.45
Helper, 7 hours, at \$.15	1.05
Cost, per 1,000 laid	\$11.00

BRICKWORK IN CEMENT MORTAR	
1,000 brick	\$6.00
1½ barrels Rosendale cement, at \$1.50	2.25
½ load sand, at \$1.5075
Labor, same as before.	3.50
Cost	\$12.50

NOTE.—If Portland cement is used, the cost will be about \$13.63 per thousand brick.

RUBBLE MASONRY IN LIME MORTAR	
1 perch stone	\$1.25
1 bushel lime25
½ load sand, at \$1.5025
Mason, ⅓ day, at \$3.00	1.00
Helper, ¼ day, at \$1.5038
Cost, per perch	\$3.13

RUBBLE MASONRY IN CEMENT MORTAR

1 perch stone	\$1.25
$\frac{1}{2}$ barrel Rosendale cement, at \$1.5075
$\frac{1}{8}$ load sand, at \$1.5025
Labor, same as before	1.38
Cost	<u>\$3.63</u>

NOTE.—Using Portland cement, at \$2.25 per barrel, the cost per perch will be \$4.01.

From these figures, it is evident that a considerable difference exists between the cost of lime and cement mortars, in favor of the former. A large part of this difference may be overcome by replacing some of the cement by lime, which will cheapen the mortar, and at the same time give it the valuable qualities possessed by both materials.

MATERIALS OF STRUCTURAL ENGINEERING

(PART 3)

TIMBER AND METALS

CHARACTERISTICS OF TIMBER

1. Wood, as a building material, is divided into three general groups; namely, the *evergreen*, the *tropical*, and the *hardwood*. In the first of these are classed pine, spruce, hemlock, cedar, cypress, etc.; in the second, palm, rattan, bamboo, etc.; in the third, oak, chestnut, walnut, locust, maple, hickory, ash, boxwood, whitewood, and a number of others. Each of these woods has peculiarities and characteristics which render it fit and useful for some building purposes, and utterly unfit and useless for others.

2. White pine, commonly known as *pine*, or sometimes referred to as *northern pine*, to distinguish it from the species described below, is a tree common in the northern part of the United States and in Canada. It furnishes a light, soft, and straight-grained wood of a yellowish color, but is not so strong as other woods of the same class, and in building is used principally as a finishing material, where a good, durable, but inexpensive job is required. As a material for patternmaking it has no equal, and its power of holding glue renders it invaluable to the cabinetmaker and joiner.

3. Georgia pine, also known as *hard pine*, *pitch pine*, and occasionally as *long-leaved pine*, which is really the

For notice of copyright, see page immediately following the title page

best name for it, is a large forest tree growing along the southern coast of the United States, from Virginia to Texas, and extending only about 150 miles inland. Its annual rings are smaller than those of the white pine, and have a dense, dark-colored, resinous summer growth, which gives the wood a well-marked grain.

The wood is heavy, hard, strong, and, under proper conditions, very durable. For heavy framing timbers and floors it is most desirable, and on account of its grain is sometimes used for the trim of unimportant rooms. It rapidly decays in a damp location, and therefore cannot be used for house sills, or as sleepers or posts that are in contact with the ground, but if situated in a dry, well-ventilated place, it will remain practically unchanged for over a century.

Great care should be exercised in obtaining Georgia pine, as in many localities this wood is confused with another material variously known as *Carolina pine* and *Northern yellow pine*, which is greatly inferior to it in every respect.

The *Carolina pine* is not a long-leaved pine, and is neither so strong nor so durable as the Georgia or Southern pine. In appearance it is somewhat lighter than the long-leaved pine, and the fiber is softer and contains less resin than the regular hard, or pitch, pine.

4. **Spruce** is a name given to all the wood furnished by the various species of the spruce fir tree. There are four varieties of the wood, known as *black spruce*, *white spruce*, *Norway spruce*, and *single spruce*.

Black spruce grows in the northern half of the United States and throughout British America. Its wood is light in weight, reddish in color, and, though easy to work, is very tough in fiber and highly desirable for joists, studs, and general framing timber. It is also greatly used for piles and submerged cribs and cofferdams, as it not only preserves well under water but also resists the destructive action of parasitic crustacea, such as barnacles and mussels, longer than any other similar wood.

White spruce is not so common as the black variety, though, when sawed into lumber, it can scarcely be distinguished from it. Its growth is confined to the extreme northern part of the United States and to British America. Another variety of white spruce is a large-sized tree growing in the central and southern parts of the Rocky Mountains, from Mexico to Montana.

Norway spruce is a variety growing in Central and Northern Europe and in Northern Asia, and its tough, straight grain makes it an excellent material for ships, masts, spars, etc., as well as the more ordinary purposes of house building. Under the name of *white deal*, it fills the same place in the European woodworking shops as white pine does in America.

Single spruce grows in the central and the western part of the United States. It is lighter in color, but otherwise its properties are similar to the black and the white spruce.

5. Hemlock is similar to spruce in appearance, though much inferior as a building material. The wood is very brittle, splits easily, and is liable to be *shaky*. Its grain is coarse and uneven, and though it holds nails much more firmly than pine, the wood is generally soft and not durable.

Some varieties of it are better than others, but in commerce they are so mixed that it is difficult to obtain a large quantity of even quality. Hemlock is used almost exclusively as a cheap, rough framing timber.

6. White cedar is a soft, light, fine-grained, and very durable wood, but lacks both strength and toughness. Its durability makes it a desirable material for shingles, and also for tanks in which water is stored; these are about the only purposes for which it is used in building construction, though it is used largely in boat building, cigar-box manufacture, and cooperage.

7. Red cedar is a smaller tree than white cedar, and of much slower growth. The wood is very similar in texture to white cedar, but even more compact and durable. It is of a reddish-brown color, and possesses a strong, pungent

odor, which repels insects. Its extreme durability makes it valuable for posts, sills, sleepers, etc. in contact with the ground, and its strong odor renders it extremely serviceable as shelving for closets and linings for chests and trunks, where the exclusion of moths and other insects is desired.

8. Cypress is a wood very similar to cedar, growing in Southern Europe and in the southern and western portions of the United States. It is one of the most durable woods, and is well adapted for outside use.

In the northern part of the United States its use is confined almost exclusively to shingles, but in the South it is used as extensively as pine is in the North.

9. Redwood is the name given to one of the species of giant trees of California, and is the most valuable timber grown in that state. It grows to a height of from 200 to 300 feet, and its trunk is bare and branchless for one-third of its height. The color is a dull red, and while the wood resembles pine and is used generally in the West for the same purposes as pine is in the East, it is inferior to pine on account of its peculiarity of *shrinking lengthwise* as well as crosswise. It is used largely for railroad ties, fence posts, telegraph poles, and other purposes where durability under exposure is required. As an interior finishing material it is highly prized, as it takes a high polish, and its color improves with age.

10. The hardwood group is headed by the oak as typical of its class, nearly all others being compared with it in regard to hardness, durability, and strength.

White oak is the hardest of the several American species of the oak tree, and it grows in abundance throughout the eastern half of the United States. It furnishes a wood that is heavy, hard, cross-grained, strong, and of a light yellowish-brown color. It is used where great strength and durability are required, as in framed structures, ship building, cooperage, and carriage making.

Red oak is similar in nearly every respect to white oak, except in its grain and color, the grain usually being

coarser and the color darker and redder. It is also about 12 per cent. softer.

English oak is similar to the American oaks in color, texture, and appearance, but is superior to them for such structural purposes as ship building and house framing.

The structure of the fiber, and the large, thick, and numerous medullary rays, make oak especially prized as a material for cabinetwork and furniture when the log is quarter-sawed. The silver grain and the high and durable polish that the wood is capable of receiving, make it one of the most beautiful used in joinery and cabinetwork.

11. Ash, the wood of a large tree growing in the colder portions of the United States, is heavy, hard, and very elastic. Its grain is coarse, and its color is very similar to that of red oak, which it also resembles in strength and hardness.

Ash is sometimes used for furniture and cabinetwork, making a good imitation of oak, but it is never so strongly marked in the silver grain as oak, and its tendency, after a few years, to become decayed and brittle renders it unfit for structural work.

12. Hickory is the heaviest, hardest, toughest, and strongest of all the American woods. The medullary rays are very numerous and distinct, and produce a fine effect in the quarter-sawed plank. The flexibility of the wood, together with its toughness and strength, render it valuable in the manufacture of carriages, sleighs, and implements requiring bent-wood details.

As a building material, it is unfit for use: first, on account of its extreme hardness and difficulty of working; and second, on account of its liability to the attacks of boring insects, even after the fibers have been filled and varnished.

13. Locust is one of the largest forest trees in the United States, and furnishes a wood that is as hard as white oak. It is composed of very wide annual layers, in which the vessels are few, but very large, and are arranged in rows, giving the wood a peculiar striped grain. Its principal use is in exposed places where great durability is required, while

for posts for buildings and fences in damp locations it has no superior. Its hardness increases with age, and on this account it is used for turned ornaments and occasionally in cabinetwork.

14. Maple is a large-sized timber tree that furnishes a light-colored, fine-grained, hard, strong, and heavy wood. The annual growth is narrow and close, but on careful examination small vessels may be seen scattered through it. The medullary rays are small and distinct, giving to the quarter-cut lumber a clearly defined silver grain. Two other characteristics of the grain are observed, especially in old trees, and are known as *curly maple* and *bird's-eye maple*. The former is a waviness of the grain similar to the burl obtained from the root timber of the walnut tree, while the bird's-eye is an effect produced in old trees by the circular inflexion of the fibers. The plank appears to be covered with numerous small spots, similar to minute knots, and strongly resembling birds' eyes, whence it derives its name. Though the appearance of both the curly maple and the bird's-eye maple is practically due to distorted fibers, which materially reduce the strength of the wood, they are highly prized in the cabinetmaker's art, as they lend to the polished surface a variegation and impart a beauty equaled by few other materials.

15. Chestnut, a large forest tree common to the eastern part of the United States, produces a comparatively soft, coarse-grained wood that, though very brittle, is exceedingly durable when exposed to the weather. It will not stand variations of slowly evaporating moisture as well as locust, and is therefore not so well suited for fence posts and sills laid in contact with the earth; but for exposed structures and sleepers laid in concrete or sandy soil, it affords a material much more easily worked than locust and nearly as durable as cedar.

At the age of 50 years the tree is in fine condition for cutting, previous to which the wood is likely to be composed of large cells filled with moisture, that do not dry out without

impairing the quality of the timber. On the other hand, if the tree is not cut at 50 years, it is almost sure to become decayed in the heart wood, and thereby rendered unfit for use.

16. Beech is the wood of a large forest tree growing in the eastern part of the United States, and in Europe. It is used but slightly in building, owing to its tendency to rot in damp situations, but it is often used, especially in European countries, for piles, in places where it will be constantly submerged. It is very hard and tough, and of a close, uniform texture, which renders it a desirable material for tool handles and plane stocks, a use to which it is often put. It is occasionally used for furniture on account of its susceptibility to a high polish, but is too brittle for very fine work requiring strength.

17. Whitewood, so called from the purity of its color, is the lumber of the tulip tree, a large, straight forest tree abundant in the United States. It is light, soft, very brittle, and shrinks excessively in drying. When thoroughly dry it will not split with the grain, and in even slight atmospheric changes will warp and twist exceedingly. Its cheapness, ease of working, and the large size of its boards cause it to be used in carpentry and joinery, in many places where it is utterly unsuited.

18. Buttonwood, also called **sycamore**, is the name given in the United States to the wood of a species of tree generally known as **plane tree**. The wood is heavy and hard, of a light brown color, and very brittle. Its grain is fine and close, but, though susceptible to a high polish, it is not much used in general carpentry or joinery, as it is very hard to work and has a strong tendency to warp and twist under variations of temperature. In damp places it will soon show signs of decay and is therefore unfitted for any but the most protected positions.

19. Lignum vitæ is an exceedingly heavy, hard, and dark-colored wood, with an almost solid annual growth. It

is very resinous, difficult to split, and has a soapy feeling when handled. Its color is dark brown, with lighter brown markings, and it is used mostly for small turned articles, tool handles, and the sheaves of block pulleys.

STRENGTH VALUES

20. The ultimate strength of any material is that unit stress that is just sufficient to break it.

The ultimate elongation is the total elongation produced in a unit of length of the material having a unit of area, by a stress equal to the ultimate strength of the material.

21. Modulus of Rupture.—When a simple beam breaks, the fibers at the top are in *compression*, and those at the bottom in *tension*, as shown in Fig. 1. By actual tests,




FIG. 1

it has been found that though some of the different fibers of materials under transverse stresses are in compression and some in tension, the ultimate

resistance of the material does not agree with the ultimate resistance of the fibers to either tension or compression. Though many attempts have been made to account for it, this fact remains; hence, it becomes necessary to obtain some constant, or value, more closely agreeing with the strength of materials under transverse stress. It is usual, therefore, where the cross-section of the beam is uniform, to obtain, by actual tests, the constant or value for each material. This value is called the **modulus of rupture** and is generally expressed in pounds per square inch.

22. Table I gives values of the strength of timber when subjected to different stresses. The column in the table, headed Compression, With Grain, will be found useful in computing the strength of columns. The values in the column headed Compression, Across Grain, are used in cases similar

TABLE I
AVERAGE ULTIMATE BREAKING UNIT STRESSES, IN POUNDS, PER SQUARE INCH

Kind of Timber	Tension		Compression			Transverse		Shearing	
	With Grain	Across Grain	With Grain End Bearing	Columns Under 15 Diam.	Across Grain	Modulus of Rupture	Modulus of Elasticity	With Grain	Across Grain
White oak	10,000	2,000	7,000	4,500	2,000	6,000	1,100,000	800	4,000
White pine	7,000	500	5,500	3,500	800	4,000	1,000,000	400	2,000
Southern long-leaf or Georgia yellow pine	12,000	600	8,000	5,000	1,400	7,000	1,700,000	600	5,000
Douglas, Oregon, and yellow fir	12,000		8,000	6,000	1,200	6,500	1,400,000	600	
Washington fir or pine (red fir)	10,000					5,000			
Northern or short-leaf yellow pine	9,000	500	6,000	4,000	1,000	6,000	1,200,000	400	4,000
Red pine	9,000	500	6,000	4,000	800	5,000	1,200,000		
Norway pine	8,000		6,000	4,000	800	4,000		350	
Canadian (Ottawa) white pine	10,000			5,000		5,000	1,400,000	400	
Canadian (Ontario) red pine	10,000	500	6,000	4,000	700	4,000	1,200,000	400	3,000
Spruce and eastern fir	8,000			4,000	600	3,500	900,000	350	2,500
Hemlock	6,000		6,000	4,000	700	5,000	900,000		
Cypress	6,000		6,000	4,000	700	5,000	700,000		1,500
Cedar	8,000		6,000	4,000	900	5,000	1,000,000	600	1,500
Chestnut	9,000			5,000	800	4,500	700,000	400	
California redwood	7,000			4,000		5,000	1,200,000		
California spruce				4,000					
Factor of safety	10	10	5	5	4	6	2	4	4

to Fig. 2, and are such as will not produce an indenture of more than $\frac{1}{16}$ inch in the surface of the timber, a value well within the safe limit. The values under the heading, Shearing, With Grain, are used in computing the strength of the end of the tie-beam at the heel of the main rafter in a




FIG. 2

roof truss, as shown in Fig. 3. The tendency is to shear off the piece *A* parallel to the grain along the line *ab*. The figures in the column headed Transverse, Modulus of Rupture, are the constants, or values, used when computing the strength of beams.




FIG. 3

The values in Table I were recommended by the committee on Strength of Bridge and Trestle Timbers of the Association of Railway Superintendents of Bridges and Buildings in its fifth annual convention, which was held in New Orleans, October, 1895.

CHARACTERISTICS OF IRON AND STEEL

23. Iron is very widely distributed in nature and its compounds are abundant. Probably no portion of the earth's crust is free from it, yet it occurs native only in very small quantities, and the iron thus found is probably of meteoric origin and is always alloyed to some extent with other metals, as nickel, cobalt, copper, etc. Its strong affinity for non-metals explains its infrequent occurrence in the native condition; and the dissimilarity between the metal and its ores may explain why it was among the later useful metals to be discovered, if, as is generally believed, such is the case. It may be mentioned, however, that some writers think that iron was known and used at a much earlier period in the world's history than is generally believed, but that its tendency to corrode has destroyed all traces of its use in ancient times, while instruments of brass and bronze remain.

Chemically pure iron is valuable only for experimental purposes and as a curiosity, as it has no use in the arts except, perhaps, in medicine. It may be obtained on a small scale in several ways, among which may be mentioned the reduction of pure ferric oxide by heating it in a current of hydrogen, and by the electrical decomposition of a solution of pure ferrous sulphate or chloride. While pure iron is devoid of value, when it contains small quantities of other elements it is the most useful and widely used of all metals; in fact, it is almost impossible to overestimate its importance in the arts.

24. The manufacture of iron from its ores depends on chemical principles with which we are familiar. As iron does not occur native, it is necessary to reduce its compounds, and this is done in such a manner that the resulting metal will contain the elements necessary to give it the properties that have made it so valuable. The method almost universally employed is to charge in the ore, together with the fuel—which at present is nearly always

either coke, coal, or charcoal—at the top of a tall furnace; as the ore always contains extraneous matter, a flux is added in the proper amount to form a fusible slag with these impurities. Hot air blown into the furnace near the bottom, on coming in contact with the highly heated fuel in excess, forms carbon monoxide, which passes up through the descending charge of ore, fuel, and flux. At the temperature of the furnace, both the carbon of the fuel and the carbon monoxide thus formed act as reducing agents on the ore, removing the oxygen and leaving metallic iron, which, at the intense heat near the bottom of the furnace, melts and drops to the bottom, taking up some carbon from the fuel, and silicon, sulphur, phosphorus, and manganese from the ore, fuel, and flux. At the same time, the silica, alumina, lime, and magnesia of the ore, fuel, and flux unite, forming a fluid slag that, being lighter than iron, floats on the molten metal in the bottom. The iron and slag thus formed are drawn out at proper intervals through openings provided for them in the bottom of the furnace.

When the ascending gas reaches the top of the furnace it contains considerable carbon monoxide, which is very combustible. It passes through an opening near the top of the furnace and is led through the “down-comer” to a feedpipe. Part of it is then used to heat the stoves that are employed to heat the blast of air blown in near the bottom of the furnace by means of blowing engines. The part of the gas not used in the stoves is burned under the boilers that produce steam to run the blowing engines.

25. Definition of Steel.—While at first thought it seems to be a simple matter to define *steel* properly, the more familiar one becomes with the subject, the more perplexing is it to write a concise definition that will apply to the wide range of steels produced, or even to the greater part of them. Before the introduction of the modern methods of manufacture, the distinction between steel and wrought iron was sharp and well marked, and steel could be defined as any alloy of iron with carbon that would take

a temper on quenching. Wrought iron does not sensibly harden on sudden cooling in water from a red heat. Modern methods of manufacture, however, have produced a metal that largely partakes of the nature of wrought iron, though it is made by the same processes that give a metal that hardens on quenching. For this reason such a classification as the above would now throw out the greater amount, or at least a very large tonnage, of the material classed and accepted by the metallurgical and commercial world as steel. The Bessemer converter and open-hearth furnace early showed an adaptability to produce a soft metal having great strength, elasticity, and ductility, capable of displacing wrought iron, and, for most purposes, far superior to it. It is impossible, therefore, to offer a thoroughly comprehensive definition of steel that is not easily assailable and whose inapplicability is shown from some standpoint.

Steel may be defined as a metal produced by the complete fusion of materials in a bath, the necessary properties being given, after conversion, by additions of carbon or carbon alloys. Wrought iron may be defined as a metal produced by the partial fusion, or bringing to a pasty condition, of materials on a hearth.

Blister, or cementation, steel, which is made by soaking bars of iron, at or above a red heat, in charcoal or carbon, would seem to be a notable exception; but as this is mainly an intermediate product for remelting in crucibles, and as its production is of little importance, it will be disregarded in this treatment of the subject.

The question of the proper classification of steels is one to which much attention has been given in the past, an international committee at one time having been selected from the metallurgical and technical societies of the principal steel-producing countries to adopt a universal classification. While much good came of their work, and strenuous efforts were made to adopt their classification, it was never generally used metallurgically nor commercially.

Many theories have been advanced as to what steel is. One that is held by many practical metallurgists is that the

ideal steel is an alloy of pure iron and carbon only, all other elements being regarded as impurities. From this point of view, all grades of steel can be produced by simply varying the amount of carbon; but as impurities are necessarily present, all steel contains varying, and usually very small, amounts of sulphur, phosphorus, silicon, metallic oxides, and gases, which require other additions for their neutralization or elimination. Again, special alloys are required for giving steels characteristic qualities for particular purposes; such are the nickel, tungsten, chrome, manganese, and molybdenum steel.

26. Processes of Manufacture.—There are only three processes for the manufacture of steel: The *crucible*, the oldest of present methods; the *Bessemer*; and the *open-hearth*. The last two were developed almost simultaneously. The *Bessemer* was first perfected, and for the first 35 years, or up to about 1890, led the *open-hearth*, both as to tonnage produced and in the perfection of methods and appliances—both metallurgical and mechanical. While the *Bessemer* process still produces the greater tonnage, this is the only direction in which it can claim superiority over the *open-hearth*. In the order of their metallurgical and commercial importance today the processes rank: first, the *open-hearth*; second, the *Bessemer*; and third, the *crucible*.

While the *crucible* process is of the least consequence, it holds the most distinctive field metallurgically, and one from which the others seem unlikely to crowd it out. Given the same composition, it is well established that *crucible* steel is superior to either of the others, but owing to the much higher cost of production, its use is now restricted mainly to the making of high-grade tools, certain mining drills, parts of intricate machines, and, in general, where the first cost of the steel can be ignored.

The *open-hearth* process can claim as its own a larger field than the *Bessemer*. *Open-hearth* steel is now used for the better grades of plate steel, forgings, car axles, and structural steel. The basic *open-hearth* process is used

where an extra-soft, pure steel is required, as in plates, sheets, rods, wires, etc. Bessemer steel is used for rails, nails, tin plate, light axles, in fact, for those articles where cheapness is desired. It is, however, being rapidly replaced by steel produced by the basic open-hearth process. The basic process, by cheaper production than was possible in the acid open-hearth, makes this a formidable rival of the Bessemer and seems practically sure to largely supplant it in the next few years. Owing to lower cost of production, the Bessemer process held undisputed sway for years in all lines using a large tonnage of steel. The open-hearth gradually demonstrated its superior fitness for special lines. While both the crucible and open-hearth processes have distinctive fields, held from the cheaper metal by the superior quality of their product, the Bessemer has no field the open-hearth cannot fill, and only by lower cost does it still produce the greater tonnage. Practically all rails are as yet made of Bessemer metal; also, most of the "billets" and "slabs" for merchant bar, tin plate, sheets, nails, light axles, and some ship and tank plates, etc.

27. Table II gives the average ultimate strengths of the various metals employed in building construction.

EXAMPLE 1.—What pull will be required to break a 2-inch diameter rod of wrought iron?

SOLUTION.—The area of the rod is equal to the area of a 2-in. circle, which is $2^2 \times .7854 = 3.14$ sq. in.; the ultimate tensile, or breaking, strength of wrought iron, according to Table II, is 48,000 lb. per sq. in. Therefore, the ultimate strength of the rod in question is $3.14 \times 48,000 = 150,720$ lb. Ans.

EXAMPLE 2.—What length of wrought-iron bar, if hung by one end, will break of its own weight, assuming the weight of 1 cubic inch of wrought iron to be .227 pound.

SOLUTION.—Assume any size of bar; say, $1\frac{1}{8}$ in. in diameter. The area of this bar is .99 sq. in., which may, for convenience, be called 1 sq. in. Now, as there is just 1 cu. in. in each lineal inch in the rod, a length of 1 ft. weighs $.277 \times 12 = 3.32$ lb. The tensile strength of wrought iron being 48,000 lb. per sq. in., and 1 ft. of its length weighing 3.32 lb., the length of rod required is $\frac{48,000}{3.32} = 14,458$ ft. Ans.

TABLE II
AVERAGE ULTIMATE STRENGTHS OF MATERIALS IN POUNDS PER SQUARE INCH

	Compres- sion	Tension	Elastic Limit	Shearing	Modulus of Rupture	Modulus of Elasticity
BRASS, BRONZE, AND COPPER						
Brass, cast	(30,000)	24,000	6,000	36,000	20,000	9,000,000
Brass wire, annealed		50,000				
Brass wire, unannealed		80,000	16,000			14,000,000
Bronze, aluminum	120,000	75,000				
Bronze, gun metal	(20,000)	32,000	10,000		53,000	10,000,000
Bronze, manganese	120,000	60,000	30,000			
Bronze, phosphor		50,000	24,000			14,000,000
Bronze, Tobin		66,000	40,000			4,500,000
Copper, bolts	30,000	30,000				
Copper, cast	(40,000)	24,000	6,000	30,000	22,000	10,000,000
Copper wire, annealed		36,000				15,000,000
Copper wire, unannealed		60,000	10,000			18,000,000
CAST AND WROUGHT IRON						
Iron, cast	80,000	15,000	6,000	18,000	30,000	12,000,000
Iron wire, annealed		60,000				15,000,000
Iron wire, unannealed		80,000	27,000			25,000,000
Iron, wrought, shapes	46,000	48,000	20,000	40,000	44,000	27,000,000
Iron, wrought, rerolled bars	48,000	50,000	27,000	40,000	48,000	26,000,000
CAST AND STRUCTURAL STEEL						
Steel, castings	70,000	70,000	40,000	60,000	70,000	30,000,000
Steel, structural, soft	56,000	56,000	30,000	48,000	54,000	29,000,000
Steel, structural, medium	64,000	64,000	33,000	50,000	60,000	29,000,000
Steel wire, annealed		80,000	40,000			29,000,000
Steel wire, unannealed	120,000	120,000	60,000			30,000,000
Steel wire, crucible	180,000	180,000	80,000			30,000,000
Steel wire, for suspension bridges	200,000	200,000	90,000			30,000,000
Steel wire, special tempered	300,000	300,000				

NOTE.—Compression values enclosed in parentheses indicate loads producing 10 per cent. reduction in original lengths.

FACTOR OF SAFETY

28. The **factor of safety**, or, as it is sometimes called, the **safety factor**, is the ratio of the breaking strength of the structure to the load that, under usual conditions, it is called on to carry. Suppose that the load required to break, dismember, or crush a structure is 5,000 pounds, and that the load it is called on to carry is 1,000 pounds, then the factor of safety may be obtained by dividing 5,000 pounds by 1,000 pounds, or $\frac{5000}{1000} = 5$, the factor of safety in this structure.

The factor of safety depends on the conditions, circumstances, or materials used; in other words, it is the *factor of ignorance*. When a piece of steel, wood, or cast iron is used in a building, the engineer does not know the exact strength of that particular piece of steel, wood, or cast iron. From his own experience, and that of others, he knows the approximate tensile strength of structural steel to be 60,000 pounds per square inch, and that it varies more or less from this value. In regard to timber, the uncertainty is much greater, because of knots, shakes, and interior rot, not always evident on the surface. Cast iron is even more unreliable, on account of almost indeterminable blowholes, flaws, and imperfections in the castings.

29. Deterioration.—Another factor to be considered is **deterioration** in the material, due to various causes. In metals there is corrosion on account of moisture and gases in the atmosphere, especially noticeable in the steel trusses over railroad sheds, where the sulphur fumes from the stacks of the locomotives unite with the moisture in the air, forming free sulphuric acid, which attacks the steel vigorously, and it demands constant painting to prevent its entire destruction. Wood is subject to decay from either dry or wet rot, caused by local conditions; it may, like iron and steel, be subjected to *fatigue*, produced by constant stress due to the load it is required to sustain. Cast iron does not deteriorate to any great extent, its corrosion not being as

rapid, possibly, as that of steel or wrought iron. However, there are internal strains produced in cast iron by the irregular cooling of the metal in the mold. Under the slightest blow, castings will sometimes, owing to these internal stresses, snap and break in a number of places.

These reasons are, in truth, sufficiently cogent to require the factor of safety now adopted in all engineering work. Table III gives the factor of safety commonly employed by conservative constructors for various materials used in building work.

TABLE III
FACTOR OF SAFETY FOR DIFFERENT MATERIALS USED
IN CONSTRUCTION

Materials	Factor of Safety
Structural steel and wrought iron	3 to 4
Wood	4 to 5
Cast iron	6 to 10
Stone	10 at least

In this table, the factor of safety generally used for structural steel is 3 to 4, which simply means that the steel structure should not break until it bears a load three or four times greater than it is designed to carry.

EXAMPLE.—If the breaking strength of a cast-iron column is 200,000 pounds, what safe load will the column sustain if a factor of safety of 6 is used?

SOLUTION.— $200,000 \div 6 = 33,333 \text{ lb.}$ Ans.

EXAMPLES FOR PRACTICE

1. Provided a factor of safety of 3 is adopted, what will be the safe working strength of a 2-inch diameter tension rod of medium structural steel?
Ans. 67,020 lb.
2. The pull on a 2-inch eyebolt, passing through a piece of Southern yellow pine, is 40,000 pounds. What should be the diameter of the washer, if the bolt hole through it is $2\frac{1}{8}$ inches in diameter?
Ans. 6.4 in.

3. The bottom of the notch in a spruce timber 10 inches wide and 12 inches deep, forming the tie-member in a roof truss, is 18 inches from the end. What resistance will the end of the tie offer to the thrust of the rafter? Ans. 72,000 lb.

4. A short block of Northern yellow pine, 10 inches by 10 inches in section, standing on end, supports 50,000 pounds. What is its factor of safety? Ans. 12

BEAMS AND GIRDERS

(PART 1)

ELEMENTS OF BEAMS

DEFINITIONS

1. Any bar resting on supports and liable to be subjected to transverse stresses is called a **beam**.

A large beam that carries smaller, or secondary beams, is a **girder**.

A beam resting on two supports very near its end is a **simple beam**.

A beam resting on one support at its middle, or having one end fixed (as in a wall) and the other end free, is a **cantilever**.

A beam that has both ends firmly secured is a **fixed beam**.

A beam that rests on more than two supports is a **continuous beam**.

The distance between the supports of a simple beam is its **span**.

MOMENTS OF FORCES

2. In order to calculate the stresses produced in beams under different conditions, and the forces at the points of support, it is necessary to understand the theory of the *moments of forces*.

In Fig. 1, W is a weight that acts downwards with a force of 10,000 pounds. If some fixed point a , not in the line along which the weight W acts, is connected with the line of

For notice of copyright, see page immediately following the title page

action of W by a rigid arm, so that W pulls on one end of this arm, while the other end is firmly held at a , experience teaches that the pull of W tends to turn, or rotate, the arm around the point a . The tendency of a force to produce




FIG. 1

rotation around a given point is called the **moment of the force** with respect to that point.

The point a that is taken as the center around which there is a tendency to rotate, is called the **center of moments**.

The perpendicular distance from the center of moments to the line along which the force acts, is the **lever arm** of the force, also called the **leverage** of the force.

3. The measure of the moment of a force, that is, of the tendency of the force to produce rotation around a given center, is the product of the magnitude of the force multiplied




FIG. 2

by the length of its lever arm. In Fig. 1, for example, the magnitude of the force is equal to the weight of 10,000 pounds, and the length of the lever arm is 10 feet; therefore, the moment of the force W , with respect to the center a , is

$10,000 \times 10 = 100,000$, which, since the factors by which it is produced represent feet and pounds, is called **foot-pounds**. Thus, the moment of a force of 10,000 pounds, whose lever arm is 10 feet long, is $10,000 \times 10 = 100,000$ foot-pounds.

EXAMPLE.—What is the moment of the force of 10,000 pounds whose line of action is $a b$, Fig. 2, the center of moments being at d ?

SOLUTION.—The perpendicular distance $c d$ from the line of action of the force to the center of moments being 5 ft., and the magnitude of the force 10,000 lb., the moment is $10,000 \times 5 = 50,000$ ft.-lb. Ans.

4. In Fig. 3, the line of action of the force of 10,000 pounds passes directly through the point d ; consequently, the

d ————— 10000 lb.

FIG. 3

perpendicular distance from the line of action to the point d is *zero* and there is no tendency to rotate around that point; therefore, there is no motion.

5. The moment of a force may be expressed in *inch-pounds*, *foot-pounds*, or *foot-tons*, depending on the unit of measurement used to designate the magnitude of the force and the length of its lever arm. For instance, if the magnitude of a force is measured in pounds, and the lever arm through which it acts, in inches, the moment will be in *inch-pounds*; if a force of 10 tons acts through a lever arm of 20 feet, the moment of the force is $10 \times 20 = 200$ *foot-tons*.

EXAMPLE.—What is the moment, in inch-pounds, of a force of 8,000 pounds, if the length of the lever arm is 13 feet?

SOLUTION.—Since the moment is to be in inch-pounds, the length of the lever arm must be in inches. $13 \text{ ft.} = 13 \times 12 = 156 \text{ in.}$, and the moment is $8,000 \times 156 = 1,248,000$ in.-lb. Ans.

6. **Equilibrium of Moments.**—When a body is at rest, the forces that act on it must balance one another; the forces are then said to be in **equilibrium**. That there may be perfect balance among the forces, it is necessary that there be not only no unbalanced force tending to move the body along some given line, but that there be, also, no

unbalanced moment, the effect of which would turn the body about some point.

Fig. 4 shows a beam or lever, resting on the support c , on the right-hand end of which a force b of 5 pounds acts downwards tending to turn it around the point of support c in the direction traveled by the hands of a clock, that is, to produce **right-hand** rotation. The measure of this tendency is $5 \times 10 = 50$ foot-pounds. Another force a acts downwards on the left-hand end of the lever, tending to produce **left-hand** rotation, or to turn the lever in the direction opposite to that traveled by the hands of a clock. Since the force a is 10 pounds, and it acts with a lever arm of 5 feet, its moment is $10 \times 5 = 50$ foot-pounds, the same as the moment of the force b . There are thus two equal moments, one tending to turn the lever to the right and the other to the left;




FIG. 4

as a result, the effect of one is neutralized by the effect of the other, and the second condition of equilibrium is fulfilled; that is, there is *equilibrium of moments*.

7. Positive and Negative Moments.—It is customary to distinguish between the directions in which there is a tendency to produce rotation by the use of the signs $+$ and $-$. Thus, if a force tends to produce right-hand rotation, its moment may be called **positive** and be given the plus sign, while a force that tends to produce rotation in the opposite direction is called **negative**, and its moment is given the minus sign. That there may be equilibrium of moments, the above considerations show that the difference between the sum of the positive moments and the sum of the negative moments must be zero; this difference is called the **algebraic sum** of the moments. The following principle is then evolved: *In order that there may be equilibrium, the algebraic sum of the moments of all the forces acting on a body must be zero.*

8. Resultant and Reactionary Moments.—In Fig. 5 is shown a lever composed of two arms at right angles to each other and free to turn about the center c . A force a , whose moment is $10 \times 5 = 50$ foot-pounds, acts on the horizontal arm in such a manner that it tends to produce left-hand rotation. Another force b , whose moment with respect to the center c is $12 \times 3 = 36$ foot-pounds, tends to produce right-hand rotation. These two forces, therefore, will not produce equilibrium, but their combined efforts will be equal to the algebraic sum of the moments. This sum is the **resultant moment** of the two forces a and b . Thus, $-50 + 36 = -14$ foot-pounds, which is the resultant moment of the forces considered, because it produces the same effect as the two moments combined.




FIG. 5

In order to secure equilibrium, there must be another force acting in such a manner as to overcome the algebraic sum of these two moments, and consequently its moment must be equal and opposite in effect to the resultant moment. The name given to the moment of this force is **reactionary moment**.

If the length of the lever arm of the force that acts to produce the reactionary moment is known, the magnitude of the force may be readily found. Thus, in the present case, the resultant moment is -14 foot-pounds; let it be required to find the force to produce equilibrium, when acting with a lever arm 7 feet long. Since the moment is the product of the force multiplied by its lever arm, it follows that the required force may be found by dividing the given moment by the length of the lever arm; consequently, the required force is $14 \div 7 = 2$ pounds.

If, instead of the two forces just considered, we have a body acted on by a number of forces whose moments about

If, instead of the two forces just considered, we have a body acted on by a number of forces whose moments about

a given center are known, the reactionary moment of these forces, that is, the moment of the force required to produce equilibrium, is the algebraic sum of the moments of the given forces with the sign changed; and, further, if the length of the lever arm of the reactionary moment is known, the magnitude of the required force can be found by dividing the moment by the length of the lever arm.

9. The above principles may be expressed as follows:

Rule.—*To find the force required to produce equilibrium of moments, when the moments of any number of given forces and the lever arm of the required force are given, divide the algebraic sum of the given moments by the length of the given lever arm. If the algebraic sum is positive, the required force must tend to produce left-hand rotation; if negative, the force must tend to produce right-hand rotation.*

EXAMPLE.—In Fig. 6, a system of forces, shown by the arrows, acts in various directions and at various distances from the center O . The force F' is 25 pounds and its lever arm Op' is 8 feet, F'' is 16 pounds with a lever arm Op'' of 12 feet, F''' is 40 pounds with a lever arm Op''' of 6 feet, and the force F^v is 100 pounds, acting directly through the center O . If the distance Op^{iv} is 12 feet, what must be the magnitude of the force F^{iv} in order to produce equilibrium of moments?




FIG. 6

SOLUTION.—As shown by the arrows, the forces tending to produce right-hand rotation are F' and F''' , and their moments, called positive, are, respectively, $25 \times 8 = +200$ ft.-lb., and 40×6

$= +240$ ft.-lb. The lever arm of the force F^v is zero; consequently, it has no moment with respect to the center O . The force F'' tends to produce left-hand rotation and its moment is $16 \times 12 = -192$ ft.-lb. The algebraic sum of the moments of the given forces is $+200 + 240 - 192 = +248$ ft.-lb.; therefore, according to the rule, the force F^{iv} must be $248 \div 12 = 20\frac{2}{3}$ lb., which, since the algebraic sum of the given moments is positive, must tend to produce left-hand rotation, as shown by the arrow. Ans.

10. The principles involved in the theory of moments are among the most simple in mechanics, and, at the same time, of the greatest practical importance in the solution of

problems relating to the strength of beams, girders, and trusses.

EXAMPLE.—In Fig. 7, the lower tie-member in the roof truss has been raised to secure a vaulted ceiling effect in the upper story of the building that the truss covers. The weight transmitted through this member to the pier wall is 30,000 pounds; there is, consequently, an equal upward force due to the reaction of the wall. This force of 30,000 pounds tends to break the truss by producing rotation about the point *b*. What is its moment around the point *b*?

SOLUTION.—Since the perpendicular distance from the line of action of the force is 3 ft., the moment of the force *a* around the point *b* is $30,000 \times 3 = 90,000$ ft.-lb. Ans.

THE LEVER

11. A lever is a bar capable of being turned about a pin, pivot, or point, as in Figs. 8, 9, and 10.

The object *W* to be lifted is called the **weight**; the force *P* used is called the **power**; and the point or pivot *F* is called the **fulcrum**.

That part of the lever between the weight and the fulcrum, or *Fb*, is called

the **weight arm**, and the part between the power and the fulcrum, or *Fc*, is called the **power arm**.

Take the fulcrum, or point *F*, as the center of moments; then, in order that the lever shall be in equilibrium, the moment of *P* about *F*, or $P \times Fc$, must equal the moment of *W* about *F*, or $W \times Fb$. That is, $P \times Fc = W \times Fb$, or, in




FIG. 7

other words, the power multiplied by the power arm equals the weight multiplied by the weight arm.

If F be taken as the center of a circle, and arcs be described through b and c , it will be seen that, if the weight arm is moved through a certain angle, the power arm will




FIG. 8




FIG. 9

move through the same angle; also, that the vertical distance that W moves will be proportional to the vertical distance that P moves. From this it is seen that the power arm is proportional to the distance through which the power moves,




FIG. 10

and the weight arm is proportional to the distance through which the weight moves.

Hence, instead of writing $P \times Fc = W \times Fb$, it might have been written $P \times \text{distance through which } P \text{ moves} = W \times \text{distance through which } W \text{ moves}$.

This is the general law of all machines, and can be applied to any mechanism, from the simple lever to the most complicated arrangement. Stated in the form of a rule, it is as follows:

Rule.—*The power multiplied by the distance through which it moves equals the weight multiplied by the distance through which it moves.*

EXAMPLE 1.—If the weight arm of a lever is 6 inches long and the power arm is 4 feet long, how great a weight can be raised by a force of 20 pounds at the end of the power arm?

SOLUTION.— 4 ft. = 48 in. Hence, $20 \times 48 = W \times 6$, or $W = 160$ lb.

Ans.

EXAMPLE 2.—(a) What is the ratio between the power and the weight in the last example? (b) In the last example, if P moves 24 inches, how far does W move? (c) What is the ratio between the two distances?

SOLUTION.—(a) $20 : 160 = 1 : 8$; that is, the weight moved is eight times the power.

(b) $20 \times 24 = 160 \times x$. $x = \frac{480}{160} = 3$ in., the distance that W moves.
Ans.

(c) $3 : 24 = 1 : 8$, or the ratio is $1 : 8$. Ans.




FIG. 11




FIG. 12

The law that governs the straight lever also governs the bent lever; but care must be taken to determine the true length of the lever arm, which is in every case the




FIG. 13




FIG. 14

perpendicular distance from the fulcrum to the line of direction of the weight or power.

Thus, in Figs. 11, 12, 13, and 14, Fc in each case represents the power arm, and Fb the weight arm.

EXAMPLES FOR PRACTICE

1. A lever arm has a length of 10 feet; the load acting on the end of the lever is 6,000 pounds. What is the moment of this load, in inch-pounds?
Ans. 720,000

2. A piece of timber 20 feet long is balanced at a point 8 feet from one end, the load at this end being 9,000 pounds. What is the load at the other end?
Ans. 6,000 lb.

3. The one support of a beam 20 feet long is 8 feet from the left-hand end; at this end is a load of 25 pounds; at the right of the support, 3 feet distant, is a load of 5 pounds; and at 7 feet to the right of the support is a load of 10 pounds. What load is required, and at which end should it be placed, to produce balance, or equilibrium, in the beam? Ans. 9.58 lb. at right-hand end

4. A steel I beam that extends 6 feet outside of the center of a building wall, and 3 feet inside, is required to support a load on the outside end of 4,000 pounds. What load on the inner end will keep the beam from tilting? Ans. 8,000 lb.

REACTIONS

12. Since one condition of equilibrium requires that the sum of all the forces acting on a body in one direction must be balanced by an equal set of forces acting in the opposite direction, it follows that, in order that any body may be kept from falling, there must be an upward pressure, or thrust, against it, just equal to the downward pressure due to its weight; this upward thrust is called a **reaction**.

In accordance with this principle, it is evident that the simple beam shown in Fig. 15 is supported by the sum




FIG. 15

of the upward pressures exerted on it by the two brick piers on which it rests; also, that this sum is equal to the weight of the beam plus the weight of any load it may carry. This is expressed by the statement: The sum of the reactions at the supports of any beam is equal to the sum of the loads.

13. Relation Between the Reactions.—If the load on a simple beam is either uniformly distributed over the entire length of the beam, applied at the center of the span, or

symmetrically placed on each side of the center of the span, the reaction at each support is equal to one-half of the total load. When, however, the loads are not symmetrically




FIG. 16

placed, the reactions are unequal and must be determined before the first step toward obtaining the strength of the beam can be taken. The reactions at the points of support




FIG. 17

of a beam carrying a number of loads irregularly placed, are determined by applying the principle of moments, as shown in the following illustrative examples:

14. Two men, a and b , 15 feet apart, carry a 50-pound weight between them on a plank, as shown in Fig. 16. What part of the load does each man carry?

If the load had been placed midway between them, it is quite evident that each man would have half the weight of the plank and load to support. But, since the load is moved until within 5 feet of a , he must support a greater proportion of the load than b . If b raises his end of the plank, as shown in dotted lines, it is evident that a simply acts as a hinge while b raises the weight with a lever arm 15 feet long. The weight of 50 pounds acts down with a leverage of 5 feet; its moment about a as a center is, therefore, $50 \times 5 = 250$




FIG. 18

foot-pounds. That there may be equilibrium of moments, it is evident that the man b must exert an upward force whose moment with a lever arm of 15 feet equals 250 foot-pounds; that is, he must exert a force of $250 \div 15 = 16\frac{2}{3}$ pounds to support his share of the weight. Since the sum of the reactions must equal the sum of the loads, it follows that if b supports $16\frac{2}{3}$ pounds, a must support the difference between the load of 50 pounds and $16\frac{2}{3}$ pounds, or $33\frac{1}{3}$ pounds.

15. Fig. 17 shows the men a and b supporting three loads of 50, 40, and 80 pounds, respectively. It is desired to estimate the force that each must exert to sustain the weights, leaving the weight of the plank out of the question. Assuming the

center of moments to be at a , find the resultant moment of all the weights about this point, as follows:

$$\begin{array}{rcl} 50 \times 3 & = & 150 \text{ foot-pounds} \\ 40 \times 8 & = & 320 \text{ foot-pounds} \\ 80 \times 12 & = & 960 \text{ foot-pounds} \\ \text{Total,} & & 1430 \text{ foot-pounds} \end{array}$$

This is the moment of all the loads on the beam about the point a as a center. Hence, the force that b must exert, in order to produce equilibrium, is $1,430 \div 15 = 95\frac{1}{3}$ pounds. The part of the load that a supports is the difference between the total load, $50 + 40 + 80 = 170$ pounds, and the part of the load supported by b ; that is, $170 - 95\frac{1}{3} = 74\frac{2}{3}$ pounds.




FIG. 19

16. Take a more practical example. In Fig. 18, let it be required to find the reactions R_1 and R_2 . (In all the subjoined problems, R_1 and R_2 represent the reactions.) The center of moments may be taken at either R_1 or R_2 . Taking R_2 as the center in this case, construct a diagram as in Fig. 19. The three loads are forces acting in a downward direction; the sum of their moments, with respect to the assumed center, may be computed as follows:

$$\begin{array}{rcl} 8,000 \times 5 & = & 40,000 \text{ foot-pounds} \\ 6,000 \times 19 & = & 114,000 \text{ foot-pounds} \\ 2,000 \times 27 & = & 54,000 \text{ foot-pounds} \\ \text{Total,} & & 208,000 \text{ foot-pounds} \end{array}$$

The magnitude of the reaction R_1 , acting in an upward direction with a lever arm of 30 feet is therefore $208,000 \div 30 = 6,933\frac{1}{3}$ pounds. The sum of all the loads is $2,000 + 6,000 + 8,000 = 16,000$ pounds. Then $16,000 - 6,933\frac{1}{3} = 9,066\frac{2}{3}$ pounds, the reaction at R_2 .




FIG. 20

EXAMPLE 1.—What is the reaction at R_1 in Fig. 20?

SOLUTION.—In computing the moment due to a uniform or evenly distributed load, as at a , the lever arm is always considered as the distance from the center of moments to the center of gravity of the load. The amount of the uniform load a is $3,000 \times 10 = 30,000$ lb., and the




FIG. 21

distance of its center of gravity from R_1 is 13 ft. The moments of the loads on this beam may then be seen from the following:

$$30,000 \times 13 = 390,000 \text{ ft.-lb.}$$

$$4,000 \times 4 = 16,000 \text{ ft.-lb.}$$

$$9,000 \times 20 = 180,000 \text{ ft.-lb.}$$

$$\text{Total.} \quad 586,000 \text{ ft.-lb.}$$

This is the sum of the moments of all the loads about R_1 , as a center. The leverage of the reaction R_1 is 30 ft. Hence, $586,000 \div 30 = 19,533\frac{1}{3}$ lbs., the reaction at R_1 . Ans.

EXAMPLE 2.—A beam is loaded as shown in Fig. 21. What is the amount of each of the reactions R_1 and R_2 ?

SOLUTION.—Considering R_1 as the center of moments, the moments of the loads about it are:

$$\begin{aligned}
 20,000 \times 3 &= 60\,000 \text{ ft.-lb.} \\
 2,000 \times 18 &= 36\,000 \text{ ft.-lb.} \\
 3,000 \times 22 &= 66\,000 \text{ ft.-lb.} \\
 5,000 \times 36 &= 180\,000 \text{ ft.-lb.} \\
 1,000 \times 6 \times 33 &= 198\,000 \text{ ft.-lb.} \\
 \text{Total,} &\quad \underline{540\,000 \text{ ft.-lb.}}
 \end{aligned}$$

This, divided by 30, the length of the lever arm of the reaction R_1 , equals 18,000 lb., the reaction at R_1 . The sum of the loads is $20,000 + 2,000 + 3,000 + 5,000 + 6,000 = 36,000$ lb.; and $36,000 - 18,000 = 18,000$ lb., the amount of the other reaction, or R_2 . Ans.




FIG. 22

EXAMPLE 3.—Compute the reactions at the supports R_1 and R_2 in a beam loaded as shown in Fig. 22.

SOLUTION.—Letting R_1 represent the center of moments, the moments of the loads are:

$$\begin{aligned}
 5,000 \times 10 &= 50\,000 \text{ ft.-lb.} \\
 10,000 \times 20 &= 200\,000 \text{ ft.-lb.} \\
 30,000 \times 40 &= 1\,200\,000 \text{ ft.-lb.} \\
 \text{Total,} &\quad \underline{1\,450\,000 \text{ ft.-lb.}}
 \end{aligned}$$

Now, $1,450,000 \div 30$, the distance between the supports, equals $48,333\frac{1}{3}$ lb., the required reaction at R_2 . The sum of the loads is $5,000 + 10,000 + 30,000 = 45,000$ lb.; therefore, the reaction R_2 is greater than the sum of the loads. This shows that the force at R_1 must act in a downward direction in order that the sum of the downward forces may equal the upward force at R_2 . Since this is opposite to the usual direction, the reaction at R_1 is called negative or minus. In other words, instead of an upward reaction at R_1 , there must be a downward force at this point, or the beam will, as shown by the dotted lines, rotate

around the support R_1 . The magnitude of this downward force is the difference between the upward reaction at R_1 and the sum of the downward pressures due to the loads; that is, $48,333\frac{1}{3} - 45,000 = 3,333\frac{1}{3}$ lb. Compute the reaction at R_1 by taking the center of moments at R_2 and applying the rule in Art. 9 to find the magnitude and direction of action of the force at R_1 whose moment is the resultant of the moments of the loads on the beam. The load of 30,000 lb. tends to produce right-hand rotation around the center R_2 ; hence, its moment, $30,000 \times 10 = 300,000$ ft.-lb., is positive. The 10,000-lb. load is 10 ft. to the left of R_2 and its tendency is to produce left-hand rotation about R_2 ; consequently, its moment is negative and equal to $10,000 \times 10 = 100,000$ ft.-lb. In a similar manner, the moment of the 5,000-lb. load is found to be negative and equal to $5,000 \times 20 = 100,000$ ft.-lb. These results may be collected thus:

Positive moment:

$$30,000 \times 10 = + 300000 \text{ ft.-lb.}$$

Negative moments:

$$10,000 \times 10 = - 100000 \text{ ft.-lb.}$$

$$5,000 \times 20 = - 100000 \text{ ft.-lb.}$$

$$- 200000 \text{ ft.-lb.}$$

$$\text{Difference, } + 100000 \text{ ft.-lb.}$$

the resultant of the moments of the three loads. Since the positive moment is greater than the sum of the negative moments, the force at R_1 must tend to produce left-hand rotation; that is, it must act downwards; its lever arm being 30 ft. long, its magnitude must be $100,000 \div 30 = 3,333\frac{1}{3}$ lb., the same result as was obtained before.

EXAMPLES FOR PRACTICE

1. The span of a simple beam is 25 feet; at distances of 9 feet, 16 feet, and 18 feet from the left-hand end are placed concentrated loads of 8,000, 4,000, and 16,000 pounds, respectively. What is the amount of the left reaction? Ans. 11,040 lb.

2. The two reactions supporting a beam are 2,500 and 3,000 pounds; what is the amount of a single concentrated load necessary to produce these reactions? Ans. 5,500 lb.

3. A 30-foot beam overhangs the right-hand support 6 feet; on this end is a weight of 6,000 pounds; 10 feet, 12 feet, and 18 feet from the left-hand support are loads of 8,000, 6,200, and 7,800 pounds, respectively. What is the amount of the right-hand reaction? Ans. 19,783 $\frac{1}{3}$ lb.

4. If for a distance of 10 feet from the left-hand end of a beam there is distributed a load of 1,000 pounds per running foot, and at the center of the beam is located the concentrated load of 16,500 pounds, what is the amount of the left-hand reaction, provided that the beam is supported at both ends and is 30 feet long? Ans. 16,583 $\frac{1}{3}$ lb.

STRESSES IN BEAMS

17. It has been seen that a beam is a body acted on by various external forces so related as to be in a condition of equilibrium; so far, however, the effect of these forces on the beam itself has not been considered.

In a body subjected to a direct pull or thrust, as a rope or a column, the external forces are directly opposed to each other, and the resultant stresses in all sections are of the same kind, tension, or compression. In a beam, however, the external forces, while they generally act in parallel lines, are not directly opposed to each other, and it is the function of the beam to transfer these forces from one line of action to another. Take, for example, the case of a weight suspended from a pin driven in a wall, as shown in Fig. 23. The downward force of 20 pounds due to the action of the weight is balanced by the upward pressure, or reaction, of the pin on the rope; the rope is thus subjected to the action of two directly opposing forces, the result being a tensile stress that is the same for each section of the rope between the weight and the pin. The pin acts as a cantilever beam that transfers the downward pressure, due to the pull of the rope, horizontally to the wall, where it is balanced by an equal upward pressure, or reaction. The pin is thus subjected to two opposing forces that, however, act in different lines; these forces produce a set of opposing forces, or stresses, in the pin itself, which are different in kind for different parts of the pin, and vary in magnitude for each section between the rope and the wall.




FIG. 23

SHEAR

18. An inspection of Fig. 23 shows that if a vertical plane is passed through any point between the rope and wall, the part of the pin between this plane and the rope will be

acted on by a downward force, due to the pull of the rope, while the other part is subjected to an equal upward force due to the reaction of the wall; the action of these two forces tends to slide the two parts of the pin past each other, along the section formed by the cutting plane. The pin is thus subjected to a stress which, from its similarity to a shearing action, is called **shear**.

19. Shear in a Simple Beam.—By observation of Fig. 24 (*a*), which shows a simple beam having a concentrated load at the center, the only apparent stress in the beam is that of bending.






FIG. 24

beam is that of bending. However, if the fibers of the beam were not continuous, and instead of being one piece it were composed of short blocks, the tendency would be for the blocks to slip past each other, as shown at (*b*). This tendency would exist in the entire beam, producing vertical shear, which must be considered in calculating its strength. If the beam were laminated, the effect would be as shown at (*c*); that is, one layer would slide on the

next one as the beam deflects. In a solid beam there is the same tendency to shear the beam longitudinally and this horizontal shear is equal to the vertical shear.

Consider now the simple beam shown in Fig. 25. Since the loads are symmetrically applied, each reaction is equal to 40 pounds, one-half of the total load on the beam. Beginning at the left reaction R_1 , there is an upward force of 40 pounds acting on the beam; since the forces are in equilibrium, this upward force is balanced by an equal downward

force, which is the vertical resultant of the loads and the reaction R_1 . Considering, therefore, any section of the beam between R_1 and the point of application of the load n , it is seen that the part of the beam at the left of this section is subjected to an upward thrust of 40 pounds, while the part at the right is subjected to an equal downward thrust; the result is a shearing stress on this section, whose magnitude is equal to the reaction R_1 .

When the point of application of n is reached, the effect of the upward force R_1 is partly balanced by the downward force of 10 pounds due to the load n ; considering, therefore, any section of the beam $a b$ between the points of application of the loads n and m , it is seen that the part of the beam at the left is acted on by the vertical resultant of the reaction R_1 and




FIG. 25

the load n ; that is, by an upward force of $40 - 10 = 30$ pounds, while the part at the right is acted on by an equal downward force, which is the vertical resultant of the remaining loads and the reaction R_2 . Any section between the points of application of n and m is therefore subject to a shearing stress equal to the difference between the reaction R_1 and the load n ; that is, to $40 - 10 = 30$ pounds. In the same way, it follows that the shearing stress for any section between m and o is $40 - (10 + 15) = 15$ pounds. For any section $c d$ between the points of application of o and p , the shearing stress is $40 - (10 + 15 + 15) = 0$; in other words, on each side of this section the downward forces and the reactions are equal, and their resultant is zero; it is, therefore, a section in which there is no shear.

For convenience, it is customary to call the reactions, or forces, acting in an upward direction, positive, and the loads, or downward forces, negative; since the difference between the sums of the positive and negative numbers representing a given set of values is called their algebraic sum, it follows that *the shear for any section of a beam is equal to the algebraic sum of either reaction and the loads between this reaction and the given section.*

In nearly all cases the external forces—loads and reactions—act on a beam along vertical lines; the shearing stress just considered is called the vertical shear, because it is the resultant of these forces along a section formed by an imaginary vertical cutting plane.

20. Maximum Shear.—From what has been said, it is evident that the shear in any simple beam is always greatest between the reactions and the nearest loads, and that in any case the **maximum shear** is equal to the greater reaction.




FIG. 26



21. Positive and Negative Shear.—If a section of the beam near the left reaction is taken and the forces acting on the part of the beam at the left are considered, it is seen that their resultant is positive; the shear at this section is therefore called **positive shear**. If, however, a section near the right reaction is taken, the resultant of the forces at the left is found to be negative, and in consequence the shear is called **negative**. It is also evident that there is a section between the two, where the resultant of the forces changes from positive to negative; at such a section the shear is said to **change sign**.

30,000 lb. in this load, it is evident that it will more than absorb the remaining amount of the reaction R_1 ; the point where the change of sign occurs must consequently be somewhere in that part of the beam covered by the uniform load. The load being 3,000 lb. per running ft., if the remaining part of the reaction, 19,466 $\frac{2}{3}$ lb., be divided by the 3,000 lb., the result will be the number of feet of the uniform load required to absorb the remaining part of the reaction, and this will give the distance of the section, beyond which the resultant of the forces at the left becomes negative, from the edge of the uniform load at a ; thus, $19,466\frac{2}{3} \div 3,000 = 6.48$ ft. The distance from R_1 to the edge of the uniform load is 8 ft. The entire distance to the section of change of sign of the shear is therefore $8 + 6.48 = 14.48$ ft. from R_1 . Ans.

EXAMPLES FOR PRACTICE

1. The uniformly distributed load on a beam supported at both ends is 40,000 pounds; what is the maximum shear on the beam?

Ans. 20,000 lb.



2. A beam supported at both ends has three concentrated loads: A of 2,000 pounds, B of 6,000 pounds, and C of 8,000 pounds, located 10 feet, 12 feet, and 18 feet, respectively, from the left-hand end of the beam, the span of which is 40 feet; what is the shear between the loads C and B ?

Ans. 2,100 lb.




FIG. 28

3. The span of a beam is 20 feet, and there is a uniformly distributed load on three-quarters of this distance from the left-hand support, of 9,000 pounds; at distances of 8 feet and 12 feet from the right-hand support are located concentrated loads of 5,000 pounds and 6,000 pounds, respectively. At what distance from the left-hand end of the beam does the shear change sign?

Ans. 8 ft. 8 $\frac{1}{2}$ in.

and 6,000 pounds, respectively. At what distance from the left-hand end of the beam does the shear change sign?

22. The shear on a beam may be represented graphically as shown in Fig. 28, in which the shaded portion designates the amount of the shear along the beam. The portion above

the horizontal line represents the positive shear, while the negative shear is indicated by the portion below the line; (*a*) shows the shear on a simple beam loaded at the center; the shear is uniform at all points except directly under the load, where it is zero. The shear on a beam uniformly loaded is illustrated at (*b*); in this case the shear is maximum at the supports and decreases gradually until it becomes zero at the center. The shear on a beam having concentrated loads may be represented as shown at (*c*). These diagrams are simply representations of the results obtained by analysis, but a method of obtaining the amount of shear graphically will be given later.

BENDING STRESSES

23. Bending Moment.—If, in a cantilever loaded as in Fig. 29, any point x on the center line ab is taken as a center of moments, and a section made by a vertical plane cd through this center is considered, it is evident that the moment of the force due to the downward thrust of the load tends to turn the end of the beam to the right of cd , around the center x ; the measure of this tendency is the product of the weight W and its distance from cd ; and, since it is the moment of a force that tends to bend the beam, it is called the **bending moment**.

24. Resisting Moment.—An inspection of Fig. 29 shows that if the end of the beam turns around the center x until it takes the position shown by the dotted lines, the parts of the two surfaces formed by the cutting plane cd that are above the center x must be pulled from each other, while those below are pushed closer together. Thus, it is seen that if a vertical section is considered through any point on the center line ab between the load and the point of support, the tendency of the load is to separate the particles in this section above the center line, and to push those below the center line closer together; in other words, through the bending action of the load, the upper part of the beam is subjected to a tensile stress, while the lower part is subjected to a compressive stress.

Fig. 29 also shows that the greater the distance of the particles in the assumed section above or below the center x , the greater will be their displacement; since the stress in a loaded body is directly proportional to the strain, or relative displacement, of the particles, it follows that the stress in a particle of any section is proportional to its distance from the center line, and that the greatest stress is in the particles composing the upper and lower surfaces of the beam.

In accordance with the conditions of equilibrium, the algebraic sum of the moments of all the forces tending to produce rotation around a given center must be zero; it is evident that the weight of the load is a force that tends to produce right-hand rotation around the center x ; therefore, if the beam does not break under the action of the load, there




FIG. 29

must be forces acting whose moments, with respect to the center x , balance the moment of the load. These forces are the resistances with which the particles of the beam oppose

any effort to change their relative positions. The tensile stresses in the particles above the center x and the compressive stresses in those below it, are a set of forces that resist the tendency of the load to turn the end of the beam, and, when the effect of the load is just balanced by the effect of these forces, it is evident that the sum of the moments of these resisting stresses is equal to the moment of the load. The sum of the moments of the stresses of all the particles composing any section of a beam is called the **resisting moment**, or **moment of resistance**, of that section.

25. The relations between the effect of a load and the resulting stresses in a beam have been thoroughly proved, both by mathematical investigations and numerous

experiments. The results of these experiments on beams may be briefly expressed by the following:

Experimental Law.—*When a beam is bent, the horizontal elongation or compression of any fiber is directly proportional to its distance from the neutral surface, and, since the strains are directly proportional to the horizontal stresses in each fiber, they are also directly proportional to their distances from the neutral surface, provided the elastic limit is not exceeded.*

26. Bending Moments in Simple Beams.—Referring to the simple beam shown in Fig. 26, take the center of moments on the neutral axis directly under the load a , and consider the effect produced on a vertical section of the beam through this center, by the reaction R_1 . It was shown in Art. 21, that the reaction R_1 is an upward force of $6,933\frac{1}{3}$ pounds; it therefore has a tendency to turn the end of the beam upwards around the assumed center with a moment of $6,933\frac{1}{3} \times 3 = 20,800$ foot-pounds. It is evident that, to prevent this turning from actually taking place, the positive moment of the reaction must be balanced by a negative moment that can be produced only by a set of internal stresses. The condition that the moment of the stresses must be negative makes it plain that the upper fibers must be in compression and the lower in tension, a result exactly opposite to the effect produced by the bending moment on the fibers in the cantilever.

27. Effect of the Moments Due to Loads.—The only force acting on the beam at the left of the section considered in the last article was the reaction R_1 . The load a acted downwards directly through this section, but its lever arm, and consequently its moment, with respect to the assumed center, was zero. Take now a point on the center line of the beam directly under the positive load b . The reaction has a moment, with respect to this center, of $6,933\frac{1}{3} \times 11 = 76,266\frac{2}{3}$ foot-pounds, while the load a , which acts downwards with a lever arm of 8 feet, has a negative moment of $2,000 \times 8 = 16,000$ foot-pounds. The bending moment at the assumed section is the algebraic sum of these moments, that is, $76,266\frac{2}{3} - 16,000 = 60,266\frac{2}{3}$ foot-pounds. Again, taking the

center of moments on a section 9 feet from the right reaction R_2 , the moments are as follows:

Positive moment:

$$\text{Reaction } R_1, 6,933\frac{1}{3} \times 21 = 145600 \text{ ft.-lb.}$$

Negative moments:

$$\text{Load } a, 2,000 \times 18 = 36,000 \text{ ft.-lb.}$$

$$\text{Load } b, 6,000 \times 10 = 60,000 \text{ ft.-lb.} \quad 96000 \text{ ft.-lb.}$$

$$\text{Difference,} \quad \underline{49600 \text{ ft.-lb.}}$$

This resultant moment is the bending moment at the given section.

28. The illustrations show that the bending moment varies from point to point in a beam, and depends on the length of the beam, and on the size as well as position of the loads. Since the stresses in the beam, and consequently its ability to carry its loads, depend directly on the bending moment, it follows that it is important to find not only the bending moment for any assumed section but also the section where the bending moment is greatest. It is, in this connection, useful to note the relation between the bending moment and the shear.

29. The shear in a simple beam is always greatest at the greater reaction, being equal to that reaction. In passing along the beam from either reaction, there is no change in the shear until a load is reached; at each point where a load is added, the shear is diminished by an amount equal to the load. At the point where the sum of the added loads equals or exceeds the reaction, the shear is said to change sign. The section where the change in sign in the shear takes place, depends on the method of loading. With a uniformly distributed load, the shear diminishes uniformly from each reaction, and the section where the sign changes is the section of the beam midway between the supports. With a single concentrated load, the shear is equal to each reaction at all sections between that reaction and the point where the load is applied, and the section where the shear changes sign is directly under the load. With any system of loading, the

section where the shear changes sign can be found by adding the successive loads from either reaction toward the center of the beam, until a sum is obtained that equals or exceeds the reaction; the section where the shear changes sign is under the point of application of the last load added.

30. The bending moment in a simple beam increases as the shear decreases; it is zero at either reaction and increases toward the center, becoming greatest at the section where the shear changes sign. With a uniformly distributed load, the greatest bending moment is at the section of the beam midway between the supports; with a single concentrated




FIG. 30

load, the greatest bending moment is directly under the load; and with any system of loading, the greatest bending moment occurs at the section where the shear changes sign. Having located the section of greatest bending moment, the magnitude of this moment can be readily computed, by taking the center of moments, on the section of greatest bending moment and computing the resultant moment of either reaction and all the loads between it and the center in question.

EXAMPLE.—A wooden beam, supported on two brick piers, is loaded as shown in Fig. 30: (a) What is the greatest shear? (b) Where does the shear change sign? (c) What is the greatest bending moment, in inch-pounds?

SOLUTION.—(a) Since the greatest shear is equal to the greater reaction, the reactions will first be computed. Take the center of moments at the edge of pier *a*, and as the moment of the uniform load is the same as the moment of an equal concentrated load acting at the center of gravity of the uniform load, the moments of the loads are:

10,000-lb. load	$10,000 \times 6 =$	60 000 ft.-lb.
Load <i>d</i>	$6,000 \times 13 =$	78 000 ft.-lb.
Load <i>e</i>	$4,000 \times 16 =$	64 000 ft.-lb.
Uniformly distributed load . .	$12,500 \times 12\frac{1}{2} =$	156 250 ft.-lb.
Total,		<u>358 250 ft.-lb.</u>

This also equals the moment of the reaction of the pier *b*. The reaction at *b* is therefore $358,250 \div 25 = 14,330$ lb. The total load is $10,000 + 6,000 + 4,000 + 12,500 = 32,500$ lb.; the reaction at *a* is therefore $32,500 - 14,330 = 18,170$ lb. This, being the greater reaction, is the greatest shear. Ans.

(b) Beginning at the left reaction and adding the loads in succession toward the right, the load of 10,000 lb., plus the uniformly distributed load between the reaction and the point of application of the load *d*, is $10,000 + 500 \times 13 = 16,500$ lb. This is less than the left reaction, but, when the load *d* is added, the sum of the loads is greater than the reaction; consequently, the shear changes sign under the load *d*. Ans.

(c) Taking the center of moments under the load *d*, and considering the forces at the left, the moments are:

Positive moment:

$$18,170 \times 13 = 236 210 \text{ ft.-lb.}$$

Negative moments:

$$6,500 \times 6\frac{1}{2} = 42 250 \text{ ft.-lb.}$$

$$10,000 \times 7 = 70 000 \text{ ft.-lb.}$$

$$\underline{\quad\quad\quad} 112 250 \text{ ft. lb.}$$

$$\text{Difference (bending moment in ft.-lb.), } 123 960 \text{ ft.-lb.,}$$

The bending moment, in inch-pounds, is therefore $123,960 \times 12 = 1,487,520$ in.-lb. Ans.

31. Formulas for Maximum Bending Moments and Safe Loads.—The following table gives formulas for obtaining the maximum safe loads that may be supported by beams under different conditions and the maximum bending moments produced by these loads. In these formulas, *W* is the weight, in pounds; *S*, the section modulus; *s_a*, the safe unit fiber stress; and *l*, the span in inches.

In Case XVI, the greatest load can be supported and consequently the least bending moment occurs when the distance x is $.207 l$, and the formulas given apply only to this condition. The bending moment for any point is found by the formula $M = \frac{Wc}{2} \left(\frac{c}{l} - 1 + \frac{x}{c} \right)$, in which the value c is the distance of the point at which the amount of the bending moment desired is located from the left-hand end of the beam.

When the end of a beam extends into the wall it is considered as being fixed, if the masonry is built around it tightly; while if the end rests on a wall or other support it is considered as being simply supported. When the load is represented by cross-sectioning, it denotes that it is a distributed load; the round weight represents a concentrated load. A load such as shown in Cases III and X is sometimes encountered, for instance, in a case where a beam is required to support the side walls or curbing of a stairway. A triangular load, as shown in Case IX, is considered when the beam is to support a solid brick wall.

32. The rule given in Case II is that most used, as it applies to a beam uniformly loaded, such as floor joists, girders, and, in some cases, the rafters of a roof. The rule in Case IX is convenient in calculating the bending moment on lintels supporting brickwork or masonry over openings. It will be observed that if the beam supporting a concentrated load at the center is firmly fixed or fastened at both ends, as in Case XIII, instead of being simply supported as designated in Case IV, the bending moment under the same load will be only half as much. Also, in Case XIV, where the ends of the beam are firmly fixed, the uniformly distributed load that may be supported is one and one-half times as great as where the ends merely rest on supports, as in Case VII. It is seldom advisable, in ordinary building practice, to consider the ends of a beam fixed, it being good practice to assume the ends of the beam as simply bearing on the wall, using the rules and formulas in Table I. However, it should be understood that all of these rules and formulas apply to static loads. The

TABLE I
FORMULAS FOR MAXIMUM SAFE LOADS AND MAXIMUM
BENDING MOMENTS ON BEAMS

















Case	Method of Loading	Maximum Bend- ing Moment	Maximum Safe Load
I		Wl (1)	$\frac{S s_a}{l}$ (17)
II		$\frac{Wl}{2}$ (2)	$\frac{2 S s_a}{l}$ (18)
III		$\frac{Wl}{3}$ (3)	$\frac{3 S s_a}{l}$ (19)
IV		$\frac{Wl}{4}$ (4)	$\frac{4 S s_a}{l}$ (20)
V		$\frac{Wxy}{l}$ (5)	$\frac{l S s_a}{xy}$ (21)
VI		$\frac{Wx}{2}$ (6)	$\frac{2 S s_a}{x}$ (22)
VII		$\frac{Wl}{8}$ (7)	$\frac{8 S s_a}{l}$ (23)
VIII		$\frac{Wl}{12}$ (8)	$\frac{12 S s_a}{l}$ (24)

TABLE I—(Continued)

Case	Method of Loading	Maximum Bend- ing Moment	Maximum Safe Load
IX		$\frac{Wl}{6}$ (9)	$\frac{6 S s_a}{l}$ (25)
X		$\frac{104}{108} Wl$ (10)	$\frac{810}{104} \frac{S s_a}{l}$ (26)
XI		$\frac{6}{32} Wl$ (11)	$\frac{16}{3} \frac{S s_a}{l}$ (27)
XII		$\frac{Wl}{8}$ (12)	$\frac{8 S s_a}{l}$ (28)
XIII		$\frac{Wl}{8}$ (13)	$\frac{8 S s_a}{l}$ (29)
XIV		$\frac{Wl}{12}$ (14)	$\frac{12 S s_a}{l}$ (30)
XV		$\frac{Wx}{2}$ (15)	$\frac{2 S s_a}{x}$ (31)
XVI		$\frac{3}{140} Wl$ (16)	$\frac{140}{3} \frac{S s_a}{l}$ (32)

same load suddenly applied produces a stress in the beam twice as great as that of a static load. The safe suddenly applied load is therefore only half as much.

A graphical method for determining the bending moment on a beam is explained in the following article:

EXAMPLE.—What will be the bending moment, in inch-pounds, on a wooden girder supporting a floor area of 150 square feet, the dead and live load being 100 pounds per square foot, and the span of the girder 20 feet?

SOLUTION.—The total uniformly distributed load is $150 \times 100 = 15,000$ lb.; therefore, by applying the formula in Case VII, Table I, the bending moment

$$M = \frac{Wl}{8} = \frac{15,000 \times 20 \times 12}{8} = 450,000 \text{ in.-lb. Ans.}$$

EXAMPLES FOR PRACTICE

1. A beam has a span of 20 feet, and is loaded with a uniformly distributed load of 2,500 pounds per lineal foot; what is the greatest bending moment, in inch-pounds, on the beam? Ans. 1,500,000 in.-lb.

2. What is the bending moment, in inch-pounds, on a cantilever beam, securely fastened into a wall, extending from the point of support 10 feet and loaded with a uniformly distributed load of 1,000 pounds per lineal foot? Ans. 600,000 in.-lb.

3. What is the bending moment, in inch-pounds, on a girder having a span of 30 feet, if there is a uniformly distributed load of 1,500 pounds per lineal foot and a load of 20,000 pounds concentrated at the center? Ans. 3,825,000 in.-lb.

4. A plate girder in a building is required to support a uniformly distributed load of 2,000 pounds per lineal foot, extending 20 feet each side of the center of the girder; in addition, it is required to support a load of 30,600 pounds, concentrated 10 feet from one end of the girder, and another load of 43,000 pounds, located 22 feet from the same end. What will be the greatest bending moment on the girder, in foot-pounds, if the span is 60 feet? Ans. 1,528,933 ft.-lb.

GRAPHICAL METHOD OF OBTAINING BENDING MOMENT AND SHEAR

33. The graphical method of obtaining bending moment and shear on a beam can best be explained by assuming an example and solving it.

Fig. 31 (a) shows a simple beam having three concentrated loads, W_1 , W_2 , and W_3 . First lay out, as in (b), the *force polygon*, or *stress diagram*, as it is sometimes called; the




FIG. 31

loads are laid off to scale at $A B$, $B C$, and $C D$. From any point o , outside of the load line, draw lines to A , B , C , and D . If a cord is supported at two points, a and b , in Fig. 31 (c), and the loads W_1 , W_2 , and W_3 are hung at the points c , d , and e ,

respectively, the cord will be in equilibrium, provided that the portions ac , cd , de , and eb are parallel to Ao , Bo , Co , and Do , respectively.

The figure in (c) is called the *equilibrium*, or *funicular polygon*, and is a representation of the variation of the bending moment along the beam. Therefore, the bending moment at any point is proportional to the ordinate in the funicular polygon below that point, or the vertical line intercepted between the sides of the polygon. For instance, the bending moment under the load W , is proportional to the ordinate fd . The reactions R_1 and R_2 may be obtained from the force polygon by drawing the line oF parallel to ab in the equilibrium polygon; AF and FD represent the reactions R_1 and R_2 , respectively.

In the force polygon, a horizontal line drawn from the point o to the load line represents the horizontal component of the tensions ac , cd , de , and eb in the funicular polygon, and is designated as H . The bending moment at any point is equal to the product of the vertical ordinate in the funicular polygon at that point and the force H . The ordinate should be measured by the scale to which the beam was drawn and the line H by the scale to which the load line was laid off. The explanation of this is given in Art. 35.

34. To construct the shear diagram shown in (d), project downwards the points at which the loads and reactions occur. The point F in the force polygon is projected horizontally, thus giving $a'b'$, the base line of the polygon. Project the point A until it intersects the line drawn from the load W_1 in (a), and the point B until it intersects the line drawn from the load W_2 . The shear at this point changes sign and consequently the remainder of the diagram will be below the base line $a'b'$. Project the points C and D until they intersect the lines projected from the load W_2 and the reaction R_2 , respectively. This completes the shear diagram, as shown by the shaded section in (d). The shear at any point is found by measuring the ordinate at that point by the scale used in laying off the load line AD .




FIG. 32

35. The graphical determination of the bending moment may be explained by means of Fig. 32, in which the beam shown in Fig. 31 is considered.

On the beam kb it is desired to find the bending moment at the point l , 9 feet from k . Let the bending moment be considered first with reference to the reaction R_1 alone, omitting the effect of the load W_1 . Construct the triangle $ah i$ by producing the lines gh and ac until they intersect at i . As the triangle $ah i$ in (a) is similar to AoF in (b), it follows that $ah : hi = Fo : AF$, and as the altitudes of the two triangles are proportional to their bases, the following proportion may be written: $am : hi = ho : AF$; therefore, $AF \times am = ho \times hi$. But $am = kl$ and $AF = R_1$, hence, $R_1 \times kl = ho \times hi$.

As the load W_1 acts in opposition to the reaction R_1 , its moment must be subtracted from that of R_1 . In the similar triangles cgi and AoB , $cg : gi = oB : AB$ and consequently $cn : gi = oh : AB$, but $AB = W_1$ and $cn =$ its moment pl ; therefore, $W_1 \times pl = gi \times oh$. The resulting moment is then found by subtracting that of W_1 from R_1 , as follows: $hi \times ho - gi \times ho$, or $ho(hi - gi) = ho \times hg$. Thus, it is proved that the bending moment at any point on a beam is equal to the product of the line representing the horizontal force oh and a vertical line intercepted between the sides of the funicular polygon and passing through the point considered.

In Fig. 32 (a) the line gh measures 6.14 feet and in (b) the line ho measures 11,000 pounds, according to the scales to which the two figures have been drawn; the product $6.14 \times 11,000 = 68,154$ foot-pounds is the bending moment at l . By calculation, the bending moment is found to be $9 \times 12,000 - 4 \times 10,000 = 68,000$ foot-pounds. The difference is caused by inaccuracies in the drawing by reason of the small scale to which it is drawn.

CONTINUOUS BEAMS

36. When beams or girders extend over three or more supports in one piece, that is, are not jointed over the supports, they are said to be *continuous*, and the strains produced are very different from those in ordinary beams.

Fig. 33 shows the action of a beam fixed at each end and having one intermediate support. The points b , c , e , and f , where the direction of the curve changes and, consequently, where the stress in the upper and lower portions of the beam changes, are called the points of **contraflexure**. The portions ab , cd , de , and fg act as cantilevers and the upper edges




FIG. 33

of the beam are in tension while the lower are in compression. The portions bc and ef resemble simple beams and their upper edges are in compression while the lower are in tension. If the ends of the girders are not fixed, but are simply supported, the curves will be as shown in Fig. 34. The curves of each span produced by a uniform load resemble those of a beam fixed at one end and supported at the other. The location of the points of contraflexure and the




FIG. 34

value of the bending moments are affected by the distribution of the load and the section of the girder.

The calculations in regard to continuous girders are very complicated and consequently will not be discussed here, but the following formulas will give all the information required in proportioning such beams to the load they are required to carry.

Tables II and III give the reactions and bending moments at the supports for continuous beams uniformly loaded and extending over a number of equal spans. In these tables, l equals the length of each span and w the weight per unit of

TABLE II
REACTIONS FOR CONTINUOUS BEAMS OVER EQUAL SPANS
Coefficients of w l

Number of Span	Number of Each Support									
	1st	2d	3d	4th	5th	6th	7th	8th	9th	10th
1	$\frac{1}{2}$	$\frac{1}{2}$								
2	$\frac{3}{8}$	$\frac{10}{8}$	$\frac{3}{8}$							
3	$\frac{4}{10}$	$\frac{11}{10}$	$\frac{11}{10}$	$\frac{4}{10}$						
4	$\frac{11}{28}$	$\frac{32}{28}$	$\frac{26}{28}$	$\frac{32}{28}$	$\frac{11}{28}$					
5	$\frac{15}{38}$	$\frac{43}{38}$	$\frac{37}{38}$	$\frac{37}{38}$	$\frac{43}{38}$	$\frac{15}{38}$				
6	$\frac{41}{104}$	$\frac{118}{104}$	$\frac{100}{104}$	$\frac{106}{104}$	$\frac{100}{104}$	$\frac{118}{104}$	$\frac{41}{104}$			
7	$\frac{56}{142}$	$\frac{161}{142}$	$\frac{137}{142}$	$\frac{143}{142}$	$\frac{143}{142}$	$\frac{137}{142}$	$\frac{161}{142}$	$\frac{56}{142}$		
8	$\frac{153}{388}$	$\frac{440}{388}$	$\frac{374}{388}$	$\frac{392}{388}$	$\frac{386}{388}$	$\frac{392}{388}$	$\frac{374}{388}$	$\frac{440}{388}$	$\frac{153}{388}$	
9	$\frac{209}{530}$	$\frac{601}{530}$	$\frac{511}{530}$	$\frac{535}{530}$	$\frac{529}{530}$	$\frac{529}{530}$	$\frac{535}{530}$	$\frac{511}{530}$	$\frac{601}{530}$	$\frac{209}{530}$

TABLE III
BENDING MOMENTS FOR CONTINUOUS BEAMS OVER
EQUAL SPANS
Coefficients of w l²

Number of Span	Number of Each Support									
	1st	2d	3d	4th	5th	6th	7th	8th	9th	10th
1	0	0								
2	0	$\frac{1}{8}$	0							
3	0	$\frac{1}{10}$	$\frac{1}{10}$	0						
4	0	$\frac{3}{28}$	$\frac{2}{28}$	$\frac{3}{28}$	0					
5	0	$\frac{4}{38}$	$\frac{3}{38}$	$\frac{3}{38}$	$\frac{4}{38}$	0				
6	0	$\frac{11}{104}$	$\frac{8}{104}$	$\frac{9}{104}$	$\frac{8}{104}$	$\frac{11}{104}$	0			
7	0	$\frac{15}{142}$	$\frac{11}{142}$	$\frac{12}{142}$	$\frac{12}{142}$	$\frac{11}{142}$	$\frac{15}{142}$	0		
8	0	$\frac{41}{388}$	$\frac{30}{388}$	$\frac{33}{388}$	$\frac{32}{388}$	$\frac{33}{388}$	$\frac{30}{388}$	$\frac{41}{388}$	0	
9	0	$\frac{56}{530}$	$\frac{41}{530}$	$\frac{45}{530}$	$\frac{44}{530}$	$\frac{44}{530}$	$\frac{45}{530}$	$\frac{41}{530}$	$\frac{56}{530}$	0

length; hence, the load on each span is equal to $w l$. The reactions are expressed in terms of $w l$ and the bending moments in terms of $w l^2$. Only the fractional coefficients are given.

To illustrate the method of using the tables, the following example will be assumed:

EXAMPLE.—The lower tie-member of an A-shaped truss, *aa* Fig. 35, supported by the four reactions R_1 , R_2 , R_3 , and R_4 , sustains a uniformly distributed load of 2,000 pounds per lineal foot. (a) What will be the theoretical amount of the reactions? (b) What is the amount of the greatest bending moment from this uniformly distributed load?




FIG. 85

SOLUTION.—(a) From Table II, the reactions at the ends are equal to $\frac{1}{10}$ of $w l$, and for the intermediate supports, $\frac{1}{5}$ of $w l$. Substituting these values, the reactions at the ends are equal to $\frac{1}{10} \times 2,000 \times 11 = 8,800$ lb. Ans.

The reactions at the intermediate supports are equal to $\frac{1}{5} \times 2,000 \times 11 = 24,200$ lb. Ans.

(b) The greatest bending moment occurs at the intermediate supports; from Table III, this moment is equal to $\frac{1}{10} w l^2$, or $\frac{1}{10} \times 2,000 \times 11 \times 11 = 24,200$ ft.-lb. Ans.

EXAMPLES FOR PRACTICE

1. The first floor of a building used as a store was supported on 12-inch I beams having a clear span of 30 feet. A subsequent tenant desired to use the first floor of the building as a storage warehouse and it was decided to place a row of piers down the center of the

basement to further support these girders. By what percentage is the carrying capacity of the floor increased by the introduction of the central pier? Ans. 400%

2. What will be the load from the girder on the central pier mentioned in the above problem, if the load is 2,000 pounds per lineal foot? Ans. 37,500 lb.




FIG. 36

3. A trussed girder, Fig. 36, is loaded with a uniformly distributed load of 1,500 pounds per foot; what will be the amount of the compressive stress in the straining posts a, a . Ans. 16,500 lb.

DEFLECTION OF BEAMS

37. **Elasticity** is that property which a body possesses of returning to its original form, after being strained or distorted by the application of a stress. This property is possessed by all bodies in a greater or less degree. If, after being distorted, a body does not perfectly resume its original form, it is said to have a **permanent set**. It is believed that the elasticity of all solids is more or less imperfect, and that the slightest strain produces a corresponding permanent set. It is customary, however, to consider the elasticity of all building materials as practically perfect within certain limits. Under this assumption, stresses, up to a certain limit, may be applied and removed, and the resulting strain or alteration of form will be only temporary, with no appreciable permanent set. However, stresses above this limit will cause permanent sets.

38. The *elastic limit* of any material is the maximum unit stress that may be applied to it without causing any apparent permanent set; or, it is that point at which the strain ceases to be proportional to the stress.

To illustrate: Consider a piece of steel wire supported at one end and loaded by a weight suspended from the other.

The wire is found to stretch under the action of the load, and by varying the weight or stress, the strain in each case is found to vary in the same proportion, so long as the weight is not greater than one-fourth of the breaking strength of the wire; within this limit it is found, on removing the weight, that the wire resumes its original length.

If the load is made considerably greater than one-fourth of the breaking strength of the wire, it is found that when the load is removed the wire has taken a permanent set; in other words, it will not return to its original length. If the wire remains permanently longer than it was before the load was applied, it has been strained beyond the limit of elasticity.

Suppose that a weight of 2,000 pounds is hung from the end of a wrought-iron rod having a sectional area of 1 square inch, and that the rod stretches about $\frac{1}{3000}$ of its original length. When the weight is removed, the bar resumes its original length, as far as can be measured by ordinary instruments. Now, instead of 2,000 pounds, attach a weight of 24,000 pounds to the rod and it stretches about $\frac{1}{1000}$ of its length; when this weight is removed, we find that the bar does not return to its original length, but that it is slightly longer than it was before; that is, the bar has a permanent set.

The unit stress where the weight on the rod is just sufficient to produce the least permanent set is called the **elastic limit**.

39. The **modulus of elasticity** is the ratio of the unit stress to the unit strain for loads within the elastic limit.

For example, if the weight of 2,000 pounds on an iron bar, whose section is 1 square inch, produces an elongation of $\frac{1}{3000}$ of the original length of the bar, the unit stress is 2,000 pounds per square inch; the unit strain is $\frac{1}{3000}$; and the modulus of elasticity is $2,000 \div \frac{1}{3000} = 26,000,000$ pounds per square inch.

In most building materials, the modulus of elasticity for tension and the modulus for compression may be considered as practically equal. The moduli of elasticity of some of the principal building materials are: yellow pine, 1,200,000 pounds

per square inch; cast iron, 17,000,000 to 20,000,000; steel, 28,000,000 to 30,000,000; neat cement, 3,000,000; concrete, 700,000.

40. The stresses of tension and compression created in a loaded beam cause elongation and shortening of the longitudinal elements above and below the neutral plane, the result of which is a curvature of the beam. The amount of this curvature depends on the amount and distribution of the load, the material of which the beam is composed, its span and manner of support, and on the dimensions and form of the cross-section.

Deflection is the name applied to the distortion or bending produced in a beam when subjected to transverse stresses. The measure of the deflection at any point on a beam is the perpendicular displacement of the point from its original position. If, on the removal of the transverse stresses or loads on the beam, it returns to the straight or original form, the material in the beam has not been strained beyond the elastic limit. On the other hand, if the internal stresses exceed the elastic limit of the material, a permanent set will be given the beam.

41. **Stiffness** is a measure of the ability of a body to resist bending; this property is very different from the strength of the material or its power to resist rupture.

The stiffness of a structure does not depend so much on the elasticity of the material of which it is composed as on its arrangement and form; for example, a floor may be built of shallow and wide joists that will be sufficiently strong to carry a given load, but it will not be nearly so stiff as a floor of equal strength built of narrow and deep ones. This property of stiffness is as important in building construction as mere strength, and the two should be considered together; thus, the floor joists of a building may be strong enough to resist breaking, but so shallow as to lack stiffness, in which case the floor will be springy and vibrate from people walking on it. If there is a plastered ceiling on the under side of the joists of such a floor, the deflection of the joists

may cause the plaster to crack and fall into the room below. Where stiffness is lacking in the rafters of a roof, they will be liable to sag, thereby causing unsightly hollows in the surface of the roof, in which moisture and snow may lodge, which would be very detrimental to the roof covering.

42. From the foregoing, it is evident that not only must the strength of the beams composing a structure be calculated to withstand rupture, but the beams must be stiff or rigid enough to resist bending. It is, therefore, important to be able to calculate the deflection of any beam under its load, and if found excessive, the size of the beam may be increased and the deflection reduced to working limits.

The amount of deflection that exists in beams loaded and supported in different ways may be calculated by the formulas given in Table IV. In using these formulas, all the loads should be expressed in pounds and the lengths in inches. The modulus of elasticity is denoted by E , and the moment of inertia of the section by I .

EXAMPLE 1.—A 10-inch steel I beam, supported at the ends, must sustain a uniformly distributed load of 10,000 pounds. The span of the beam is 20 feet, and its moment of inertia is 146.4; there is to be a plastered ceiling on its under side, the allowable deflection of which is $\frac{1}{30}$ inch for each foot of span. Will the deflection of the beam be excessive?

SOLUTION.—The formula for the deflection of a beam of this character, from the table, is $\frac{5 W l^3}{384 E I}$. From Art. 39, the modulus of elasticity of structural steel is 28,000,000 to 30,000,000; taking the average value, and substituting the other values of the example in the formula, the deflection equals

$$\frac{5 \times 10,000 \times 240^3}{384 \times 29,000,000 \times 146.4} = .42, \text{ or about } \frac{7}{16} \text{ in.}$$

Since the allowable deflection for each foot of span is $\frac{1}{30}$ in., the total allowable deflection is $\frac{1}{30}$ of 20 = $\frac{2}{3}$ in. This is greater than the calculated deflection, and the beam therefore satisfies the required conditions. Ans.

EXAMPLE 2.—A 12" \times 16" yellow-pine girder must support a symmetrically placed triangular piece of brickwork, which weighs about 12,000 pounds. What will be the deflection of the timber if the span is 20 feet?

TABLE IV
FORMULAS FOR DEFLECTION OF BEAMS

















Case	Method of Loading	Deflection Inches
I		$\frac{W l^3}{3 E I}$ (
II		$\frac{W l^4}{8 E I}$ (
III		$\frac{W l^5}{15 E I}$ (
IV		$\frac{W l^3}{48 E I}$ (
V		$\frac{W x y (2 l - x) \sqrt{3 x (2 l - x)}}{27 l E I}$ (
VI		$\frac{W x}{48 E I} (3 l^3 - 4 x^3)$ (
VII		$\frac{5 W l^4}{384 E I}$ (
VIII		$\frac{3 W l^5}{320 E I}$ (

TABLE IV—(Continued)

Case	Method of Loading	Deflection Inches
IX		$\frac{W l^3}{60 E I}$ (41)
X		$\frac{47 W l^3}{3,600 E I}$ (42)
XI		$\frac{3 W l^3}{322 E I}$ (43)
XII		$\frac{5 W l^3}{926 E I}$ (44)
XIII		$\frac{W l^3}{192 E I}$ (45)
XIV		$\frac{W l^3}{384 E I}$ (46)
XV		For overhang: $\frac{W x}{12 E I} (3 x l - 4 x^2)$ (47) For part between supports: $\frac{W x}{16 E I} (l - 2 x)^2$ (48)
XVI		Variable

SOLUTION.—The formula for the deflection, in this case, from the table, is $\frac{W l^3}{60 E I}$. From Art. 39, the value of the modulus of elasticity is found to be 1,200,000. The moment of inertia of the section, from the formula $I = \frac{b d^3}{12}$, is $I = \frac{12 \times 16^3}{12} = 4,096$. Then, by substituting the given values, the deflection is

$$\frac{12,000 \times 240^3}{60 \times 1,200,000 \times 4,096} = .56, \text{ about } \frac{9}{16} \text{ in. Ans.}$$

EXAMPLES FOR PRACTICE

1. The moment of inertia of a 12-inch steel I beam is 228.3, and its span is 25 feet. If the ends of the beam are simply supported, what will be its deflection under a concentrated load of 10,000 pounds suspended from its center? Ans. .85 in.

2. A cantilever beam of 12" \times 16" yellow pine extends from a building wall 10 feet, and is loaded on the end with a concentrated load of 12,500 pounds; what will be the greatest deflection of the beam? Ans. 1.46 in.

3. The span of a 15-inch steel I beam is 30 feet, and the moment of inertia of its section is 455.8; the load on the beam is uniformly distributed and amounts to 3,000 pounds per lineal foot. If the ends of the beam are firmly fixed, what will be its deflection? Ans. .83 in.

BEAMS AND GIRDERS

(PART 2)

WOODEN, STEEL, AND REENFORCED CONCRETE BEAMS

FORMULA OF GENERAL APPLICATION

1. In every section of a beam under stress, each fiber offers against rupture a resistance whose moment is equal to the resisting force of the fiber multiplied by its perpendicular distance from the neutral axis of the section. The sum of these fiber moments is called the **resisting moment** of the section, and is equal to the bending moment producing the stress. By higher mathematics, it is proved that the resisting moment is equal to the product of the greatest unit stress in any part of a section multiplied by a factor, called the **section modulus**, or the **resisting inches**, which depends on the shape of the section; the latter term is now rarely used.

If the greatest unit stress is assumed to be the **modulus of rupture** or ultimate fiber stress of the material composing the beam, the following rule may be stated:

Rule I.—*To find the ultimate resisting moment of a beam, multiply the section modulus by the modulus of rupture of the material of which the beam is composed.*

The moduli of rupture for the materials used in building construction may be obtained from the table in *Materials of Structural Engineering*, Part 3.

For notice of copyright, see page immediately following the title page

From rule I; the ultimate resisting moment, which is represented by M , is equal to the product of the section modulus and the modulus of rupture, or Ss . If M represents the bending moment, the beam is loaded to its maximum capacity when M and M_1 are equal; that is, the load applied to produce this condition would be the breaking load. For a uniformly distributed load the formula for the bending moment on a beam is $M = \frac{WL}{8}$, in which W equals the total load in pounds, and L the span of the beam in feet.

The bending moment is expressed in foot-pounds while the resisting moment is in inch-pounds; therefore, in equating these values it is necessary to reduce both values to the same denomination, which is accomplished by dividing Ss by 12. This gives the equation

$$\frac{WL}{8} = \frac{Ss}{12}, \text{ then, } W = \frac{8 Ss}{12 L}, \text{ or}$$

$$W = \frac{2 Ss}{3 L} \quad (1)$$

in which S = section modulus;

s = modulus of rupture;

L = span of beam, in feet;

W = total load, in pounds.

The uniformly distributed load that will break a beam whose size is known is determined by formula 1, which may be stated by the following rule:

Rule II.—*To determine the uniformly distributed load, in pounds, that will break a beam, multiply twice the section modulus by the modulus of rupture and divide this product by three times the span, in feet.*

EXAMPLE.—Taking the modulus of rupture of hemlock at 3,500 pounds and using a factor of safety of 4, what uniformly distributed load can be safely carried by a hemlock beam 8 inches by 12 inches, the span being 25 feet?

SOLUTION.—Section modulus $= \frac{b d^2}{6} = \frac{8 \times 12^2}{6} = 192$. The formula for the breaking load is $W = \frac{2 Ss}{3 L}$; hence, using a factor of safety

of 4, the safe uniformly distributed load will be $\frac{2 S s}{4 \times 3 L}$. Substituting the values in this formula, the breaking load is

$$\frac{2 \times 192 \times 3,500}{4 \times 3 \times 25} = 4,480 \text{ lb. Ans.}$$

WOODEN BEAMS

2. In practice, it is often necessary to determine what size beam will be required to carry a given load; the formula to be used in such a case is obtained by transposing the values in formula 1. Thus,

$$W = \frac{2 S s}{3 L}, \quad 3 W L = 2 S s, \quad \frac{3 W L}{2 s} = S, \text{ or}$$

$$S = \frac{3 W L}{2 s} \quad (2)$$

This formula will give the value of the section modulus that the beam must have in order to furnish the necessary resistance. Then, for a rectangular beam, the formula $S = \frac{b d^3}{6}$ is used, in which the value of S found from the previous formula is substituted and a width or depth is assumed. The other dimension may be readily determined. The following example will illustrate this method:

EXAMPLE.—What size yellow-pine beam is required to support a uniformly distributed load of 500 pounds per foot over a span of 10 feet, the modulus of rupture of yellow pine being 6,000, and a factor of safety of 4 being used?

SOLUTION.—The safe strength of the wood, using 4 as a factor of safety, is $6,000 \div 4 = 1,500$ lb. per sq. in. Substituting the values of W , L , and s in the formula $S = \frac{3 W L}{2 s}$ gives

$$S = \frac{3 \times (500 \times 10) \times 10}{2 \times 1,500} = \frac{150,000}{3,000} = 50$$

the required section modulus. Assuming 6 in. as the width of the beam, the values of S and b may be substituted in the formula $S = \frac{b d^3}{6}$; thus, $50 = \frac{6 d^3}{6}$; $d^3 = 50$; $d = \sqrt[3]{50} = 7.07$ in. It will therefore be necessary to use a 6" \times 8" beam. Ans.

3. When a beam is designed to resist the bending moment produced by the loads on it, it will usually be

strong enough to resist the vertical and horizontal shear, so that it is not necessary to take into account these stresses in proportioning the size of the beam. However, they must be considered to some extent in designing the beam at its bearing, and care should be taken that no material is cut away at the bottom. If the section is reduced at the bearing by cutting out the under side, the resistance to the horizontal shear at this point will be partially destroyed.

GENERAL NOTES RELATIVE TO WOODEN BEAMS

4. In the framing of floors it is frequently necessary to frame around chimney breasts, elevator shafts, and similar projections. This construction is generally accomplished by framing or hanging the joists from a beam or girder that extends in front and parallel to the face of the projection. This girder is known as a *header* and is, in timber framing, composed of two or more joists placed side by side and spiked together; it is supported at the ends by similar girders extending parallel with the joists, which are termed **trimmers**; the joists that are framed into the header are called **tail-beams**.

Wooden beams or any other timbers entering a party wall of a building constructed of stone, brick, or iron should be separated from the beam or timber entering in the opposite side of the wall by at least 4 inches of solid masonry.

A header or trimmer more than 4 feet long should be hung in stirrup irons of suitable thickness for the size of the timbers. Patent hangers are also frequently used. All beams, except headers and tail-beams, should have one end resting 4 inches in the wall, or on a girder.

The ends of all wooden floorbeams and roof beams resting on brick walls should be cut to a bevel sloping away from the vertical toward the top, this slope being not less than 3 inches for their depth. Except in framed buildings, a floorbeam or roof beam should not be supported on stud partitions. Also, all wooden beams should be bridged with cross-bridging placed not more than 8 feet apart.

Each tier of beams should be anchored to the side, front, rear, or party walls at intervals of not more than 6 feet, with good, strong, wrought-iron anchors not less than 1½ inches by ⅜ inch; these anchors should be fastened to the side of the beams by two or more wrought-iron nails at least ¼ inch in diameter. Where beams are supported by girders, the latter should be anchored to the walls and fastened to each other by iron straps.

Where the ends of wooden beams rest on girders, they should be butted together and strapped by wrought-iron straps, those beams being strapped that were anchored into the wall. The straps are secured to the beams in the same manner as the anchors. If the beams are not butted on the girder, they should lap each other at least 12 inches and should be well spiked or bolted together.

It is necessary to anchor front and rear walls and all piers to the beams of each story. The same size anchors as are required for the side walls should be used and should extend over four beams.

TABLE I

5. The safe uniformly distributed load that a floorbeam will support, as determined by the New York building laws, is found by multiplying the area, in square inches, by

Wood	Factor of Safety
Hemlock	70
Spruce	90
Oak	120
White pine	90
Yellow pine	140

its depth, in inches, and dividing this product by the span of the beam, in feet. This result is then multiplied by the value given in Table I for the wood of which the beam is composed.

EXAMPLE.—What will be the safe uniformly distributed load, in pounds, for a yellow-pine beam 3 inches by 10 inches and having a span of 20 feet?

SOLUTION.—Substituting the values stated in the example and solving according to the method explained above gives

$$\frac{3 \times 10 \times 10}{20} \times 140 = 2,100 \text{ lb.}$$

the safe uniformly distributed load. Ans.

FLITCH-PLATE GIRDERS

6. A flitch-plate girder is composed of a steel plate having a wooden beam bolted on each side. In designing a girder of this kind, it is necessary to proportion it so that the different parts will deflect equally. The load distribution may be disregarded, as it is the same for the wood and steel; also, the span is the same for each portion of the beam, and hence this value and all constants may be eliminated when considering the tendency of the materials to deflect under the same conditions.

By referring to the deflection formula and disregarding the values just mentioned, it will be observed that in order to have equal deflection in the two materials, the ratio of the load to the product of the modulus of elasticity and the moment of inertia must be the same for each material. When the depth of the wooden beams and the plate are the same, the moment of inertia will vary with the breadth; the other values used in determining this property may be disregarded, as they are constant. Then the ratio will be the load divided by the product of the modulus of elasticity and the width of the section for each material.

As the bending moment M is equal to the section modulus multiplied by the modulus of rupture, the value of the latter may be found by dividing the bending moment by the section modulus. The cross-section of a flitch-plate beam is rectangular; therefore, the section modulus is obtained from the formula $\frac{b d^2}{6}$; as the width b is the only value that varies, the others may be disregarded, and it may be said that the modulus of rupture, or unit fiber stress, for each material varies as the ratio of the load to the width of the section for each. When s represents the unit fiber stress; W , the load; and b , the width of the section for one material; and s' , W' , and b' represent the same values for the other material, the relation stated above may be expressed by the proportion:

$$s : s' = \frac{W}{b} : \frac{W'}{b'}$$

It has been stated that the ratio of the load to the product of the modulus of elasticity and the width of the section for each material must be equal; or, when E and E' represent the moduli of elasticity for the materials, $\frac{W}{E b} = \frac{W'}{E' b'}$; but, as the unit fiber stress for each material varies in the ratio of the load to the width, the former may be substituted for this ratio in the proportion. Thus, $\frac{s}{E} = \frac{s'}{E'}$, or $s : s' = E : E'$; hence, the unit fiber stress varies as the modulus of elasticity for each material. This proportion must always be true in order to provide for a uniform deflection in the two materials.

EXAMPLE.—If a flitch-plate girder 12 inches in depth is required to resist a bending moment of 300,000 inch-pounds, what thickness of spruce planks will be required, the steel plate being $\frac{1}{2}$ inch thick? The modulus of elasticity for structural steel is 29,000,000 and for spruce 1,200,000, while the safe unit stress for steel may be taken at 15,000 pounds.

SOLUTION.—The ratio of the moduli of elasticity for the two materials is $\frac{1,200,000}{29,000,000} = \frac{12}{290}$. Then the safe unit stress that may be employed for spruce is $\frac{12}{290}$ of 15,000 = 620 lb. per sq. in. The bending moment is equal to the modulus of rupture multiplied by the section modulus, or $M = S s$. As in this instance there are two separate beams, there are also two section moduli, viz.: $\frac{b d^3}{6}$ and $\frac{b' d^3}{6}$, that have to be added together; hence, in this case, $M = \frac{b s d^3}{6} + \frac{b' s' d^3}{6}$. By transposing, it is found that $b = \frac{6 M - b' s' d^3}{s d^3}$. Considering s and b as the values for wood, and substituting in the formula gives

$$b = \frac{6 \times 300,000 - .5 \times 15,000 \times 144}{620 \times 144} = 8 \div 2 = 4 \text{ in.}$$

Therefore, each plank should be $8 \div 2 = 4$ in. in width. Ans.

7. Flitch-plate girders should have two lines of bolts, as shown in Fig. 1, the distance between centers on each line being twice the depth of the girder, while at each end there should be two bolts in the same vertical line. When a flitch-plate girder is connected to a column and it is desired to have the column flanges concealed, the girder may be notched out to fit over the flange. The floor may then be laid up to

the column and the bolts in the girder arranged as shown in Fig. 2, which is a sectional plan and elevation of a column




FIG. 2

with two steel and two flitch-plate girders. The flooring shown in the elevation is omitted in the plan.

If a lug projects from the column, the iron plate may be cut away sufficiently to permit the lug to slip between the wooden beams, which should be bolted to it. Where a flitch-plate beam is connected to an I beam or plate girder, an angle may be riveted to the web of the girder to support the flitch plate, and if the floor is to be raised above the top flange of the I beam, it will be necessary to cut the flitch plate in the same manner, as illustrated in Fig. 2 (*b*).

BUILT-UP WOODEN BEAMS

8. Difficulty is frequently experienced in obtaining timbers of the size required for very heavy work; therefore, the method of building up a beam of smaller pieces is sometimes resorted to. The most efficient built-up beam, and the form commonly used, is constructed by securing narrow pieces of material together so that the joints are vertical, as shown in Fig. 3. They may be fastened with through




FIG. 3

bolts, which give the more efficient beam, or with lagscrews; in some cases they are simply spiked together. These built-up members are of advantage in trusses for church roofs, especially when it is desired to have the lower member of the truss curved. Fig. 4 shows a portion of a church roof truss, in which the rafter member, as well as the lower chord member, is built up of three pieces $1\frac{1}{2}$ inches thick, secured by lagscrews. Theoretically, a beam built up in this manner is as strong as a solid beam of

BEAMS AND GIRDERS

the same dimensions, and it is found in many cases to be even stronger. This is due to the fact that a solid beam of large dimensions is liable to have defects in the center of the timber or to be composed partly of the heart wood, which is not so strong as the outer layers. Better material




FIG. 4

can be obtained in small pieces and they are more likely to be well seasoned than the larger timbers. By having the lower chord member made up of sections it is also possible to cover up the tension bar entirely, which is sometimes desirable.

9. Another form of built-up beam is one in which the pieces are placed so that the joints are horizontal, as shown in Fig. 5 (a). The longitudinal shear produced in this beam




FIG. 5

when it is subjected to transverse stress is resisted only by the bolts. Probably a better construction is one in which hardwood or iron keys are used, in addition to the bolts. This is known as a *keyed beam*, and is shown in (b). Another

method of resisting the longitudinal shear is by inserting pieces of pipe in the beam, as shown in (c). This is a fairly cheap form, but is inferior to the keyed beam.

10. Clark's design for a built-up beam consists of two pieces, one above the other, fastened by narrow strips on each side, running diagonally, those on opposite sides of the beam running in opposite directions. Sometimes the diagonal strips are wide pieces and the heavy timbers are bolted together. These two forms of the Clark beam are shown in Fig. 5 (d) and (e), respectively. What is known as the *indented beam*, shown at (f), is sometimes used. The notches are intended to resist the horizontal shear, or the tendency of the two pieces to slide on each other, but when shrinkage occurs, the indented surfaces are not held tightly together and the efficiency of the beam is greatly diminished.

11. **Efficiency of Built-Up Beams.**—Table II gives the average efficiency of several kinds of built-up beams. These results were obtained from tests and the efficiency is the ratio of the strength of a built beam to a solid

TABLE II
EFFICIENCY OF BUILT-UP WOODEN BEAMS

Kind of Beam	Deflection	Efficiency Per Cent.
Indented	2.00	69.5
Clark's	2.00	76.0
Piped	1.70	84.6
Oak keys	1.25	90.6
Flat iron keys	1.50	78.6
Square iron keys	1.50	89.5

one of the same size and quality of material. The deflection is expressed in the same ratio, the deflection of a solid beam being the unit of comparison, so that from the table it may be observed that Clark's and the indented beams

have a deflection equal to twice that of a solid beam under the same condition of loading, while the deflection of the other beams tested and listed varies from $1\frac{1}{4}$ to $1\frac{3}{4}$ times the deflection of a solid beam.

DETAILS OF DESIGN

12. Beam Hangers.—Various devices for supporting the ends of beams where they are carried by headers and trimmers or where they run into the wall, have been manufactured; some of these give very good results, while others are not entirely satisfactory. When the **Goetz hanger**, shown in Fig. 6, is employed the beam is held in place by a nail driven up through the hole *a*; therefore, when the beams are placed opposite on each side of the girder, this arrangement ties the beams together. The pins, or lugs, that enter






FIG. 6

the main beam are bent at an angle so that the hanger will lock against the beam when the weight is applied to the joist.

The **Van Dorn hanger** for wooden beams is shown in Fig. 7 (*a*), while the double and single hangers used on I beams are shown in (*b*) and (*c*), respectively. The double hanger is formed by bolting two hangers to an iron plate that rests on the top of the I beam; a block of wood is placed on each side of the web of the beam to keep the hanger in position. Fig. 8 shows a special Van Dorn hanger arranged to support joists on the opposite sides of a beam or girder.



(a)



(b)

FIG. 7

(c)




FIG. 8

A **stirrup iron hanger** is made by bending an iron strap to fit over the top of the beam and form a loop to hold the joist. Some special stirrup iron hangers are shown




FIG. 9




FIG. 10




FIG. 11

in Fig. 9, the one in (a) being a simple hanger with a plate riveted in the loop of the hanger to carry the joist and one on the top to rest on the beam or to be built into the wall.




FIG. 12




FIG. 13

In (b) is shown a double hanger having one side shorter than the other, while (c) illustrates a double hanger that is used where the beams are not opposite each other and do not run in the same direction. These hangers are generally held in place by being nailed to the beams that support them.

The Duplex hanger for a small joist or beam is shown in Fig. 10; the girder on which it is hung has a hole drilled in it to receive the lug *a*. For wide beams, a double hanger, shown in Fig. 11, is used. The beam is bolted to the hanger, the latter being secured to the girder by bolts run through the lugs that enter the beam. Fig. 12 (a) shows a side and front elevation of a double hanger in position, while (b) shows a perspective of a






FIG. 14



(a)



(b)

FIG. 15

connection made with such a hanger, the beam being moved out of position and shown in full lines, while the dotted lines

indicate its position when held by the hanger. In Fig. 13 (*a*) and (*b*) are shown the hangers used for I beams; these are made to fit exactly the flange of the I beam and are bolted through the web of the beam. Fig. 14 represents the single hanger, used for narrow beams, in position on the I beam. The double hanger used for heavier construction is shown in

position in Fig. 15 (*a*) and (*b*), (*a*) showing the manner in which the end of the wooden beam should be cut to fit in the hanger, while (*b*) illustrates the method of bolting the




FIG. 16




FIG. 17

hangers to the I beams, and also shows the rib over which the joists must be cut and which serves as a tie when the latter are in place. The Duplex wall hangers, shown in Fig. 16 (*a*) and (*b*), are used extensively and give satisfactory results.

13. Tests Made on Beam Hangers.—The results of a test made on a Van Dorn hanger, a stirrup iron hanger, and a Duplex hanger are shown in Figs. 17, 18, and 19. In each case, one end of the I beam to which the load was applied rested on a pine block 7 inches thick, that was securely fastened in the hanger; the other end was supported on an iron bar. When 13,300 pounds had been applied to the beam

carried by the Van Dorn hanger, shown in Fig. 17, the hanger began to straighten out, and failed at a load of 18,750 pounds. The stirrup iron hanger failed at a load of 18,750 pounds, by pulling off from the header, as shown in Fig. 18; the crushed parts of the header are the points where the stirrup was hung for the test. The beam supported by the Duplex




FIG. 18




FIG. 19

hanger, Fig. 19, was loaded to 20,000 pounds, when the wood began to show signs of failing, but the hanger held until a load of 39,550 pounds was applied. At this point, one side of the hanger broke off short under the lug projecting into the header. The Duplex hanger was bolted to the header with two $\frac{1}{2}$ -inch bolts through the lugs.

14. Heavy Wooden Construction.—In heavy wooden construction, the wooden beams are carried by iron girders and are sometimes supported on beam ledges or blocks bolted to the girder. Fig. 20 shows a 15-inch I beam that carries 8" \times 12" wooden beams placed opposite each other. These beams rest on beam ledges *a*, of which only one is shown in the illustration. They extend the full length of the girder and are bolted to it with $\frac{1}{2}$ -inch bolts. The ledges are notched out to receive the wooden beams and are also cut out to fit around the lower flange of the I beam, extending $\frac{1}{8}$ inch below it. The wooden beams, which are cut out to fit the upper flange of the girder, are notched at the top and a $1\frac{1}{8}$ -inch anchor plate is set in the full width of the beams; this arrangement ties the beams together. For

additional stiffness, a $\frac{1}{2}$ -inch cleat *b* is nailed on each side of the beam, extending from the beam ledge to within $\frac{1}{8}$ inch of the top of the wooden beam; the cleat is fastened




FIG. 20

to the anchor plate and the beam, thus forming a rigid connection. A $\frac{1}{2}$ -inch casing is rabbeted into the beams and extends from one beam to the next, thus enclosing the girder and making a neat finish. The only part of the girder that is exposed is the lower flange, but even this is protected to some extent by the beam ledge. Fig. 21 shows

an elevation of the girder with the finished casing at (a) and without it at (b).

The arrangement for the casing of a 20-inch girder carrying $8'' \times 12''$ wooden beams is shown in Fig. 22, in which *a, a* are the blocks that are placed under each beam and bolted through the web of the girder in two places, the blocks being counterbored to allow the bolt heads to sink below




FIG. 21

the surface. The beams are notched and an anchor plate is set in as shown; a cleat, extending from the bottom flange of the I beam almost to the top of the wooden beam, is

spiked to each side, thus keeping the block, beam, and anchor plate in line and securing them rigidly together. The casings *b*, *c*, and *d* and the molding *e* are then put in place, the piece marked *d* being rabbeted into the beam. Though the arrangements shown in Figs. 20 and 22 can hardly be considered as strictly slow-burning construction, they are especially strong and rigid and may be employed with good results in buildings where it is necessary to provide against the effects of vibration.




FIG 22

STEEL BEAMS

15. The steel beams used in building construction are generally either channels or I beams. When the word *beam* is used, it is understood that an I beam is meant. For instance, a 12-inch 40-pound beam means an I beam 12 inches in depth, weighing 40 pounds to the lineal foot; a channel of the same size is expressed as a 12-inch 40-pound channel. In designating rolled shapes on working drawings, various systems of abbreviations are used. A 12-inch 40-pound beam may be expressed as 12" I 40 #, or a channel as 12" C 40 #. This is entirely a matter of judgment with the draftsman, or is governed by the practice used in the particular drafting room. As long as the size, character, and weight of the beam are given, it matters little how they are expressed, if intelligibly written.

TRANSVERSE STRENGTH

16. In calculating the strength of steel beams, it is first necessary to find the bending moment, using the methods and rules already given. Then the section modulus required in the beam may be obtained by dividing the bending moment, in inch-pounds, by the quotient obtained by dividing the modulus of rupture by the factor of safety. Assume, for example, the bending moment on a beam to be 50,000 foot-pounds. Reduce it to inch-pounds by multiplying it by 12, which gives 600,000 inch-pounds. The modulus of rupture for structural steel is 60,000 pounds. If a factor of safety of 4 is used, the safe working value of this material will be $60,000 \div 4 = 15,000$ pounds per square inch. Then $600,000 \div 15,000 = 40$, the section modulus required.

The approximate section modulus of an I beam, or a channel, may be found by the following rules:

Rule I.—*To obtain the approximate section modulus of an I beam, multiply the sectional area of the beam, in square inches, by the depth, in inches, and divide by the constant 3.2.*

Rule II.—*To obtain the approximate section modulus of a channel, multiply the sectional area of the channel, in square inches, by the depth, in inches, and divide by the constant 3.67.*

Letting A equal the sectional area, in square inches, of an I beam or a channel, and d its depth, in inches, the approximate section moduli S_i and S_c of an I beam and channel, respectively, may be found from the formulas

$$S_i = \frac{A d}{3.2} \quad (3)$$

and
$$S_c = \frac{A d}{3.67} \quad (4)$$

EXAMPLE.—What is the section modulus of a 12-inch I beam, the sectional area of which is 9.01 square inches?

SOLUTION.—Applying the formula,

$$S_i = \frac{A d}{3.2} = \frac{9.01 \times 12}{3.2} = 33.8. \quad \text{Ans.}$$

17. Finding the Dimensions of a Steel Beam.—To illustrate the method of calculating the dimensions of a steel beam, let it be required to find what size steel I beams are necessary to support the floor of an office building; this floor rests on brick arches sprung between the beams, and weighs complete 110 pounds per square foot. The building is designed to carry a live load of 40 pounds per square foot. The span of the beams is 20 feet and they are spaced 5 feet on centers. The owner requires that the building have a large factor of safety, and suggests that for the floorbeams a safety factor of 5 be used. The total dead and live load on the floor is 110 pounds + 40 pounds = 150 pounds per square foot. The floor area supported by one beam is $20 \times 5 = 100$ square feet. Then the total load on one beam is $100 \times 150 = 15,000$ pounds. The load being uniformly distributed, the formula for the bending moment is $M = \frac{WL}{8}$; substituting the values for W and L ,

$M = \frac{15,000 \times 20}{8} = 37,500$, the bending moment in foot-pounds, which, being multiplied by 12, equals 450,000 inch-pounds.

The modulus of rupture for structural steel is 60,000 pounds per square inch, and, since a factor of safety of 5 is required, the safe working value will be $60,000 \div 5 = 12,000$ pounds per square inch. The bending moment in inch-pounds is 450,000, which, divided by 12,000, gives a section modulus of 37.5.

From the table Properties of Standard I Beams in *Properties of Sections*, it is found that the section modulus of a 12-inch 35-pound beam is 38; hence this size beam should be used.

In selecting beams from the table, care should be taken to obtain the deepest beam of the least weight with the required section modulus. Thus, from the table, it is found that the section modulus of a 10-inch beam, weighing 40 pounds, is 31.7, while a 12-inch beam of 40 pounds, or the same weight as the 10-inch beam, has a section modulus of 41, and, in consequence, possesses nearly one-third more strength, making it, therefore, the more economical beam to use.

18. By way of general review of the subject of beams, the following practical example will be considered: Fig. 23




FIG. 23




FIG. 24

shows the transverse sectional elevation of a large department store, in which the girder B is made up of two I beams. What is the size and weight of these steel beams?

Before commencing the calculations, draw the outline diagram, as shown in Fig. 24; this is called a frame diagram. The two supports for the girder are the wall W and the column C . The loads g, h on the girder are uniform; the load h is due to the weight of the floor, girder, and the ceiling, together with the live load on the floor due to the people, furniture, etc. This load has been assumed to amount to 500 pounds per running foot of the girder. The load g , being due only to the ceiling and a portion of the roof, and there being no floor load on it, has been considered as amounting to 200 pounds per running foot.

The girder is also loaded with four concentrated loads: a of 10,000 pounds, due to the weight of the light wall and a portion of the roof; d of 20,000 pounds, due to the load coming down the small column from a portion of the roof; and two hanging loads f and e , of 3,000 and 2,000 pounds, respectively, from the weight of the stair landing or hall.

The reactions may now be calculated. The moments about W are as follows:

DUE TO	FOOT-POUNDS
Load g ($200 \times 6 = 1,200$ lb.)	$1,200 \times 3 = 3\,600$
Load h ($500 \times 28 = 14,000$ lb.)	$14,000 \times 20 = 28\,000$
Load a	$10,000 \times 6 = 60\,000$
Load f	$3,000 \times 9 = 27\,000$
Load d	$20,000 \times 34 = 68\,000$
Load e	$2,000 \times 34 = 68\,000$
Total moments	<u>$= 111\,860$</u>

This, divided by the distance between the supports, or the span, 25 feet, will give 4,474, the load, in pounds, coming on the column C ; or, in other words, the reaction at C . The loads are as follows:

Load g =	1 2 0 0 pounds
Load h =	1 4 0 0 0 pounds
Load a =	1 0 0 0 0 pounds
Load f =	3 0 0 0 pounds
Load d =	2 0 0 0 0 pounds
Load e =	<u>2 0 0 0 pounds</u>
Total load =	<u>5 0 2 0 0 pounds</u>

Then, the reaction at W is $50,200 - 44,744 = 5,456$ pounds
Find the point between the two supports W and C , where the shear changes sign.

Working out on the beam from W , the first load encountered and to be deducted from the reaction W is the uniform load g , equal to $200 \times 6 = 1,200$ pounds. Then, $5,456$ (reaction at W) $- 1,200$ (load g) $= 4,256$ pounds. The next load on the beam is the concentrated load a of $10,000$ pounds, which is much more than the remaining portion of the reaction W . The greatest bending moment occurring between the column and the wall is, therefore, at the point a , and is equal to $5,456$ (reaction at W) $\times 6 = 32,736$ foot-pounds, from which is to be taken the moment of the load g of $1,200 \times 3 = 3,600$ foot-pounds. Then, $32,736 - 3,600 = 29,136$ foot-pounds, the greatest bending moment between the supports C and W .

Again referring to the diagram, Fig. 24, it is seen that there is quite a bending moment directly over the column C , due to the two concentrated loads d, e on the end of the beam and the portion of the uniform load h overhanging the support C . This portion of the beam may be considered as a cantilever; the bending moment at C is equal to the sum of the moments of all the loads on the overhanging portion of the beam, which are:

LOAD	FOOT-POUNDS
d	$20,000 \times 9.0 = 180000$
e	$2,000 \times 9.0 = 18000$
h ($500 \times 9 = 4,500$ lb.) .	$4,500 \times 4.5 = \underline{20250}$
Total moments	$= 218250$

$218,250 \times 12 = 2,619,000$ inch-pounds. This, divided by $20,000$, the safe working value of structural steel (using the modulus of rupture of $60,000$ pounds $\div 3$, the safety factor used in this case) $= 131$, the required section modulus in the two beams. Then, $131 \div 2 = 65.5$, section modulus required in one of the beams.

From the table in *Properties of Sections*, it is found that the section modulus of a 15-inch 55-pound beam is 68.1 . The 18-inch beam of the same weight has a section modulus

of 88.4, and while this is in excess of the required amount, it is the preferable beam to use, two of the kind being required.

19. Relation Between Span and Depth of Beam.—In order to select beams that will not deflect too much under the load that they are required to sustain, the depth of the beam, in inches, should never be less than half the span of the beam, in feet. Thus, if the span of the beam be 20 feet, a beam not less than 10 inches in depth should be used to avoid excessive deflection.

20. Separators for I Beams.—In building construction, it frequently happens that a single I beam is insufficient to carry the imposed load. Where heavy loads, such as brick walls, vaults, etc., are to be supported, a single I beam is inadequate; therefore, two or more beams are placed side by side and bolted together, with steel separators between, as shown in Fig. 25, or with cast-iron separators, as shown in Fig. 26 (*a*) and (*b*). In (*a*) is shown a type of cast-iron separator so formed that the bolts pass through a hole in the





FIG. 25

swollen portion of the casting. Another pattern of cast-iron separator is shown in (*b*), in which the connecting bolt passes through a lug cast on the separator. A common use for a double beam secured together by bolts and separators is shown at *a, a*, Fig. 26 (*c*). These separators hold the compression flanges of the beams in position, preventing deflection sideways, and also, in a measure, cause the beams to act together, distributing the load uniformly on both. Separators should be spaced from 6 to 7 feet apart

throughout the length of the beam; they should also be provided at the supports and at the points where heavy loads are concentrated.

Standard separators may be obtained in such widths that the inner edges of the flanges of the two beams connected are about $\frac{1}{4}$ inch apart. For beams 10 inches in depth and under, one $\frac{1}{4}$ -inch bolt is used through the separator, while



(c)
FIG. 26

two $\frac{1}{4}$ -inch bolts are used for connecting beams over 10 inches in depth. Where two bolts are used, the distance between centers is usually made 10 inches for beams 18 and 20 inches in depth, 7 inches for 15-inch beams, and 6 inches for 12-inch beams. Separators for 18-inch and 20-inch beams weigh about 20 pounds each; for 15-inch beams, about 12 pounds;

for 12-inch beams the weight is from 8 to 10 pounds; for 8-, 9-, and 10-inch beams, from 5 to 7 pounds; and for 4-, 5-, and 6-inch beams, from 1 to 4 pounds.

21. I Beam Girders.—In designing floors of buildings it is desirable to have a minimum number of interior supporting columns, consistent with economy. A beam girder consisting of a pair of I beams is frequently advantageous for supporting the steel floorbeams, as shown at *a* in Fig. 26 (*a*).

Girders composed of two or more I beams are commonly used to span openings in brick walls. If the wall to be supported is thoroughly seasoned and without openings, the




FIG. 27

weight carried by the girder can safely be assumed as the weight of a triangular piece of brickwork, whose altitude is one-third of the span of the girder. If the wall is newly built, or has openings for windows or other purposes, the girder must be designed to carry the entire wall above it between the supports.

EXAMPLE.—Required, the size of a steel I-beam girder to carry a wall 12 inches thick, made of hard brick laid in lime mortar; there are no openings in the wall above the girder, nor does the wall support floor joists or roof beams, while the span of the opening is 24 feet.

SOLUTION.—Draw the diagram as shown in Fig. 27. The area of the triangular piece of brickwork is $24 \times 4 = 96$ sq. ft., since the area of a triangle is equal to the base, multiplied by one-half the altitude.

As the wall is 1 ft. thick, there are 96 cu. ft. in this triangular piece. The weight of brickwork in lime mortar per cubic foot is 120 lb. Then, $96 \times 120 = 11,520$ lb., the load on the girder.

The bending moment may be determined by the formula or rule given in *Beams and Girders*, Part 1, for a beam carrying a triangular load, or it may be determined by calculating the moments, as follows: The reactions at the two supports are each equal to half the load, or $11,520 \div 2 = 5,760$ lb. The greatest bending moment is at the center of the beam. Then, the moment of the reaction about the point x is $5,760 \times 12 = 69,120$ ft.-lb. But, counteracting this, and to be deducted from it, is the moment of the load at the left of x , equal to half of the triangular piece of brickwork. The moment of this load about the point x is equal to the product of its weight, multiplied by the horizontal distance from a vertical line through its center of gravity to the point x . Take the line ab as the base of a triangle, remembering that a line drawn parallel to the base line of a triangle, at a distance of one-third of the altitude from it, always passes through its center of gravity. Now, the distance from the point x to the vertical line through the center of gravity m of the triangle is 4 ft., and the moment due to the triangular piece of brickwork to the left of the center is $5,760 \times 4 = 23,040$ ft.-lb. Deducting this from the moment of the reaction already found, the calculation is: $69,120 - 23,040 = 46,080$ ft.-lb., the bending moment on this beam or girder; or, $46,080 \times 12 = 552,960$ in.-lb. This calculation may be checked by applying the formula $\frac{WL}{6}$. The bending moment, in inch-pounds,

being 552,960, using a safe working value, or fiber stress, of 15,000 lb., the section modulus required would be $552,960 \div 15,000 = 36.86$. From the table in *Properties of Sections*, it is seen that the section modulus of a 12-in. 35 lb. beam is 38, which gives the required strength in this case. It may be found to be better practice to use two channels instead of one I beam, for the top flange of the I beam may be too narrow to properly support the brick wall, while the two channels placed side by side, with separators between, could be made of the same thickness as the wall.

22. Connections.—The standard connections for the principal sizes and weights of steel I beams are illustrated in Fig. 28. These connections are based on an allowable shearing stress of 10,000 pounds per square inch, a bearing stress of 20,000 pounds per square inch on the bolts, and an extreme fiber stress of 16,000 pounds. They may be used for beams whose spans are not less than those given in Table III.




FIG. 28

TABLE III
MINIMUM SPANS FOR I BEAMS, WITH STANDARD CONNEC-
TIONS, THAT ARE UNIFORMLY LOADED TO REALIZE
A UNIT STRESS OF 16,000 POUNDS

Depth of Beam	Weight per Foot	Minimum Safe Span	Depth of Beam	Weight per Foot	Minimum Safe Span	Depth of Beam	Weight per Foot	Minimum Safe Span
Inches	Pounds	Feet	Inches	Pounds	Feet	Inches	Pounds	Feet
3	5.50	1.7	9	30.0	6.8	15	80.0	15.9
3	6.50	1.2	9	35.0	7.5	15	85.0	16.4
3	7.50	1.2	10	25.0	9.3	15	90.0	17.0
4	7.50	2.8	10	30.0	8.1	15	95.0	17.5
4	8.50	2.2	10	35.0	8.8	15	100.0	18.1
4	9.50	2.0	10	40.0	9.6	18	55.0	13.7
4	10.50	2.2	12	31.5	7.3	18	60.0	11.9
5	9.75	4.1	12	35.0	7.7	18	65.0	11.8
5	12.25	3.3	12	40.0	8.2	18	70.0	12.4
5	14.75	3.7	12	45.0	9.6	20	65.0	13.9
6	12.25	5.6	12	50.0	10.2	20	70.0	12.5
6	14.75	4.8	12	55.0	10.8	20	75.0	12.8
6	17.25	5.3	15	42.0	10.2	20	80.0	14.8
7	15.00	4.9	15	45.0	9.4	20	85.0	15.2
7	17.50	3.8	15	50.0	9.7	20	90.0	15.7
7	20.00	3.6	15	55.0	10.3	20	95.0	16.2
8	18.00	6.2	15	60.0	10.8	20	100.0	16.7
8	20.25	5.1	15	65.0	12.8	24	80.0	17.7
8	22.75	4.8	15	70.0	13.4	24	85.0	16.1
8	25.25	5.1	15	75.0	13.9	24	90.0	16.1
9	21.00	7.7	15	80.0	14.5	24	95.0	16.6
9	25.00	6.2				24	100.0	17.1

Beams that are shorter than this are, as a consequence, able to support greater loads without exceeding the unit stress of 16,000 pounds on which the standard connections are based. The joints illustrated would, in such cases, be exposed to a stress greater than that for which they are

intended. To avoid such excessive stresses the minimum safe spans have been specified in Table III for the various beams. The larger beams to which these connections are made are supposed to have webs not less than $\frac{9}{16}$ inch in thickness. If these beams or girders are framed opposite one another, into another beam or girder whose web is less in thickness than $\frac{9}{16}$ inch, the length of the minimum spans should be increased. The reason for this is that a thinner web cannot carry so large a load. To prevent the overloading of the connections it is necessary to increase the length of the spans of the adjoining beams in the ratio of the $\frac{9}{16}$ -inch web to the thickness of the thinner web.

For instance, a beam 7 inches deep, weighing 20 pounds per foot should, according to Table III, have a minimum span of 3.6 feet when connected to a beam with a $\frac{9}{16}$ -inch web. In case the latter web is only $\frac{3}{8}$ inch thick, the following proportion will give the length x of the longer beam required:

$$x : 3.6 = \frac{9}{16} : \frac{6}{16}, \text{ or } x = \frac{3.6 \times \frac{9}{16}}{\frac{6}{16}} = 5.4 \text{ feet}$$

The standard connections given are designed for $\frac{1}{8}$ -inch holes and $\frac{3}{4}$ -inch diameter rivets or bolts. Connection angles may, if so specified, be riveted instead of bolted to the beams; but, unless otherwise ordered, bolted connections are generally used.

When beams having very short spans are loaded to their full capacity, the shear at the end, which must be transmitted through the connections, becomes so great that connections




FIG. 29

stronger than the standard must be used. Table III gives the limits of lengths below which the standard connections cannot be used and below which special designs should be made.

Where floorbeams of different depths are to be joined to a larger girder and the tops or bottoms of the beams are to be level, a special construction is required. An example of this is given in Fig. 29 (*a*), in which two beams are joined with their tops flush. It was necessary to cut the flange of one enough to receive half the flange of the other, as shown in (*b*). This method of cutting the beam is called *coping*.

LATERAL STRENGTH OF BEAMS

23. Obtaining the Fiber Stress of Beams.—Where beams are subjected to a horizontal force in addition to the vertical load, some means must be provided to resist the lateral flexure. In a floor that is composed of arches sprung between the beams, the horizontal thrust from each arch is counteracted by the thrust of the arch on the opposite side of the beam in all except the outside beams and those around shafts or wells.

If the allowable stress for the extreme fibers of the beam is assumed to be 16,000 pounds per square inch, the vertical stress should be reduced to such an extent that the resultant intensity of the vertical and horizontal forces will not exceed this amount. The fiber stress due to the lateral forces is obtained by the formula

$$s_h = \frac{T c x^2}{I'} \quad (5)$$

in which s_h = stress, in pounds per square inch, due to lateral forces;

T = thrust of arch, in pounds per lineal foot;

c = distance of extreme fiber from neutral axis, in inches;

x = distance between tie-rods or lateral supports, in feet;

I' = moment of inertia about vertical axis of section, or axis at right angles to line of application of lateral forces.

When the web of the I beam is placed vertically, as usual, c is equal to $\frac{b}{2}$, b representing the width of the flange in inches. Then the preceding formula becomes

$$s_h = \frac{T b x^3}{2 I'} \quad (6)$$

The formula is derived from the equation, bending moment $M =$ resisting moment M_1 .

The portion of the beam between two adjacent tie-rods may be regarded as a beam with fixed ends; the bending moment for a uniform load will then be $\frac{WL}{12}$. The distance between supports is represented by x in formula 5; therefore, x will be used in this formula instead of L , while instead of W , the thrust per lineal foot, or T , will be used. The load is equal to Tx and the bending moment created by it is $\frac{Tx \times 12x}{12}$, or Tx^2 , considering the span in inches, as usual.

The resisting moment is equal to the section modulus multiplied by the safe unit fiber stress, or Ss . As explained in *Properties of Sections*, the section modulus is equal to the moment of inertia divided by the distance from the neutral axis to the farthest edge of the section, or $S = \frac{I}{c}$. In this case, the moment of inertia is taken with respect to the neutral axis parallel to the web; consequently, c equals half the width of the flange, or $\frac{b}{2}$, and $S = \frac{2I}{b}$. Hence, substituting the values thus obtained for M and M_1 gives $Tx^3 = \frac{2Is}{b}$. Then, $s = \frac{T b x^3}{2 I}$.

24. Obtaining the Horizontal Thrust.—The horizontal thrust is found by the formula

$$T = \frac{3 w L^2}{2 r} \quad (7)$$

in which T = pressure or thrust, in pounds per lineal foot of arch;

w = load on arch, in pounds per square foot, uniformly distributed;

L = span of arch, in feet;

r = rise of arch, in inches.

The thrust of an arch having a concentrated load at the center equal to W , is found from the formula

$$T = \frac{3WL}{r} \quad (8)$$

If the floor arch is flat, the value of r may be taken as the effective depth of the arch, as will be explained in Art. 27.

25. Obtaining the Resultant Stress.—The vertical and horizontal forces may be laid off on the legs of a right triangle, when the hypotenuse will be the resultant stress, but as this must not exceed the allowable stress per square inch, which in this case will be assumed as 16,000 pounds, the stress due to the vertical load, which may be designated as s_v , should be

$$s_v = \sqrt{16,000^2 - s_h^2} \quad (9)$$

If the vertical load is considerable, it would be economical to provide tie-rods or braces at shorter intervals, thus permitting the use of a lighter beam than would otherwise be required.

26. Obtaining the Maximum Safe Load.—As the resisting moment of a beam is equal to the section modulus multiplied by the safe unit fiber stress, or Ss , and the

bending moment is $\frac{Wl}{8}$, these moments must be equal;

$Ss = \frac{Wl}{8}$; then, $W = \frac{8Ss}{l}$, which value the load should not

exceed. It should be noticed that the l introduced in this formula differs from the L used in formula 8, the latter being in feet and the former in inches. This allowable load

must be reduced in the ratio of $\frac{s_v}{16,000}$ when there is a hor-

izontal force acting on the beam. Thus, the load W , that

the beam may carry is equal to $\frac{8 S s}{l} \times \frac{s_v}{16,000}$; but as the allowable stress, or s , is generally assumed as 16,000 pounds, the equation becomes

$$W_s = \frac{8 S \times 16,000}{l} \times \frac{s_v}{16,000} = \frac{8 S s_v}{l} \quad (10)$$

EXAMPLE.—The floor in a heavy fireproof structure is composed of brick arches, having a rise of 6 inches, sprung between 15-inch 42-pound I beams placed 4 feet apart; the span of the beams is 15 feet and two tie-rods are to be used in each span, spaced at a distance of 5 feet apart. The dead load is 150 pounds and the live load is 200 pounds per square foot; determine whether this size beam is large enough to support the load and offer sufficient resistance to the thrust of the arch.

SOLUTION.—The thrust of the arch obtained from formula 7 is

$$T = \frac{3 \times 350 \times 4 \times 4}{2 \times 6} = 1,400 \text{ lb. per ft.}$$

As the neutral axis parallel to the web is through the center of the beam, formula 6 may be used in obtaining the horizontal stress due to the thrust of the arch. From the table in *Properties of Sections*, the moment of inertia with respect to an axis parallel to the web of a 15-in. 42-lb. I beam is 14.62 and the width of the flange b is 5.50. Then

$$s_h = \frac{1,400 \times 5.50 \times 5 \times 5}{2 \times 14.62} = 6,583.45, \text{ or } 6,583 \text{ lb. per sq. in.}$$

The allowable vertical stress according to formula 9 is

$$s_v = \sqrt{16,000^2 - 6,583^2} = 14,583 \text{ lb. per sq. in.}$$

The section modulus of this beam, obtained from the table in *Properties of Sections*, is 58.9; then the load that may be safely carried by the beam is determined by substituting in formula 10. Thus,

$$W_s = \frac{8 \times 58.9 \times 14,583}{180} = 38,175 + \text{lb. Ans.}$$

The actual load on the beam is $350 \times 15 \times 4 = 21,000 \text{ lb.}$, which is less than the allowable load, and therefore the beam is sufficiently strong.

SPACING OF TIE-RODS

27. When an arch is placed between two beams, tie-rods should be supplied to resist its thrust. The conditions are shown in Fig. 30, in which $abcd$ represents a flat tile arch sprung between the I beams e and f . In this case the nominal depth of the arch is considered as 10 inches. The dotted line

dgc represents the theoretical line of pressure in the flat arch while gh may be considered as the theoretical rise, or as it is called, the *effective depth* of the arch. The point g may be




FIG. 30

taken as a center of moments, and the thrust of the arch to be resisted by the tie-rods may be represented by the force T . For a section 1 foot in width, the load on one-half of the arch is equal to $\frac{wL}{2}$ when w equals the load per square foot of

surface and L the span of the arch, in feet. The moment of the force T about the point g must equal the moment of the load about the same point; and as the lever arm r of the force T is in inches, the lever arm of the load must also be in inches in order to equate the expressions; hence, the lever arm of the load will be $\frac{12}{4}L$ and its moment $\frac{wL}{2} \times \frac{12}{4}L = \frac{3}{2}wL^2$.

The moment of the force T about the point g is Tr . Then, as these moments must be equal, $Tr = \frac{3}{2}wL^2$.

The strength of one rod is equal to its area A multiplied by its safe unit fiber stress, and this value divided by the resistance T required in 1 foot of length of beam will give the distance between rods. Hence, assuming the safe unit fiber stress to be 15,000 pounds, the spacing of the rods is obtained from the formula

$$x = \frac{A \times 15,000}{T} \quad (11)$$

From the formula $Tr = \frac{3}{2}wL^2$, the value of T is found

to be $\frac{3wL^2}{2r}$. Substituting this value for T in formula 11

gives $x = \frac{A \times 15,000}{\frac{3wL^2}{2r}}$, or $x = \frac{A \times 15,000 \times 2r}{3wL^2}$. By cancel-

ation the formula becomes

$$x = \frac{10,000 Ar}{wL^2} \quad (12)$$

In the formulas just given, the load w includes the weight of the arch as well as the load on it. Ordinarily, $\frac{3}{4}$ -inch tie-rods are used in floor construction; these should not be placed farther apart than 6 feet. In calculating the spacing of the rods the area should be taken at the root of the thread.

EXAMPLE.—In the example in Art. 26, what size rods will be required if they are placed 5 feet apart?

SOLUTION.—Transposing formula 12, $A = \frac{xwL^2}{10,000r}$; then substituting the values obtained from the example in Art. 26 in this formula gives

$$A = \frac{5 \times 350 \times 16}{10,000 \times 6} = .466 \text{ sq. in.}$$

A 1-in. rod, which has an area of .550 sq. in. at the root of the thread is the nearest commercial bar that can be used, for a $\frac{7}{8}$ -in. rod has an area at root of thread of only .420 sq. in. Ans.

28. The effective depth and nominal depth of flat tile arches, in inches, are given below:

Nominal depth . .	6.0	7.0	8.0	9.0	10.0	12.0
Effective depth . .	3.6	4.6	5.6	6.6	7.6	9.6

EXAMPLE.—What should be the greatest distance between tie-rods that resist the thrust of an 8-inch tile arch having a span of 4 feet? The diameter of the rods is $\frac{3}{4}$ inch, and the arch carries a load of 120 pounds per square foot.

SOLUTION.—The area of the rod at the root of the thread is found to be .302 sq. in., and the weight of the arch, including the filling, flooring, and ceiling is found to be 63 lb. per sq. ft.; therefore, the total load per square foot is $120 + 63 = 183$ lb. From the above table, the effective depth of the arch is found to be 5.6 in. Substituting these values in formula 10 gives

$$x = \frac{.302 \times 5.6 \times 10,000}{183 \times 4 \times 4} = 5.77, \text{ or } 5 \text{ ft. } 9 \text{ in. Ans.}$$

29. In designing a floor system for the support of fireproof arches of brick, it is advisable to provide tie-rods throughout the system. Though the beams supporting many portions of the floor will not be subjected to a material thrust, from the fact that adjacent arches react against each other, nevertheless, in actual construction it is often convenient to lay the arches in alternate panels, and the wooden centers are frequently removed from one panel to the adjacent one. Where a single arch is supported on two I beams, as shown in Fig. 31 (a), each beam is subjected to a lateral force equal to the thrust of the arch, and in proportioning such beams for the floor load, this lateral thrust should be considered in conjunction with the vertical load on the beam, in order to determine the ultimate unit stress.




FIG. 31

Considering the system of arch construction shown in Fig. 31 (b) from the center beam x outwards each way, it will be noticed that the arches a, a react on the beam x and their thrusts are balanced. Likewise, the thrust of the arches a and b are balanced on the beam x_1 , and in a similar manner b and c react against each other. The horizontal thrust of the arch c must be provided for in the beam x_3 , and sufficient transverse lateral resistance must be obtained either by the use of a larger beam, or tie-rods must be placed at frequent intervals. If tie-rods connect all the beams in the series, the effect is the same as though a continuous tie-rod extended from the beam x_3 to the beam x_6 , and the outward thrusts of the system due to the arches c and d are resisted by the series of tie-rods. If the tie-rods in the bay $y-y$

toward the center of the system are omitted for reasons of economy or design, the thrust of the arch a is resisted by the transverse strength of the three beams x_1 , x_2 , and x_3 . In large floor systems, however, if it is possible to construct all the arches at once, the tie-rods may be omitted in central portions of the system and provided only for the exterior beams and three or four adjacent panels.

30. It is interesting to observe the effect of the horizontal force on the bending moment in a beam supporting




FIG. 32

arches and tied to the adjacent beam by tie-rods. Such a beam is subjected to two bending moments—one vertical and the other horizontal. In each case the load is uniform and the bending moment may be represented by a parabola. Fig. 32 shows the conditions that exist, the parabola abc representing the bending moment due to the vertical load, and def , fgh , and hij the bending moments between tie-rods or support and tie-rod. The resultant bending moment is found as shown in Fig. 33, in which ab represents the

length of the beam and a the bending moment for one-half of the beam. The tie-rods are located at the points d and e , and a' shows the bending moment for one-half of the distance between the end support and the first tie-rod.

The bending moment at any point on the beam is equal to the resultant of the vertical and horizontal bending moments; hence the bending moment at g is represented by the resultant of gk and gi or the line hj . This is obtained by laying off gi at right angles to hg and equal to gi , and joining h and j . The divisions from x to b are made equal to those from a to x and the line hj is laid off at $j'h'$. Likewise, the bending moment at k is equal to the resultant of kl and km ,




FIG. 33

or ln , and this distance is laid off at $n'l'$. The bending moment at the succeeding points is found in a similar manner until the first tie-rod is reached. The horizontal thrust is counteracted at this point and hence no horizontal bending moment is produced. Therefore, the distance do is laid off at co' and the resultant bending moments at the remaining points are laid off as explained. A curve drawn through the points thus determined, as $b h' l' o' c'$, represents the resultant bending moment on one-half of the beam.

31. Some engineers consider only the live load in calculating the thrust of the arches against the interior beams, and assume that the sum of the stresses produced

by the full vertical loading and the lateral thrust, may be 20,000 pounds per square inch. The vertical load is usually allowed to produce a stress of 16,000 pounds per square inch; hence, the lateral force must not exceed 14,000 pounds per square inch. For the exterior beams, the thrust of the arch is obtained by considering the full live and dead load and the sum of the stresses should not exceed 18,000 pounds per square inch. Though this method would probably give safe results, the one previously explained is more conservative and is to be preferred.

EXAMPLE.—What size I beam is required to support a tile arch on one side for a distance of 20 feet, the conditions being as follows: The span of the arch is 5 feet; its nominal depth, 10 inches; and the weight, including filling, flooring, and ceiling, is 69 pounds per square foot; the live load is 150 pounds per square foot. The tie-rods are $\frac{3}{4}$ inch in diameter and the allowable unit fiber stress of the beam is assumed as 16,000 pounds.

SOLUTION.—The spacing of the rods is found by substituting the values in the formula $x = \frac{A \times r \times 10,000}{w L^2}$; thus, $x = \frac{.302 \times 7.6 \times 10,000}{219 \times 5 \times 5} = 4.19$ in.

The lateral thrust of the arch is determined from the formula $T = \frac{3 w L^2}{2 r}$. Substituting the values gives

$$T = \frac{3 \times 219 \times 5 \times 5}{2 \times 7.6} = 1,080.59, \text{ or, say, } 1,081 \text{ lb.}$$

Assuming a 10-in. 25-lb. beam, the values of b and I are found to be 4.66 and 6.89, respectively. Substituting these values in the formula $s_h = \frac{T b x^2}{2 I}$, gives $s_h = \frac{1,081 \times 4.66 \times 4.19 \times 4.19}{2 \times 6.89} = 6,418$ lb. per sq. in.

Hence, $s_v = \sqrt{16,000^2 - 6,418^2} = 14,656$ lb. per sq. in. Therefore, the safe vertical load is found by substituting in the formula $\frac{8 S s_v}{l}$;

thus, $W_s = \frac{8 \times 24.4 \times 14,656}{240} = 11,920$ lb. The actual load on the beam,

or W , is equal to $\frac{20 \times 5 \times 219}{2} = 10,950$ lb.; consequently, the beam assumed is the correct size. Ans.

EXAMPLES FOR PRACTICE

1. What size I beam, having a total fiber stress of 16,000 pounds per square inch, will be required to support a tile arch on one side over a distance of 18 feet? The nominal depth of the arch is 9 inches

and it has a span of 4 feet. The weight of the arch, including filling, flooring, and ceiling, is 65 pounds per square foot and the load to be supported by it is 135 pounds per square foot. The only lateral support is the usual tie-rods, in this case $\frac{3}{4}$ -inch rods, spaced according to formula.

Ans. 9-in. 21-lb. beam

2. The outside beam of a floor system supporting brick segmental arches is connected with the other beams by the usual $\frac{3}{4}$ -inch tie-rods, and it is to have a safe unit fiber stress of 16,000 pounds. The span of the arch is 4 feet, the rise or effective depth 6 inches, and its weight 130 pounds per square foot. The live load is 200 pounds per square foot and the span of the beam is 22 feet. What size I beam will be required?

Ans. 12-in. 31 $\frac{1}{2}$ -lb. I beam

BEARING PLATES

32. Beams resting on masonry walls or piers will usually require bearing plates to distribute the load over an area such that the safe bearing value of the masonry will not be exceeded. These bearing plates are usually of steel or cast iron, though stone templets are sometimes used. The method of computing the size required is explained in *Statics of Masonry*, Part 1.

Table IV gives the bearing value, in pounds, for plates of various sizes bearing on the different kinds of masonry. As the thickness of the plate is not stated, it must be computed for each case. It depends on the allowable load and unit stress and the width of the beam or channel resting on it, and may be determined by the following formula:

$$t = .866 (l - b) \sqrt{\frac{R}{s_a b' l}} \quad (13)$$

in which t = thickness of plate, in inches;

l = length of plate perpendicular to axis of beam, in inches;

b = width of flange of beam or channel, in inches;

R = reaction at point of support, in pounds;

b' = width of plate, in inches, in direction of axis of beam or channel;

s_a = allowable stress, in pounds per square inch, on extreme fiber of plate.

TABLE IV
BEARING PLATES FOR I BEAMS AND CHANNELS

Bearing on Wall Inches	Size of Plate Inches	Safe Bearing Value of Plates, in Pounds				
		Ordinary Stone Masonry	Good Stone Masonry	Brick in Lime Mortar	Brick in Rosendale Cement Mortar	Brick in Portland Cement Mortar
4	4 × 4	2,880	4,800	1,600	2,400	3,200
4	4 × 6	4,320	7,200	2,400	3,600	4,800
4	4 × 8	5,760	9,600	3,200	4,800	6,400
6	6 × 6	6,480	10,800	3,600	5,400	7,200
6	6 × 8	8,640	14,400	4,800	7,200	9,600
6	6 × 10	10,800	18,000	6,000	9,000	12,000
8	8 × 8	11,520	19,200	6,400	9,600	12,800
8	8 × 10	14,400	24,000	8,000	12,000	16,000
8	8 × 12	17,280	28,800	9,600	14,400	19,200
10	10 × 10	18,000	30,000	10,000	15,000	20,000
10	10 × 12	21,600	36,000	12,000	18,000	24,000
10	10 × 14	25,200	42,000	14,000	21,000	28,000
12	12 × 12	25,920	43,200	14,400	21,600	28,800
12	12 × 14	30,240	50,400	16,800	25,200	33,600
12	12 × 16	34,560	57,600	19,200	28,800	38,400
12	12 × 18	38,880	64,800	21,600	32,400	43,200
14	14 × 14	35,280	58,800	19,600	29,400	39,200
14	14 × 16	40,320	67,200	22,400	33,600	44,800
14	14 × 18	45,360	75,600	25,200	37,800	50,400
14	14 × 20	50,400	84,000	28,000	42,000	56,000
16	16 × 16	46,080	76,800	25,600	38,400	51,200
16	16 × 18	51,840	86,400	28,800	43,200	57,600
16	16 × 20	57,600	96,000	32,000	48,000	64,000
16	16 × 22	63,360	105,600	35,200	52,800	70,400
18	18 × 18	58,320	97,200	32,400	48,600	64,800
18	18 × 20	64,800	108,000	36,000	54,000	72,000
18	18 × 22	71,280	118,800	39,600	59,400	79,200
18	18 × 24	77,760	129,600	43,200	64,800	86,400
20	20 × 20	72,000	120,000	40,000	60,000	80,000
20	20 × 22	79,200	132,000	44,000	66,000	88,000
20	20 × 24	86,000	144,000	48,000	72,000	96,000
20	20 × 26	93,600	156,000	52,000	78,000	104,000

If the allowable unit stress in the extreme fiber for steel is considered as 16,000 pounds, the formula may be written:

$$t = .00685(l - b)\sqrt{\frac{R}{b'l}} \quad (14)$$

EXAMPLE.—What size steel bearing plate is required in a brick wall laid in lime mortar, to support the end of a 12-inch 31.5-pound standard I beam having a flange width of 5 inches, which carries a uniformly distributed load of 600 pounds per lineal foot over a span of 25 feet? The allowable unit stress in the extreme fiber of the plate may be considered as 16,000 pounds.

SOLUTION.—The bearing value required is equal to the reaction, or $\frac{16,000}{2} = 7,500$ lb. From Table IV, it is seen that an 8" \times 10" plate will give the required bearing value for a plate on brickwork laid in lime mortar. Substituting the values in the formula $t = .00685(l - b)\sqrt{\frac{R}{b'l}}$ gives

$$t = .00685(10 - 5)\sqrt{\frac{7,500}{8 \times 10}} = .332 \text{ in.}$$

The nearest size above this is $\frac{3}{8}$ in.; hence, an 8" \times 10" \times $\frac{3}{8}$ " bearing plate will be required. Ans.

EXAMPLES FOR PRACTICE

1. An 18-inch 65-pound I beam having a flange width of 6.18 inches supports a uniformly distributed load of 1,000 pounds per lineal foot. The span of the beam is 32 feet and its ends rest on piers built of ordinary stone masonry. Provided that the allowable unit stress in the extreme fiber of the plate is 16,000 pounds, what size bearing plate will be required?

Ans. $\left\{ \begin{array}{l} .515 \text{ in. thick} \\ 8'' \times 12'' \times \frac{9}{16}'' \text{ plate} \end{array} \right.$

2. A steel lintel composed of two 15-inch 35-pound channels placed flange edge to flange edge supports the wall above and also a floor load, the combined weight amounting to 4,000 pounds per lineal foot. The span is 15 feet, and the over-all width of flange is 8 inches. Assuming an allowable unit stress of 16,000 pounds in the extreme fiber of the plate, what size bearing plate will be required to support the end of the lintel on a brick wall laid in Portland cement mortar?

Ans. 12" \times 14" \times $\frac{9}{16}$ " plate

REENFORCED CONCRETE BEAMS

33. Adaptability.—Reenforced concrete in building construction is beginning to occupy an important place in fireproof and slow-burning mill construction. Concrete is one of the best fire retardants known and is very strong under compression, but when subjected to a tensile stress it is weak and soon cracks and fails. For this reason it is necessary to reenforce it with some material that is strong under tension, such as steel or iron.

The reliability of reenforced concrete depends, to a great extent, on the workmanship; that is, reenforced concrete constructed under thorough and conscientious supervision will be as safe as any other form of construction, while if the work is carelessly executed there is a liability of its failing when least expected.

The increase in weight may sometimes be advanced as an argument against this construction. However, when the saving in cost over other methods of fireproof construction is considered, the additional weight is a question of little importance. That this work can be erected with considerable speed has been demonstrated in several building operations of magnitude. In the instance of a building 50 feet wide by 160 feet long, having a basement and four stories, the concrete construction of the entire building was completed in 12 weeks, the plastering was finished in 1 month, and the entire structure was completed in $4\frac{1}{2}$ months, which was 34 days before the time of completion stated in the contract. As the concrete work included the laying of about 35,000 square feet of floor and roof, in addition to the columns, girders, etc., the progress was remarkable.

34. Durability.—That reenforced concrete will develop fire-resisting qualities has been proved by numerous tests and by its behavior in conflagrations of considerable magnitude. A test was made on reenforced concrete composed of one part of Portland cement, three parts of gravel, and five parts of trap rock, in which the average temperature was

about 1,800°; when it was further subjected to the severe condition of rapid cooling by water from a hose under a pressure of about 65 pounds it revealed: First, no separation between the reinforced concrete girders and the concrete




FIG. 34

slab; second, no spalling of the exposed surfaces of the floor system; third, only slight, superficial cracks in the under surface of the concrete composing the system; fourth, a fair condition of the reinforced concrete columns, though

shearing breaks and cracks were observed and one of the columns was buckled about $\frac{5}{8}$ inch. This test was made under a load of 150 pounds per square foot, which was afterwards increased.

It was further proved by the Baltimore fire of 1904 that reinforced concrete can at least partially withstand the severe destructive effects of a great fire. A survey of the United States Fidelity and Guaranty building of that city, which was composed of floor systems carried by reinforced concrete columns and girders, showed that though the cast-iron front and the brick party wall of the building had been destroyed, the concrete floor systems and their supporting columns remained in place. Fig. 34 shows the condition of the building several weeks after the fire, some of the party wall having been removed. When in this condition, the floors of the building were tested without failure, the load-being 400 pounds per square foot. Even the overhanging portion *a* sustained a load of 200 pounds per square foot without damage. The reinforced concrete of which the structural members of this building were constructed, was composed of crushed granite, sand, and American Portland cement. Most of the plaster in the building had fallen from the concrete, thus making it evident that the former afforded no adequate protection.

35. Rigidity of Reinforced Concrete Construction. As there are no joints, such as the column and girder connections, used in structural steel work, which sometimes prove inefficient, the structure is practically a monolith and is, consequently, extremely rigid. This construction is particularly desirable for buildings that contain looms, presses, rotary mills, etc., or any machinery liable to run in unison and produce considerable vibration, in buildings as ordinarily constructed.

36. Comparison of the Cost.—An investigation of the cost per square foot of area of reinforced concrete when compared with other recognized types of good construction, such as slow-burning and steel-frame construction, shows


that it occupies a middle position between the two. as may be observed from the following tabulation:

Slow-burning construction	\$1.07
Reenforced concrete	1.45
Steel floor and roof, fireproofed	1.85

As a fireproof construction, the reenforced concrete is cheaper than the steel frame fireproofed with terra cotta, and is cheap enough to be used in mills and factories.

37. Details of Reenforced Concrete Construction. In Fig. 35 (*a*) is shown a system of reenforced concrete construction that corresponds to the usual framed construction executed in wood. The longitudinal girder is made a few inches deeper than the cross-girders to permit the bottom rods in the latter to rest on top of those in the longitudinal girder. By this means a direct bearing is secured and the straining of the concrete is avoided. Wooden planks are bolted to the concrete beams, to which the sleepers supporting the shafting may be secured. The columns are reenforced by rods placed in each corner and braced by horizontal bars. In view (*b*) is shown the method of anchoring concrete beams to the wall. The mason builds a dove-tailed pocket in the brick wall into which the concrete is poured at the same time that the beam is formed. All girders should rest on cast- or wrought-iron bearing plates placed in the wall. An isometric view of the steel reenforcement is shown in Fig. 35 (*c*).

A type of reenforced concrete construction very similar to the one just described is illustrated in Fig. 36. View (*a*) shows an elevation, partly in section, of the reenforced concrete girder, while (*b*) represents an enlarged cross-section taken on the line *cd*. In this case, the reenforcement is composed of the plain round steel rods *a*, part of which are straight and part bent, as shown in (*a*), these rods being held in place by a number of **U** bars or stirrups *b* of hoop steel. A comparison between a steel girder and the reenforced concrete girder may be made by referring to Fig. 37. The lower flange of the steel girder is replaced by the rods;



the upper flange, by the concrete floor slab; and the web, by the U bars and the concrete rib.

Experience has proved that concrete ribs that are reinforced with a large percentage of metal, as is generally the case, show the first signs of failure near the supports. Diagonal cracks appear, caused by the combined tensile and




FIG 36

shearing stresses. In order to resist this tendency to fail, some of the rods are bent up similar to the construction of a cambered beam, as shown in Fig. 36, the inclined portion of the bent rods resisting the stress that produces the diagonal cracks. The U bars hold the rods in position and prevent




FIG 37

their breaking out of the concrete; they are usually placed closer together near the supports, as the shearing stresses are maximum in that portion of the beam.

Concrete girders are seldom constructed with the ends free, but are generally connected in a monolithic manner

with other girders, making them continuous and, consequently, much stronger than girders freely supported at the ends. The deflection is also considerably less than in girders with free ends.

Fig. 38 shows a perspective view of the longitudinal section of a reinforced, or armored concrete, girder. A connection between the reinforcing material in a continuous girder and a column is shown in Fig. 39 (*a*). The column is composed of four rods braced at intervals by pieces of sheet metal, as shown in (*b*). If a stronger column is required, more rods are used, as shown in Fig. 40, where they are tied

together by wires at intervals of not more than the diameter or least side of the column. The rods are placed near the surface of the column in order to give the largest radius




FIG. 38




FIG. 39

of gyration and to resist the tensile stresses produced by eccentric loading, wind pressure, pull of beltings, etc.

38. Size of Girders.—The economical depth of reinforced concrete girders is practically the same as the depth

of steel girders having the same carrying capacity. As a rule, the depth should not exceed one-twentieth of the span.

The following tabulation shows the widths of concrete beams that correspond to steel beams of the same strength:

- 6 inches for girders corresponding to 12-inch I beams.
- 8 inches for girders corresponding to from 12-inch to 18-inch beams.
- 10 inches for girders corresponding to from 20-inch to 24-inch beams.
- 12 inches for girders corresponding to riveted girders from 30 to 40 inches in height.

From 12 to 24 inches for girders corresponding to very heavy box girders.




FIG. 40

JOHNSON'S METHOD OF CALCULATION

39. The strength that the reinforcing bars are required to furnish may be determined by the following method:

When the steel bar is rigidly attached to the concrete its distortion is the same as that of the concrete in the same horizontal plane. But the stresses, or the resistances of the materials to distortion, vary as their

rigidities, or as their moduli of elasticity. The modulus of elasticity of steel is usually taken at about 28,000,000, but that of concrete varies with the quality of the material, and in this discussion will be considered as 1,000,000. Hence, if the steel is twenty-eight times as rigid as concrete, it resists twenty-eight times as much as the same area of concrete for equal distortions; and in making the calculations for the strength of a concrete beam, the area of the steel bars may be replaced by an area of concrete twenty-eight times as

great, provided that it is placed in the same horizontal plane as the bars. Thus, in Fig. 41 (b) the area of the bars shown in (a) has been replaced by concrete of an area twenty-eight




FIG. 41

times the combined area of the bars. Considering this new section, the strength of the beam to resist the tension in the concrete is determined from the equation

$$M_r = \frac{s_c I}{c_1} \quad (15)$$

in which s_c = ultimate unit tensile strength of concrete;

I = moment of inertia of transformed cross-section;

c_1 = distance from neutral axis to tension side;

M_r = moment of resistance of actual beam.

If the reinforcement were not used, the equation would be $M = \frac{s_c b d^3}{6} \left(\text{since } \frac{I}{c_1} = \text{section modulus, or } \frac{b d^2}{6} \right)$. In

this formula s_o represents the stress on the outer portion of the beam if no steel bars are used; then, $s_o = \frac{6M}{bd^2}$.

The tensile stress in the concrete at the bottom of the beam may be determined from the formula $s_t = \frac{Mc_1}{I}$; but the moment of inertia for the transformed section is

$$I = bd \left(\frac{d^2}{12} + \frac{e^2}{1+m} \right) \quad (16)$$

in which e = distance from center of beam to center of steel bars;

$$m = \text{a value used for convenience} = \frac{bd}{A} \times \frac{E_c}{E_s}$$

(A = area of steel bars; E_c = modulus of elasticity of concrete; E_s = modulus of elasticity of steel.)

Also, $c_1 = \frac{d}{2} - f$; but $f = \frac{e}{m+1}$, and, therefore, $c_1 = \frac{d}{2} - \frac{e}{m+1}$. Substituting these values in the original formula gives

$$s_t = s_o \left(\frac{1+m - 2\frac{e}{d}}{1+m + 12\frac{e^2}{d^2}} \right) \quad (17)$$

The formula for the compressive stress in the concrete at the top is

$$s_c = s_o \left(\frac{1+m + 2\frac{e}{d}}{1+m + 12\frac{e^2}{d^2}} \right) \quad (18)$$

The steel bars are assumed to stretch the same as the concrete adjacent to them, and for any distance c from the center of the beam, the total stress on the steel bars is

$$- \frac{2s_o e b}{1+m + 12\frac{e^2}{d^2}} \quad (19)$$

40. The following example will make clear the application of the above formulas:

EXAMPLE.—A concrete beam in a metal and concrete factory building has a span of 14 feet and is to be 15 inches in width and 24 inches in depth. Ten $\frac{1}{2}$ " \times 1" bars are embedded in the bottom, the center of the bars being 2 inches from the edge of the beam, and a load of 1,000 pounds per lineal foot is to be supported. Taking the safe unit compressive stress of the concrete at 250 pounds, the safe tensile stress at 100 pounds per square inch, and the unit stress of the steel that may be developed before the concrete fails at 3,000 pounds, determine whether the beam has sufficient strength to carry its load.

SOLUTION.—The greatest bending moment $M = \frac{WL}{8} = \frac{1,000 \times 14 \times 14}{8}$
 $= 24,500 \text{ ft.-lb.} = 294,000 \text{ in.-lb.}; s_o = \frac{6M}{bd^2} = \frac{6 \times 294,000}{15 \times 24 \times 24} = 204\frac{1}{8} \text{ lb.}$
 per sq. in.; $m = \frac{bd}{A} \times \frac{E_c}{E_s}$, and when $\frac{E_c}{E_s}$ is taken as $\frac{1}{28}$, $m = \frac{15 \times 24}{10 \times 1 \times \frac{1}{2}} \times \frac{1}{28} = 2.57$.

Substituting these values in the formula $s_r = s_o \left(\frac{1 + m - 2 \frac{e}{d}}{1 + m + 12 \frac{e^2}{d^2}} \right)$
 gives $s_r = 204\frac{1}{8} \left(\frac{1 + 2.57 - \left(2 \times \frac{10}{24} \right)}{1 + 2.57 + \left(12 \times \frac{10^2}{24^2} \right)} \right) = 98 \text{ lb. per sq. in.}$ Also,
 $s_c = 204\frac{1}{8} \left(\frac{1 + 2.57 + \left(2 \times \frac{10}{24} \right)}{1 + 2.57 + \left(12 \times \frac{10^2}{24^2} \right)} \right) = 159 \text{ lb. per sq. in.}$

The total stress on the steel bars is equal to $\frac{2 \times 204\frac{1}{8} \times 10 \times 15}{1 + 2.57 + \left(12 \times \frac{10^2}{24^2} \right)}$
 $= 10,841 \text{ lb.}$ The unit stress on the steel will then equal the result just obtained divided by the entire sectional area of the reenforcing metal. There being ten bars $\frac{1}{2}$ inch by 1 inch the area of reenforcing metal equals 5 and the unit stress is $10,841 \div 5 = 2,168 \text{ lb.}$ As these values are all within the safe limit, the beam is considered as having sufficient strength to support its load. **Ans.**

RANSOME SYSTEM

41. In the Ransome system of reenforced concrete construction, the square steel bars have been twisted cold, by being gripped at the ends, until the angle made by the edge with the axis of the bar is about 20° . This makes the

bar like a long screw and the mortar of the concrete embeds itself in the concave whorls; in order to remove the bar an area of concrete must be sheared off equal to the superficial area of the cylinder enclosing the bar. The bar is held rigidly throughout its entire length, so that it cannot draw out or become loosened from the concrete when the load is applied to the beam. The bond may be considered as prac-




FIG. 42

tically perfect, and the composite beam can be figured accurately by assuming that the steel resists the tensile stress while the concrete takes care of the compression. A formula in common use, and one that is sufficiently accurate for practical work, is obtained by equating the external force, or the bending moment on the beam, with the resistance that the bars offer.

The point about which the bars tend to revolve is considered as the center of gravity of the section of concrete supplying the resistance to compression; this section is assumed to be the upper third of the concrete beam, or $abcd$, in Fig. 42. Disregarding the distance from the bars to the lower edge of the beam, which is only 2 or 3 inches, and considering the center line of the bars as the lower line of the beam section, their lever arm about the point x is $\frac{5}{6}d$. Then, if $s_a A$ represents the strength of all the steel bars, the equation is

$$\frac{Wl}{8} = s_a A \times \frac{5d}{6} \quad s_a A = \frac{Wl}{8} \times \frac{6}{5d} = \frac{Wl}{6\frac{2}{3}d}$$

or
$$A = \frac{Wl}{6\frac{2}{3}d s_a} \quad (20)$$

in which s_a = safe unit fiber stress of bars;

A = area of steel bars, in square inches;

W = uniformly distributed load on beam;

l = span of beam, in inches;

d = depth of beam, in inches.

It is claimed that cold twisting of mild steel increases the tensile strength and raises the elastic limit from 10 to 15 per cent.; therefore, it will do no harm to increase the denominator 5 per cent., changing $6\frac{1}{2}$ to 7. This gives the formula

$$A = \frac{Wl}{7ds_s} \quad (21)$$

HENNEBIQUE SYSTEM

42. A formula used by M. Hennebique for determining the area of the reenforcing material is based on the assumption that the resistance to compression in the concrete takes care of one-half the bending moment on the beam while the other half is resisted by the tension in the steel. The concrete is not considered as offering any resistance to the tension in the beam. This engineer assumes that the neutral axis is at a distance of two-thirds of the depth of the beam from the top, or at ad , Fig. 43, and that the portion $abcd$, acting about the axis ad , provides the resistance to compression. This resistance is assumed to be concentrated at the point x located at a distance of one-fourth ab or one-sixth d from this axis. The resistance to tension, supplied by the steel bars, is assumed to act about the same axis and therefore its lever arm is de . Considering d as the depth and b the width of the beam, and taking 350 pounds per square inch as the compressive stress in the concrete, the equation that represents the resistance of the beam to compression is




FIG. 43

$$\frac{2}{3} b d \times 350 \times \frac{d}{6}$$

or

$$\frac{350}{9} b d^2 = \frac{M}{2} \quad (22)$$

When A equals the area of steel required and the unit tensile stress is taken at 14,000 pounds, the following equation expresses the resistance to tension: $14,000 A \times \frac{d}{3} = \frac{M}{2}$ or

$$A = \frac{3 M}{28,000 d} \quad (23)$$

In this formula, the distance from the center of the bar to the lower line of the beam is disregarded and the lever arm is considered as $\frac{d}{3}$.

It can be seen that the assumptions made by Hennebic are not entirely correct, but the results obtained from the reasoning would probably be sufficiently accurate.

METHOD USED IN COMMON PRACTICE

43. A method of determining the strength of reinforced concrete beams is based on the assumption that, within the elastic limit, the stresses vary uniformly across the section. The strength of a rectangular beam with reinforcement in the bottom only and with the reinforcing bars supplying all the tension, is expressed by the following formula:

$$M = \frac{1}{3} s_c c^2 b + s_s A c_1 \quad (24)$$

in which M = bending moment, in inch-pounds:

c = distance from neutral axis to most remote fiber in compression;

s_c = unit compressive stress on concrete;

b = width of beam;

s_s = unit tensile stress on steel;

A = area of steel in square inches;

c_1 = distance from neutral axis to center of action of steel.

The explanation of this formula is clear when reference is made to Fig. 44, in which the shaded portion represents the section over which the unit compressive stress is assumed to be distributed. The greatest compressive stress occurs in the fibers along the line mn , and the compression will

decrease as the fibers approach the neutral axis, so that at this location the stress is zero. In the formula, however, the stress per unit of area is assumed to be uniform, but the result obtained by gradually decreasing the area instead of the unit stress is practically the same, and, therefore, the portion mnr may be considered as the area resisting the compression. Its center of gravity is the point x , located at a distance of $\frac{2c}{3}$ from the

neutral axis; therefore, when the unit compressive stress is designated by s_c , the resisting moment of this portion of the beam is $\frac{1}{2}cb \times \frac{2c}{3} \times s_c$.

$= \frac{1}{3}s_c c^2 b$. The area of the steel bars is represented by A , and the unit tensile stress

by s_s ; then their resisting moment is $s_s A c_s$. These two values are together equal to the entire bending moment, which is expressed by the equation above.

It is evident from the formula that, before the solution can be accomplished, it is necessary to locate the neutral axis of the reinforced beam. This location is determined by means of a formula derived from what is known as the *elastic theory of beams*, which is based on the assumption that the ratio of the strain on the concrete to the distance c , in Fig. 45, is the same as the ratio of the strain on the steel

to the distance c_s . Equating these ratios gives $\frac{s_c}{E_c c} = \frac{s_s}{E_s c_s}$.

By transposition, $s_s = \frac{E_s c_s s_c}{E_c c}$. The Philadelphia Bureau of

Building Inspection has adopted 20 as the ratio of the modulus of elasticity of steel to that of concrete and this value will be used in the evolution of the formula for determining the location of the neutral axis. The formula is also




FIG. 44

based on the assumption that the reinforcing bars are at a distance from the top equal to five-sixths of the depth of the beam. Substituting 20 for $\frac{E_s}{E_c}$ in the equation gives

$s_s = 20 s_c \frac{c_1}{c}$. The compressive stress in the concrete must

equal the tensile stress in the steel. In Fig. 45, assume that ac represents the ultimate unit compressive stress s_c on the




FIG. 45

concrete. As the unit stress gradually decreases until it is zero at the neutral axis, it is evident that the average, or mean unit, stress will be equal to $\frac{1}{2} ac$, or $\frac{s_c}{2}$. Then the

stress on the entire section resisting the compression is $\frac{s_c}{2} \times b \times c$, b representing the width of the beam; the tensile stress on the concrete is $s_s \times A$. Therefore, $\frac{s_c b c}{2} = s_s A$,

but $s_s = 20 s_c \frac{c_1}{c}$; substituting this value, the equation becomes

$\frac{s_c b c}{2} = 20 A s_c \frac{c_1}{c}$. s_c cancels out, and c_1 , from the condition

of the problem, is known to be equal to $\frac{5d}{6} - c$. Substituting

this value gives $\frac{bc^2}{2} = 20A\left(\frac{5d}{6} - c\right)$, and from this equation the following formula is derived:

$$\frac{c}{d} = \frac{20A}{bd}\left(-1 + \sqrt{1 + \frac{bd}{12A}}\right) \quad (25)$$

In this formula d equals the depth of the beam, the other values being the same as before. In designing reinforced concrete beams by the system of calculation stipulated in these formulas, unit working values as high as 500 and 16,000 pounds, respectively, may be used for the concrete and steel.

THE KAHN SYSTEM OF REINFORCED CONCRETE

44. The Kahn system of reinforced concrete construction is illustrated in Fig. 46, which shows the shape of the reinforcing metal for the beams and columns. This system




FIG. 46

is based on the assumption that all the tensile stresses should be resisted by the steel reinforcement, which is constructed on the principle of a Pratt trussed beam. For instance, in

Fig. 47, which represents a Pratt truss, the diagonal members and the lower chord are in tension while the vertical members and the upper chord are in compression. The Kahn standard bar is shown in section in Fig. 48. It consists of a central rib c with a web d on either side and may be so formed as to correspond to the lower chord and oblique members of a Pratt truss. This is done by shearing the webs d along the rib c for a certain distance and bending them into the positions indicated at a, a in Fig. 46. It is evident that a bar bent up as described cannot possibly slip through the concrete and, therefore, it must resist all of the tension produced in the beam, provided that the concrete is so proportioned that it will not fail. When a load is applied on top of the beam, the concrete throughout the whole length of the beam tends to arch itself, the steel bar in the bottom acting as a




FIG. 47




FIG. 48

tie. In addition to this, a series of concentric arches, gradually decreasing in length, may be supposed to be produced. For instance, one arch will extend from the prongs e to the corresponding prongs at the other end of the beam, which are not shown in the illustration; another arch from the prongs f to prongs similarly placed at the other end, and so forth, the arches gradually decreasing in size until the central arch at c is reached. In each of these arches the prongs receive the weight and carry it upwards, distributing it on the other arches of larger span, which are tied together by the horizontal tension bar. It is evident then that, theoretically, the tension bar is subjected to a stress equal to the horizontal component of the stresses in the oblique members, and it would be strong enough to resist this stress, if it were placed on the outside of the concrete. However, it is more advisable to embed the steel in the concrete

to prevent rusting and secure a fireproof construction. When a beam composed of good materials and properly proportioned is tested to destruction, either the concrete crushes at the top or the steel bar pulls in two; as the resistance to compression in the top of the concrete beam is largely supplied by the floor itself, it is usually impossible for the beam to fail in compression. It is evident, therefore, that a large amount of steel can be placed in the bottom of the beam to balance the compression.

45. Formulas.—The formulas and values used in the calculations made by the company manufacturing the Kahn system of reenforced concrete are given below:

E_s = modulus of elasticity of steel, or 30,000,000;

E_c = modulus of elasticity of concrete, or 2,000,000;

s_s = ultimate unit tensile strength of steel, or 64,000;

s_c = ultimate unit tensile strength of concrete, or 200;

s_c = ultimate unit compressive strength of concrete,
or 3,000;

A = area of metal.

The values for b , d , x , and y are shown in Fig. 49, which shows the bar in section with part of the web bent up to form a pair of prongs. The location of the neutral axis is determined by the formula

$$y = \frac{15A + bd^2}{30A + 2bd} \quad (26)$$




FIG. 49

When the tensile strength of the concrete is taken into consideration, the moment of resistance is

$$M_r = \left(\frac{1}{2}x + y\right) A s_s + \frac{s_c b y^2}{3} \quad (27)$$

If the concrete is disregarded in calculating the resistance to tension, the formula for the resisting moment is

$$M_r = \left(\frac{1}{2}x + y\right) A s_s \quad (28)$$

The value of b should never be less than $\frac{A s_s}{1,800 x}$. A

factor of safety of 4 or 5 should be used in determining the strength of reenforced concrete. The values used in these calculations are somewhat higher than those given in *Beams and Girders*, Part 1.

46. Safe Loads.—Table V gives the safe uniformly distributed loads for concrete beams reenforced with Kahn trussed bars.

Fig. 50 shows a section of the ordinary beam, and in Case I of Table V the bars are $\frac{1}{2}$ inch by $1\frac{1}{2}$ inches, the area being .76 square inch and the weight per lineal foot 2.8 pounds; the length of the diagonals, shown at d , Fig. 46, is 6 inches, and b equals 8 inches. The batter of the sides of the beam




FIG. 50

should not be less than 1 inch in 6 inches for beams up to 12 inches in depth, but above that depth the sides may be made vertical.

In Case II, $b = 10$ inches; the size of the bars is $\frac{3}{4}$ inch by $2\frac{3}{8}$ inches; their area and weight per lineal foot are 1.56 square inches and 5.4 pounds, respectively, and the length of the diagonals is 12 inches. $1'' \times 3''$ bars are used in Case III, the area being 2.84 square inches, and the weight per lineal foot 9.6 pounds. The length of the diagonals is 12 inches for beams under 24 inches in depth and 18 inches for those over this depth, and b equals 12 inches.

In Case IV, $b = 14$ inches, the bars are $1\frac{1}{4}$ inches by $3\frac{3}{4}$ inches, weighing 13.8 pounds per square foot and having an area of 4 square inches. The length of the diagonals is 18 feet. In Cases III and IV, the beams should have a batter of 1 to 6 up to a depth of 16 inches, but for a greater depth they may have vertical sides. The loads given in the table were figured for a fiber stress in the steel of 16,000 pounds per square inch. If the beams are continuous across two or more supports, having inverted reenforcing bars built in as required, the safe loads may be increased by $\frac{1}{4}$.

47. Bars.—Fig. 51 shows the bars kept in stock and having standard cuts; these may be obtained in any length.

Fig. 52 illustrates the method of placing the reenforcing bars for the different conditions of loading and support. At (a) is shown a cantilever having a concentrated load at the end, and as the tension is at the upper side of the beam, the bars are placed at the top with the diagonals pointing downwards. Under these conditions the safe load will be one-eighth of that given in the table. (b) shows a cantilever supporting a uniform load; in this case the safe load is




FIG. 51

one-fourth of that given in the table. As the load in (c) is concentrated at the center, the safe load will be one-half of that given in the table, while under the conditions shown in (d), it will be the same as stated. At (e) is shown a continuous beam uniformly loaded and supported at three points, and as there will be tension in the upper part of the beam over the central support, an inverted bar is placed at this point; the safe load under these conditions is the

TABLE V
SAFE UNIFORMLY DISTRIBUTED LOAD, IN HUNDREDS OF POUNDS

Depth Inches	Distance Between Supports, in Feet																								
	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30		
Case I	6	40	35	31	29	27	25	23	21	20	19	18	17	16											
	8	56	50	45	41	38	35	32	30	28	27	25	24	23	21	20									
	10	74	66	59	53	49	45	42	40	37	35	33	31	30	28	27	26	25	24	23					
	12	93	82	74	67	62	57	53	50	46	44	41	39	37	35	34	32	31	30	28	27				
	14	110	98	88	80	73	68	63	59	55	52	49	46	44	42	40	38	37	35	34	33	31			
	16	123	110	98	89	82	75	70	65	61	58	55	52	49	47	45	43	41	39	38	36	35	34		
	18	136	122	110	100	92	85	79	73	69	65	61	58	55	52	50	48	46	44	42	41	39	38	37	
	20	154	137	123	113	102	95	88	82	77	72	68	65	61	58	56	54	51	49	47	46	44	42	41	
	Case II	8	110	96	86	80	73	68	63	59	55	52	49	46	44	42	40	38	37	35	34	33	31		
		10	147	130	117	106	98	90	84	78	73	69	65	62	59	56	53	51	49	47	45	43	42	40	
12		190	169	152	138	127	117	108	101	95	90	85	80	76	72	69	66	63	61	58	56	54	52		
14		210	188	169	154	141	130	121	113	106	99	94	89	85	81	77	74	71	68	65	63	60	58		
16		248	220	198	180	165	152	142	132	124	117	110	104	99	94	90	86	82	79	76	73	71	68		
18		280	249	224	203	186	172	160	149	140	132	124	118	112	107	102	97	93	90	86	83	80	77		
20		314	279	251	228	209	193	179	168	157	148	139	132	125	120	114	109	105	100	97	93	90	87		
22		347	309	278	252	232	214	198	185	174	163	154	146	139	132	126	121	116	111	107	103	99	96		
24																								93	
26																									93

Case III									
10	244	217	195	177	163	150	140	130	122
12	328	290	261	237	218	200	186	174	163
14	394	350	315	286	263	242	225	210	197
16	448	400	358	326	298	276	256	239	224
18	508	452	406	369	338	312	290	270	254
20	568	504	453	412	378	348	324	302	283
22	634	564	507	461	423	390	362	338	317
24	680	605	544	495	455	418	388	362	340
12	452	402	361	328	300	277	258	240	226
14	540	480	432	392	360	332	308	288	270
16	625	555	499	45	4	6	382	357	333
18	707	630	566	5	472	435	405	377	352
20	788	700	630	57	525	485	450	420	394
22	867	770	694	630	577	535	495	462	434
24	960	854	768	700	640	590	550	512	480
26	1,040	925	832	757	695	640	595	555	520
28	1,125	1,000	900	820	750	692	642	600	563
30	1,210	1,075	968	878	805	744	680	645	605
Case IV									
10	244	217	195	177	163	150	140	130	122
12	328	290	261	237	218	200	186	174	163
14	394	350	315	286	263	242	225	210	197
16	448	400	358	326	298	276	256	239	224
18	508	452	406	369	338	312	290	270	254
20	568	504	453	412	378	348	324	302	283
22	634	564	507	461	423	390	362	338	317
24	680	605	544	495	455	418	388	362	340
12	452	402	361	328	300	277	258	240	226
14	540	480	432	392	360	332	308	288	270
16	625	555	499	45	4	6	382	357	333
18	707	630	566	5	472	435	405	377	352
20	788	700	630	57	525	485	450	420	394
22	867	770	694	630	577	535	495	462	434
24	960	854	768	700	640	590	550	512	480
26	1,040	925	832	757	695	640	595	555	520
28	1,125	1,000	900	820	750	692	642	600	563
30	1,210	1,075	968	878	805	744	680	645	605

same as that given in the table. View (f) shows a continuous beam supported at four points, that is, carried across two supports, and in this case the safe load is equal to one and one-fourth times that given in the table.




FIG. 52

THE UNIT CONCRETE STEEL REINFORCEMENT

48. The most modern type of reinforced concrete construction is illustrated in Fig. 53. This construction is known as the **unit system**, and takes its name from the fact that all the metal necessary for the actual reinforcement of the concrete girder is in one piece, differing in this respect from other reinforced concrete systems. The steel reinforcement of the unit-girder frame is made from a roll section consisting of four round bars connected with a tie

web, as shown in Fig. 53 (*b*). For a considerable distance from each end, the web is sheared through the section at *a a* and the round bars with the attached portion of web are bent up in a similar form to a trussed girder, as shown at *b, b*, Fig. 53 (*a*). The web remaining on the two central bars of the four-bulbed rolled section is punched and bent downwards, as shown at *c, c*, while the web between the two inside bars of the rolled section is punched out at intervals with slotted holes, as at *d, d*. The purpose of these slotted holes is best understood by referring to Fig. 54.

In Fig. 54 (*a*) a sectional elevation of a unit-girder frame is shown, while cross-sections through the girder are shown at (*d*) and (*c*). From these three views it will be seen that especially designed bolts are placed through the slotted holes punched in the central web of the rolled section.

These bolts consist of an annealed cast-steel socket *b*,




FIG. 53





FIG. 54

Fig. 54 (*d*), arranged to fit into the space between the two center bars. Both ends of this casting are capped and supplied with stud bolts, as at *a* and *c*, the stud bolts being furnished with the nuts *d* and *e*. The purpose of these especially designed bolts is threefold: First, when put in place and securely fastened, by the nut *d*, to the steel girder, they form a means by which the bottom of the mold into which the concrete for the beam is tamped may be held in place. Second, when the bottom of the mold is secured in this manner the trussed unit of steel is held in the correct position within the mold and there is no danger of disturbing the reenforcing metal, as there is in some systems by the tamping of the concrete. Third, the nut *e*, when the concrete has set and the bottom of the mold is removed, may be used to secure wooden stringers, as at *f*. These stringers are used in mill construction for the purpose of holding up the shafting by lagscrewing the hangers to them.

Again referring to Fig. 54 (*a*), it is observed that the trussed frame is supplied with stirrups *i, i* consisting of $\frac{1}{8}'' \times 1''$ bars punched at the upper end, as at *j*, to allow the steel reenforcing members of the concrete floor between the girders to pass through them. These bars are U-shaped, as shown at *h* in view (*d*), and are bent at the bottom, as at *g, g* to fit the shape of the rolled section. They are securely held in place at the bottom by bending back the prongs, as illustrated at *k, k* in view (*a*). In this manner, the prongs, or clips, answer the double purpose of securing the stirrups in position and acting as a key for the concrete at the bottom of the girder, thus preventing it from spalling or breaking off with exposure to fire or water. The stirrups toward the end of the bar are arranged somewhat differently at the top, for these are bent around the upper bar as shown at *l, l* in view (*a*), and at *m, m* in view (*e*). The stirrups are necessary throughout the girder to take care of the shearing stresses, and as the shear increases toward the abutments they are spaced closer together at the supports, in a similar manner to the stiffeners in a plate girder. The girders are so arranged in plan at

the ends as to be interchangeable and interlocking; that is, where the girders meet on the supporting wall, pier, or column the bars are bent to one side, as shown in view (c), and where they enter a wall of masonry the dovetailed end construction is employed, simulating the Goetz-Mitchel wall-box construction, as shown in view (b).

The advantages claimed for the unit-girder system of reinforced concrete are that it is designed, built, delivered, and erected as a unit, or in one piece; that the principal members are made of one rolled section and all other parts are securely held together so that none will be inadvertently omitted when the concrete is put in place; further, that the entire frame is placed in position at once, and that it is the only system in which the concrete can be thoroughly tamped without disturbing the reinforcing members; also, that the slab reinforcement is braced through the stirrups. The cost of this system of reinforced concrete is a little more than slow-burning construction, but it will not exceed the combined cost of slow-burning construction and the usual fire-equipment, such as sprinkler system, stand pipes, etc., that is necessary with the latter.

SPECIFICATION FOR REINFORCED CONCRETE

49. In connection with reinforced concrete construction, the following specification is interesting and covers most of the necessary stipulations:

The work is to be executed entirely in reinforced concrete and the system employed must be one that provides for the shearing stresses at the ends of girders and beams. The floors are to be made sufficiently strong to carry their own weight and the superimposed load of . . . pounds; the ceilings, to carry . . . pounds; and the roof . . . pounds. The live load on the floor will include the finish used on top of the concrete construction. The floor shall be able to carry, without failure, a superimposed load of four times the amount stated in the specification, and the right is reserved to test any unit area of the floor construction to failure. If it fails before the required load has been placed on it, the damage must be made good and all work must be strengthened so as to meet the requirements of these specifications, without expense to the owner.

The reenforced concrete beams must be in accordance with an approved system of construction. They must provide resistance to bending moment and also to shearing, by being reenforced in the vertical plane as well as in the horizontal. The members resisting the shear shall be rigidly connected to the main horizontal tension member, and shall make an angle of about 45° with this member. In calculating the resistance to shear, the adhesion of the concrete to steel will not be assumed at more than 50 pounds per square inch and the vertical reenforcement shall therefore be proportioned to take care of the remaining stresses not provided for by the concrete.

The metal in the floor system must be protected from fire by making the distance from the lower surface of the concrete slab to the edge of the metal at least 1 inch, while in girders and beams this thickness shall be $1\frac{1}{2}$ inches.

The concrete shall be composed of sand, broken stone or gravel, and an approved quality of Portland cement. If broken stone is used, it must be free from fine dust, and small enough to pass through a 1-inch screen, while if gravel is employed, it must be clean and vary in size from $\frac{1}{4}$ to 1 inch. For beams, the proportion of concrete shall be one part of cement, two parts of sand, and four parts of broken stone. For floor slabs, the proportion shall be one part of cement, two and one-half parts of sand, and five parts of broken stone. In general, one layer of concrete shall be entirely completed before another is commenced and the layers shall not exceed about 6 inches in thickness. The concrete shall be deposited as closely as possible to the place where it is to be used, in order to avoid rehandling while in the mold, and each layer shall be thoroughly rammed until moisture appears on the surface. The mixture shall be as nearly uniform as possible in character, and shall be mixed by one of the approved standard batch machine mixers; it shall be of such consistency that when thoroughly rammed it will quake slightly.

General sketches must be furnished by each bidder, showing his system of reenforced concrete and the method of applying it to the work in hand, the thickness of floor slabs, general location of beams, etc., and he must state the tensile strength, elastic limit, elongation, etc. of the steel bars he intends to use. The steel must come up to the standard structural material adopted by the Association of Steel Manufacturers, which provides an ultimate strength of from 55,000 to 60,000 pounds per square inch. Before the work is commenced, detail working drawings and specifications must be furnished by the successful bidder and approved by the architect. The centering used must be strong enough to hold the plastic concrete to the true line and shape.

The architect shall have power to condemn any concrete improperly mixed or proportioned and prevent its incorporation in the work, and whenever, in his judgment, the concrete is liable to be injured from




FIG. 56

its thinnest part. It is laid out in panels and is arranged so that each column will be supported at the intersection of two beams. Between the date of construction of the footings and the date of construction of the first floor, this building settled $3\frac{1}{2}$ inches in the front and 3 inches in the rear, but no further settlement occurred. It is not advisable to use this character of foundation for supporting a building where it is possible to employ isolated piers.

Fig. 56 shows a section through a laundry; this structure, including the roof, is composed entirely of concrete. It is interesting to note the sizes of the beams, girders, and columns used in this building, which may be considered as a fair sample of reenforced concrete construction applied to factory buildings.

51. The Practice of Construction.—It is customary to leave the centering for the floors in place at least 2 weeks. Where two sets of forms are used, rapid progress can be made. After the concrete is laid on the first set of forms, the centering for the second floor may be built up, for by the time the concrete for the second floor is in place the first floor will be sufficiently hardened to permit the removal of the forms supporting it, which may be used for the third floor, and so on. In fact, reenforced concrete construction can be executed as fast as the material can be put in place. Concrete may be laid in freezing weather, provided that the temperature does not fall below 26° F., but if freezing has occurred, the centering should not be removed until every indication of frost has disappeared and the concrete has thoroughly set. Many contractors use only 1-inch material for the centerings, but it is more advisable to use 2-inch. The forms should be put together so that they can be readily taken down. This may be accomplished by not driving the nails to their full length.

Limestone should never be used for the aggregate in concrete, as it renders it worthless as a fireproof material. The limestone will disintegrate under heat and water and the pieces will swell and break out of the slab of concrete. It is

very important for the cement to be uniform and of the best quality. In many cases, the mixtures for foundation work may have a high percentage of stone, sometimes as much as eight parts of stone to one part of cement and four parts of sand, but on an average, the best results for foundation work are obtained from one part cement, three parts of sand, and five parts of broken stone. It is not advisable to attempt to color exterior concrete walls by mixing the coloring matter in the concrete, as the cement tends to combine chemically with the coloring matter. If it is desired to color the wall, the best method is to paint the concrete afterwards. However, the most satisfactory method of obtaining a color scheme is to use sand that has considerable color, as red or yellow.

GOVERNMENTAL REGULATIONS FOR REENFORCED CONCRETE CONSTRUCTION

52. Municipalities and some national governments have adopted laws and ordinances regulating the construction of reenforced concrete. The following is an extract from the latest of these, with some alterations, and adherence to its stipulation cannot but insure excellent results.

53. Materials.—Only Portland cement, delivered in original packages, shall be used in the making of reenforced concrete construction. The sand used in mixing the concrete shall be clean and sharp while the other ingredients shall be of such a suitable size as experience has found to be satisfactory.

54. Mixing Concrete.—The concrete shall be mixed only in quantities required for immediate use. It shall be put in place immediately after mixing and be tamped uniformly; if laid in the consistency of moist earth, it shall be tamped until water appears on the surface. Suitably shaped tampers of proper weight shall be used in tamping.

55. Testing.—In the case of untried methods of construction, the building authorities may first require preliminary trial constructions and load tests.

The building authorities may also determine the qualities of the building materials that are employed, by the aid of an official testing laboratory or in any other way they may deem suitable, and they also may test the strength of the concrete made.

At the final inspection for acceptance, the structure shall be uncovered and accessible at the places indicated by the representative of the building authorities, to show the quality and character of construction. The building authorities have also the right to test the quality of the construction, the degree of hardening obtained, and the sustaining strength, by special tests.

If loading tests are deemed necessary, they shall be made according to the directions of the representative of the building authorities. The owner and the contractor shall be invited to be present at these tests.

If a strip of a floor panel be cut out and tested by a trial load, this load shall be distributed uniformly over the whole strip and not exceed the weight of the floor and double the live load it is computed to sustain. If such a strip is tested without being cut out of the panel, the test load shall be increased by one-half. Thus, if W_d denotes the dead load and W_l the live load, the test load will be, for the former case, $W_d + 2 W_l$ and for the latter, $1.5 W_d + 3 W_l$.

56. Regarding Work in Freezing Weather.—No work shall be done in freezing weather, except when the influence of frost is excluded. After prolonged freezing weather, the work shall not be taken up again in warmer weather until the approval of the building authorities has been obtained.

Until sufficient hardening of the concrete has occurred, the structural parts shall be protected against the effect of freezing and premature drying as well as against vibrations and loads. If freezing weather occurs during the hardening period, the time ordinarily allowed for setting shall be extended by the time of freezing because of the retardation in the hardening caused by the latter.

A daily account of the work shall be kept on the ground and be always open for inspection. Freezing weather shall be especially noted, and the hour and temperature recorded.

57. Molding the Concrete.—Special care shall be exercised in placing the reenforcing metal in its correct position and in surrounding it tightly with cement mortar.

The concrete shall be laid in layers that shall have a thickness not exceeding 6 inches and each layer shall be thoroughly tamped in place.

Continuous walls shall be laid uniformly for their entire length, and care shall be taken to obtain good connections with the adjacent transverse walls. Layers that form the top surfaces of a story must be leveled off.

The molding boards must have sufficient resistance to bending as well as to shocks and vibrations due to tamping, and they shall be arranged to be safely removable after taking away their supports.

The side molds of concrete beams and the molds of floor slabs up to spans of 5 feet shall not be removed before 3 days, and the remaining molds and the supports not before 14 days from the completion of the tamping. In removing the molds and supports all jar and vibration shall be avoided.

If the tamping has been completed only a short time before the occurrence of the freezing weather, special care shall be taken in removing the molds and supports.

In placing a new layer of concrete on a fresh one it will suffice to wet the old surface thoroughly, though in building on hardened concrete the old surface shall be roughened, cleaned, and wet.

In constructing walls and piers for buildings of several stories, the upper stories shall not be started before the molds of the lower story shall have been removed.

58. Rules for Static Computation.—The weight of concrete, inclusive of the reenforcing metal, shall be taken at 150 pounds per cubic foot, unless another weight be definitely ascertained, and in the computation for floors the

weight of the flooring material shall be added to the weight of the sustaining parts.

59. Determination of External Forces.—For the members subject to bending, the end moments and reactions shall be computed, according to the character of loading and support, by the formulas for freely supported or continuous beams. •

For freely supported slabs, the clear opening plus the depth of the slab shall be taken as the span; for continuous slabs, the distance between centers of supports.

For slabs continuous over several spans, the bending moment at the centers of slabs may be taken as four-fifths the value of the moment for a freely supported beam, unless the actually occurring moments and reactions be ascertained by computation or tests.

The same rule holds true for beams, tee-formed beams and girders, with the exception, however, that no end moment shall be taken into account unless special structural details to insure the fixed end be provided. The span shall be taken as the free opening plus the length of one bearing.

For T-formed beams, the flange shall not be considered for a width of more than one-third of the length of the beam.

For columns, consideration shall be given to possible eccentric loading.

60. Allowable Working Stresses.—In the members subject to bending, the compressive stress in the concrete shall not exceed one-fifth of its ultimate resistance; the tensile and compressive stresses in the steel shall not exceed 17,000 pounds per square inch. The following loads shall be provided for: (a) For structural parts subject to moderate impact, such as floors of dwellings, offices, and warehouses; the actual dead and live loads. (b) For parts subject to higher impact or widely varying loads, such as floors of assembly rooms, dancing halls, factories, and storehouses; the actual dead load and one and one-half times the live load. (c) For parts subject to heavy shocks, such •

as roofs of vaults, under passageways and yards; the actual dead load and twice the live load.

In columns, the concrete shall not sustain a stress above one-tenth its breaking strength. In computing the steel reenforcing for column flexure, a factor of safety of 5 shall be provided.

The shearing stress in the concrete shall not exceed 64 pounds per square inch. In any instance, the shearing stress shall not exceed one-fifth of the ultimate resistance. The adhesive stresses shall not exceed the allowable shearing stress.

61. Determination of Internal Forces.—The modulus of elasticity of steel shall be taken as fifteen times that of concrete, unless another ratio be shown.

The stresses in a section of a body subject to bending shall be computed on the assumption that the elongations are proportional to their distances from the neutral axis and that all the tensile stresses are taken up by the steel reenforcement.

Shearing stresses shall be computed, unless the form and design of the members show at once their insignificance. If no allowance is made for them in the design of the member, they must be taken up by suitably shaped steel reenforcement.

The reenforcing steel shall, as far as possible, be so formed that its displacement in the concrete shall be prevented by its form. As far as this is lacking, the adhesive stress shall be computed.

Computations for the flexure of columns shall be made if the height exceeds eighteen times the least diameter. Transverse connections that shall hold the embedded steel rods in their positions relative to each other shall be placed at distances apart not more than thirty times the diameter of the rods.

For the computation of the columns for flexure, Euler's formula shall be used.

62. Method of Computation.—If the beam is a simple one reenforced on the tension side only, the computation

for the stresses in the concrete and steel may be made by formulas 27 and 28, respectively.

The following formulas are those stipulated in the government regulations introduced in Art. 52. In these formulas,

f_s = sectional area of reinforcing steel for width b of beam;

n = ratio of coefficient of elasticity of steel to that of concrete;

M = bending moment of beam;

h = depth of beam from center of reinforcement to top surface of concrete;

x = distance of neutral axis from upper surface;

A = area of metal;

b = width of beam.

$$x = \frac{n f_s}{b} \left[\sqrt{1 + \frac{2b(h-A)}{n f_s}} - 1 \right] \quad (29)$$

From the equation of moments, the greatest compressive stress in the concrete s_c and the greatest tensile stress in the steel s_s will be:

$$s_c = \frac{2M}{b \left(h - A - \frac{x}{3} \right)} \quad (30)$$

$$s_s = \frac{M}{f_s \left(h - A - \frac{x}{3} \right)} \quad (31)$$

For T-formed beams, the computation remains the same as the above if the neutral axis lies in the flange or at the junction of flange and web. If the neutral axis passes through the web, the slight compressive stresses in the web may be neglected. The resulting formulas are:

$$x = \frac{(h-A)n f_s + \frac{b d^2}{2}}{b d + n f_s} \quad (32)$$

$$y = x - \frac{d}{2} + \frac{d^2}{6(2x-d)} \quad (33)$$

$$s_s = \frac{M}{f_s(h-A-x+y)} \quad (34)$$

$$s_c = s_s \left(\frac{x}{n(h-A-x)} \right) \quad (35)$$

63. Centric Pressure on Columns.—If F be the cross-sectional area of the concrete in compression, and f_s that of the total reinforcing steel, the allowable load will be

$$P = s_c(F + n f_s) \quad (36)$$


The greatest stress in the concrete will be

$$s_c = \frac{P}{F + n f_s} \quad (37)$$

The greatest stress in the steel will be

$$s_s = n s_c = \frac{n P}{F + n f_s} \quad (38)$$

64. Eccentric Pressure on Columns.—The computation is the same as for a homogeneous material, except that in the expressions for the cross-sectional area and the moment of inertia of the reinforcing steel, n times the value of an equivalent section of concrete is substituted. Any tensile stresses that may be produced must be taken up by reinforcing steel provided for this purpose.



BEAMS AND GIRDERS

(PART 3)

BUILT-UP GIRDERS

GENERAL CONSTRUCTION

1. **Definitions.**—A plate girder is one built up of a number of plates and angles securely riveted together. The names given to its different parts may be understood by referring to Fig. 1, in which *a* is the **flange plate**, of which there may be one or more on each flange, depending on the strength required. These plates are the principal elements that resist the bending stresses in the girder. The **flange angles** *b, b* are the means of connecting the flange plates to the **web-plate** *c*. When the load on the girder is small, the flange plates may be omitted, in which case the flange angles are the members that chiefly offer resistance to the bending stresses.

On account of the construction of a plate girder, there is very little stiffness in the web-plate; consequently, there is always a strong tendency for it to fail by buckling and twisting under the load imposed on the girder. This tendency to buckle is greatest at the supports or abutments of the girder and at the points where concentrated loads are applied. Because of this buckling tendency it becomes




FIG. 1

For notice of copyright, see page immediately following the title page

necessary to reenforce the girder by riveting to it at stated intervals stiffeners generally made of angles.

The most common and cheapest form of stiffener is shown in Fig. 2 (*a*). This is simply a straight piece of angle riveted to the web-plate and flange angles. The space between the stiffeners and web-plate, due to the thickness of the flange angles, is filled with a piece of bar iron or plate, as




FIG. 2

shown at *d*; this is called a **filler or packing piece**.

Another form of stiffener for plate girders is shown in Fig. 2 (*b*). The angle is swaged out, to allow it to fit over the flange angles, and is riveted directly to the web-plate, thus doing away with the filler or packing piece. This construction does not require as much material as that shown in (*a*), but, unless there are a large number of girders of the same dimensions to be built, in which case dies, in connection with a power or hydraulic press, may be used for swaging the ends,

the labor required is so much greater that it makes the girder more expensive.

The stiffeners shown at (*c*) are sometimes used, but are subject to the same general criticism in regard to cost of manufacture as those shown at (*b*). Stiffeners of this shape possess a possible advantage in the fact that they stiffen the flanges considerably more than either of the other styles.

2. Usual Forms of Sections.—The four principal sections used in plate-girder construction are shown in Fig. 3.

A simple plate girder with a web-plate and two flange angles, but with no flange plate, is shown in (a); this section is used for short spans or light loads. In (b) is shown a similar girder with one flange plate; this girder is used to support heavier loads and to clear longer spans. The girder in (c), which may have two or more flange plates at each flange, may, if the conditions require, be made as heavy as is necessary in order to carry great loads over long spans. In fact, the strength of a girder of this character may be increased almost indefinitely by the addition of flange plates. The section, Fig. 3 (d), is a plate girder of box section. It is stiffer laterally than the other forms shown, but the difficulty of reaching the interior for painting and inspecting and




FIG. 3

the excessive amount of labor required in its construction, are such serious objections that it is much less used than the sections shown at (a), (b), and (c). On account of their open construction, the latter are especially good forms to use in buildings where the objection in regard to lateral stiffness does not hold good, as when the girder is used in the position in which it is usually found, it is generally prevented from deflecting laterally by the floorbeams; any lack of stiffness in comparison with the box girder is more than compensated for by the simplicity of construction and easy access on all sides for painting and inspecting.

PRINCIPLES OF DESIGN

STRESSES

3. The external forces, loads, and reactions produce the same kind of stresses in a plate girder as in an ordinary beam, but, on account of its special construction, the distribution of these stresses in the girder is assumed to be somewhat different from that in a beam made of a single piece. In the girder, the shear is generally assumed to be borne wholly by the web-plate, while the bending moment is assumed to be resisted by the stresses in the flange members. The method of calculating the magnitude of the shear and bending moment is the same as that for beams; owing, however, to the different assumption in regard to the distribution of these forces, a different method of calculation is used in determining the relations between them and the stresses in the girder.

4. Shearing Stresses in Web-Plate.—In discussing the methods of calculating the dimensions of a plate girder for a given purpose, we will first consider the shear, which is the principal factor that determines the thickness of the web-plate and the number and size of stiffeners required. The greatest shear in a beam occurs at the point of support at which the reaction is greatest, and the magnitude of the shear is equal to the reaction at that point; consequently, in a simple plate girder, the greatest shear occurs at a point of support, and is equal in amount to the reaction at that point.

WEB-PLATES AND STIFFENERS

5. Depth of Girder.—Having calculated the shear, the depth of the girder is assumed in accordance with practical rules that fix the relation between the depth and span. In accordance with the best practice, the depth should not be less than one-fifteenth of the span, though some authorities consider one-twentieth ample. The latter proportion, however, gives an exceedingly shallow girder, and cannot be

recommended except where the loads are very light and the span short, or where it is absolutely necessary that an extremely shallow girder be used, on account of decorative features, or lack of space in regard to headroom, in which case the girder should be so proportioned that when fully loaded its deflection will not be excessive.

6. Thickness of Web-Plate.—Knowing the depth of the girder, and the shear at the points of support, the thickness of the web-plate is proportioned so as to give it sufficient area to resist the maximum shear. It is always necessary to stiffen the plates over the supports, as shown in Fig. 5; these stiffeners are riveted to the plate and transfer the shearing stress from it to the supports.

A considerable portion of the plate is cut away by the holes for the rivets by which it is fastened to the stiffeners; hence, the least strength of the plate is along the line of the rivet holes. It can be seen, by referring to Fig. 4, which shows the end of a plate




FIG. 4

with the holes punched for riveting to the stiffener, that the net or efficient depth of the plate is equal to the actual depth minus the sum of the diameters of the rivet holes.

The following rule may be used for calculating the thickness of a web-plate so that it will have sufficient strength to resist the shearing stress:

Rule.—*From the total depth of the web-plate, deduct the sum of the diameters of the rivet holes, which will give the net*

or efficient depth of the web-plate; multiply the net depth by the safe resistance of the material to shear, and divide the maximum shear, in pounds, by the product; the quotient will be the required thickness of the metal in the web of the girder.

This rule may be expressed by the formula

$$t = \frac{R}{d \times s} \quad (1)$$

in which t = thickness of web-plate;

R = greatest reaction or maximum shear;

s = safe shearing resistance of material per square inch;

d = net depth of web-plate after all rivet holes have been deducted.

7. The safe resistance of the material to shear is of course governed by the factor of safety required in the girder. For example, the

ultimate shearing strength of structural steel being 52,000 pounds per square inch, if a factor of safety of 4 is required, the safe resistance of the metal will be $52,000 \div 4 = 13,000$ pounds, while if a factor of safety of 5 is desired, the safe strength will be $52,000 \div 5 = 10,400$ pounds.

In deducting the metal for the rivet holes in order to ascertain the net depth of the web-plate, the holes should always be considered as being $\frac{1}{8}$ inch larger than the nominal diameter




FIG. 5

of the rivet; this allowance is made because the holes are always made $\frac{1}{8}$ inch larger in diameter than the rivet so

that the rivet may be inserted easily, and another $\frac{1}{16}$ inch should also be allowed in the diameter of the hole to compensate for any injury that the metal immediately around it may suffer from the punch.

It will often be found that the calculated thickness of the web-plate is less than is allowable for practical reasons. The thinnest plate that should be used for any case is $\frac{5}{16}$ inch.

EXAMPLE.—Fig. 5 shows the end of a plate girder in which the greatest reaction is 120,000 pounds. The girder is made of structural steel, the safe fiber stress of which is assumed to be 11,000 pounds per square inch for shear. What should be the thickness of the web-plate?

SOLUTION.—The width of the plate is 48 in., and there are thirteen holes punched for $\frac{3}{4}$ -in. rivets. The deduction to be made for each rivet hole is $\frac{1}{8}$ in. + $\frac{3}{4}$ in. = $\frac{7}{8}$ in.; therefore, the net depth of the plate is $48 - 13 \times \frac{7}{8} = 48 - 11\frac{3}{8} = 36\frac{5}{8}$ in. Applying formula 1, the thickness of the plate is $t = \frac{120,000}{36\frac{5}{8} \times 11,000} = .297$ in. In no case, however, should the web-plate of a girder be less than $\frac{5}{16}$ in. in thickness. Hence, as .297 is less than $\frac{5}{16}$, the thickness of the web-plate in this girder should be $\frac{5}{16}$ in. Ans.

8. Buckling of Web-Plate and Distribution of Stiffeners.—The shearing stresses in a web-plate, in addition to their tendency to shear the plate, are liable to cause it to fail by buckling; therefore, in order to properly resist the vertical shearing stresses and prevent them from buckling the web-plate before its full shearing strength is realized, it is necessary to provide the stiffeners.

The shearing stresses in a simple beam are always greatest at the points of support, and diminish toward the center of the beam until a point is reached such that the sum of the loads between it and the support is equal to the reaction; at such a point the shear is said to change sign. Therefore, the stiffeners should be most numerous at the points of greatest vertical shear, and should decrease in number as the shear decreases. Theoretically, this would be a correct method of locating the stiffeners, but practically they are spaced at equal distances along the length of the girder,

except at the points of support, where several are placed near together in order to give the end of the girder more nearly the character of a column and enable it to successfully resist the great vertical shear, due to the reaction at this point. In no case should the stiffeners at the end of a plate girder be omitted, even if the conditions make the intermediate ones unnecessary.

It is good practice to place stiffeners directly under any concentrated load that may be placed on the girder. These not only stiffen the web-plate at the point of application of the load, and thus prevent buckling, but also, through the medium of the rivets, assist in distributing the load on the web-plate and other members of the girder.

The end stiffeners of a plate girder may be considered as columns subjected to a compressive stress equal to the reaction, and calculated by the rules and formulas for columns. For safety, the stress on the end stiffeners should never exceed 15,000 pounds per square inch of section.

9. Practice in regard to the placing of stiffeners on plate girders varies considerably, being more a matter of judgment and experience than of calculation. Some engineers determine the resistance of the web-plate to buckling by the formula

$$b = \frac{11,000}{1 + \frac{d^2}{3,000 t^2}} \quad (2)$$

in which b = safe resistance of web to buckling, in pounds per square inch;

d = depth of web-plate, in inches;

t = thickness of web-plate, in inches.

If the value of b given by this formula is less than the unit shearing stress, the girder should be stiffened.

EXAMPLE.—The allowable shearing stress on the web of a plate girder is 11,000 pounds per square inch. The stiffeners at the end supports are riveted by nine $\frac{7}{8}$ -inch rivets to the web-plate, which is 36 inches wide. The end reaction on the girder is 100,000 pounds. (a) What should be the thickness of the web-plate? (b) Will it be sufficiently strong without the addition of stiffeners?

SOLUTION.—(a) Since $\frac{7}{8}$ -in. rivets are used, the allowance to be made for one rivet hole is $\frac{7}{8} + \frac{1}{8} = 1$ in., and the effective depth of the plate along the line of rivets is $36 - 9 \times 1 = 27$ in. Applying formula 1, the thickness of the plate is found to be $t = \frac{100,000}{27 \times 11,000} = .33$ in. The thickness of the nearest standard-size plate above this is $\frac{3}{8}$ in., which will be the thickness used. Ans.

(b) By formula 2, the safe unit resistance of the plate to buckling is $b = \frac{11,000}{1 + \frac{36^2}{3,000 \times (\frac{3}{8})^2}} = 2,700$ lb. per sq. in.; which, since it is much less than the unit shearing stress on the web-plate, shows that stiffeners are required. Ans.

10. Practical Rule for Spacing Stiffeners.—It is not the general practice to make the above calculations to determine whether stiffeners are required; according to the best engineering practice, stiffeners should be provided, unless the thickness of the web-plate is at least one-fiftieth of the clear distance between the vertical legs of the flange angles.

EXAMPLE 1.—Assume the girder in the previous problem to be provided with 6" \times 6" flange angles; the depth and thickness of the plate, as shown, are 36 inches and $\frac{3}{8}$ inch, respectively. According to the above rule, does this girder require stiffeners?


SOLUTION.—The unsupported depth of the plate between the flange angles is $36 - 2 \times 6 = 24$ in.; $\frac{1}{50}$ of 24 in. = .48, say, $\frac{1}{2}$ in. As the thickness of the web-plate is only $\frac{3}{8}$ in., the girder must be provided with stiffeners. Ans.

Another rule, which gives nearly the same result, is as follows:

Rule.—*Provide stiffeners whenever the thickness of the web-plate is less than one-sixtieth of its total depth.*

This rule is modified by some authorities so as to allow a thickness of one-eightieth of the total depth of the plate as being amply safe without stiffeners. The more conservative rule, however, which requires the thickness to be at least one-fiftieth of the unsupported depth of the web or the distance between the flange angles, is the one to be recommended, and will be used in this Section.

The spacing and size of stiffeners to be used on a plate girder is almost entirely a matter of experience and judgment. As a general rule, it may be said that stiffeners should be provided at the ends of all plate girders over the supports or abutments, and they should be so proportioned that they will take care of the entire reaction at these points. The stiffeners between the abutments or supports should be



Section on a b




FIG. 6

of such size that they will best suit the general requirements of the design of the girder. The practice in spacing intermediate stiffeners is to make the distance between their center lines equal to the depth of the girder, thus dividing the girder into equal square panels. Under no conditions, however, should stiffeners be placed more than 5 feet apart from center to center of line of rivets.

Having proportioned the stiffeners at the abutments to take the entire reaction, it is good practice, when possible, to make the intermediate stiffeners of the same size as the end ones. In general, the angles used for stiffeners should not be less than 3 inches by

3 inches by $\frac{5}{16}$ inch, though on shallow girders, with extremely light loads, it might be economical to use angles as light as $2\frac{1}{2}$ inches by $2\frac{1}{2}$ inches by $\frac{5}{16}$ inch. Sizes smaller than this should certainly never be used for this purpose.

Stiffeners should always extend over the vertical legs of the flange angles; they should always be either swaged out to fit over the flange angles, or be provided with a filling piece, as illustrated in Fig. 2.

EXAMPLE 2.—The end reaction on a plate girder is 300,000 pounds. If a compressive fiber stress of 13,000 pounds per square inch is allowed on the stiffeners, and four stiffeners are used, as shown in Fig. 6, what should be the size of the angles?

SOLUTION.—The reaction or greatest shear being 300,000 lb., and the allowable stress 13,000 lb. per sq. in., the area of the stiffeners required must be $300,000 \div 13,000 = 23$ sq. in.; this sectional area, divided among four angles, gives $23 \div 4 = 5.75$ sq. in. as the area required for each angle.

By referring to the list of Angles With Equal Legs, in the table in *Properties of Sections*, it is seen that a $5'' \times 5'' \times \frac{5}{8}''$ angle has a sectional area of 5.86, while in the list of areas of the angles with unequal legs, a $5'' \times 4'' \times \frac{11}{16}''$ is shown to have an area of 5.72 sq. in.; therefore, either of these angles may be used. Ans.

FLANGES

11. The flanges of a riveted girder include all the metal at the top and bottom of the girder, and are sometimes called the top and bottom chords, though this term is more frequently applied to lattice or open girders, such as are more often used for railroad and highway bridges.

In building construction, it is customary to include in the flange the two flange angles, the flange plates, and one-sixth or one-eighth of the web-plate included between the flange angles.

The resisting moment, or the resistance to bending, of the section may be calculated as follows:

Taking the center of gravity of one flange section as a center, the moment of resistance of the other flange is equal to the area of the flange section multiplied by the distance between the centers of gravity of the flange areas and the safe stress per square inch of section. The resistance of the web is equal to its section modulus multiplied by the safe stress per square inch. Assuming d as the depth of the web which is considered here as being the distance between the

centers of gravity of the two flanges, the resisting moment of the entire section may be expressed by the formula

$$M_1 = A d s + \frac{s b d^2}{6} \quad (3)$$

in which A = area of flange section;

d = height of girder between centers of gravity of flanges;

s = allowable stress per square inch;

b = thickness of web.

Considering $b d$ as equal to the area of the web, or A' , we have $M_1 = A d s + \frac{A' s d}{6}$, or $M_1 = d s \left(A + \frac{A'}{6} \right)$. Thus, it may be seen that the entire resistance of the section includes about one-sixth of the area of the web, and consequently, one-sixth of the web may be considered as assisting to resist the bending moment on the girder.

The reduction of the moment of resistance of the web by rivet holes must be taken into consideration, however, and consequently it would be more nearly correct to assume one-eighth of the depth of the web as acting with the flange to resist the bending moment.

The building ordinances of some of the large cities in the United States, however, will not allow any portion of the web-plate to be included as part of the flange. In this Section, the web-plate will not be considered in calculating the flange area.

If, because of economic considerations, one-sixth or one-eighth of the web-plate must be included as part of the flange, it should be remembered that the plate should never be spliced near the center, when the girder is uniformly or symmetrically loaded, or directly under the point of greatest bending moment, when the load on the girder is unsymmetrically placed. Especial care must also be taken to insure that any splice made on the length of such a web-plate is so designed as to furnish the greatest possible percentage of strength of the solid plate included within one-sixth or one-eighth of the depth of the web.

The best practice dictates that where flange plates are used, the sectional area of the flange angles should equal the sectional area of the flange plates. This, however, is not possible in heavy work, where the best that can be done is to use the heaviest sections obtainable for the flange angles.

12. Flange Stresses.—In a simple girder, the top flange is subjected to compression and the bottom flange to tension. Nevertheless, it is customary in practice to make the two flanges equal and composed of the same size of rolled plates and angles.




FIG. 7

In proportioning the flanges of a plate girder, the lower flange is calculated for tension; the areas of the rivet holes cut out of the flanges are deducted from the total area, so as to give the net or actual area of the flange at the point of least strength.

The stresses in the flanges are assumed to be produced wholly by the bending moment on the girder, and the moments of these stresses are assumed to be equal to the moments of the external forces.

The principles on which the flange stresses of a plate girder are calculated will be made clear by reference to Fig. 7, which shows a girder in two sections joined by a

hinge pin c at the upper flange, and a chain at the lower flange. The resultant moment of the loads and reactions tends to produce rotation about the center c , which, however, is taken at a point in the upper flange instead of on the neutral axis, as was done in the case of the beam composed of a single section; in reality, owing to the fact that the web is entirely neglected in calculating the resistance of the girder to the bending stresses, there is no neutral axis, in the sense in which that term was used in connection with ordinary beams. Strictly speaking, there may be said to exist a neutral axis in the web, similar to that in an ordinary beam, but, on account of the thinness of the web, the additional tensile and compressive resistance offered by it is so small that it may be neglected, as far as the longitudinal stresses in the flanges are concerned. The centers of moments of the tensile and compressive stresses are therefore supposed to be shifted to the upper and lower flanges, respectively. The vertical stresses have still to be transmitted by the web to the points of support, the compressive stresses being taken up by the stiffeners and the tensile ones by the web.

The stress in the chain, which represents the lower chord or flange of the girder, resists the tendency to rotation about the center of moments c , with a lever arm l_1 , which is the perpendicular distance from the chain to the point c . It is evident, then, that the strength of the girder depends on two factors: the tensile strength of the lower chord, and its distance from the center of the hinge c , the latter of which represents the depth of the girder.

If the center of moments is taken on the center line of the chain, directly under the point c , it is evident that the resultant moment of the external forces, with respect to this center, is the same as when the center was taken at c ; it is also evident that the force in the beam whose moment, with respect to this center, balances the resultant moment of the external forces, is the compression on the pin c . Since the moment and the lever arm of the compressive stress on the pin are respectively equal to the moment and the lever

arm of the tensile stress in the chain, it follows that these two stresses are equal; in other words, the compressive stress in the top flange of the girder is equal to the tensile stress in the bottom flange.

13. Proportioning the Flanges.—Having determined the principles on which the bending strength of a plate girder is calculated, it remains to show a method for proportioning the metal in the flanges. The usual process is as follows:

First calculate the maximum bending moment on the girder; in calculating the bending moment on a plate girder it is customary to express the moment in foot-pounds, the depth of a girder being generally given in feet and not in inches, as in solid beams of shallow depth. If, however, the depth of the girder is expressed in inches, the bending moment must be calculated in inch-pounds.

Having found the maximum bending moment on the girder, it is necessary to assume an allowable fiber stress for the material of which the flanges are composed. The following rule may be used to calculate the sectional area of either flange:

Rule.—*Divide the bending moment on the girder, in foot-pounds, by the product obtained by multiplying the depth of the girder, in feet, by the safe fiber stress.*

The safe fiber stress for a given case is obtained by dividing the ultimate fiber stress per square inch of the material by the factor of safety required in the girder.

The rule may be expressed by the formula

$$A = \frac{M}{D \times s_a} \quad (4)$$

in which A = net area of one flange, in square inches;

D = depth of girder, in feet;

s_a = safe fiber stress per square inch of material;

M = bending moment on girder, in foot-pounds.

EXAMPLE.—The depth of a plate girder is 6 feet, the span is 80 feet, and the load on the girder is 3,000 pounds per lineal foot: (a) What

will be the required net flange area for structural steel, if a factor of safety of 4 is used? (b) Of what size rolled sections should the flange be composed?

SOLUTION.—(a) The span being 80 ft. and the load 3,000 lb. per lineal ft., the entire load on the girder will be $80 \times 3,000 = 240,000$ lb.

Substituting in the formula $M = \frac{WL}{8}$ for the bending moment on a simple beam, gives $M = \frac{240,000 \times 80}{8} = 2,400,000$ ft.-lb. The net area of the flange, from formula 4, is

$$A = \frac{2,400,000}{6 \times 15,000} = 26.7 \text{ sq. in. Ans.}$$

(b) In order to determine the size of the flange plates and angles, it is useful to assume some particular size of angles and plates, and make a detail sketch of the flange, as shown in Fig. 8, marking on it the size of the respective plates and angles that have been assumed. The




FIG. 8

rivets should also be shown, so that the metal cut out of the rivet holes may be deducted from the sectional area of the flange in order to determine that area.

It is assumed in the section under consideration that there are two rows of rivets through the vertical legs of the angles, each pair of these rivets being placed in the same vertical plane, in consequence of which the amount to be deducted from the net section is double the area cut out for one rivet. The rivets in the two rows

through the horizontal legs of each angle are staggered, and consequently only one rivet hole in each horizontal leg affects the area of the flange section.

According to the table Properties of Standard Angles, in *Properties of Sections*, the area of a $6'' \times 6'' \times \frac{5}{8}''$ angle is 7.11 sq. in.; therefore, the total area of the metal in the flange is

$$\text{Two } 6'' \times 6'' \times \frac{5}{8}'' \text{ angles, } 7.11 \times 2 = 14.22 \text{ sq. in.}$$

$$\text{Four } 14'' \times \frac{3}{8}'' \text{ plates, } 4 \times 14 \times \frac{3}{8} = 21.00 \text{ sq. in.}$$

$$\text{Total, } \underline{35.22 \text{ sq. in.}}$$

From the total area of the flange it is necessary to deduct the metal cut out for the rivet holes. As $\frac{7}{8}$ -in. rivets are used, the rivet holes are considered to be $\frac{1}{4}$ in. larger, or 1 in. in diameter.

There are four 1-in. holes through $\frac{5}{8}$ in. of metal to be deducted from the vertical legs of the angles, and in the plates and the horizontal legs of the angles there are two 1-in. holes through $2\frac{1}{8}$ in. of metal. The areas to be deducted for the rivet holes are, therefore,

$$\text{Four 1-in. holes through } \frac{5}{8} \text{ in. of metal} = 2\frac{1}{4} \text{ sq. in.}$$

$$\text{Two 1-in. holes through } 2\frac{1}{8} \text{ in. of metal} = 4\frac{1}{4} \text{ sq. in.}$$

$$\text{Total, } 6\frac{3}{4} \text{ sq. in.}$$

and the net area of the flange is $35.22 - 6.75 = 28.47$ sq. in. Since the calculations showed that the net area required in this flange is 26.6 sq. in., it is evident that the assumed flange is amply strong. Ans.

While plate girders are more economical than box girders, the latter are stiffer in a lateral direction and hence should be used where a wide top flange is required in order to furnish the necessary lateral stiffness for a long span. If the girder is not held in place laterally the top flange should have a width equal to at least $\frac{1}{20}$ of the span. Otherwise, the gross area of the top flange may be found by the following formula:

$$A' = A \left(1 + \frac{e^2}{5,000} \right) \quad (5)$$

in which A = gross area required in top flange, with girder supported laterally;

A' = gross area in top flange, girder unsupported laterally;

e = span \div width of flange, both in inches.

14. Lengths of Flange Plates.—Since the bending moment in a simple beam varies along the entire length of the beam, the location of the maximum bending moment depending on the distribution of the load, it would seem that in order to design an economical girder, the area of the flange should vary with the bending moment. Where flange plates are used, this condition may be partially fulfilled by the use of plates of different lengths, each extending only as far as may be required in order to provide the flange section demanded by the bending moment.

Reference to Fig. 9 will make this construction more clear. In this figure, it is seen that the top plate of the top flange is the shortest, and extends over a small portion of

the girder only, each successive plate under this one being longer than the one above it. The third plate from the top is the longest and extends nearly the full length of the girder, while the angles extend from end to end.




FIG. 9

Where the beam is uniformly loaded, the following method may be used to obtain the theoretical length of each of the flange plates:

Commencing with the outside plate of the flange, find the sum of all the net areas, in square inches, of the plates to and including the plate in question. Thus, in Fig. 10, if it be required to obtain the length of the third plate from the top, find the sum of the areas of the first, second, and third plates. If the length of the second plate is required, then the sum of the areas of the first and second plates is to be




FIG. 10

taken. Divide the area so obtained by the net area of the whole flange, in square inches, and multiply the square root of this quotient by the length of the girder, in feet; the product will be the theoretical length of the plate in feet.

Having obtained the theoretical length of the plate, it is necessary to add from 12 to 16 inches to each end,

in order that the plate in question may be carried sufficiently past the point of bending moment that governs the area of the flange at its ends to be securely riveted to

the plates and angles making up the flange from there on to the abutment.

The method for determining the length of flange plates where the beam is uniformly loaded may be expressed by the formula

$$L_p = L \sqrt{\frac{a}{A}} \quad (6)$$

in which L_p = theoretical length, in feet, of plate in question;

L = length of girder, in feet;

a = net area of all plates to and including plate in question, beginning with outside plate;

A = total net area of entire flange.

EXAMPLE.—In Fig. 11 is shown a section through the flange of a plate girder the span of which is 60 feet. What is the theoretical length of each of the three flange plates?

SOLUTION.—The area of a $4'' \times 4'' \times \frac{1}{2}''$ angle, according to the table *Properties of Standard Angles*, in *Properties of Sections*, is 3.75 sq. in. The area of each plate is $\frac{3}{8} \times 12 = 4.5$ sq. in. The diameter to be deducted for the rivet holes is $\frac{3}{4} + \frac{1}{8} = \frac{7}{8}$ in.

The area cut out by a $\frac{7}{8}$ -in. hole through a $\frac{3}{8}$ in. plate is $.875 \times .375 = .328$ sq. in. Then, as there are two rivet holes in each plate, its net area is 4.5 sq. in. — $(.328 \text{ sq. in.} \times 2) = 3.844$ sq. in.

The net area of the angles is $(3.75 \text{ sq. in.} \times 2) - (.4375 \text{ sq. in.} \times 4) = 5.75$ sq. in.

The net area of the flange section is, therefore,

Three plates $3.844 \times 3 = 11.532$ sq. in.

Two angles $= 5.750$ sq. in.

Total, 17.282 sq. in.

Now calculate the length of the outside plate. Substituting in the formula gives

$$L_p = 60 \sqrt{\frac{3.844}{17.282}} = 28.29 \text{ ft.}$$




FIG. 11

By substituting the proper values, the theoretical length of the second or middle plate is

$$L_2 = 60 \sqrt{\frac{7.688}{17.282}} = 40.0 \text{ ft.}$$

The length of the third or last plate in the flange, that is, the one next to the flange angles, is next to be calculated, though some engineers prefer to run this the entire length of the girder, as it stiffens the girder laterally and assists in preventing any tendency toward side deflection. The theoretical length of this plate is

$$L_3 = 60 \sqrt{\frac{11.532}{17.282}} = 49.12 \text{ ft.}$$

15. Graphic Method of Determining Length of Flange Plates.—The graphic method for determining the theoretical length of flange plates in built-up girders is




FIG. 12

more convenient than the analytic method previously given. In order to explain this method, a section through the flange of a plate girder will be assumed and the lengths of the several flange plates determined.

Fig. 12 shows a section through the flange of a girder, built up of four $\frac{1}{2}'' \times 14''$ flange plates, the span of the girder being 90 feet. It will be noticed that there are two rows of rivets in the flange, and two rows in the vertical leg of the angles, but as the latter are staggered, there will be but one rivet hole to be deducted from the vertical leg of each angle.

The sectional area of a $6'' \times 6'' \times \frac{3}{4}''$ angle is found from the table Properties of Angles, in *Properties of Sections*, to be 8.44 square inches; from this deduct $1\frac{1}{2}$ square inches, the area cut out by the two rivet holes, making the net area of each flange angle 6.94 square inches.

The sectional area of a $\frac{1}{2}'' \times 14''$ flange plate is 7 square inches, from which there is to be deducted 1 square inch for

the sectional area cut out by the two rivet holes. Hence, the net area of one flange plate is 7 square inches — 1 square inch = 6 square inches.

The net area of the entire flange will, therefore, be

$$\begin{array}{rcl} \text{Two } 6'' \times 6'' \times \frac{3}{4}'' \text{ angles} & = & 13.88 \text{ square inches} \\ \text{Four } \frac{1}{2}'' \times 14'' \text{ flange plates} & = & 24.00 \text{ square inches} \\ \hline \text{Total,} & & 37.88 \text{ square inches} \end{array}$$

Since the load is uniformly distributed, the flange plates extend equally on each side of the center; consequently, the diagram for only one-half of the girder will be drawn. Draw, to any scale, a horizontal line ab , Fig. 13, equal to one-half of the span; divide this line into any number of equal parts (in the figure, twelve parts have been used). Upwards from the points of division, draw indefinite perpendicular lines. On the perpendicular from b , lay off to some scale a distance that represents the entire net section of the flange, thus locating the point r . For example, the net area of the flange in this case is 37.88 square inches; letting $\frac{1}{16}$ inch represent 1 square inch, the distance br must be $37.88 \times \frac{1}{16} = 2.37$ inches, nearly.

Lay off to the same scale on the line br a distance bn , which represents 13.88 square inches, the net area of the two flange angles, also the distances no , op , pq , and qr , each representing 6 square inches, the net area of each of the flange plates. From the point r , draw a horizontal line cutting the vertical line erected at a , thus locating the point b' . Divide the vertical line ab' into the same number of equal parts as the line ab , thus locating the points c' , d' , e' , f' , etc.; and from these points, draw the lines $c'r$, $d'r$, etc. Draw the curve $asvr$ through the points where the vertical lines from c , d , e , etc. intersect the corresponding lines $c'r$, $d'r$, $e'r$, etc. Now from the points q , p , o , and n draw horizontal lines as shown, cutting the curve in the points s , t , u , and v , and from each of these points of intersection, draw a perpendicular, extending it until it intersects the horizontal line next above. The rectangles $t'rqv$, $u'qp u$, $t'po t$, etc. thus formed, represent the flange plates and angles.




FIG. 13

order that the student may always have a guide for laying out this diagram.

16. Application of Graphic Method to Girders With Concentrated Loads.—The graphic method for determining the theoretical length of flange plates when the girder is loaded with concentrated loads, which is similar to that given for a uniformly loaded girder, will be illustrated by constructing a diagram for the lengths of the four flange plates required for a girder with a span of 80 feet and a depth of 6 feet, carrying a concentrated load of 185,000 pounds at 30 feet from one end.

The bending moment on the girder may be calculated by the formula

$$M = W \times \frac{xy}{L} \quad (7)$$

in which M = bending moment;

W = load on girder;

L = span, in feet;

x = distance that load is located from one abutment;

y = distance that load is located from other abutment.

In Fig. 15, the load is located at the point L , 30 feet from R_1 and 50 feet from R_2 . Substituting these values in the formula, the bending moment is found to be $M = 185,000 \times \frac{30 \times 50}{80} = 3,468,750$ foot-pounds.

From this bending moment, the required net flange area, assuming a safe unit stress of 15,000 pounds per square inch, is found to be, approximately, 38 square inches, which is provided by the use of four $\frac{1}{2}'' \times 14''$ plates and two $6'' \times 6'' \times \frac{3}{4}''$ angles. The flange therefore has the section shown in Fig. 12.

To construct the diagram, which is shown in Fig. 15, draw the base line cd , to any scale, equal to the span of the girder, in feet. (In this case, owing to the fact that the load is not symmetrically placed, the center line of the girder will not

divide the lengths of the plates in halves, and it will be necessary to draw the entire diagram.) Locate the point of application of the concentrated load at 30 feet from R_1 ,




FIG. 15

and draw the perpendicular line ef . On this line, lay off, to any scale, a distance that represents the bending moment. For example, in this case, a scale has been used on which

BEAMS AND GIRDEKS

000 foot-pounds is represented by $\frac{1}{32}$ inch; the distance to be laid off is, therefore, $\frac{3468750}{60000} \times \frac{1}{32} = 2.168$ inches. This represents the point g , which is then connected by straight lines to the points c and d . Draw vertical lines from the points c and d until they meet a horizontal line through the point g , at q and r .

In the flange section, the angles have a combined net area of 13.88 square inches, and each flange plate a net area of 6 square inches. The combined net sectional area of the flange is 37.88 square inches.

Place the zero mark of any convenient scale at the point f , and slant the scale until the marking on the scale that represents 37.88 square inches, the net area of the flange, falls on the horizontal line qr . Thus, in this case, a $\frac{1}{16}$ -inch scale has been used, and the zero mark is placed at f , while the mark on the scale representing the division 37.88 is placed on the horizontal line qr . With the scale still in this position, begin at the zero mark and lay off a distance 13.88 to represent the net sectional area of the two angles; then lay off four distances, each equal to 6, to represent the net sectional area of each of the flange plates.

Through the points thus found, draw the horizontal lines hi , kl , mn , and op . At the points s, u, w, y , etc., where these horizontal lines cut the oblique lines gc and gd , draw the perpendicular lines $st, uv, wx, yz, a'b'$, etc., extending each until it meets the next horizontal line above. Then the rectangles enclosed by the horizontal and vertical lines, shown heavy in the diagram, represent the cover-plates and flange angles. By measuring the lengths of these rectangles with the scale to which the span was laid off on the line cd , the angles in the diagram, represent the cover-plates and flange angles.

In this case the length of the angles is equal to the span, 80 feet, as marked on the diagram. The length of the first, or top, plate measures 12 feet 9 inches; of the second plate, 26 feet 0 inches; of the third plate, 39 feet 3 inches; and of the fourth, or last, plate, 52 feet 0 inches. It may be that when the student lays out the diagram for himself, he will obtain results that will vary slightly from those given.

However, a variation of a few inches in the length of a flange plate on a girder need not be considered.

17. Graphic Diagram for Several Concentrated Loads.—In order to illustrate this method still further, a more complicated problem, in which there are three concentrated loads, will now be presented.

Assume that a girder having a span of 80 feet with a depth of 6 feet is loaded as shown in Fig. 16. What flange area is required, provided that a safe unit fiber stress of 16,000 pounds per square inch is used, and of what should the flange be constructed; also, what will be the length of the several flange plates?

The reactions at R_1 and R_2 are found to be 142,500 and 117,500 pounds, respectively. It will first be necessary to




FIG. 16

calculate the bending moment, in foot-pounds, at the points where the loads a , b , and c , are concentrated. The bending moment under load a is $142,500 \times 20 = 2,850,000$ foot-pounds; under load b , the bending moment is $(142,500 \times 30) - (80,000 \times 10) = 3,475,000$ foot-pounds; and the bending moment under load c is $(142,500 \times 50) - [(80,000 \times 30) + (60,000 \times 20)] = 3,525,000$ foot-pounds.

From this it is seen that the greatest bending moment is under the load c , and its magnitude is 3,525,000 foot-pounds.

From this the flange area required may be calculated by applying formula 4, as follows:

$$A = \frac{3,525,000}{6 \times 16,000} = 36.71 \text{ square inches}$$

We will now select a flange section that will have the required net sectional area; referring to the section shown in Fig. 12, the area is found to be 37.88 square inches; this flange will therefore satisfy the requirements.

18. Having determined the bending moments and the greatest net flange area, begin the diagram shown in Fig. 17 by drawing to any scale the horizontal line de equal in length to the span of the girder; with the same scale locate the points of application a , b , and c of the concentrated loads. Upwards from the points d , a , b , c , and e draw indefinite perpendicular lines, and on the perpendiculars from a , b , and c lay off to some convenient scale distances af , bg , and ch , which represent the respective bending moments at these points.

For example, the bending moment at a is 2,850,000 foot-pounds; at b , it is 3,475,000 foot-pounds; and at c , it is 3,525,000 foot-pounds; therefore, assuming a scale on which each $\frac{1}{32}$ inch represents 50,000 foot-pounds of bending moment, the respective bending moments at the points a , b , and c are represented by lengths af of 57 thirty-seconds, bg of 69 $\frac{1}{2}$ thirty-seconds, and ch of 70 $\frac{1}{2}$ thirty-seconds.

Draw straight lines connecting the points d , f , g , h , and e . Through the highest point h , representing the greatest bending moment, draw the horizontal line jk .


The net area of the flange being 37.88 square inches, place the zero mark of any convenient scale on the line de , and slant the scale until the mark that represents 37.88 falls on the line jk .

Starting from the zero mark on the scale, lay off a distance that represents the net area of the two flange angles, in this case 13.88 square inches, then divide the remaining distance into equal parts, each of which represents 6 square inches, the net sectional area of the several flange plates.

Through the points just found, draw the horizontal lines lm , no , pq , and rs . Where these horizontal lines intersect the oblique lines at the points t , u , v , w , x , etc., draw vertical lines until they intersect the next horizontal line above.

Then draw in, with heavy lines, the rectangles representing the flange plates and flange angles.

The theoretical length of the flange plates may now be



determined by measuring with the scale to which the span was laid off on the line de . The length of the top, or first, plate in this case is found to be 32 feet 11 inches; of the

second plate, 42 feet 6 inches; of the third plate, 51 feet 3 inches; and of the fourth, or last, plate, 50 feet 9 inches.




FIG. 18

In Fig. 18 is shown a diagram that will serve as a general rule for determining the length of the several flange plates of a girder loaded with several concentrated loads.

19. Diagram for a Combination of Concentrated Loads With a Uniformly Distributed Load.—There is another condition of girder loading that is frequently




FIG. 19

encountered in practical work in which it is necessary to determine the length of the several flange plates by the graphic method; this condition is produced by a combination

of a uniformly distributed load with several concentrated loads located at different points along the girder.

In order to explain the method for obtaining the length of the flange plates in a girder loaded in this manner, the following problem will be assumed and the diagram will be constructed as was done in previous cases.

Assume the girder to be loaded, as shown in Fig. 19, with a uniformly distributed load and the two concentrated loads. The flange section shown in Fig. 20 is sufficient to resist the bending moments due to these loads. It is required to determine by the graphic method the theoretical lengths of the several cover-plates making up the flange section.




FIG. 20




FIG. 21

Before starting to draw the diagram shown in Fig. 21, it is necessary to make the calculations for the following: The greatest bending moment; the maximum bending

moment due to the uniformly distributed load; and the bending moment under each of the concentrated loads, neglecting the uniformly distributed load. These bending moments should be expressed in foot-pounds. The flange area required to resist successfully each of these bending moments should also be calculated.

The calculations in this case have been made in the usual manner, and the results are as follows:

	FOOT-POUNDS
Greatest bending moment	= 2,070,000
Bending moment due to a uniform load	= 900,000
Bending moment under concentrated load <i>a</i> , considering the concentrated loads only . .	= 1,170,000
Bending moment under concentrated load <i>b</i> , considering the concentrated loads only . .	= 792,000

Since the depth of the girder is 4 feet, if a unit fiber stress of 15,000 pounds is used, the flange area required to resist the greatest bending moment is $A = \frac{2,070,000}{4 \times 15,000} = 34.5$ square inches.

The flange area required to resist the bending moment due to the uniform load is $A = \frac{900,000}{4 \times 15,000} = 15$ square inches.

The flange area required to resist the bending moment at the point on the girder where the concentrated load *a* is situated, considering the concentrated loads only, is $A = \frac{1,170,000}{4 \times 15,000} = 19\frac{1}{2}$ square inches.

The flange area required to resist the bending moment at the point on the girder under the concentrated load *b* is $A = \frac{792,000}{4 \times 15,000} = 13.2$ square inches, considering, as before, only the concentrated loads.

20. As the loads on the girder are not symmetrically placed with regard to the center, it will be necessary to draw the complete diagram. Begin the diagram by drawing, to any convenient scale, the horizontal line *cd*, Fig. 21, equal

in length to the span of the girder, and locate the points of application of the concentrated loads at a and b ; upwards from the points c , a , b , and d draw indefinite vertical lines. .

Now, in accordance with the method explained in Art. 15, make the construction to determine the curved line representing the bending moment due to the uniform load as follows:

At the center of the girder draw a vertical line (in this case the center of the girder is found to be at the point where the load a is concentrated); divide half the span into any number of equal parts, as at e , f , g , h , i , etc., and from the points so obtained draw perpendiculars. Lay off on the vertical line passing through the center a distance al , which may represent either the greatest bending moment at this point due to the uniform load, or the flange area required to resist this bending moment, as they are proportional. In this case the net area required in the flange will be used; hence, as the area of the flange required for the uniform load is 15 square inches, if $\frac{1}{16}$ inch is assumed to represent 1 square inch of flange area, the distance al will be $\frac{1}{16}$ inch.

Through the point l , draw the horizontal line mn . Divide the distance mc into the number of equal parts into which the half of the span was divided, and from the points r , s , t , u , v , etc. thus obtained, draw converging lines to the point l ; where these oblique lines intersect the vertical lines, mark the points a' , b' , c' , d' , etc., and through these points draw the curve cl . Draw the other half of the curve ld in the same manner, thus completing the diagram for the uniform load.

21. Now draw the diagram for the concentrated loads. On the vertical line al , extended, lay off the distance ah' , equal to the net flange area required to support the concentrated load a , and on the perpendicular line erected at b lay off the distance bi' equal to the flange area required at the point b to support the concentrated loads.

It must be remembered that the same scale is to be used as that with which the flange area required for the uniform load diagram was laid off; also, that if the vertical distances are laid off to represent the bending moment in the one

as resisting any portion of the bending moment, this increment is found by the formula

$$f_i = \frac{S}{h} \quad (8)$$

in which S = maximum shear at point considered;

h = height, in inches, between center lines of rivets;

f_i = increment of stress per inch of run.

The increment of stress divided into the resistance of one rivet, gives the distance between centers of rivets, or their pitch. Hence,

$$p = \frac{r}{\frac{S}{h}} = \frac{r h}{S} \quad (9)$$

in which

p = pitch of rivets;

r = resistance of one rivet;

h and S = same as in formula 8.

Where the maximum bending moment is considered as being resisted by the flange area and one-eighth of the web area, the pitch of the rivets is increased as the ratio of the flange area and the combined area, including the flange area and one-eighth of the web. Therefore,

$$p = \frac{A + \frac{A'}{8}}{A} \times \frac{r h}{S} \quad (10)$$

when a portion of the web is included in the area resisting the shear. In this formula, A has the same value as in formula 4; A' is equal to the area of the web, while p , r , h , and S are the same as in formula 9. The application of formula 10 is shown in the following example:

EXAMPLE.—A plate girder having a span of 40 feet supports a uniform load of 5,000 pounds per lineal foot. The distance from the outside reinforcing angle of the girder over the abutment to the first stiffener is 4 feet, while the depth of the girder from center to center of the flange rivets is 3 feet. The thickness of the web-plate is $\frac{5}{8}$ inch and its depth is 40 inches; it is perforated on a single section with ten

$\frac{1}{8}$ -inch rivet holes. Provided that the safe unit flange stress is 15,000 pounds, what will be the theoretical pitch of the $\frac{3}{4}$ -inch rivets in the vertical legs of the flange angles of the first panel?

SOLUTION.—The bending moment at the first panel point is equal to the moment of the reaction about this point minus the moment of the load on the first panel; hence, $M = (100,000 \times 4) - (5,000 \times 4 \times 2) = 360,000$ ft.-lb. In this example, the depth of the girder will be considered as the distance between centers of rivets; then substituting in formula 4, the net flange area equals $\frac{360,000}{3 \times 15,000} = 8$ sq. in. The net area of the web equals $(40 \times \frac{5}{16}) - (10 \times \frac{1}{8} \times \frac{5}{16}) = 9.961$ sq. in. The area of the flange, not including any portion of the web, is therefore equal to $8 - \frac{9.961}{8} = 6.755$ sq. in.

From the table Shearing Value of Rivets, in *Details of Construction*, the shearing value of a $\frac{3}{4}$ -in. rivet in double shear is 6,627 lb. The maximum shear at the point under consideration is $100,000 - (5,000 \times 4) = 80,000$ lb. Then substituting these values in formula 10,

$$p = \frac{A + \frac{A'}{8}}{A} \times \frac{r h}{S} = \frac{6.755 + \frac{9.961}{8}}{6.755} \times \frac{6,627 \times 36}{80,000} = 3.53 \text{ in.}, \text{ or } 3\frac{1}{2} \text{ in.}$$

Ans.

25. The example given below illustrates the method of finding the pitch of the rivets when no portion of the web-plate is considered as resisting the bending moment, or when formula 9 is applied.

Assume a girder of 40 feet span, as shown in Fig. 22, with a depth of 4 feet, and a uniformly distributed load of




FIG. 22

200,000 pounds. The shearing stress in the girder at the left reaction, or point a , is equal to R_1 , in this case 100,000 pounds. At b , 4 feet from R_1 , the vertical shear in the girder is $100,000 - (5,000 \times 4) = 80,000$ pounds; at c , 8 feet

from R_1 , the vertical shear is $100,000 - (5,000 \times 8) = 60,000$ pounds; at d , it is $100,000 - (5,000 \times 12) = 40,000$ pounds; at e , the shear is 20,000 pounds, and at f it is zero.

By substituting the above results in formula 8, the rate of increase, per inch of length, or the increment of the horizontal stress in the flange at the several points a, b, c, d, e , and f may be obtained. Thus, at the end a of the girder the increase in the horizontal flange stress is $\frac{100,000}{4 \times 12} = 2,083$ pounds per inch of run; at b , $\frac{80,000}{4 \times 12} = 1,667$ pounds per inch of run; at c , $\frac{60,000}{4 \times 12} = 1,250$ pounds per inch of run; at d , $\frac{40,000}{4 \times 12} = 833$ pounds per inch of run; and at e , $\frac{20,000}{4 \times 12} = 417$ pounds per inch of run.

If $\frac{7}{8}$ -inch rivets are used, the safe load for one rivet, at 12,000 pounds per square inch, in a $\frac{3}{8}$ -inch plate, is 3,938 pounds, from the table, Bearing Value of Riveted Plates, in *Details of Construction*, and in web bearing, the strength of one rivet is $3,938 \times 1\frac{1}{3} = 5,251$ pounds per square inch. At the end, where the increase in stress is 2,083 pounds per inch of run the pitch of the rivets should be $5,251 \div 2,083 = 2.52$ inches, from center to center. At b , the maximum allowable pitch of the rivets is $5,251 \div 1,667 = 3.75$ inches; at c , the pitch may be $5,251 \div 1,250 = 4.20$ inches; and at d , $5,251 \div 833 = 6.30$ inches. Since, for practical reasons, the rivets in the vertical leg of the flange are spaced the same in both the upper and lower chords, and since the greatest allowable pitch of rivets in a compression member is 6 inches, it is needless to carry the calculation further.

Hence, the pitch of the rivets between a and b should be $2\frac{1}{2}$ inches; between b and c , $3\frac{3}{4}$ inches; between c and d , $4\frac{1}{4}$ inches; since the theoretical pitch between d and e is more than 6 inches, which for practical reasons is not allowable, all the rivets between d and the center of the girder should be spaced 6 inches from center to center.

26. Effect of Vertical Stress.—Sometimes the vertical as well as the horizontal stress in the flange is taken into account in spacing the rivets, in which case the resultant of the two stresses is the stress that must be provided for. The vertical stress is due directly to the load resting on the flange of the girder, which, through the rivets, is transmitted to the web-plate.

In the plate girder shown in Fig. 22, the increase in the horizontal flange stress at the end is, as previously calculated, 2,083 pounds per inch of run; the load on the girder being uniformly distributed, the vertical stress on the flange, per lineal inch, is equal to the entire load on the girder divided by the span of the girder in inches; it is, therefore, $200,000 \div (40 \times 12) = 416$ pounds per inch of run.

The total stress to be resisted by the rivets is, therefore, equal to the resultant of 2,083 pounds—due to the increase in the horizontal stress on the flange—and the vertical stress of 416 pounds; this resultant is $\sqrt{2,083^2 + 416^2} = 2,124$ pounds per inch of run. The pitch of the rivets at the end of the girder would then be $5,251 \div 2,124 = 2.47$, approximately, $2\frac{1}{2}$ inches.

At *b*, 4 feet from the end of the girder, the horizontal increment of stress on the flange, as previously calculated, is 1,667 pounds per inch of run, while the vertical stress remains the same; the combined action of these two forces produces a resultant stress on the rivets of $\sqrt{1,667^2 + 416^2} = 1,717$ pounds per inch of run, and this divided into the value of one rivet gives $5,251 \div 1,717 = 3.06$, or about $3\frac{1}{4}$ inches. Similar calculations may be made for each panel point to the center of the girder, or until the pitch exceeds the allowable limit of 6 inches.

The above results show that the values of the pitch in which the vertical stress due to the load is taken into account, are nearly the same as those first obtained; the effect of the vertical stress has, therefore, little influence on the pitch of the rivets, and it is hardly necessary to go into such refinement in the design of an ordinary plate girder.



27. Rivets Spaced According to Stress Produced by Bending Moment.—The rivets that connect the flange angles with the web-plate may also be spaced according to the stresses produced on the flanges by the bending moment.

The horizontal stress on the flanges diminishes either way from the point of greatest bending moment toward the end reactions, where it becomes zero, and for any point this stress may be calculated by the application of the principle of moments.

If the bending moment is obtained at any panel point and is divided by the depth of the girder, the stress on the flange at that point will be obtained; and, if this stress is divided by the allowable load on one rivet, the number of rivets required between that point and the end reaction will be obtained.

For example, in the girder used in the previous illustration, Fig. 22, the span being 40 feet and the load 200,000 pounds, the bending moment at the center is equal to $\frac{WL}{8} = \frac{200,000 \times 40}{8} = 1,000,000$ foot-pounds; then the depth of the girder being 4 feet, the flange stress at this point is $1,000,000 \div 4 = 250,000$ pounds. The allowable load on each rivet being 5,251 pounds, the number of rivets between the center and the end reaction is $250,000 \div 5,251 = 48$ rivets, approximately.

Now, although the number of rivets between the end reaction and the center of the girder has been obtained, the pitch of these rivets is still unknown. Since the horizontal stress in the flange varies, being greatest at the ends and least under the position of maximum bending moment, it follows that the rivets should be spaced nearer together at the ends, with an increase in the spacing toward the point of greatest bending moment.

In practical work, the rivet spacing is seldom varied in any one panel; if, however, the flange stress is obtained at each of the stiffeners *b, c, d, e*, and *f*, Fig. 22, the number of rivets required between each of these points and the end reaction may be obtained: by finding the difference between

these numbers for any two consecutive stiffeners, the number of rivets required in the panel between those stiffeners is arrived at. For example, the stresses on the flange at each of the stiffeners of the girder shown in Fig. 22 are as follows:

	BENDING MOMENT FOOT-POUNDS		DEPTH OF GIRDER FEET		FLANGE STRESS POUNDS
At <i>b</i> ,	360,000	÷	4	=	90,000
At <i>c</i> ,	640,000	÷	4	=	160,000
At <i>d</i> ,	840,000	÷	4	=	210,000
At <i>e</i> ,	960,000	÷	4	=	240,000
At <i>f</i> ,	1,000,000	÷	4	=	250,000

The approximate number of rivets between each stiffener and the reaction R_1 is as follows:

Between *b* and R_1 , $90,000 \div 5,251 = 18$ rivets

Between *c* and R_1 , $160,000 \div 5,251 = 31$ rivets

Between *d* and R_1 , $210,000 \div 5,251 = 40$ rivets

Between *e* and R_1 , $240,000 \div 5,251 = 46$ rivets

Between *f* and R_1 , $250,000 \div 5,251 = 48$ rivets

Then the number of rivets required is:

Between *b* and *a*, $18 - 0 = 18$ rivets

Between *c* and *b*, $31 - 18 = 13$ rivets

Between *d* and *c*, $40 - 31 = 9$ rivets

Between *e* and *d*, $46 - 40 = 6$ rivets

Between *f* and *e*, $48 - 46 = 2$ rivets

Consequently, the pitch between the stiffeners will be as follows:

Between *b* and *a*, $48 \div 18 = 2.67$ inches

Between *c* and *b*, $48 \div 13 = 3.69$ inches

Between *d* and *c*, $48 \div 9 = 5.33$ inches

Between *d* and *e*, $48 \div 6 = 8.00$ inches

Between *d* and *c* the theoretical pitch exceeds 6 inches, the limit allowable for a compression member.

By the first method, the pitch at each stiffener or panel point is determined, while by the second the average pitch between two consecutive panel points is obtained; in order

to compare the two, we will reduce the results obtained by the first to the basis of the second. In the first method the pitch at the several stiffeners or panel points was found to be:

At a = 2.52 inches

At c = 4.20 inches

At b = 3.75 inches

At d = 6.30 inches

From these the average pitch between the several points would be:

Between a and b , $(2.52 + 3.75) \div 2 = 3.14$ inches

Between b and c , $(3.75 + 4.20) \div 2 = 3.98$ inches

Between c and d , $(4.20 + 6.30) \div 2 = 5.25$ inches

These, on comparison, are found to correspond approximately with the values 2.67, 3.69, and 5.33 inches obtained by the second method.

28. Rivets Spaced According to Direct Vertical Shear.—This is the method much used in practical work, and will be found to give safe results, corresponding favorably with those obtained by the previous methods. The method is based on the assumption that at any point the horizontal shear between the flange angles and the web-plate is equal to the vertical shear on the girder; for example, the vertical shear at the end stiffener or point a , Fig. 22, is 100,000 pounds; then, according to this method, the shearing stress between the flange angles and the web-plate is 100,000 pounds, distributed over the space between the panel points a and b , and sufficient rivets should be placed between these points to safely sustain this shear.

The allowable web-bearing load on a $\frac{7}{8}$ -inch rivet in a $\frac{3}{8}$ -inch plate being 5,251 pounds, the number of rivets required between a and b is $100,000 \div 5,251 = 20$, approximately; the vertical shear at b is 80,000 pounds, and $80,000 \div 5,251 = 16$, approximately, the number of rivets to be used between b and c ; the shear at c is 60,000 pounds, and $60,000 \div 5,251 = 12$, approximately, the number of rivets to be used between c and d ; similarly, the number of rivets required between d and e is found to be 8. According to these results, the pitch of the rivets between a and b should be $48 \div 20$

= 2.4 inches; between b and c , $48 \div 16 = 3$ inches; between c and d , 4 inches; and from there on, 6 inches.

Rivet spacing in plate girders is governed so largely by practical considerations, that this method is to be recommended on account of its convenience. It gives safe results that agree closely with those obtained by the more cumbersome methods.

29. Graphic Method of Determining Number of Rivets in Vertical Leg of Flange Angles.—Besides the several analytical methods of determining the number of




FIG. 23

rivets through the vertical legs of the flange angles in the several panels of the plate girder, a convenient graphic method that gives approximate results sufficiently accurate for all practical purposes is illustrated in Fig. 23. In this method, a diagrammatic drawing of one-half of the plate girder with the stiffeners properly placed, is made to scale, as shown at $abcd$. The number of rivets required through the vertical leg of the top flange of the plate girder, from the center line of the girder to the abutment, is next calculated

by the method described in Art. 27, which consists in first calculating the bending moment, in foot-pounds, due to the uniformly distributed load and dividing by the depth of the girder, in feet, the result being the horizontal flange stress. This stress divided by the allowable resistance of one rivet will give the number of rivets between the center of the plate girder and the abutment, or between a and b in the sketch. Having determined the number of rivets required between these points, lay off any vertical distance, as be , and through the points a and e describe a parabola by the method explained in Art. 15. Having drawn in the parabola as shown in the figure, extend upwards the center lines of the angle stiffeners on the plate girder until they intersect the parabola, as at f, g, h, i , and j . Through the points of intersection, extend horizontal lines until they intersect the line be , the greatest ordinate of the parabola, which is coincident with the center line of the plate girder. Having proceeded thus far, divide the length of the greatest ordinate of the parabola, or the distance be , into the same number of equal parts as there are rivets required between a and b . This may conveniently be done by applying the scale obliquely between the horizontal lines ke and ab , as explained in connection with the method for determining the length of the flange plates in compound riveted girders.

Assuming that in the diagram forty rivets are required between a and b , and that in consequence there are forty divisions on the scale, the number of rivets between a and l will equal the number of spaces between b and l' , or nine. The number of rivets between l and m will equal the spaces between l' and m' , or eight, while between m and n , from the portion included between m' and n' , there would be required ten rivets. In the panel no , the theoretical number of rivets will equal eight, while between o and p , the theoretical requirements will be fulfilled by placing four rivets through the vertical leg of the flange angles. In all cases where there is a fraction of a rivet in a panel, one additional rivet should be used. Since between a and l nine rivets are required, and the distance from the center of the end stiffener to the

center of the stiffener l is 36 inches, the theoretical pitch between a and l will equal $36 \div 9 = 4$ inches.

In the panel $l m$, since there are eight rivets required, the pitch will be $36 \div 8 = 4.5$ inches. Between m and n , there are ten rivets required and the theoretical pitch will be $57 \div 10 = 5.70$ inches. The number of rivets required between n and o is eight, and consequently their pitch will be $57 \div 8 = 7.13$ inches. This last distance is greater than the maximum allowable pitch for rivet spacing in plate girders; therefore, it is needless to calculate the theoretical pitches in the remaining panels. From these calculations it is probable that in designing the plate girder a pitch of 4 inches will be adopted for the panels $a l$ and $l m$, provided that a single row of rivets is used, while throughout the remaining panels of the girder the rivets will be spaced at the maximum pitch of 6 inches.

30. The student will observe in this method the application of the principles involved in the graphic method for determining the length of the flange plates of the girder supporting the uniformly distributed load. The parabola always represents graphically the bending moment created in a simple beam by a uniformly distributed load. Since the horizontal flange stress varies directly with the amount of the bending moment throughout the girder, it is evident that the parabola likewise truly represents the flange stress between the abutments and the center line of the girder. Likewise, if the middle or greatest ordinate of the parabola represents the horizontal flange stress, to scale, at the center of the girder, the ordinates of the parabola at any point will equal the horizontal flange stress at that point. If the heights of the ordinates projected from the center line of each stiffener are laid off on the center ordinate and the center ordinate is reduced from horizontal flange stress to the number of rivets whose resistance will equal the amount of flange stress, then the ratio between the several ordinates and the greatest ordinate will be the same as the ratio of the number of rivets required between the ordinate and

the abutment of the girder and the number of rivets required between the center of the girder and the abutments; that is, the length mg is to the length cb as the number of rivets between a and m is to the number of rivets between a and b ; thus, if the length of the ordinate mg were equal to $1\frac{1}{4}$ inches and the length of the ordinate cb were $8\frac{1}{2}$ inches, while the number of rivets required between a and b is 40, the number of rivets required between m and a would equal $\frac{mg \times 40}{bc}$; or,

substituting the values, $\frac{1.56875 \times 40}{8.75} = 16.92$, or 17. Fig-

uring in the same way, if lf were $\frac{1}{2}$ inch, the number of rivets between l and a would equal $\frac{.84375 \times 40}{8.75} = 9$. The

difference between the number of rivets required between the points a and m and the points a and l equals $17 - 9 = 8$, which accurately expresses the number of rivets called for by the space lm .

EXAMPLE 1.—A plate girder 60 feet long and 4 feet in depth is loaded with a uniformly distributed load of 2,000 pounds per lineal foot. Required, by the graphic method, the theoretical pitch of rivets through the vertical leg of the flange angle in the several panels, assuming that the allowable resistance of each rivet is 4,800 pounds. The first two panels are 3 feet 9 inches, and the remainder 5 feet in length.

SOLUTION.—The maximum bending moment, which occurs at the center of the girder, is expressed by the formula $M = \frac{WL}{8}$. The value of W , according to the problem, is $2,000 \times 60 = 120,000$, while L or the length of the girder equals 60 ft. By substitution, the bending moment, $M = \frac{120,000 \times 60}{8} = 900,000$ ft.-lb. Since the depth of the girder is 4 ft., the horizontal flange stress at the center of the girder is $900,000 \div 4 = 225,000$ lb. The strength of each rivet equals 4,800 lb; hence, the number of rivets required between the center and the end is $225,000 \div 4,800 = 46.875$, or approximately 47. Having obtained this result, lay out a diagrammatic elevation of one-half of the plate girder to scale, as shown in Fig. 24, locating the stiffeners where required. On this plate girder draw one-half of the parabola, the center ordinate of the parabola coinciding with the center line of the girder. By placing a convenient scale obliquely between the horizontal lines ab and cd , divide the greatest ordinate into 47 equal

parts. Extend upwards from the points $k, l, m, n, o,$ and p the several **ordinates**, as shown, and project the points $e, f, g, h, i,$ and j horizontally to the greatest ordinate of the parabola.

From the diagram, Fig. 24, the number of rivets required between the several panel points is as follows:

Between a and k , 11 rivets	Between n and o , 5 rivets
Between k and l , 10 rivets	Between o and p , 3 rivets
Between l and m , 11 rivets	Between p and b , 1 rivet
Between m and n , 8 rivets	

The distance between the panel points or the center line of the stiffeners for the first two panels is equal to 45 in., while for the




FIG. 24

remaining panels the stiffeners are spaced 60 in. on center lines; hence, the pitch between the several theoretical panel points from the abutment toward the center is as follows:

Between a and k = $45 \div 11$ = 4.09 in.
Between k and l = $45 \div 10$ = 4.5 in.
Between l and m = $60 \div 11$ = 5.45 in.
Between m and n = $60 \div 8$ = 7.5 in.

The calculations need not be carried further, for the theoretical pitch of the rivets in the next panel beyond lm exceeds the maximum allowable pitch for rivets in plate girders. Ans.

EXAMPLE 2.—Find the pitch of the rivets, by the graphic method, in the several panels of a plate girder having a span of 75 feet and a depth of 5 feet. The length of the panels throughout the girder is 5 feet and the load supported is 2,500 pounds per lineal foot. The strength of one rivet may be taken at 5,000 pounds, and the rivets should be placed in two rows.

SOLUTION.—As in the previous examples, the diagram should be laid out and the parabola representing the bending moment drawn, as shown in Fig. 25. The number of rivets required between the




FIG. 25

center and the end is found by dividing the strength of one rivet into the quotient obtained by dividing the bending moment by the depth of the girder. Thus, $\frac{2,500 \times 75 \times 75}{8 \times 5 \times 5,000} = 70.3$, or 71 rivets.

Divide the greater ordinate bc into seventy-one equal spaces and project horizontal lines from the points where the lines drawn from the panel points e, f, g, h , etc. intersect the parabola, thus determining the number of rivets required in each panel. The first requires

eighteen; the second, fifteen; the third, thirteen; etc. Then the spacing in the first panel is $60 \div 18 = 3.3$ in.; for the second panel the pitch is $60 \div 15 = 4$ in.; for the third and fourth panels the pitch is found to be 4.6 in. and 6 in., respectively. As 6-in. angles would undoubtedly be used in this girder, it is advisable to place the rivets in two rows; in the first two panels they may be spaced 6 in. in each row, while in the remaining panels the pitch will be 8 in., which is the maximum pitch for rivets placed in a double row. Ans.

31. Pitch of Rivets in Girders Supporting Concentrated Loads.—In order to illustrate the method of finding the pitch of the rivets in a girder that supports concentrated loads, the conditions shown in Fig. 26 (a) will be




FIG. 26

assumed. The greatest bending moment occurs under the loads and along the length of the girder between them. Lay off $a b$, in (b), equal to the span of the girder, and mark the points c and d where the concentrated loads occur. At these points erect perpendiculars and lay off any convenient distance on each, as $c e$ and $d f$, to represent the bending moment. Draw $a c$, $c f$, and $f b$, and from the panel points

erect perpendiculars intersecting these lines at j , k , and l . The maximum bending moment, occurring at c , is equal to the moment of the reaction about that point, or $100,000 \times 20 = 2,000,000$ foot-pounds. The flange stress equals $2,000,000 \div 5 = 400,000$ pounds. Assuming the strength of one rivet to be 6,750 pounds, the number required is $400,000 \div 6,750 = 59.26$, or 60. Divide ce into sixty equal parts and from




FIG. 27

the points j , k , and l draw horizontal lines cutting ce . These lines show that fifteen rivets are required for each panel up to the point c and from c to d no rivets are necessary, theoretically. The pitch of the rivets in the first four panels is $60 \div 15 = 4$ inches, while for the panels from c to d , they will be spaced at the maximum pitch, or 6 inches.

EXAMPLE.—In Fig. 27 (a) is shown a girder having a span of 40 feet and carrying a concentrated load of 125,000 pounds at a distance of 15 feet from one end. If the girder is 4 feet deep and the

panels are 5 feet in length, what will be the pitch of the rivets, assuming the strength of 1 rivet to be 5,000 pounds?

SOLUTION.—Lay off the span of the girder at ai in view (b), marking the panel points, as at b, c, d , etc., and at the location of the concentrated load erect a perpendicular, as fj , of any convenient height. Draw aj and ji , and from the panel points draw perpendiculars to ai , intersecting these lines at k, l, m, n, o , and p . The maximum bending moment is under the load and is equal to $46,875 \times 25 = 1,171,875$ ft.-lb.; $1,171,875 \div 4 = 292,968.75$ lb. flange stress; $292,968.75 \div 5,000 = 58.59+$, or, say, sixty rivets are required between the concentrated load and each end of the girder. Divide fj into 60 equal parts and draw horizontal lines from the points k, l, m , etc. until they intersect fj . This shows that twelve rivets are required in each panel to the left of the load, while twenty are needed in each panel to the right. The pitch will then be $60 \div 12 = 5$ in. in the first five panels from the left, and $60 \div 20 = 3$ in. in the remaining panels.

32. Rivet Spacing in Flange Plates.—In spacing the rivets that bind the several flange plates together, a sufficient number of rivets, spaced from $2\frac{3}{4}$ to 3 inches on centers, should be used at the ends of each plate to transmit the allowable stress in it to the members below. For the remainder of the plate, the rivets should have the greatest allowable pitch for a compression member; that is, sixteen times the thickness of the thinnest outside plate, provided that such a distance does not exceed 6 inches. To illustrate:

An intermediate flange plate in a certain girder is $\frac{3}{8}$ inch by 12 inches, the sectional area thus being $4\frac{1}{2}$ square inches. From this area is to be deducted the section cut out by two $\frac{7}{8}$ -inch rivet holes, $(1 \times \frac{3}{8}) \times 2 = \frac{3}{4}$ square inch; then the net area of the cover-plate is $4\frac{1}{2} - \frac{3}{4} = 3\frac{3}{4}$ square inches. Assuming that a safe fiber stress of 15,000 pounds was used in calculating the strength of the girder, the safe strength of the cover-plate is $3\frac{3}{4} \times 15,000 = 56,250$ pounds. Now the safe load on a $\frac{7}{8}$ -inch rivet depends, in this position, on the ordinary bearing value of a $\frac{3}{8}$ -inch plate, which, calculated on the basis of a fiber stress of 12,000 pounds, is 5,119 pounds. Hence, the number of rivets required in the end of this cover-plate is $56,250 \div 5,119 = 10.9$, say, 11; but in order to have them symmetrical, there should be six on each side

of the web, and they should be spaced about 3 inches from center to center. The remaining rivets in this plate may have the greatest allowable pitch until the next cover-plate is reached.

EXAMPLES FOR PRACTICE

1. Determine, by the graphic method, the theoretical pitch for the rivets in the vertical legs of the flange angles in a plate girder 45 feet long from center to center of bearing plate. The depth of the girder is 36 inches and the load per lineal foot is 1,400 pounds. The safe resistance of the rivets is determined to be 4,200 pounds; the distance between the stiffeners or panel points is 5 feet throughout the girder.

Ans. $\left\{ \begin{array}{l} \text{First panel, 5 in.} \\ \text{Second panel, 6.67 in.} \\ \text{Third panel, 10 in., etc} \end{array} \right.$

2. Theoretically, how many rivets will be required in the vertical legs of the flange angles between the several panel points or stiffeners of a plate girder having a span of 80 feet and a depth of 5 feet, assuming that the load on the girder is uniformly distributed and is equal to 3,000 pounds per lineal foot; also, that the resistance one rivet offers is 5,200 pounds.

Ans. $\left\{ \begin{array}{l} \text{First panel, 22 rivets} \\ \text{Second panel, 19 rivets} \\ \text{Third panel, 16 rivets} \\ \text{Fourth panel, 13 rivets} \\ \text{Fifth panel, 10 rivets} \end{array} \right.$

3. Find the pitch of the rivets in the vertical legs of the flange angles in a girder 4 feet in depth and having a span of 50 feet, which supports a concentrated load of 90,000 pounds located at a distance of 20 feet from one end of the girder. The value of one rivet is 4,500 pounds and the length of each panel is 5 feet.

Ans. $\left\{ \begin{array}{l} \text{4-in. pitch in four panels at end nearest load} \\ \text{6-in. pitch in remainder} \end{array} \right.$

PRACTICAL DESIGN

33. In order to illustrate the application of the rules and formulas previously given, the following practical problem will be assumed and worked out:

The floor of a building used for light manufacturing purposes is to be supported by three plate girders, as shown at *a, a, a*, Fig. 28. The floor is composed of 1-inch yellow-pine flooring laid on 3" \times 12" hemlock joists, spaced on 16-inch centers; these joists are to carry a plastered ceiling on the under side. The live load on the floor will be

80 pounds per square foot. The girder itself is to extend below the surface of the ceiling and is to be painted. A detail of the construction is shown in Fig. 29.




FIG. 29

The total load on each square foot of floor surface is as follows:

Live load, per square foot of floor surface	80 pounds
Lath and plaster, per square foot of floor surface	8 pounds
1-inch yellow-pine flooring, per square foot of floor surface	4 pounds
Hemlock joist flooring, per square foot of floor surface	6 pounds
Girder (assumed), per square foot of floor surface	8 pounds
Total	<u>106 pounds</u>

The floor area to be supported by one girder is $60 \times 17.5 = 1,050$ square feet; and the total uniformly distributed load on the girder is $1,050 \times 106 = 111,800$ pounds.

The greatest bending moment on the girder is

$$M = \frac{WL}{8} = \frac{111,800 \times 60}{8} = 834,750 \text{ foot-pounds}$$

The depth of the girder is 4 feet, and the allowable unit fiber stress to be used is 15,000 pounds; therefore, the




FIG. 29

required flange area may be determined by formula 4. Substituting the proper values in the formula gives

$$A = \frac{834,750}{4 \times 15,000} = 13.91 \text{ square inches}$$

Assume a flange composed of two $5'' \times 5'' \times \frac{7}{16}''$ angles and two $\frac{3}{8}'' \times 12''$ flange plates; a sketch of the section with the location of the rivets is shown in Fig. 30. The entire area of the flange is:

Two $\frac{3}{8}'' \times 12''$ plates	=	9	square inches
Two $5'' \times 5'' \times \frac{7}{16}''$ angles	=	8.36	square inches
Total,		17.36	square inches

The sectional areas cut out for rivet holes are:

Four $\frac{7}{8}$ -inch holes through $\frac{3}{8}$ -inch plate = 1.312 sq. in.

Four $\frac{7}{8}$ -inch holes through $\frac{7}{16}$ -inch angles = 1.531 sq. in.

Total, 2.843 sq. in.

The net area of the flange is, therefore, $17.36 - 2.84 = 14.52$ square inches, which, since the required area is 13.91 square inches, is ample, and this section will be adopted.

We will now determine the thickness of the web-plate. The reaction at either end is equal to one-half of the load, or 55,650 pounds. Assuming that there are eleven $\frac{7}{8}$ -inch holes cut in line through the web-plate, the net depth of the plate will be $48 - 11 \times .875 = 38.375$ inches. Using an allowable unit shearing stress of 11,000 pounds, the theoretical thickness of the web-plate, from formula 1,

$$\text{is } t = \frac{55,650}{38.375 \times 11,000} = .132 \text{ inch.}$$

However, it is not practicable to use this thickness of metal for a web-plate, since it would not provide sufficient bearing value for the rivets. As it is never good practice to use a web-plate less than $\frac{5}{16}$ inch in thickness, this size will be adopted.

34. The lengths of the flange plates are now required; they may be determined either by the graphic method or by formula 6; using the latter method, the theoretical length of the outside plate is found to be

$$l = 60 \sqrt{\frac{3.844}{14.52}} = 30.87 \text{ feet, or about 30 feet 10 inches, to}$$

which is to be added 1 foot at each end to allow for riveting. The total length of the plate is therefore 32 feet 10 inches, say, 33 feet.

Applying the formula again, the length of the second flange plate is $l = 60 \sqrt{\frac{7.688}{14.52}} = 43.66$ feet, or about 43 feet 8 inches; adding a foot at each end gives us 45 feet 8 inches.




FIG. 30

Consider now the size of the four stiffeners at the end of the girder. The reaction at the end of the girder is 55,650 pounds, and the allowable compressive strength of the material in the girder will be taken at 13,000 pounds. Then the sectional area required in the four angles composing the stiffeners on the plate girder over the abutments is $55,650 \div 13,000 = 4.28$ square inches. Since it would not be advisable to use smaller than a $4'' \times 4'' \times \frac{1}{8}''$ angle in this position, the sectional area of which is 2.4 square inches (see table Properties of Angles, in *Properties of Sections*), it is evident that there will be ample strength in the four stiffeners. The other stiffeners may be made of $3'' \times 3'' \times \frac{1}{8}''$ angles, which is the smallest size that should be used for any girder requiring intermediate stiffeners.

35. The rivet spacing, etc. needs no explanation; it would be well, however, for the student to calculate the number of rivets for the several parts and compare the results with the number actually used, as shown by the detail drawing, Fig. 31. He will undoubtedly find that more rivets are used than are actually required, but he must bear in mind that there are always practical considerations that influence more or less the design of structural work.

In Fig. 31 it will be noticed that the web-plate is spliced at the point *a*. The shear at this point is equal to 55,650 pounds, the reaction at *R*, minus the load on the girder between *R*, and the point *a* under consideration, that is, $55,650 - 37,150 = 18,500$ pounds. A sufficient number of rivets must be placed on the two sides of the joint to take care of this shear safely.

Fig. 32 shows the design of a heavily loaded girder with a long span; this girder was designed to carry a uniformly distributed load of 2,400 pounds per lineal foot and two concentrated loads of 60,000 pounds, placed one on each side of the center of the girder and 12 feet 6 inches therefrom. The unit fiber stress allowable in calculating the flange section was taken at 15,000 pounds.

The student should note particularly the splices on this

girder. In this case it was necessary to splice the flange angles; when this is done, care must be taken to weaken the sectional area of the angle as little as possible by the punching of the rivet holes, and a sufficient number of rivets must also be placed each side of the joint, so that the resistance of the rivet section may equal that of the net section of the flange angles. A careful study should be made of the various other details on this drawing, which represents excellent modern practice.

CAMBERED GIRDERS

ANALYTIC METHOD OF COMPUTING STRESSES

GIRDERS WITH ONE STRUT

36. When wooden girders of great span are heavily loaded, it becomes necessary to strengthen them with iron or steel camber rods, as in Figs. 33 and 34, which show a girder with one and with two supports, respectively. The span of the beam or girder may be considered, in each case, as the distance between the supports, the strength of the girder being thereby materially increased.




FIG. 33

37. In Fig. 35, let W represent the load concentrated at D . Then the stress in the member DC is equal to W . The stress in the other members may be found by applying the following rules:

Rule.—I. *To find the stress in AC or BC , divide the length of the line AC by the length of the line DC , and then multiply this result by one-half of the load W .*

II. *To find the stress in the beam AB , divide the length of the line AD by the length of the line DC , and multiply this result by one-half of the load W .*




FIG. 84

In the diagram, Fig. 85, the members represented by the solid lines are in compression, and those shown dotted are in tension.

The length of the members in the above rules may be taken in feet or inches, but all lengths should be taken in the same




FIG. 85

unit of measurement. The rules may be expressed by the formulas:

$$\text{Stress } DC = + W \quad (11)$$

$$\text{Stress } AC \text{ or } BC = - \frac{AC}{DC} \times \frac{W}{2} \quad (12)$$

$$\text{Stress } AB = + \frac{AD}{DC} \times \frac{W}{2} \quad (13)$$

The + and - signs in the formulas indicate compression and tension, respectively. The + sign denotes that the result obtained is a *compressive stress*. The - sign means that the result is a *tensile stress*.

EXAMPLE.—What is: (a) the tension in the camber rod; (b) the compression on a trussed beam of the dimensions and loads shown in Fig. 36?

SOLUTION.—The load W coming on the strut DC must first be computed. The load is, in this case, usually considered equal to one-half




FIG. 36

the entire load on the beam. But as the beam is composed of one length of timber, and is not hinged at D , being, in effect, a continuous beam, it is more correct to consider the load on the center strut as being five-eighths of the entire load on the beam. The entire load on the beam is equal to $30 \times 1,000 = 30,000$ lb.; five-eighths of $30,000 = 18,750$ lb., the load W acting on the beam directly over the strut DC .

(a) The tension in the camber rod AC is equal to the length $AC \div DC$ multiplied by one-half of W , or, substituting the given dimensions, $15.2 \div 2.5 = 6.08$; and $6.08 \times (\frac{1}{2} \text{ of } 18,750) = 57,000$ lb., the tensile stress in the rod AC . Ans.

(b) To determine the stress in beam AB , divide the length AD by DC , and multiply by one-half of W . Thus, $15 \div 2.5 = 6$; $6 \times (\frac{1}{2} \text{ of } 18,750) = 56,250$ lb., the compressive stress in the beam AB . Ans.

GIRDERS WITH TWO STRUTS

38. In Fig. 37, the calculations for the stresses in the various members are similar to those given for the trussed




FIG. 37

beam with one support. In the two trussed beams, the stress in BH or $CE = W$. The stresses in the other members may be expressed by rule, as follows:

Rule.—I. To obtain the stress in AH or DE , divide the length of AH by the length of BH , and multiply this result by the amount of the load W .

II. To find the stress in AD or HE , divide the length of the line AB by the length of the line BH , and multiply this result by the amount of the load W .

The above may be expressed in formulas:

$$\text{Stress } BH \text{ or } CE \simeq +W \quad (14)$$

$$\text{Stress } AH \text{ or } DE = -\frac{AH}{BH} \times W \quad (15)$$

$$\text{Stress } HE = -\frac{AB}{BH} \times W \quad (16)$$

$$\text{Stress } AD = +\frac{AB}{BH} \times W \quad (17)$$

As previously noted, compression is indicated by the $+$ sign, and tension by the $-$ sign.

EXAMPLE.—A beam is trussed, as shown in Fig. 38. What is: (a) the stress in camber rod HE ; (b) the compression in the beam AD ?

SOLUTION.—The entire load on the beam AD is $30 \times 1,000 = 30,000$ lb. The loads W, W could be considered equal to one-third of the entire load on the beam. But the beam, being a con-




FIG. 38

tinuous girder, as in the previous example, it is better practice to consider it equal to eleven-thirtieths of the entire load. Hence, W is equal to eleven-thirtieths of 30,000, or 11,000 lb.

(a) Applying formula 16, we have

$$\text{Stress } HE = \frac{10}{2.5} \times 11,000 = 44,000 \text{ lb. Ans.}$$

(b) Applying formula 17, we have

$$\text{Stress } AD = \frac{10}{2.5} \times 11,000 = 44,000 \text{ lb. Ans.}$$

GRAPHIC METHOD OF DETERMINING STRESSES

39. The stress in the various members of a trussed beam may be obtained by means of a graphic method that is simply an application of the principles of the resolution of forces. Although not as exact in its results as the mathematical method, it is probably more satisfactory, there being, under it, less chance of errors creeping into the calculation. This method is fully explained in the subjoined example:

A floor is to be supported by yellow-pine girders, each composed of two $4'' \times 12''$ beams, trussed with a wrought-iron rod, as shown in Fig. 39. The span of the girders is 24 feet, and they are spaced 8 feet from center to center. The load is light, amounting to only 40 pounds per square




FIG. 39

foot of floor surface. Required, to determine whether the two yellow-pine beams are sufficiently strong, and what should be the size of the wrought-iron camber rod; also, to design the detail construction for the parts *A* and *B*.

The floor area supported by each girder is $24 \times 8 = 192$ square feet; therefore, the total load on a girder is $192 \times 40 = 7,680$ pounds. To find the stress produced in the different members of the truss by this load, first draw to some convenient scale, as in Fig. 40, the lines *ab*, *ac*, *bc*, and *dc* corresponding, respectively, to the center lines of the girder, the wrought-iron camber rod, and the strut; thus, the line *ab* represents the center line of the pine beams, its length being equal to 24 feet on the assumed scale; while *dc*, drawn perpendicular to *ab* at its middle point, represents, on the same scale, 20 inches, the length of the strut.

In accordance with the principles stated in Art. 37, the load carried by the strut may be taken as five-eighths the total load on the girder; therefore, the force f , Fig. 40, acting downwards on the frame, and borne directly by the strut dc , is $7,680 \times \frac{5}{8} = 4,800$ pounds. This force is held in equilibrium by the stresses in the members of the truss represented by the center lines ad , db , ac , and cb , one-half of it, or 2,400 pounds, being held by each of the pairs a



FIG. 40

and ac , db and bc . Considering the half of the load carried by the pair ad and ac , we have a downward force of 2,400 pounds, which it is required to resolve into two components, one acting along the line ac and the other along ad . Assuming a scale of forces, one, for example, in which a line 1 inch long represents a force of 800 pounds, draw the line dc , Fig. 41, parallel to the center line dc , Fig. 40, of the strut, and make its length correspond to a force of 2,400 pounds, the part of the total load on the strut that is




FIG. 41

borne by the members ad and ac . From the upper extremity of dc , Fig. 41, draw the line da parallel to the line da of Fig. 40, and from the lower extremity draw the line ca parallel to ca of Fig. 40, prolonging these two lines until they meet at the point a . The lines da and ca of Fig. 41 represent, on the scale of forces to which the line dc was drawn, the stresses in the corresponding members of the girder. With the assumed scale of 1 inch = 800 pounds,

the line dc must be $2,400 \div 800 = 3$ inches long; by measurement, the lines da and ca are found to be $21\frac{1}{2}$ and $21\frac{3}{4}$ inches long, respectively; therefore, the stress represented by the line da is $21\frac{1}{2} \times 800 = 17,200$ pounds, and that represented by ca is $21\frac{3}{4} \times 800 = 17,400$ pounds.

DETAIL DESIGN

40. The stress of 17,200 pounds is the total compressive stress produced in the two yellow-pine beams through the action of the downward thrust on the strut. The ultimate resistance to compression of yellow pine per square inch is usually taken at about 4,400 pounds; and as wood is not so reliable as iron, it is considered advisable to use a factor of safety of 6, as against a factor of safety of 4 for the camber rods. Since the trussed girder is secured against lateral deflection by the floor joist, and as it is secured from deflection in an upward direction at the center by the load on the floor, and by the camber rod and strut, the length of the wooden girder, which may be considered as a column under compressive stress, is only one-half the span, or 12 feet. The sectional dimension of the girder is so great in comparison with its length, that it is not necessary to apply the column formula, and its strength may be considered as its resistance to direct compression. Hence, $4,400 \div 6 = 733$ pounds, which is the allowable compressive strength of the girder per square inch of section. Then, 17,200 pounds (the compression) $\div 733$ pounds (the allowable unit stress) $= 23$ square inches required to take care of the compressive stress. As the girder is known to be 12 inches in depth, it is readily seen that this compressive stress will require a section of the timber girder equal to 2 inches by 12 inches.

There is, in addition to this, a transverse stress on one-half of the girder produced by the uniformly distributed load. To find the amount of this bending stress, consider the left-hand half of the girder as a simple beam sustaining a uniformly distributed load equal to one-half of the total load on the girder, that is, a load of $7,680 \div 2 = 3,890$ pounds.

Applying formula 1, the bending moment due to this load is $M = \frac{3,800 \times 12 \times 12}{8} = 70,020$ inch-pounds. The sec-

tion modulus is obtained by the formula $S = \frac{M}{s}$, where S equals the section modulus, M the bending moment in inch-pounds, and s , the allowable unit fiber stress of the material, which is equal, in this case, to 7,300 (the modulus of rupture of yellow pine) \div 6 (the factor of safety) = 1,216 pounds. Substituting the values in the above formula $S = \frac{70,020}{1,216}$

= 57.6, the section modulus required to resist the transverse stress. The bending moment might also be obtained by considering the beam as continuous, having three supports.

41. Since the section modulus of a rectangular beam may be obtained by the formula $S = \frac{bd^2}{6}$, b being the width of the beam in inches, and d the depth, and as S is already known to be 57.6 and the depth of the beam to be 12 inches, the width of the beam required to resist the transverse stress may be obtained by transposing the formula to $b = \frac{S \times 6}{d^2}$; the values substituted give $b = \frac{57.6 \times 6}{12 \times 12}$

= 2.4 inches, which is the width of the required beam. Then, adding the size of the timber required to resist compression and the size of timber required to resist the transverse stress, we have a timber 2 inches wide by 12 inches deep, added to a timber 2.4 or, say, 2½ inches by 12 inches, which equals a piece 4½ inches by 12 inches. In the girder, there are two 4" \times 12" timbers, and, as only a single 4½" \times 12" timber is required, it is evident that the girder is nearly twice as strong as is necessary. However, it must be borne in mind that the theoretical dimensions of members do not always agree with those required in practical rules; for instance, in the above case it would not be good practice to make the combined sectional area of the girder equivalent to that of a 4½" \times 12" timber, as obtained by the calculation,

because this would make each timber a little larger than $2'' \times 12''$, and no timber or girder, especially where rafter or flooring is spiked to it, should be less than 3 inches wide.

42. The ultimate tensile strength of wrought iron is usually taken at 50,000 pounds per square inch; hence, if we use a factor of safety of 4, the safe working fiber stress in the rod must be $50,000 \div 4 = 12,500$ pounds per square inch.

According to the results given by the diagram, the total stress in the rod is 17,400 pounds; therefore, the rod must have a net section of $17,400 \div 12,500 = 1.39$ square inches. The area of a $1\frac{3}{8}$ -inch round rod is 1.48 square inches, and as this is the nearest standard size having the required sectional area, it will be used. As the area at the bottom of the thread of a $1\frac{3}{8}$ -inch bolt is, however, only 1.06 square inches, it will be necessary to upset or enlarge the ends of the rod to a diameter of $1\frac{5}{8}$ inches, in order to get the requisite strength in the threaded portion. The washer at *B*, Fig. 39, must be large enough to distribute the pressure due to the pull of the rod over a sufficient area of the end of




FIG. 42




FIG. 43

the beams to prevent danger of crushing the wood. The allowable compressive strength of yellow pine, parallel to the grain, may be taken as 800 pounds per square inch; this requires a washer whose area is $17,400 \div 800$

$= 22$ square inches, nearly. Using a washer 6 inches wide, extending across the ends of the two beams, we get a bearing area of $2 \times 4 \times 6 = 48$ square inches. In order to

resist the bending stress due to the pull of the rod, the washer should be from $\frac{3}{4}$ inch to 1 inch in thickness.

Figs. 39, 42, and 43, which are so clearly drawn as to require no further explanation, show excellent details for the different parts of the trussed stringer under consideration.

EXAMPLES FOR PRACTICE

1. It is found necessary to truss the yellow-pine purlins supporting a roof, with a wrought-iron camber rod on each side of the purlin; the length of the purlin is 20 feet, the depth of the truss from the center of the rods to the center of the purlin is 14 inches, and the load on the central strut is 3,200 pounds. What should be the diameter of the camber rods if the ends of the rods are upset, and a safety factor of 4 is desired? Ans. $\frac{7}{8}$ in. diam.

2. A girder of 24-foot span is trussed at the center by a camber rod and strut; the depth of the truss from the center of the girder to the center of the rod is 2 feet; if the beam is loaded with a uniformly distributed load of 2,000 pounds per lineal foot: (a) what is the stress on the rod? (b) what is the compressive stress on the beam? (c) what is the stress on the central strut? Ans. $\begin{cases} (a) & 91,200 \text{ lb.} \\ (b) & 90,000 \text{ lb.} \\ (c) & 30,000 \text{ lb.} \end{cases}$

TRUSSED GIRDERS

43. In some buildings it is necessary to use trussed girders to support the weight over a large space, such as a stock exchange, ballroom, etc. They are also sometimes required when it is desired to place a runway or bridge between two adjacent buildings.

In the first case, the girder may support only the weight of the floor above and its live load or it may carry the weight from several stories above, in which case the girder will probably have concentrated loads due to columns, in addition to the uniform load produced by the dead and live loads.

The trussed girders supporting a bridge between two buildings should be proportioned to carry the entire dead load of the bridge and also a moving or rolling load of considerable weight

A trussed girder may be constructed of wood with iron or steel tension members, or it may be entirely of steel.

THE HOWE TRUSS

44. A form of truss known as the **Howe** is shown in Fig. 44. The stresses in the different members may be determined analytically or graphically. As the latter method is explained in *Graphical Analysis of Stresses*, Parts 1 and 2, only the analytic method will be considered here.

Suppose the truss shown in Fig. 44 to be divided along the dotted line $d e$, thus cutting the members a , b , and c ; it is evident that if the section at the left were considered as a separate piece, it would be held in equilibrium by applying to each bar that is cut, a force of the same direction and magnitude as the stress existing in the bar before the




FIG. 44

section was made. Therefore, the forces R_1 , A , a , b , and c acting on this portion of the truss are in equilibrium, and the sum of their moments is zero. To find the stress in a , moments will be taken about the point x . As the other unknown forces b and c and the vertical force A pass through this point, they have no effect on the equilibrium of the forces taken about this point, and consequently only the forces R_1 and a need be considered. The moment of R_1 is $7,000 \times 10 = 70,000$ foot-pounds, and the opposing force a is equal to this amount divided by its lever arm, or $70,000 \div 10 = 7,000$ pounds. Regarding the moment of the reaction as positive, the moment of the force a will be considered as negative, because it tends to revolve around the point x

in the opposite direction from the reaction R_1 , or in the direction of the arrow. Since the arrow points toward the joint z , the stress in a is compressive.

The stress in b is found by taking the center of moments at the point y . As R_1 and c pass through this point, they are not taken into consideration, but only A , a , and b . The moment of a is $7,000 \times 10 = 70,000$ foot-pounds, while that of A is $2,000 \times 10 = 20,000$ foot-pounds. $70,000 - 20,000 = 50,000$ foot-pounds; then the value of b is $50,000 \div 7.071 = 7,071$ pounds.

Taking z as the center of moments, the forces to be considered are R_1 , b , and c . The positive moments of R_1 and b are

$$\begin{array}{rcl} & 7,000 \times 10 = & 70,000 \text{ foot-pounds} \\ \text{and} & 7,071 \times 7.071 = & 50,000 \text{ foot-pounds} \\ \text{Total,} & & 120,000 \text{ foot-pounds} \end{array}$$

Then the force c is equal to $120,000 \div 10 = 12,000$ pounds. The stress in b is compressive, as designated by the arrow, and, in this case, produces a positive moment, while that in c is tensile and produces a negative moment. In the same manner, a section may be taken at any point and thus the stress in any member may be obtained. This method is called the *method of sections*.

45. As stated above, the stress in the three members a , b , and c must be in equilibrium with the external forces on the left of the section; and therefore the algebraic sum of the vertical components of these forces equals zero the same as the horizontal components a and c . Then, as $b \sin \alpha$ is the vertical component of the oblique force, $R_1 - A - b \sin \alpha = 0$; but $R_1 - A$ is equal to the vertical shear in the panel AB . Hence, $\text{shear} - b \sin \alpha = 0$, and transposing, $-b \sin \alpha = -\text{shear}$, or $b \sin \alpha = \text{shear}$. Then $b = \frac{\text{shear}}{\sin \alpha} = \text{shear} \times \sec \alpha$, and the following rule may be deduced:

Rule.—*The stress in any oblique web member is equal to the vertical shear in the panel multiplied by the secant of the angle that the member makes with the vertical.*

It is assumed that the angle α is equal to 45° . After obtaining the secant of α , as explained in Art. 46, and applying this rule to determine the stresses in the remaining web members, it is found that

Stress in $CG = (7,000 - 2,000 - 2,000) \times \sec \alpha = 3,000 \times 1.4142 = 4,242.6$ pounds.

Stress in $DH = (7,000 - 2,000 - 2,000 - 2,000) \times \sec \alpha = 1,000 \times 1.4142 = 1,414.2$ pounds.

Stress in $AE = 7,000 \times \sec \alpha = 7,000 \times 1.4142 = 9,899.4$ pounds.

46. The same results may be obtained by the following method: The load at the center of the truss or the point D is equal to 2,000 pounds and half of this load goes to each of the compression members DH and DJ , since DI does not take any of the load, but is simply a rod to prevent the chord HJ from sagging, or to assist in supporting any load placed on the lower chord. Therefore, the stress in each of these members is equal to one-half of the load at D multiplied by the secant of the angle HDI . The secant of the angle may be found from a table of secants, if the angle is known. If not, it may be calculated by considering HDI as a right triangle and ascertaining the ratio between the hypotenuse DH and the side DI adjacent to the angle, which ratio is equal to the secant of the angle α . Therefore, $\sec \alpha = \frac{DH}{DI}$; but $DH = \sqrt{DI^2 + HI^2}$; therefore, $\sec \alpha = \frac{\sqrt{DI^2 + HI^2}}{DI}$. This formula, so as to apply to any of the other panels, may be stated as follows:

$$\sec \alpha = \frac{\sqrt{(\text{height of panel})^2 + (\text{width of panel})^2}}{\text{height of panel}}$$

As the width and height in this instance are equal, the angle α is 45° , the secant of which is 1.4142. The horizontal thrusts of the members HD and DJ are resisted by the tension member HJ . The vertical thrusts must also be resisted at the points H and J by the tension members CH

and KJ , which transmit the downward forces to the points C and K . At the point C , there is applied a load of 2,000 pounds in addition to the force of 1,000 pounds transmitted by the tension bar CH from the member HD . Consequently, the stress in CG is $1,000 + 2,000 = 3,000$ pounds multiplied by the secant of the angle HDI , or α , since the compression web members are all slanted at the same angle. The stresses in the other oblique web members may be found in a similar manner and be expressed in a tabulation as follows:

$$\begin{aligned} DI &= 2,000 \times \frac{1}{2} \times \sec \alpha = 1,000 \times 1.4142 = 1,414.2 \text{ pounds} \\ CG &= 2,000 \times 1\frac{1}{2} \times \sec \alpha = 3,000 \times 1.4142 = 4,242.6 \text{ pounds} \\ BF &= 2,000 \times 2\frac{1}{2} \times \sec \alpha = 5,000 \times 1.4142 = 7,071.0 \text{ pounds} \\ AE &= 2,000 \times 3\frac{1}{2} \times \sec \alpha = 7,000 \times 1.4142 = 9,899.4 \text{ pounds} \end{aligned}$$

Theoretically, there is no stress in the vertical web DI , but practically there would be a slight tensile stress. In the web CH , there is a tensile stress equal to the vertical component of the stress in HD , or 1,000 pounds, which stress may be found by means of the formula $CH = \frac{DH}{\sec \alpha} = \frac{1,414.2}{1.4142} = 1,000$. The stress in BG is equal to the vertical component of the stress in CG and is found, by means of the preceding formula, to be 3,000 pounds. The other stresses may be found in a similar manner and are as given in the following tabulation:

$$\begin{aligned} DI &= 0 \\ CH &= 2,000 \times \frac{1}{2} = 1,000 \text{ pounds} \\ BG &= 2,000 \times 1\frac{1}{2} = 3,000 \text{ pounds} \\ AF &= 2,000 \times 2\frac{1}{2} = 5,000 \text{ pounds} \end{aligned}$$

47. The stresses in the horizontal members, or chords, may be obtained when the stresses in the web members are known. Consider the compression member AE separately, as shown in Fig. 45. Then the forces acting on it are the reaction R , of 7,000 pounds and a vertical load at A of 2,000 pounds. The stress in AF was found to be 5,000 pounds, so that the total downward force acting on the end of the strut

AE is $2,000 + 5,000 = 7,000$ pounds, which just counteracts the reaction, or upward force. The stress in AF is the vertical component of that in AE , while the stress in EF is the horizontal component of AE . It may also be observed that in order to keep the end of the strut from being pushed upwards by the reaction, the force EF must act away from the joint E , or in the direction of the arrow; this indicates a tensile stress in the chord. In order that the strut may be in equilibrium, it is necessary to have a horizontal force at the point A equal and opposite in direction to the force EF . Therefore, the stress in AB is equal to that in EF , but it is a compressive stress, as indicated by the arrow. This stress is equal to the horizontal component of the stress in AE , which may be expressed as $AF \times \tan \alpha$; similarly, the stress in B or FG , Fig. 44, is equal to the horizontal component of the stress in BF , or $BG \times \tan \alpha$. The tangent of α is obtained from the formula $\tan \alpha = \frac{\text{width of panel}}{\text{height of panel}}$.




FIG. 45

Substituting these values for the problem under consideration, the value of the tangent is $\frac{10}{10} = 1$. The following notation of the chord stresses may now be made:

$$AB = EF = 7,000 \times \tan \alpha = 7,000 \times 1 = 7,000 \text{ pounds.}$$

$$BC = FG = (7,000 + 5,000) \times \tan \alpha = 12,000 \times 1 = 12,000 \text{ pounds.}$$

$$CD = GH = (7,000 + 5,000 + 3,000) \times \tan \alpha = 15,000 \times 1 = 15,000 \text{ pounds.}$$

$$HI = IJ = (7,000 + 5,000 + 3,000 + 1,000) \times \tan \alpha = 16,000 \times 1 = 16,000 \text{ pounds.}$$

It may be noticed that the stress in the outside panel of the upper chord, or AB , is equal to the shear in that panel multiplied by the tangent of the angle AFB , that is, equal to the reaction $\times \tan \alpha$, while in the next panel, or BC , the stress is equal to the sum of the shears in AB and $BC \times \tan \alpha$.

In CD , the stress is equal to shear in AB + shear in BC + shear in $CD \times \tan \alpha$. Hence, the following rule may be given for the stress in a chord member of a Howe truss:

Rule.—*To find the stress in any chord member, multiply the sum of the shears in all panels from the reaction up to and including the one in question, by the tangent of the angle that the inclined web member makes with the vertical.*

The portions of the upper chord are all in compression, while those of the lower chord are all in tension. If it is desired to check the results obtained by either of the preceding methods, the stress diagram may be drawn for the truss and the stresses measured on it.

MAXIMUM STRESSES PRODUCED BY LIVE LOAD

48. The live and dead loads are generally figured separately in structures where it is necessary to provide for a moving load, such as a bridge. The greatest chord stress is produced when the live load covers the entire truss, while the greatest stress is created in the web member when the live load covers the portion of the truss from the web member in question to the remote abutment and the portion to the other abutment is unloaded. This fact may be demonstrated by considering the following example: The live load per panel in Fig. 44 is 5,000 pounds. When the live load covers the entire truss, the reactions are 17,500 pounds and the chord and web stresses are as follows:

WEB STRESSES

$$\begin{aligned}
 AF &= 17,500 - 5,000 &= 12,500 \text{ pounds} \\
 BG &= 17,500 - 5,000 - 5,000 &= 7,500 \text{ pounds} \\
 CH &= 17,500 - 5,000 - 5,000 - 5,000 &= 2,500 \text{ pounds} \\
 DI &= 0 \\
 AE &= 17,500 \times \sec \alpha = 17,500 \times 1.4142 &= 24,748.5 \text{ pounds} \\
 BF &= 12,500 \times \sec \alpha = 12,500 \times 1.4142 &= 17,677.5 \text{ pounds} \\
 CG &= 7,500 \times \sec \alpha = 7,500 \times 1.4142 &= 10,606.5 \text{ pounds} \\
 DH &= 2,500 \times \sec \alpha = 2,500 \times 1.4142 &= 3,535.5 \text{ pounds}
 \end{aligned}$$

CHORD STRESSES

$$AB = EF = 17,500 \times \tan \alpha = 17,500 \times 1 = 17,500 \text{ pounds}$$

$$BC = FG = (17,500 + 12,500) \times \tan \alpha = 30,000 \times 1 = 30,000 \text{ pounds}$$

$$CD = GH = (17,500 + 12,500 + 7,500) \times \tan \alpha = 37,500 \times 1 = 37,500 \text{ pounds}$$

$$HI = (17,500 + 12,500 + 7,500 + 2,500) \times \tan \alpha = 40,000 \times 1 = 40,000 \text{ pounds}$$

49. Assuming the truss to be loaded at every panel point except A , as shown in Fig. 46, the left-hand reaction R_1 is found by taking moments about R_2 . Considering the width of the panel as the unit of measurement, the moments of the loads are $(5,000 \times 1) + (5,000 \times 2)$, etc., and as the load is the same at each panel point and the lever arms increase




FIG. 46

in arithmetical progression, the sum of the lever arms, or the terms of the progression, is equal to the sum of the first and last terms multiplied by half the number of terms; therefore, the sum of the moments about R_2 is $5,000 \times \frac{6(1+6)}{2} = 105,000$, and the reaction at R_1 is equal to this amount divided by the number of panels, or $105,000 \div 8 = 13,125$ pounds. The stresses now existing are as follows:

WEB STRESSES

$$AF = 13,125 \text{ pounds}$$

$$BG = 13,125 - 5,000 = 8,125 \text{ pounds}$$

$$CH = 13,125 - 5,000 - 5,000 = 3,125 \text{ pounds}$$

$$DI = 0$$

$$AE = 13,125 \times \sec \alpha = 13,125 \times 1.4142 = 18,561 \text{ pounds}$$

$$BF = 13,125 \times \sec \alpha = 13,125 \times 1.4142 = 18,561 \text{ pounds}$$

$$CG = 8,125 \times \sec \alpha = 8,125 \times 1.4142 = 11,490 \text{ pounds}$$

$$DH = 3,125 \times \sec \alpha = 3,125 \times 1.4142 = 4,419 \text{ pounds}$$

CHORD STRESSES

$$AB = EF = 13,125 \times \tan \alpha = 13,125 \times 1 = 13,125 \text{ pounds}$$

$$BC = FG = (13,125 + 13,125) \times \tan \alpha = 26,250 \times 1 = 26,250 \text{ pounds}$$

$$CD = GH = (13,125 + 13,125 + 8,125) \times \tan \alpha = 34,375 \times 1 = 34,375 \text{ pounds}$$

$$HI = (13,125 + 13,125 + 8,125 + 3,125) \times \tan \alpha = 37,500 \times 1 = 37,500 \text{ pounds}$$

50. Consider the load as covering all points except *A* and *B*. The reaction at *R*₁ is equal to $\left[\frac{5(1+5)}{2} \times 5,000 \right] \div 8 = 9,375$ pounds, and the stresses are as shown in the following tabulation:

WEB STRESSES

$$AF = 9,375 \text{ pounds}$$

$$BG = 9,375 \text{ pounds}$$

$$CH = 9,375 - 5,000 = 4,375 \text{ pounds}$$

$$DI = 0$$

$$AE = 9,375 \times \sec \alpha = 9,375 \times 1.4142 = 13,258 \text{ pounds}$$

$$BF = 9,375 \times \sec \alpha = 9,375 \times 1.4142 = 13,258 \text{ pounds}$$

$$CG = 9,375 \times \sec \alpha = 9,375 \times 1.4142 = 13,258 \text{ pounds}$$

$$DH = 4,375 \times \sec \alpha = 4,375 \times 1.4142 = 6,187 \text{ pounds}$$

CHORD STRESSES

$$AB = EF = 9,375 \times \tan \alpha = 9,375 \times 1 = 9,375 \text{ pounds}$$

$$BC = FG = (9,375 + 9,375) \times \tan \alpha = 18,750 \times 1 = 18,750 \text{ pounds}$$

$$CD = GH = (9,375 + 9,375 + 9,375) \times \tan \alpha = 28,125 \times 1 = 28,125 \text{ pounds}$$

$$HI = (9,375 + 9,375 + 9,375 + 4,375) \times \tan \alpha = 32,500 \times 1 = 32,500 \text{ pounds}$$

The results of the preceding calculations, arranged in a convenient form, are given below:

FULLY LOADED	ALL JOINTS LOADED EXCEPT <i>A</i>	ALL JOINTS LOADED EXCEPT <i>A</i> AND <i>B</i>
$AE = 24,748.5$	18,561	13,258
$BF = 17,677.5$	18,561	13,258
$CG = 10,606.5$	11,490	13,258
$DH = 3,535.5$	4,419	6,187
$AB = EF = 17,500.0$	13,125	9,375
$BC = FG = 30,000.0$	26,250	18,750
$CD = GH = 37,500.0$	34,375	28,125
$HI = 40,000.0$	37,500	32,500

It may be observed from these results that the greatest stress is produced in the chord members when the entire truss is loaded; also, that the greatest stress in AE is when the truss is fully loaded. In BF the greatest stress is created when the truss is loaded to the right of the panel, including this member, that is, all joints are loaded except A , while CG has the greatest stress when all joints except A and B are loaded. If loads are considered at every point except A , B , and C , it will be found that the greatest stress occurs in DH under that condition.

51. Counterbracing is required in the panels where the shear created by the dead load is exceeded by the shear of opposite kind produced by the live load. This may be readily ascertained by drawing the shear diagrams; for instance, Fig. 47 (*a*) represents the frame diagram of the truss having only the dead load on it. The live load is 5,000 pounds at each panel point and will be considered first as being applied at only the first panel point to the left, or AB . Then the reaction for the live load is $\frac{5,000 \times 70}{80}$ = 4,375 pounds at R_1 and $5,000 - 4,375 = 625$ pounds at R_2 . In the shear diagram (*b*), the shaded portion represents the shear, to scale, created by the dead load along the truss; the portion above the line will be called positive and

that below negative. The heavy line designates the shear produced by the live load, which for the first panel is equal to the left reaction, while for the remainder of the truss it is

equal to the right reaction, or 625 pounds. It is observed from this diagram that the negative shear from the live load does not exceed the positive shear produced by the dead load and, consequently, no counterbraces are required.

The shear shown by the heavy line in the diagram (c) is produced by placing live loads on two panel points of the truss, at AB and BC in (a). As will be observed, the negative shear in the panel D , created by the live load and represented by the heavy line, exceeds the positive shear produced by the dead load, that is, x is greater than y ; therefore, it will be necessary to counterbrace this panel. Also, the diagrams (d) and (e) show that counterbracing is required in the panel D ,




FIG. 47

but not in any other, though in practice the panel C would be braced as an additional precaution. Then, theoretically, the only panels to be braced are those at D and E .

THE PRATT TRUSS

52. The Pratt truss has its vertical members in compression and the inclined members in tension, while the top chord is in compression and the lower one in tension. This fact may be readily determined by considering a portion of the truss as being separated from the remainder by a line, as at de , Fig. 48, cutting three members of the truss. The kind of stress in each of these members and its amount may then be found by taking moments about different points, as x , y , and z . To ascertain the stress in the member c , moments will be taken about the point x as a center. The positive moment is $7,000 \times 24 = 168,000$ foot-pounds, while the negative moment is $2,000 \times 12 = 24,000$ foot-pounds.




FIG. 48

The algebraic sum is $168,000 - 24,000 = 144,000$ foot-pounds, which is the moment of the stress in c . The lever arm of this force is 15 feet; hence, the stress is equal to $144,000 \div 15 = 9,600$ pounds. The surplus of the moment $R_1 \times 24$ is therefore equal to 144,000 foot-pounds and is positive. To create equilibrium, the moment of c should equal this amount, but be of opposite sign, therefore negative, and must act in the direction shown by the arrow, or away from the joint, which indicates that it is a tensile stress.

The stress in b is determined by considering the moments about the point y as a center. The positive moments are:

$$\begin{array}{rcl} 7,000 \times 12 & = & 84,000 \text{ foot-pounds} \\ 2,000 \times 12 & = & 24,000 \text{ foot-pounds} \\ \text{Total,} & & 108,000 \text{ foot-pounds} \end{array}$$

The negative moment of c is $9,600 \times 15 = -144,000$ foot-pounds; hence, the excess of this moment over the positive one is $108,000 - 144,000 = -36,000$ foot-pounds. To produce equilibrium, the moment of b should be of opposite sign, that is, positive, and as its lever arm is 9.37 feet, its stress is equal to $36,000 \div 9.37 = 3,842$ pounds. The arrow points away from the joint, and the stress is therefore tensile.

The stress in a may be obtained by considering z as the center of moments. The positive moments are:

$$7,000 \times 24 = 168,000 \text{ foot-pounds}$$

$$3,842 \times 9.37 = 36,000 \text{ foot-pounds}$$

$$\text{Total,} \quad 204,000 \text{ foot-pounds}$$

The negative moment is $2,000 \times 12 = 24,000$ foot-pounds. As the positive moments exceed the negative by $204,000 - 24,000 = 180,000$ foot-pounds, the moment of a must equal this amount in order to establish equilibrium and it must be of opposite sign, or negative. As its lever arm is 15 feet the stress is equal to $180,000 \div 15 = 12,000$ pounds. In order to produce a negative moment, this force must act in the direction of the arrow shown at a , or toward the joint, and consequently the stress is compressive. The stress in any member may be obtained by this method.

53. The method of determining the stresses by a notation, as explained in connection with the Howe truss, may also be applied to this form of truss. The stress in EJ is compressive and equal to the amount of the load at E , or 2,000 pounds. One-half of this stress must be taken care of by each of the rods, DJ and FJ ; thus, 1,000 pounds is transmitted to the point D by DJ , so that the compression in DI is $2,000 + 1,000 = 3,000$ pounds. This amount is carried up the oblique member IC , and consequently the stress in CH is $2,000 + 3,000 = 5,000$ pounds. Hence, the stress in the vertical web members may be tabulated as follows:

Stress in $EJ = 2,000$ pounds

Stress in $DI = 3,000$ pounds

Stress in $CH = 5,000$ pounds

Stress in $BG = 7,000$ pounds

The stress in DJ is equal to 1,000 multiplied by the secant of the angle DJE , or α ; in CI it is equal to 3,000 multiplied by $\sec \alpha$, etc. Hence, the following notation may be made:

Stress in $DJ = 1,000 \times \sec \alpha = 1,000 \times 1.28075 = 1,281$ pounds.

Stress in $CI = 3,000 \times \sec \alpha = 3,000 \times 1.28075 = 3,842$ pounds.

Stress in $BH = 5,000 \times \sec \alpha = 5,000 \times 1.28075 = 6,404$ pounds.

Stress in $AG = 7,000 \times \sec \alpha = 7,000 \times 1.28075 = 8,965$ pounds.

The stress in the chord members may be obtained as explained in connection with the Howe truss. For instance, the stress in AB is equal to the horizontal component of that in AG and is a compressive stress, while the stress in GH is equal to the same amount, but is tensile. In this problem, the horizontal component of AG is equal to $7,000 \times \tan \alpha = 7,000 \times .800196 = 5,601$ pounds. The stress in the members BC and HI is equal to $(7,000 + 5,000) \times \tan \alpha = 12,000 \times .800196 = 9,602$ pounds. Then the chord stresses may be written as follows:

$AB = GH = 7,000 \times \tan \alpha = 7,000 \times .800196 = 5,601$ pounds.

$BC = HI = (7,000 + 5,000) \times \tan \alpha = 12,000 \times .800196 = 9,602$ pounds.

$CD = IJ = (7,000 + 5,000 + 3,000) \times \tan \alpha = 15,000 \times .800196 = 12,003$ pounds.

$DE = (7,000 + 5,000 + 3,000 + 1,000) \times \tan \alpha = 16,000 \times .800196 = 12,803$ pounds.

which shows the horizontal components of these stresses. The members bm and cn are in compression; hence, their vertical components x' and z' act downwards and their horizontal components x and z toward the left, as shown by the arrows. The member bn is in tension and its vertical component y' is an upward force, while its horizontal component y acts toward the left. Therefore, the sum of the horizontal components, since all act in the same direction, is $x + y + z$, and the stress in no must be equal to this sum and act in the opposite direction. Then, as the horizontal component of any web member is equal to the vertical shear in that member multiplied by the tangent of the angle which that member makes with the vertical, the following rule may be stated:

Rule.—*The stress in any chord member is equal to the sum of the products of the vertical shear in each web member between the chord in question and the nearer reaction, multiplied by the tangent of the angle that the web member makes with the vertical.*

Hence, the stress in no is equal to $s_1 \tan \alpha_1 + s_2 \tan \alpha_2 + s_3 \tan \alpha_3$, but as α_1 , α_2 , and α_3 are all equal, the equation becomes, stress in $no = \tan \alpha (s_1 + s_2 + s_3)$.

55. The stress in the web member is equal to the vertical component of its stress multiplied by the secant of the angle that the web makes with the vertical, or, referring to Fig. 49 (b) $x' \times \sec \alpha$; but as the vertical component of the oblique force represents the shear in that member, its stress is equal to the shear multiplied by the secant of its angle, or $s \times \sec \alpha$. Hence, the following rule may be given:

Rule.—*The stress in any web member is equal to the shear in that member multiplied by the secant of its angle with the vertical.*

Assume a Warren truss to be of the dimensions given in Fig. 49; the sum of the live and dead loads is taken at 26,000 pounds per panel. It will be noticed that at the points b and k there is a load of only 19,500 pounds. This may be explained by supposing that the extent of a panel is that part of the truss included between two adjoining apexes and that between each of these there is a distributed load of 26,000

pounds. Between the points a and b there is only one-half panel with a load of 13,000 pounds, one-half of which is supported directly at the point m through the member am . The other half, or 6,500 pounds, is supported at the point b , which point also supports one-half of the total panel load bc , or 13,000 pounds. Adding these loads, $13,000 + 6,500$, gives a total load of 19,500 pounds, as indicated in the diagram. The small load at a is disregarded and, in fact, the members am and ab are not considered in determining the stresses in the members of the truss. Applying the rule given in this article, the stress in the member bm is equal to the shear in that member, which is 123,500 pounds, since no load is applied until the point b is reached, multiplied by the secant of α ; as this angle is 30° , its secant is 1.1547. Hence,

Stress in bm is $123,500 \times 1.1547 = 142,605$ pounds.

Shear in bn is $123,500 - 19,500 = 104,000$ pounds.

Stress in bn is $104,000 \times 1.1547 = 120,089$ pounds.

The shear in cn is the same as in bn and consequently the stress is the same amount, but a different kind, the stress in cn being compressive, while that in bn is tensile. The stresses in the remaining web members may be obtained similarly. The chord stress, as previously stated, is equal to the sum of the shears in all the web members to the left, multiplied by the tangent of α . Then,

Stress in $mn = s_1 \times \tan \alpha = 123,500 \times .57735 = 71,303$ pounds.

Stress in $no = (s_1 + s_2 + s_3) \times \tan \alpha = (123,500 + 104,000 + 78,000) \times .57735 = 176,380$ pounds.

Stress in $op = (s_1 + s_2 + s_3 + s_4 + s_5) \times \tan \alpha = (123,500 + 104,000 + 104,000 + 78,000 + 78,000) \times .57735 = 281,458$ pounds.

Considering the upper chord, the stress in $bc = (s_1 + s_2) \times \tan \alpha = (123,500 + 104,000) \times .57735 = 131,347$ pounds.

Stress in $cd = (s_1 + s_2 + s_3 + s_4) \times \tan \alpha = (123,500 + 104,000 + 104,000 + 78,000) \times .57735 = 467,365$ pounds.


The stresses in all the chord members may be obtained similarly, and those in the lower chord are always in tension while those in the upper are in compression.

THE LATTICE TRUSS

56. The lattice truss, or double Warren, as it is sometimes called, is shown in Fig. 50. It consists of two systems of triangular bracing, one of which is represented in the figure by full lines and the other by dotted lines. The truss is equivalent to the two trusses welded into one and the loads at c , e , and g , in view (a), are considered as being carried to the abutments by the diagonals shown dotted, while the full-line diagonals transfer the loads at b , d , f , and h to the abutments. The chord stresses are found by the method of chord increments, as in the Warren truss. For instance, the stress in ab is equal to the vertical shear in the web ak multiplied by the tangent of the angle jak , or α , which in this case is 45° , and consequently its tangent is 1. Taking the dead load at 350 pounds per foot, the panel loads are $350 \times 8 = 2,800$ pounds. The system of diagonals to which ak belongs receives three panel loads; then half of the center load will be carried to the left reaction down the diagonal em and up mc , at which point another load is added, so that one and one-half panel loads are carried down to k and up to a . Hence, the vertical shear in ak is $1\frac{1}{2} \times 2,800 = 4,200$ pounds, and the stress in the chord ab is shear in $ab \times \tan \alpha = (1\frac{1}{2} \times 2,800) \times 1 = 4,200$ pounds.

The stress in the chord bc is equal to the sum of the shears in all the web members cut by the curved section xx , multiplied by $\tan \alpha$. The whole load at d supported by the full-line diagonals is transferred to the left abutment by passing down dl and up lb , where it encounters another panel load; hence, the vertical shear in bj is equivalent to two panel loads, while that in bl is equal to one panel load. As ak is equal to one and one-half panel loads, the stress in the chord bc equals $(1\frac{1}{2} + 2 + 1) \times 2,800 \times 1 = 12,600$ pounds. In the same manner, the stresses in all the chord members may be determined, those in the upper chord always being compressive and in the lower tensile.

The stress in any web member is equal to the vertical shear in that member multiplied by the secant of its angle with



the vertical, which, in this truss, is 1.4142; hence, the stress in ak produced by the dead load is $1\frac{1}{2} \times 2,800 \times 1.4142 = 5,940$ pounds. To find the maximum stresses in the webs, it is necessary to consider the truss as only partly covered by the live load; therefore, it will be assumed that the live load extends over the entire portion of the truss to the right of the panel c , as shown in Fig. 50 (b). As stated previously, the two systems of diagonals must be considered separately in determining the web stresses, the loads supported by the dotted diagonals and the resulting reactions being shown in Fig. 50 (c). The dead-load reaction is marked $D. L.$, while that produced by the live load is designated by $L. L.$ The stress in ak , under the condition of loading shown in (c), is $(3,000 + 5,600 - 1,400) \times \sec \alpha = 7,200 \times 1.4142 = 10,182$ pounds. The same stress exists in kc , while in cm and me it is $(3,000 + 5,600 - 1,400 - 2,800) \times \sec \alpha = 4,400 \times 1.4142 = 6,222$ pounds. In eo and og , the stress is $(3,000 + 5,600 - 1,400 - 2,800 - 2,800 - 4,000) \times \sec \alpha = -2,400 \times 1.4142 = -3,394$ pounds. The stress in gq and qi is $(3,000 + 5,600 - 1,400 - 2,800 - 2,800 - 4,000 - 2,800 - 4,000) \times \sec \alpha = -9,200 \times 1.4142 = -13,011$ pounds.

The $-$ sign in the last two results does not denote a tensile stress, but simply indicates that the shear in these members is negative, when the shear at the left-hand reaction is considered as positive; in other words, the shear changes sign at the point e , for the system of dotted diagonals.

Referring to Fig. 50 (d), the stresses in the full-line diagonals are determined as follows:

Stress in $jb = (5,600 + 4,500) \times \sec \alpha = 10,100 \times 1.4142 = 14,283$ pounds.

Stress in bl and $ld = (5,600 + 4,500 - 2,800) \times \sec \alpha = 7,300 \times 1.4142 = 10,324$ pounds.

Stress in dn and $nf = (5,600 + 4,500 - 2,800 - 2,800 - 4,000) \times \sec \alpha = 500 \times 1.4142 = 707$ pounds.

Stress in fp and $ph = (5,600 + 4,500 - 2,800 - 2,800 - 4,000 - 2,800 - 4,000) \times \sec \alpha = -6,300 \times 1.4142 = -8,909$ pounds.

Stress in $hr = (5,600 + 4,500 - 2,800 - 2,800 - 4,000 - 2,800 - 4,000 - 2,800 - 4,000) \times \sec \alpha = -13,100 \times 1.4142 = -18,526$ pounds.

The same method may be pursued to determine the web stresses under the different conditions of loading, and the maximum stress in each member may thus be ascertained. The members ak , cm , go , iq , and bl , dn , fn , hp are in tension, while ck , em , eo , gq , and bj , dl , fp , hr are in compression.

57. In Fig. 51, the stress diagrams for the different conditions of loading are shown. The stresses may be scaled from these diagrams, computed by the method of sections, or determined analytically, as explained below.

When the dead load only is considered, the reactions produced by the loads on the full-line diagonals are each 5,600 pounds; then the stress in hr , Fig. 51 (*a*), is compressive and is equal to $5,600 \times \sec \alpha$. At the point h , a load of 2,800 pounds counteracts half of the force, thus leaving $5,600 - 2,800 = 2,800$ pounds of vertical force that creates tension in the member hp . The same force is carried up the web fp , producing a compressive stress in that member, and at f it meets the load of 2,800 pounds, which is just equal to it and consequently entirely neutralizes it. Hence, under a uniform load, there is no stress in fn and dn ; that is, the truss would be stable without these members. This condition is changed, however, when the live load of 4,000 pounds is applied at H/I . The right-hand reaction is then equal to 9,100 pounds and the left-hand reaction to 6,100 pounds. The stress in hr is $9,100 \times \sec \alpha$; at h , the load of $4,000 + 2,800 = 6,800$ pounds is encountered and a force of $9,100 - 6,800 = 2,300$ pounds is left to pass down hp and up pf . The load of 2,800 pounds at f must be taken care of, but as fp can take only 2,300 pounds, the remaining 500 pounds must be resisted by fn ; hence, the stress in fn , which is compressive, is equal to $500 \times \sec \alpha$. The same amount of stress is created in dn , but it is of opposite character, or tensile. At d , another load of 2,800 pounds is applied, so that dl must carry $2,800 + 500 = 3,300$ pounds.



The stress in this member is, of course, compressive and the same amount of tension exists in bl . At b , the load of 2,800 pounds is added, thus producing a force of $(3,300 + 2,800) = 6,100$ pounds to be resisted by bj ; therefore, the compression in this member is $6,100 \times \sec \alpha$. If the live load is applied at the points h and f , the right-hand reaction is 11,600 pounds and the left-hand, 7,600 pounds. Then the stress in hr is $11,600 \times \sec \alpha$, while in hp and fp the stress is $(11,600 - 6,800) \times \sec \alpha$. At f , another load of 6,800 pounds is to be resisted and as fp can take care of 4,800 pounds, the remainder, or 2,000 pounds, must be resisted by fn . Hence, the compression in fn and the tension in dn are equal to $2,000 \times \sec \alpha$. In dl and bl , the stress is $(2,000 + 2,800) \times \sec \alpha$, while the compression in bj is $(2,000 + 2,800 + 2,800) \times \sec \alpha$. In this manner the web stresses may be determined for all conditions of loading. It will be observed that when the live load comes from the right, as considered in the calculations given above, the stress in fn is compressive, while in dn it is tensile, but when the live load is applied at the left-hand end of the truss, the stresses in these members will be reversed. Therefore, it will be necessary to make dn and fn capable of resisting both tension and compression. In the dotted diagonals, the kind of stress does not change under the different conditions of loading.

LATERAL BRACING

58. When a trussed girder is used to support a tramway between two buildings or in any similar position, it is necessary to take into consideration the wind pressure on the girder, and to provide a system of lateral bracing to resist this pressure. When the girder is not enclosed, as in a bridge, the wind acts on both sides of it, that is, on both trusses forming the girder; but the area to be regarded as exposed to the wind is a question that the designer must decide. If the girder is enclosed, of course the surface exposed to the wind is equal to the entire area of one covered side.

In the following example the stresses in the members of the trusses may be determined as previously explained; therefore, only the bracing required to resist the wind pressure will be considered.




FIG. 52

EXAMPLE.—A covered runway, or bridge, connecting two wings of a large factory at the fifth story has a span of 120 feet and a depth of 12 feet. The trusses are composed of twelve panels and the distance between trusses is 8 feet. The floor of the bridge, which is supported on the lower chords of the trusses, is composed of two layers of 2½-inch tongued-and-grooved spruce plank laid diagonally, one layer crossing the other, and a 1-inch finished floor; this construction furnishes sufficient bracing against the wind at the lower chords, but it is necessary to introduce a system of diagonal bracing between the upper chords, as shown in Fig. 52. Considering the wind pressure as 30 pounds per square foot, what will be the stresses created in the system of lateral bracing?




FIG. 53

SOLUTION.—As the ends of the trusses are to be built into the walls, the horizontal reactions due to the wind load are transmitted to the masonry instead of being resisted by the transverse strength of the end struts. (The transverse strength of columns or struts against




lateral forces is treated in *Wind Bracing*, and consequently it is not necessary to consider it here.) The area of one panel is $12 \times 10 = 120$ sq. ft. and therefore the wind load per panel is $120 \times 30 = 3,600$ lb., but as one-half of this amount is to be resisted by the floor, the panel loads acting on the system of bracing between the upper chords are 1,800 lb. each. A plan of the top of the girder showing the wind loads applied is given in Fig. 53. The members ah , bi , cj , etc. are heavy wooden beams and hence should always be in compression. The tension rods designated by the heavy lines are in use when the load is applied as shown, but when the wind comes from the other side the dotted diagonals provide the required tension and the heavy diagonals are not in use. The stress in gn is 1,800 lb. and half of this force reacts on fn , while the other half goes to the tension member on the right of gn . Then the tensile stress in fn is $900 \times \sec fng = 900 \times 1.601 = 1,441$ lb. The stress in fm is $900 + 1,800 = 2,700$ lb., compression, and the tension in em is $2,700 \times 1.601 = 4,323$ lb. The remaining stresses may be analyzed and the following tabulation made:

$gn = 1,800 +$	$ck = 6,300 \times 1.601 = 10,086 -$
$fn = 900 \times 1.601 = 1,441 -$	$cj = 6,300 + 1,800 = 8,100 +$
$fm = 1,800 + 900 = 2,700 +$	$bj = 8,100 \times 1.601 = 12,968 -$
$em = 2,700 \times 1.601 = 4,323 -$	$bi = 8,100 + 1,800 = 9,900 +$
$el = 2,700 + 1,800 = 4,500 +$	$ai = 9,900 \times 1.601 = 15,850 -$
$dl = 4,500 \times 1.601 = 7,205 -$	$ah = 9,900 + 900 = 10,800 +$
$dk = 4,500 + 1,800 = 6,300 +$	Ans.

DETAILS OF TRUSS CONSTRUCTION

WOODEN TRUSSED GIRDERS

59. It is frequently desirable to support roofs on trussed girders; that is, trusses with horizontal top and bottom chords. A truss of this kind constructed of timber is illustrated in Fig. 54 by a plan (a), an elevation (b), and with details (c), (d), (e), and (f). The elevation shows that the timber trusses A and B have a theoretical span of 47 feet 11 inches and the plan shows that they are placed 16 feet $11\frac{1}{2}$ inches between centers. The elevation, Fig. 54 (b), shows the general outline of the truss. Its structural elements consist of a rigid central panel counterbraced with 1-inch diagonal rods that insure this portion of the frame against any distortion produced by unsymmetrical loads, and the two triangles



DETAILS OF TRUSSES A+B

$e b a$ and $d c f$ form a rigid frame incapable of distortion. The chord members and end posts of the truss g, g , Fig. 54 (*b*), are each composed of two $3'' \times 12''$ pieces of yellow pine, placed side by side and separated by yellow-pine blocks $1\frac{1}{2}$ inches thick. The position of these blocks is shown in the elevation (*b*) at B, B, B .

Referring to the details shown in Fig. 54 (*c*), it will be seen that the diagonal counterbracing, consisting of 1-inch rods, extends through the space left between the timbers making up the upper and lower chords and that they are secured at the ends by especially designed check-washers a, a . The strut members b, b in the middle panel of the truss are each made up of two $3'' \times 6''$ yellow-pine timbers. These are cut to the shape shown in the detail at the ends and are secured in place by being spiked to cleats c, c $1\frac{1}{2}$ inches thick that fit between the middle space of the connecting members and form what would be termed in steel construction, a gusset plate. The vertical members d , as designated in the drawing of the details, are composed of two $3'' \times 9''$ yellow-pine pieces fitted tightly between the upper and lower chord members and further held in place and reenforced by two $1'' \times 9''$ yellow-pine pieces nailed on each side of the heavier pieces of the member. These side pieces extend over the top and bottom chords and are bolted to them with $\frac{3}{4}$ -inch bolts. The required strength in the heel connection of the truss is obtained by the introduction of the $1\frac{1}{2}$ -inch through bolt e and by $3'' \times 9''$ and $3'' \times 6''$ cleats e_1 and e_2 , one being placed above the bolt and the other below it, both being inserted between the pieces composing the end post and the lower chord of the truss. The presence of the lower cleat e_2 is not quite evident in the drawing, because its outline coincides with that of the lower chord and end post. The connection is secured to the cleats by through bolts, and the $1\frac{1}{2}$ -inch bolt forming the main resistance of the joint is provided with special cast-iron washers, details of which are shown at (*e*) and (*f*). Additional resistance is obtained at this important joint by notching the end post into the lower chord member and thus

obtaining the shearing resistance of the timber along the line *ff*. From the plan, Fig. 54 (*a*), it is noticed that purlins *h, h* composed of $3'' \times 12''$ pieces of yellow pine extend between the trusses *A* and *B*. These purlins are supported from the truss by wrought-iron stirrup irons *g*, as shown in (*c*), and carry the bulk of the weight of the roof between the trusses *A* and *B*. The other purlins, marked *i* in the plan, are supported on the end posts of the truss in the manner shown in (*d*), which is so clear as to need no explanation.

60. Another type of timber truss, which is frequently used in mill construction or temporary work, is that shown




FIG. 55

in Fig. 55. This trussed girder was designed for a span of 45 feet and a total live and dead load of 50,000 pounds, uniformly distributed. It is constructed of Georgia yellow pine and is 5 feet 6 inches in depth. The members and details of construction are designed for a factor of safety of at least 4. Both chords of the trusses are composed of three pieces of timber placed side by side and separated with $3'' \times 4''$ separators composed of the same material as the truss. These separators are gained into the chord timbers about $\frac{1}{4}$ inch. While this is apt to weaken the chord in tension somewhat, the rigidity gained by the insertion of the

separators in this manner, laterally and vertically, more than compensates for the loss in strength. From the figure, it will be noticed that the web compression members are all composed of $4'' \times 4''$ pieces. Those marked a, a, a are doubled, for with the rods b, c , and d , they form the principal members of the web, while the members e, e, e are composed of single pieces of timber. These pieces would not be necessary if it were certain that the load would always be uniformly distributed. The possibilities are, however, that with a girder of this span and supporting the great floor area that it necessarily must, the floor load will frequently be concentrated on portions of the girder, and consequently the counterbraces are necessary to insure the truss against distortion. The structural outline of this truss extends along the lines $f g h i$ and the upper chord is extended from g to j only in order to support the portion of the floor adjacent to the wall. It is evident from this that the frame diagram of the truss is as shown in Fig. 56, or in the




FIG. 56

form of a Howe truss. Consequently, the rods k are of little use except to rigidly tie the extended portion of the upper chord to the lower one at the abutments, while the struts l, l are introduced to take up the reaction at the end j of the extended portion of the upper chord. The timber strut members of the web are held in place on bearing blocks by means of oak dowels, as shown at m , special care being taken to secure a rigid and adequate connection at n by the introduction of a cast-iron foot-plate.

61. Should it be necessary to splice the timbers making up both the top and bottom chord, the splices should be kept as near as possible to the abutments, for, in the chords, the stresses decrease toward the supports. For the splice in the upper, or compression, chord it is only necessary to observe

that the spliced timbers are cut true and square and abut, their alinement being secured by pieces of timber bolted on each side. Such a detail as described is shown in view (b). The splice for the chord in tension is shown at p in view (a). It is necessary to use wrought-iron splice plates having a lug q , Fig. 55 (c), on each end. All such splice connections should be analyzed for shear parallel with the grain and for bearing on the end wood, and, if possible, a strength greater by 25 per cent. than the strength of the net section of the member spliced should be realized. The washers r, r are subjected to considerable bending stress and are therefore made of pieces of 5-inch channel iron equal in length to the width of the chord members. When channels are thus used for washers it is generally necessary to provide a socket wrench to tighten up the bolts.

62. In Fig. 57 is shown a trussed girder having a span of over 50 feet. At the ends, it is built in a manner similar to a plate girder with a web a extending between the flange angles. Toward the center, however, for economy and also because it was desired to provide a construction that would allow the diffusion of light from a skylight, the girder was made open, as shown. The girders are stiffened laterally at the lower flange by I beams extending to the walls and at the top flange by a brace, secured at c , extending to a horizontal steel beam member resting on the walls. At the center of the span, the girder is further reenforced laterally by the beams for the support of the diffusing sash shown at d . There are no peculiarities of the design requiring detailed explanation, as the drawing is sufficiently clear with reference to the constructive details.

63. In Fig. 58 is shown a detail design of a trussed through bridge, such as would be used to connect two wings or two buildings of a manufacturing plant. It must be designed to carry, besides its own weight, the truck loads of the heaviest merchandise that would be likely to be sent across it. The bridge has a span of 120 feet, is 10 feet from center to center of trusses across, and is 15 feet 6 inches

100

101

102

103

104

105

106

107

108

109

110

111

112

113

114

115

116

117

118

119

120

121

122

123

124

125

126

127

128

129

130

131

132

133

134

135

136

137

138

139

140

141

142

143

144

145

146

147

148

149

150

151

152

153

154

155

156

157

158

159

160

161

162

163

164

165

166

167

168

169

170

171

172

173

174

175

176

177

178

179

180

181

182

183

184

185

186

187

188

189

190

191

192

193

194

195

196

197

198

199

200

201

202

203

204

205

206

207

208

209

210

211

212

213

214

215

216

217

218

219

220

221

222

223

224

225

226

227

228

229

230

231

232

233

234

235

236

237

238

239

240

241

242

243

244

245

246

247

248

249

250

251

252

253

254

255

256

257

258

259

260

261

262

263

264

265

266

267

268

269

270

271

272

273

274

275

276

277

278

279

280

281

282

283

284

285

286

287

288

289

290

291

292

293

294

295

296

297

298

299

300

301

302

303

304

305

306

307

308

309

310

311

312

313

314

315

316

317

318

319

320

321

322

323

324

325

326

327

328

329

330

331

332

333

334

335

336

337

338

339

340

341

342

343

344

345

346

347

348

349

350

351

352

353

354

355

356

357

358

359

360

361

362

363

364

365

366

367

368

369

370

371

372

373

374

375

376

377

378

379

380

381

382

383

384

385

386

387

388

389

390

391

392

393

394

395

396

397

398

399

400

401

402

403

404

405

406

407

408

409

410

411

412


413

414

415

416

417



from out to out of chord members in height or depth. The two main views are elevations supposed to join along the lines aa . The chord members of the truss are composed of two $6'' \times 6'' \times \frac{1}{2}''$ angles riveted to a $\frac{1}{2}'' \times 18''$ web-plate. By the adoption of a built-up T section of this kind the necessity of gusset plates is obviated, as the web members of the truss can be riveted through the vertical parts of the chord members. Owing to the fact that it is impossible to obtain such angles and plates as are shown in the drawing longer than 50 or 60 feet, the upper and lower chord members must be spliced as shown at a, b .

In the upper splice, it is only necessary to provide sufficient splice plates and rivets to hold the ends of the upper chord member in alinement, but in the design of the splice b for the lower chord, long splice plates must be used and sufficient rivets to realize, by their shearing resistance, the strength of the net section of the chord member. To stiffen the lower chord laterally at the splice, it is advisable to use cover angles that fit into the chord angles, as at c . Where possible, it would be well to splice the angles of the lower chord at a different place from the splice of the web plate. The central panels are counterbraced so that there will be no distortion of the frame from a moving load. The end posts of the truss, as at d , should be strongly constructed so as to withstand the bending stress produced by the gusset-plate brace e , shown in the view placed in the lower right-hand corner. This gusset-plate brace transmits considerable stress from the upper lateral wind bracing, and the only way to resist the stress is to provide a sufficient section modulus in the end members so as to supply the necessary resisting moment. While the floor system will offer sufficient lateral resistance at the bottom of the truss, it is good practice to provide lateral bracing at the bottom as well as at the top. As the truss is of steel, and of considerable span, it is necessary to provide for the expansion and contraction of the frame. For this purpose the steel bearing plate f is supplied and the anchor bolts are passed through slotted holes in the heel plate g .



COLUMNS AND STRUTS

(PART 1)

INTRODUCTION

1. With the exception of the foundations, the **columns** are the most important element in the constructive design of a building. To them should be devoted the most careful study of the architect and engineer, for the failure of one of them means the falling of a portion of the building, or its entire demolition. They may be classified according to the material of which they are constructed, and according to the shape or form of their cross-section.

Under the first classification are included wooden, cast-iron, and structural steel columns and monoliths of stone subjected to compression. In making the second classification, the first must be considered. Wooden columns are either square, rectangular, or round in section. Cast-iron columns are usually hollow, and are square, rectangular, or round in section, though frequently necessity requires the use of a variety of sections. Steel columns are made in all forms that can be built up of the usual rolled shapes, and in some instances special shapes are made in order to secure a column of desirable section.

It is always a matter of some nicety for the engineer to make a selection of the column that will be best adapted to the work under consideration, particularly where the material to be used is structural steel. In selecting wooden and cast-iron columns, the choice is limited and is generally decided by the matters of appearance, availability of material, and the practicability with which the girders and columns can be made.

For notice of copyright, see page immediately following the title page

2. In selecting steel columns that will best fulfil the conditions imposed by the structure, the following considerations should be carefully studied:

1. Economy in both material and cost of construction. The first is attained when the metal in the column section is distributed at a maximum distance from the central axis of the column, which will also fulfil the condition that the radii of gyration shall be the same, or nearly so, on all the axes of the column section. Economy in cost of construction is principally accomplished by so designing the column section that it can be readily built up of stock-rolled shapes, arranged in such a manner that the column can be readily fitted up and the riveting done with facility, by power. The availability of the material should be embodied in this consideration; that is, patented sections controlled by a distant manufacturer should be avoided unless prompt shipment is assured, as the delay occasioned by failure to ship, and the impossibility of getting the material elsewhere, would cause pecuniary loss.

2. That column section should be considered the best constructively in which it is arranged that the loads may be transmitted directly to the center of the column. Thus eccentric loading and its attending dangers are avoided.

3. The column section should be such that all beam and girder connections thereto can be made conveniently without the use of swaged or bent plates of peculiar shape, and that all fitting in the field is avoided, in order that the work can be rapidly and securely assembled.

4. Where, as in buildings of many stories, the columns extend from the basement to the roof in one continuous length, and for reasons of economy it is necessary to reduce the column section at every several stories, that section should be used that will allow the reduction of the sectional area of the rolled-steel shapes employed, without materially reducing the general dimensions of the column section. Should the general dimensions of the column be materially reduced at the several floors, it is evident that economy will require a column of such small dimensions in the upper tiers

that the difficulty of making good constructive details at the beam and girder connections will be manifest.

5. The column section should be of such form as to be easily accessible for inspection and painting; though when completely fireproofed this consideration is of less importance, as the covering will tend to prevent the accumulation of moisture on the columns and lessen the liability of deterioration.

COLUMNS IN GENERAL

STRESS IN COLUMNS

3. The stresses in a tension member always tend to straighten it, but in a column a very slight inequality at the ends, or a weakness on one side, will produce a bending moment and cause the column to bend. This is shown




FIG. 1

exaggerated in Fig. 1. The stress in the plane AB may be considered as the algebraic sum of the diagrams shown in Fig. 2, in which the line cd may be considered as the zero line, its length representing the total thickness of the column, based on any




FIG. 2

assumed unit length, while the ordinates ac , kj , bd , or any of the intermediate verticals, represent the value of the longitudinal pressure in the column, in pounds per square inch, drawn to any convenient scale. Ordinates above cd represent positive stress, that is, compression; those below, negative or tension. When the column remains straight, the

pressure is uniform throughout the section, as seen by the uniform length of the ordinates in the rectangle $abcd$. As soon as the pressure on the column becomes one-sided the length and signs of these ordinates are changed, some changing from positive to negative, as in the triangle cej while those in the triangle jfd remain positive, increasing from zero, at j , to maximum compressive, at d . The triangles cgi and ihd represent the algebraic sums of the two stresses, showing a very large amount of compression from i to d and tension from i to c . At the extreme left of the figure, the algebraic sum of the stresses is $ac - cc$ or cg , a negative or tensile stress. At i , the compression and tension are equal and counterbalance each other, the result being zero. From i to j , the algebraic sum of the tension and compression is equal to a compressive stress $ikhj$. At d the stress is all compression and is equal to the sum of fc and bd , or hd . In this way the total algebraic sum of $abdc$ and $cejfd$ is found to equal $cgihd$. It will be seen that the maximum compression hd should not exceed the safe compressive strength of the material.

If we consider the area $abdc$ to be represented by the letter A and $cejfd$ by the letter B , the strength of the column depends on the sum of A and B . The compressive strength A is very easily found, being equal to the sectional area of the column multiplied by the ultimate unit compressive strength of the material, but the value of B varies considerably and increases as the center line of the bent column is farther from the line of pressure, Fig. 1. On this elementary formula, most formulas for the strength of columns are founded.

As a general rule, the shorter the column the lower is the value of B ; and, vice versa, the longer the column the greater is the value of B . It is for this reason that two formulas are generally adopted, one for short columns and one for long. *Short columns* are those in which the length is small compared with the width of the shortest side; *long columns* are those in which the length is great compared with the shortest side. The limit or point of

change between short and long columns will be given under the proper heading.

4. Method of Failure of Short Columns.—Materials under compression fail in two distinct ways, depending on the nature of the material. Those that are malleable, such as steel, flatten and are deformed. Those that are comparatively brittle shear along a plane. In some of the first tests made, the test pieces being cubical, it was found that the pieces sheared along planes extending diagonally across the sides from one top edge to the opposite lower edge, making an angle of 45° with the horizontal. This was supposed to be the angle of rupture and was the same for all materials. Later tests, however, proved that this angle varies, and with most materials is about 60° with the horizontal. It is for this reason that in making compression tests with cast iron, or any other brittle material, the height of the test piece is made at least $1\frac{1}{2}$ times the diameter, or shortest side. These test pieces are actually diminutive columns and show the method of failure of short columns. Where the height is not greater than the least dimension, the angle of rupture will be along planes of 45° with the horizontal, but as the length is increased in proportion to the least side, this angle increases until it reaches about 60° , where it remains the same. A test piece of cast iron showing the plane of rupture of this material is shown in Fig. 3.



FIG. 3

5. Method of Failure of Long Columns.—Materials in compression develop more strength if the surfaces are true and level. Under this condition the tendency is to resist compression equally, and not to crush in one place before the balance of the material can be brought under compression, as would be the case if the bearing surfaces were uneven and rough.

The theoretical column is assumed to be hinged on a knife edge so as to be free to bend sidewise, as illustrated in Fig. 4 (a). This is never met with in practice, the nearest

approach to it being the compression members of a connected truss where the pin is comparatively small. However, the pin is large, the strength of the column increased by the friction existing in the connection. In (b) shown a column with rounded ends. Here the results different from those of a knife-edge column, because the bearing of the column changes the point of application of the load and consequently the line of pressure. (c) shows a column with flat ends. Here the column must be considerably bent out of line in order to overcome the effect of the flat




FIG. 4

ends. This case approaches the conditions shown in (d) where the ends are held tight, and the curve assumed by the column is similar to that of a beam uniformly loaded and fixed at the ends. The portion considered as the actual column lies between the points *a* and *b*, for at these two points the bending moment changes sign and compression alone exists. In (c) is shown a column fixed at one end and movable at the other, the portion between *a* and *b* acting as the column. The entire column assumes an S shape under the load.

COLUMN FORMULAS

6. The column formulas in general use do not give a direct method of calculating the dimensions of a column that will safely support a given load. The usual method of obtaining these is to assume values for the dimensions of the column, substituting these values in the following formulas and solving for the ultimate average compression u , of this column. If the assumed size gives a value of u , that is satisfactory for the given conditions, it is correct. If, however, the resulting value of u , is smaller than the load per square inch, the assumed size is too small and it will be necessary to choose a larger size and solve again. If, on the contrary, the value of u , is greater than the load per square inch of column section, a smaller size of column is assumed and a new value of u , obtained. After a few trials, a size that gives a satisfactory stress for the given conditions will be found.

The four formulas in general use for calculating the strength of columns are: *Gordon's* or *Rankin's*, *Euler's*, the *straight-line*, and the *parabolic*.

7. Gordon's or Rankin's Formula.—This formula is based on the assumption that the column is subjected to three distinct stresses: (1) a direct compressive stress uniform throughout the section of the column; (2) a stress due to any slight eccentricity of the applied load; (3) a transverse stress created by the initial deflection of the column under the action of the applied load. Assuming these conditions, we have the following rule:

Rule.—*The load, per square inch, on any column should not exceed the compressive strength of the material at the elastic limit divided by 1 plus a value representing the eccentricity of the load plus a value representing the bending of the column.*

This rule is expressed by the formula

$$u = \frac{f_c}{1 + \frac{v c}{r^2} + \frac{f_c - u}{10 E} \left(\frac{l}{r} \right)^2} \quad (1)$$

in which u_1 = average compression, per square inch, of column section when maximum stress, per square inch, equals elastic limit of material;
 f_c = elastic limit of material under compression;
 E = modulus of elasticity of material;
 l = length of column, in inches;
 r = least radius of gyration, in inches;
 v = eccentric displacement of load;
 c = distance of center of gravity of section from extreme fiber.

This formula is the most rational of the theoretical formulas, its results giving a safe unit value for the compressive strength of the material. Its form, however, is indeterminate, since the value u_1 appears on both sides of the equation; besides, the second term of the denominator is very difficult to obtain. In the formula in general use, this term has been neglected and a constant a substituted for the value of $\frac{f_c - u_1}{10E}$. Also, the ultimate strength s per square inch of the material in the column is used instead of f_c , the elastic limit, the result obtained being the ultimate strength, per square inch, of the column section. Thus,

$$u = \frac{s}{1 + a \left(\frac{l}{r} \right)^2} \quad (2)$$

in which u = ultimate strength, per square inch, of column section;

s = ultimate strength, per square inch, of material in column;

a = constant varying with material;

l = length, in inches;

r = radius of gyration.

8. Euler's Formula.—This formula is based on the assumption of an ideal column; that is, a column that is centrally loaded and pivoted at the ends so as to be free to bend sidewise, and will fail by compression and bending alone, no eccentric load being taken into consideration. It also assumes that the strength of the column is realized when the elastic

limit of the material is reached. The values given by this formula are correct only for long columns, or columns whose lengths are great in comparison with their radii of gyration. Its general form is

$$u_l = \frac{\pi^2 E}{\left(\frac{l}{r}\right)^2} \quad (3)$$

in which u_l = average compression, per square inch, of column section;

E = modulus of elasticity of material;

l = length of column, in inches;

r = least radius of gyration.

For fixed ends, the constant 4 is introduced into the numerator, and for one end pivoted and one end fixed, a constant of $\frac{\pi}{4}$ is used.

9. Straight-Line Formula.—This formula was suggested by Thos. H. Johnson, C. E., in 1886, and was derived by plotting, on squared paper, similar to that shown in Fig. 7, the values of the breaking loads of columns of different materials. From these results the values in the following formula were obtained. It was found that an approximately straight line would pass through the plottings of the tests and hence the name of the formula is derived. The general form of this formula is

$$u = a - b \frac{l}{r} \quad (4)$$

in which u = ultimate strength, per square inch, of column section;

a = constant, representing strength of material under compression, whose value is determined by test;

b = constant;

l = length of column, in inches;

r = radius of gyration.

This formula, while fairly accurate for the general sizes, is not good in cases where $\frac{l}{r}$ falls below a certain value, which varies for different materials and will be given later.

10. Parabolic Formula.—This formula is similar to the straight-line formula in that it is very convenient to apply and agrees closely with the actual tests on full-size columns. Its general form is

$$u_r = f_c - b \left(\frac{l}{r} \right)^2 \quad (5)$$

in which u_r = average compression, per square inch, of column section;

f_c = elastic limit for compression of material composing column;

b = constant determined by experiment;

l = length of column, in inches;

r = radius of gyration, in inches.

This formula is also limited in its application to columns in which the ratio of $\frac{l}{r}$ does not exceed a certain value. This value is so high, however, that it is beyond the general practice, and if a case occurs in which the ratio of $\frac{l}{r}$ is greater than the limit of the parabolic formula, the strength may be calculated by Euler's formula. These limitations of the formulas are fully explained later.

TIMBER COLUMNS AND POSTS

11. Timber, although not generally used in modern buildings, is a valuable constructive material for columns. Timber columns or posts are adapted to mill construction, owing to the fact that they are economical and when of considerable size are not easily destroyed by fire. The kinds of timber usually employed for this purpose are the long-leaf and short-leaf yellow pines, white pine, red pine, white oak, spruce, hemlock, cypress, cedar, and redwood. The timber generally preferred is the yellow pine, the long-leaf variety being stronger and more durable than the short-leaf. The disadvantage of this wood is that the resinous sap makes it rather more inflammable than the other woods.

SHORT COLUMNS

12. The column may, in its first stage of development, be considered a cubical or rectangular block, as shown in Fig. 5. If the length of the column does not exceed from six to about ten times the width of the least side, the load it can safely carry may be estimated by multiplying its sectional area, in square inches, by the safe resistance to compression of the material parallel to the grain. To obtain the safe resistance of a short column, or block, divide the




FIG. 5



FIG. 6

ultimate resistance to compression of the material parallel to the grain, by the factor of safety, which, for wooden columns, is from 4 to 5, though it may be, in some instances, good practice to use 6; it is all a matter of judgment, governed by the conditions to be met with. After having obtained the safe resistance of the material to compression, multiply by the sectional area of the column, in square inches, and the result will be the safe resistance of the short column to compression.

EXAMPLE.—What safe load will be supported by a short yellow-pine block, 12 inches square and 8 feet long, standing on end, a safety factor of 5 being used?

SOLUTION.—Assuming that the ultimate compressive strength of yellow pine parallel to the grain, per square inch, is 5,000 lb., with a factor of safety of 5, the safe load, per square inch, on this short column will be $5,000 \div 5 = 1,000$ lb. per sq. in. The area of the column is $12 \text{ in.} \times 12 \text{ in.} = 144 \text{ sq. in.}$, and therefore the safe resistance to compression of the column $= 144 \times 1,000 = 144,000 \text{ lb.}$ Ans.

LONG COLUMNS

13. When long columns, or those over ten times the width of the smallest side, are under compression, and not secured against yielding sidewise, it is evident that they are liable to bend before breaking. To ascertain the exact stress in such pieces is sometimes quite difficult. Hence, we must have a formula making due allowance for this tendency in the column to bend, or to split, and spread from the center, as shown in Fig. 6.

GORDON'S FORMULA FOR RECTANGULAR POSTS

14. Square-End Columns.—The Gordon formula for the different timbers usually employed in building construction is expressed in the following equations:

$$\text{Southern yellow pine, } u_s = \frac{1,125}{1 + \frac{l^2}{1,100d^2}} \quad (6)$$

$$\text{White oak, } u_s = \frac{925}{1 + \frac{l^2}{1,100d^2}} \quad (7)$$

$$\text{White pine and spruce, } u_s = \frac{800}{1 + \frac{l^2}{1,100d^2}} \quad (8)$$

in which u_s = safe unit load, or safe bearing strength of column, in pounds per square inch of cross-section;

l = length of column, in inches;

d = dimension of least side, in inches.

The factor of safety varying from 4 to 5 gives results of from $\frac{1}{4}$ the ultimate strength in the case of small columns, to $\frac{1}{5}$ the ultimate strength in long columns.

By comparing these formulas with formula 2, it will be observed that d' has been substituted for r^2 . This is done for convenience in calculation, since the dimension of the least side is known, while r , or the least radius of gyration, would have to be calculated. In making this substitution, the constant a in formula 2 does not represent the same value as the constant of 1,100 given in formulas 6, 7, and 8, for, to introduce the value of r^2 or $\frac{d'^2}{12}$ as given in *Properties of Sections*, a different value of a than that in formula 2 is substituted in the denominator.

EXAMPLE.—What will be the safe compressive strength of a white-oak post 8 inches by 10 inches by 15 feet long?

SOLUTION.—In this case, l equals 15×12 , or 180 in., and d equals 8 in. By substituting these values in formula 7, which gives the safe unit stress for a white-oak column, we have $u_s = \frac{925}{1 + \frac{180^2}{1,100 \times 8^2}} = 634$ lb.

per sq. in. This result multiplied by the area of cross-section of the column, which is 8 in. \times 10 in., equals $634 \times 80 = 50,720$ lb. **Ans.**




FIG. 7

15. Diagram Chart for Safe Load.—Fig. 7 gives the curves for these formulas for the different materials, by which the values of u_s , in pounds per square inch, may be

obtained. These curves are described by plotting the values of u , for corresponding values of $\frac{l}{d}$ that have been laid off on a horizontal line. From the points thus established, vertical lines are drawn, on which are laid off, to some convenient scale, vertical heights equal to the resulting values of u . The use of this chart is shown in the following example:

To find the value of u , for any value of $\frac{l}{d}$, divide the length, in inches, by the smallest dimension of the column or post and find the corresponding value on the line $a b$. By following up the vertical line through this point and reading on the vertical scale, the value of u is found. In the example in Art. 14, $\frac{l}{d}$ equals $\frac{180}{8}$ or $22\frac{1}{2}$. The value of u , corresponding to the value of $22\frac{1}{2}$ for white oak is 635. This is very nearly the same value as that found in the previous example, the slight difference being due to the impossibility of accurate reading of the chart.

EXAMPLE.—What size square column of white oak, 18 feet long, will be required to sustain 30 tons?

SOLUTION.—It will be necessary to assume some size column and substitute its value in formula 7, solving for the safe strength of the column; if this equals or exceeds slightly the load to be sustained, the assumed size is satisfactory. Assuming in this case a 10-in. square column, and substituting the values in formula 7, the safe unit load of a white-oak column of the dimensions named is

$$u = \frac{925}{1 + \frac{216^2}{1,100 \times 10^3}} = 649 \text{ lb.}$$

and the entire safe load is $649 \times 100 = 64,900 \text{ lb.}$, which exceeds the load of 30 T. to be sustained, and the assumed size is therefore satisfactory. Ans.

EXAMPLES FOR PRACTICE

1. What is the safe strength of a $10'' \times 12''$ Southern yellow-pine post 20 feet long? Ans. 88,560 lb.
2. Find the size of a square post of white pine 14 feet 6 inches long required to support a load of 20 tons. Ans. $8\frac{1}{2}$ in.

STRAIGHT-LINE FORMULA

16. The formula mostly used for long, square or rectangular wooden columns, with square ends, is the following, deduced from elaborate tests made on full-length columns at Watertown arsenal:

$$u = s_c - \left(\frac{s_c l}{100 d} \right) \quad (9)$$

in which u = ultimate strength per square inch of sectional area of column;

s_c = ultimate compressive strength of material per square inch parallel to grain;

l = length of column in inches;

d = length of least side of column, in inches.

EXAMPLE.—What safe load will a white-pine column 10 inches square and 20 feet long, support, using a factor of safety of 6?

SOLUTION.—The ultimate compressive strength of white pine parallel to the grain is 3,500 lb. per sq. in. Therefore, by substituting in the formula, we have $u = 3,500 - \left(\frac{3,500 \times 240}{100 \times 10} \right) = 2,660$ lb., the ultimate bearing value of the column per square inch. As the factor of safety required is 6, the safe bearing value per square inch of sectional area is $2,660 \div 6 = 443\frac{1}{3}$ lb. The area of the column being 100 sq. in., the safe load is $100 \times 443\frac{1}{3} = 44,333$ lb. Ans.

PARABOLIC FORMULAS

17. The parabolic formulas for various materials are given as follows, in which u_r is the same value as defined in Art. 8.

For white pine,

$$u_r = 2,500 - .6 \left(\frac{l}{d} \right)^2 \quad (10)$$

For short-leaf yellow pine,

$$u_r = 3,300 - .7 \left(\frac{l}{d} \right)^2 \quad (11)$$

For white oak,

$$u_r = 3,500 - .8 \left(\frac{l}{d} \right)^2 \quad (12)$$

For long-leaf yellow pine,

$$u_1 = 4,000 - .8 \left(\frac{l}{d} \right)^2 \quad (13)$$

These formulas apply to posts with flat ends when the value of $\frac{l}{d}$ is less than 60.

18. The following rules and tables are based on a system of figuring recommended by the Department of Agriculture, Bureau of Forestry, and on the values of the ultimate strength of timber recommended by the committee on strength of bridges and trestle timbers, of the fifth annual convention of the Association of Railway Superintendents of Bridges and Buildings in 1895.

The strength of timber varies with the amount of moisture it contains and hence on its exposure to the elements. On account of this fact, the following classification is made of timber in general use:

Class *a*, moisture contents, 18 per cent., is used for structures freely exposed to the weather, such as railway trestles, uncovered bridges, etc.

Class *b*, moisture contents, 15 per cent., is used for structures under roof but without side shelter, freely exposed to outside air but protected from rain, such as roof trusses of open shops and sheds, covered bridges over streams, etc.

Class *c*, moisture contents, 12 per cent., is used for structures in buildings unheated but more or less protected from outside air, such as roof trusses or barns, enclosed shops and sheds.

Class *d*, moisture contents, 10 per cent., is used for structures in buildings at all times protected from the outside air, heated in winter, such as roof trusses in houses, halls, churches, etc.

The difference in strength due to exposure in the above classes of buildings is accounted for in the factor of safety used.

19. Factor of Safety.—Table I gives the factors of safety for these different classes of structures.

TABLE I
FACTOR OF SAFETY TO BE USED WITH THE
DIFFERENT CLASSES

Classes	Yellow Pine	All Others
Class <i>a</i>20	.20
Class <i>b</i>23	.22
Class <i>c</i>28	.24
Class <i>d</i>31	.25

20. A. L. Johnson, Civil Engineer in the United States Department of Agriculture, Division of Forestry, suggests the following formula:

$$u = s_c \frac{700 + 15g}{700 + 15g + g^2} \qquad (14)$$

in which *u* = ultimate strength of post, in pounds per square inch;
s_c = ultimate crushing strength of material, in pounds per square inch;
 $g = \frac{l}{d}$.

EXAMPLE.—Apply this formula to the example given in Art. 16.

SOLUTION.—In this case, $g = \frac{20 \times 12}{10} = 24$. Substituting in formula 14, $u = 3,500 \times \frac{700 + 15 \times 24}{700 + 15 \times 24 + 24^2} = 2,267.7$ lb. This, divided by 6, the factor of safety, gives a safe bearing value per square inch of sectional area of $2,268 \div 6 = 378$ lb. The area of the column being 100 sq. in., the safe load is $100 \times 378 = 37,800$ lb. This is less than the result given by the formula in Art. 16, but it is reliable and goes to show the variation in different formulas.

21. Table II gives values of *u* for various values of *g*. Its use greatly shortens the work, as it is only necessary to find *g* for any desired column. The table is divided into five classes:

Class *A* includes all woods whose ultimate crushing

TABLE II
ULTIMATE STRENGTH PER SQUARE INCH FOR TIMBER
POSTS

Value $\frac{l}{d}$	Class A $s_c = 3,500$	Class B $s_c = 4,000$	Class C $s_c = 4,500$	Class D $s_c = 5,000$	Class E $s_c = 6,000$
2	3,481	3,978	4,475	4,973	5,967
3	3,458	3,952	4,446	4,940	5,928
4	3,428	3,918	4,407	4,897	5,876
5	3,391	3,875	4,359	4,844	5,813
6	3,347	3,826	4,304	4,782	5,739
7	3,299	3,770	4,242	4,713	5,656
8	3,247	3,710	4,174	4,638	5,566
9	3,190	3,646	4,102	4,558	5,469
10	3,132	3,579	4,026	4,474	5,368
11	3,070	3,509	3,948	4,386	5,264
12	3,008	3,438	3,867.	4,297	5,156
13	2,944	3,365	3,785	4,206	5,047
14	2,880	3,291	3,703	4,114	4,937
15	2,815	3,217	3,620	4,022	4,826
16	2,751	3,144	3,537	3,930	4,716
17	2,687	3,071	3,455	3,838	4,606
18	2,624	2,998	3,373	3,748	4,498
19	2,561	2,927	3,293	3,659	4,391
20	2,500	2,857	3,214	3,571	4,286
21	2,440	2,788	3,137	3,486	4,183
22	2,381	2,721	3,061	3,402	4,082
23	2,324	2,656	2,988	3,320	3,983
24	2,268	2,592	2,916	3,240	3,888
25	2,213	2,529	2,846	3,162	3,794
26	2,160	2,469	2,777	3,086	3,703
27	2,109	2,410	2,711	3,013	3,615
28	2,059	2,353	2,647	2,941	3,529
29	2,010	2,298	2,585	2,872	3,446
30	1,963	2,244	2,524	2,805	3,366
32	1,874	2,142	2,409	2,677	3,212
34	1,790	2,046	2,301	2,557	3,068
36	1,711	1,956	2,200	2,445	2,934
38	1,638	1,872	2,106	2,340	2,808
40	1,569	1,793	2,017	2,241	2,690
42	1,505	1,719	1,934	2,149	2,579
44	1,444	1,650	1,857	2,063	2,476
46	1,388	1,586	1,784	1,982	2,379
48	1,335	1,525	1,716	1,907	2,288
50	1,285	1,468	1,652	1,835	2,203

strength s_c is 3,500 pounds per square inch, white pine being the most common wood of this strength.

Class *B* includes all woods whose ultimate crushing strength is 4,000 pounds per square inch, such as Northern or short-leaf yellow pine, red pine, Norway pine, spruce and Eastern pine, hemlock, cypress, cedar, California redwood, and California spruce.

Class *C* represents white oak, its strength being 4,500 pounds per square inch.

Class *D* includes those woods whose strength per square inch is 5,000 pounds, such as Southern long-leaf or Georgia yellow pine, Canadian (Ottawa) white pine, and Canadian (Ontario) red pine.

Class *E* includes such woods as Douglas, Oregon, and Washington yellow pine, or pine whose strength per square inch is 6,000 pounds.

To solve the example in Art. 20 by means of Table II, find the given value of g in the table, then take the number opposite it, in the column headed Class *A*. The value of g being 24, the corresponding value of u is found to be 2,268, which is the result of the preceding calculations. The rest of the calculation for finding the safe load is the same as that in Art. 20.

22. Actual tests of posts made up of three pieces bolted and keyed together show that, by the combination, their ultimate strength per square inch is not materially increased over the strength of the three separate pieces. In other words, the strength per square inch of three 4" \times 12" joists bolted together, making a 12" \times 12" built-up column, is not more than three times that of a column consisting of a 4" \times 12" joist, and the strength per square inch of the former is not as great as that of a solid 12" \times 12" column.

EXAMPLE.—What is the difference in strength between three 4" \times 12" spruce joists bolted and keyed together as a column and a 12" \times 12" timber, both being 16 feet long?

SOLUTION.—In the first case, $g = \frac{16 \times 12}{4} = 48$, and by Table II, $u = 1,525$, the ultimate strength per square inch for this ratio of l to d .




FIG. 9

the vertical web *b* and bolted to it, while these cross-webs transmit the load from column to column.

The column cap shown in (*f*) is modeled after the *Goetz-Mitchell style* shown in (*c*) and (*d*), and embodies the advantages of that form of cap. It is especially designed for flitch-plate girders, the flitch plate being kept back at the end enough to allow the two beams to slip in beside the vertical web *c*. Provisions may be made for bolting the side beams to the vertical web *c*, making a very rigid connection. In this case the rib *d* might be omitted, although by its use additional rigidity is secured, as the liability of the web *c* to shear opposite the bolt holes is overcome by the rib, which tends to prevent any lateral movement. The rib *d* is notched at the center to allow the flitch plate to pass through, while the wooden beams are notched to fit over the rib *d*. A flitch-plate girder will, in case of fire, burn on the outside and form a charcoal covering for the flitch plate, thus protecting it from fire, and the flitch plate being protected, will in turn hold up the beam.

The style of column cap shown in (*g*) is made up of wrought-iron plates and is secured to the lower column by means of spikes driven through holes in the flange *f* at the base. In (*i*) is shown the same cap with brackets for supporting four beams instead of two. In (*h*) and (*j*) are shown two forms of cast-iron caps to be used where four beams are supported by the same column.

The form shown in (*k*) has many advantages. Here the side plate *a* is removed from its true position, as indicated by the dotted lines, in order to show the shape of the post and beams at the joint. The side plates *a* and *d* are secured to the base plates *b* and *c* by means of long and short bolts *e* and *f*, respectively, while long bolts extend through the column, thus tying the side plates securely to it. Like those in views (*g*) and (*i*), this cap is made up of plates and angles, but has the advantage that it can be easily taken apart, and is the only cap that may be used with a continuous column, as by its use columns may be extended through two or even three stories.

All these caps are designed for buildings where wooden girders are used. Sometimes, however, it is desirable to use wooden columns and steel girders on which the wooden beams are supported. This requires a slight variation in the caps, and although a number of these designs may be changed sufficiently to accommodate steel beams, the problem may be solved by using such a cap as is shown in (*l*). This cap consists of a cast-iron plate *a* made with a recess into which the top of the lower column is inserted. The upper side of the cap is designed with a lip on either side, between which the two steel beams forming the box girder are placed, thus keeping them from sliding off the column. The steel beams are connected by a special form of separator *b*, which extends through to the next pair of beams, thus tying the two pairs firmly together. On this joint rests a cap *c*, similar to *a*, placed in the reverse position and extending over the sides of the beams, which supports the upper column. Since the ends of the beams form a portion of the column, the separator *b* should be a snug fit so as to relieve the beams of compression and transmit the stress from the upper to the lower flanges.

The caps shown in (*c*), (*d*), (*e*), (*h*), and (*j*) are known as *Goetz caps*; those shown in (*g*) and (*i*) are the *Van Dorn patents*; and (*k*) is known as the *duplex cap*. These styles of caps are patented and cannot be used without paying a royalty to the patentees.

25. It is a common practice, in using wooden columns, to bore a 1-inch or a 1½-inch hole the full length of the column through the center, in order to ventilate the interior and prevent dry rot. For the same reason a hole is often left through the cap or base in order to give ventilation to the ends of the column. Such construction is shown in the caps in Fig. 9 (*c*) and (*d*), and in the base, Fig. 8 (*b*). A further advantage of this is that no water can collect and stand at the base of the column.

CAST-IRON COLUMNS

26. Cast-iron columns are most frequently used in buildings of moderate height, but have been used, in some cases, in buildings of sixteen, and even more, stories. The best practice has, during the last few years, so uniformly declared in favor of steel columns that the employment of cast iron is now generally confined to buildings of ordinary height, say four or five stories, or to special cases, where advantages are to be gained in the use, for instance, of a number of ornamental cast-iron columns.

The uncertain strength of cast iron has compelled the adoption of a very low unit stress per square inch; in other words, a very high factor of safety. The uniform strength of structural steel is, on the other hand, so well understood that cast iron, for columns, and especially girders, is falling into disuse. Considerations of economy may, however, in some cases, still justify its employment. But, though cast-iron columns are cheaper per pound and perhaps easier to erect than steel, the declining price of structural steel is removing this advantage of cast iron.

27. Objections to Use of Cast-Iron Columns.—One disadvantage in the use of cast-iron columns is that when fracture occurs, it comes without warning. In high buildings, erected entirely upon cast-iron columns, the danger from wind pressure is very much increased on account of lack of stiffness in the joints of the connections at the several floors. In fact, buildings have been blown 10 inches out of plumb, owing to this lack of rigidity in the connections.

One of the greatest objections to the use of cast-iron columns is that they are liable to be broken by sudden contraction, due to water being played on them in case of fire.

This objection, while held by many engineers, cannot be said to agree with practice, for there are many cases of buildings destroyed by fire in which the beams and girders have been bent and twisted, while the columns have stood the heat remarkably well. The strength of the columns that have stood the test is very uncertain, and every precaution should be taken to test them after a fire.

FORMULAS FOR CAST-IRON COLUMNS

28. The uncertain strength of cast iron gives rise to a number of formulas and rules for calculating the strength of columns made of this material. The only method of testing these formulas is to compare their results with those of actual tests. Unfortunately, these tests are very few in number, but they serve as the basis of calculation, and are undoubtedly more reliable than the theoretical conditions. The formulas for cast-iron columns are usually such that they may be applied to long and short columns, with the exception of the straight-line formulas, whose results for long columns are too high.

GORDON'S FORMULA

29. The strength of a cast-iron column with square ends may be calculated by the following rule:

Rule.—*To find the ultimate strength per square inch of sectional area of a cast-iron column with square ends, divide the ultimate compressive strength per square inch of the material composing the column by 1 plus the quotient obtained by dividing the square of the length of the column, in inches, by 3,600 times the square of the radius of gyration of the section of the column.*

This rule is expressed by the formula

$$u = \frac{s_c}{1 + \frac{l^2}{3,600 r^2}} \quad (15)$$

in which u = ultimate strength per square inch of column section;

s_c = ultimate compressive strength per square inch of material composing column (for cast iron s_c may be taken as 80,000);

l = length of column, in inches;

r^2 = square of least radius of gyration.

EXAMPLE.—Find the proper working load for a 10-inch, square, cast-iron column, 20 feet long, using a factor of safety of 6, the thickness of the metal being 1 inch.

SOLUTION.—The ultimate compressive strength s_c of cast iron, per square inch, is 80,000 lb., the length $l = 20 \times 12 = 240$ in.; and r^2 for a hollow, square, rectangular column is $\frac{a^2 + a_1^2}{12}$, in which a is the length, in inches, of one side measured outside and a_1 , the length of same side measured inside of column. Therefore, $r^2 = \frac{10^2 + 8^2}{12} = 13.6$.

Substituting these values in formula 15, we have

$$u = \frac{s_c}{1 + \frac{l^2}{3,600 r^2}} = \frac{80,000}{1 + \frac{240^2}{3,600 \times 13.6}} = \frac{80,000}{2.18} = 36,706 \text{ lb.},$$

the breaking strength of the column in pounds per square inch of section. With a factor of safety of 6, the safe bearing value of the column is $36,706 \div 6 = 6,118$ lb. per sq. in. The net area of the section of the column is $10^2 - 8^2 = 100 - 64 = 36$ sq. in. The entire load that it will support with safety is therefore $36 \times 6,118 = 220,248$ lb. Ans.

30. Formula 15 may be replaced by formula 16. Though the latter is not as general in its application, it is more convenient in form and may be applied to the usual sections of cast-iron columns.

$$u = \frac{80,000}{1 + a \frac{l^2}{d^2}} \quad (16)$$

in which u = ultimate strength per square inch of sectional area;

d = least outside dimension of the column, in inches;

l = length of column, in inches;

a = value taken from Table III.

This may be expressed by the following rule:

Rule.—*To find the ultimate strength per square inch of sectional area of a cast-iron column, divide 80,000 by 1 plus the product of a constant and the quotient obtained by dividing the square of the length, in inches, by the square of the least dimension of the column, in inches.*

TABLE III
VALUE OF *a* FOR DIFFERENT BEARINGS

Cylindrical Columns			Rectangular Columns		
Square Bearing	Pin and Square Bearing	Pin Bearing	Square Bearing	Pin and Square Bearing	Pin Bearing
$\frac{1}{800}$	$\frac{3}{1,600}$	$\frac{1}{400}$	$\frac{3}{3,200}$	$\frac{9}{6,400}$	$\frac{3}{1,600}$

In Table III, the values given in the second column are for columns in square bearing on one end and pin bearing on the other end.

EXAMPLE.—Required, the ultimate strength, per square inch of section, of a square-ended, round, hollow column 15 feet 10 inches long, whose outside diameter is 15 inches, the average thickness of the metal being 1 inch.

SOLUTION.—According to Table III, the value of *a* for a cylindrical column with square bearing is $\frac{1}{800}$. The value of *l* in this case is equal to 15 × 12 + 10, or 190, and *d* equals 15.

Substituting these values in formula 16, we have

$$u = \frac{80,000}{1 + \frac{190^2}{800 \times 15^2}} = 66,666 \text{ lb. Ans.}$$

31. Comparison of Building Laws.—The value of the constant *a* varies according to the several building laws of New York, Chicago, and Boston, as shown in Table IV, which gives the formulas for obtaining the safe unit strength *u*, of columns. These formulas embody their own factors of safety, which vary in the different cities, as mentioned in Art. 34.

TABLE IV

FORMULAS FOR FINDING THE VALUE u_s FOR COLUMNS

Cylindrical Columns			Rectangular Columns		
New York Old Law	Chicago	Boston	New York Old Law	Chicago	Boston
$16,000$	$10,000$	$10,000$	$16,000$	$10,000$	$10,000$
$1 + \frac{l^2}{400d^2}$	$1 + \frac{l^2}{600d^2}$	$1 + \frac{l^2}{800d^2}$	$1 + \frac{l^2}{500d^2}$	$1 + \frac{l^2}{800d^2}$	$1 + \frac{l^2}{1,066d^2}$

STRAIGHT-LINE FORMULAS

32. It has been demonstrated lately that the results of the formula of the New York building laws, as given in Table IV, were entirely too high. In the revised copy of these laws, this formula has been discarded and the one following is recommended, which embodies its own factor of safety. The results given, however, are rather large, as will be seen in the comparison later.

Rule.—The safe load per square inch of a cast-iron column may be obtained by subtracting thirty times the ratio of the length, in inches, to the radius of gyration, in inches, from 11,300.

This rule is expressed by the formula

$$u_s = 11,300 - 30 \frac{l}{r} \quad (17)$$

in which u_s = safe strength, in pounds, per square inch of sectional area;

l = length of column, in inches;

r = radius of gyration, in inches.

EXAMPLE.—What will be the allowable load per square inch on the column in the example in Art. 30, according to the new formula of the New York building laws?

SOLUTION.—The radius of gyration equals $\frac{\sqrt{15^2 + 13^2}}{4} = 4.9623$;

hence, $u_s = 11,300 - \frac{190 \times 30}{4.96} = 10,151 \text{ lb. Ans.}$

EULER'S AND THE PARABOLIC FORMULAS

33. The following examples show the application of these formulas to cast-iron columns:

For pin-bearing columns, when $\frac{l}{r}$ is less than 70,

$$u = 60,000 - \frac{25}{4} \left(\frac{l}{r} \right)^2 \quad (18)$$

For pin-bearing columns, when $\frac{l}{r}$ is greater than 70,

$$u = \frac{144,000,000}{\left(\frac{l}{r} \right)^2} \quad (19)$$

For square-bearing columns, when $\frac{l}{r}$ is less than 120,

$$u = 60,000 - \frac{9}{4} \left(\frac{l}{r} \right)^2 \quad (20)$$

For square-bearing columns, when $\frac{l}{r}$ is more than 120,

$$u = \frac{400,000,000}{\left(\frac{l}{r} \right)^2} \quad (21)$$

in which u = ultimate strength, in pounds per square inch, of sectional area;

l = length of column, in inches;

r = radius of gyration, in inches.

EXAMPLE.—Apply this formula to the column specified in the example in Art. 30.

SOLUTION.—The radius of gyration found is 4.96 and the length is 190 in.; then, since

$$\begin{aligned} \frac{9}{4} \times \left(\frac{190}{4.96} \right)^2 &= \frac{9}{4} \times \frac{36,100}{24.6016} = 3,301.6 \\ u &= 60,000 - 3,301.6 = 56,698 \text{ lb. Ans.} \end{aligned}$$

EXAMPLES FOR PRACTICE

1. Compare the results of the parabolic and the second form of Gordon's formula, for the ultimate unit strength of a cast-iron column whose length is 10 feet and whose outside diameter is

10 inches, with a uniform thickness of 1 inch, and with flat or square-bearing ends.

Ans. { By parabolic formula, 56,839 lb.
 { By Gordon's formula, 67,796 lb.

2. Compare the results of the same formulas for pin-bearing ends.

Ans. { By parabolic formula, 51,220 lb.
 { By Gordon's formula, 58,823 lb.

34. Factor of Safety.—In cast-iron columns a generous factor of safety should be used. The old New York building laws required a factor of safety of 5, while the new laws embody their own factor of safety. With formula 15, a factor of safety of 6 or 7 may be used, but in Boston and Chicago 8 is required.

35. For convenience of comparison, a list is given below of the results of the above formulas for the column mentioned in the example in Art. 30, by which the student may judge how near these come to the actual results.

	UNIT BREAKING LOAD. POUNDS PER SQUARE INCH	UNIT ALLOWABLE LOAD. POUNDS PER SQUARE INCH
By formula 15	56,858 ÷ 7	8,123
By Boston building laws . .	66,664 ÷ 8	8,333
Chicago building laws . . .	63,136 ÷ 8	7,892
New York building laws (old)	57,100 ÷ 5	11,420
New York building laws (new)		10,151
By parabolic formula . . .	56,698	
By test, average results . .	30,000	

This shows that, while in Boston a safety factor of 8 is allowed, the actual factor of safety is hardly 4, considering the average result of the tests, and in New York the actual factor of safety is only 3. Great care should, therefore, be taken in the use of cast-iron columns, as the results of the preceding formulas and tests show.

DESIGN OF CAST-IRON COLUMNS

36. General Remarks.—In designing a column, to insure a good casting, no part should be made less than $\frac{3}{4}$ inch thick. It is considered poor designing to make one part or section considerably thicker than an adjacent section,




FIG. 10

on account of the liability of the thinner parts to cool more quickly than the thick parts and break away from them. Even if they do not break apart in casting, the metal, especially if in tension, is very liable to crack after the

column is in place. Therefore, when it is found necessary to thicken a portion of a column, the increase in thickness should be gradual.

Cast iron, in cooling in the mold, forms a fiber that runs perpendicular to the surface. When a corner is made as shown in Fig. 10 (a), the metal is very liable to crack off; for this reason the corner should have a generous curve connecting the surfaces, as in Fig. 10 (b). This curve is called a *fillet* and should have a radius of at least $\frac{1}{4}$ or $\frac{3}{8}$ inch.

37. In casting columns, it is necessary to use a *core* or cylinder made to the inside diameter of the column and composed of sand, flour, and water. After being molded in a




FIG. 11

core box, it is taken out and baked in an oven prepared for that purpose. The core, being relatively light, tends to float on the surface of the molten iron, and if the column is

cast on its side, means must be taken to prevent the core from rising and approaching too close to the top side of the column, as shown in Fig. 11. The dotted lines represent the true position of the core before the iron was poured in. The full lines show the position of the core bent by its buoyancy, making the top side of the column thinner than the bottom. The dirt and air caught in the mold float on the molten iron and form blowholes and sand spots on the top side of the column. To avoid these blowholes a small wire rod is forced through the sand mold at intervals, making air vents by which the gases may escape.

There are two ways of avoiding the displacement of the core: (1) If the column is cast in a horizontal position, the core must be held firmly in its position. (2) The best method, however, of casting a cylinder is by standing it on end and admitting the molten metal from the bottom. In this way the core is kept in a central position, with respect to the column, and any dirt or sand that may have been displaced is floated up on top of the metal, thus making a sounder casting. This method, while very useful in casting pipe and engine cylinders, cannot, however, be used in casting columns of any considerable length because the mold will not stand the great pressure due to the head of metal.

38. Sections of Cast-Iron Columns.

The usual sections of cast-iron columns are shown in Fig. 12. The solid column (a) is not very much used except when the columns are short, or in unimportant work where light loads are to be sustained. They may, however, be employed to hold up balconies, as in a theater, when it is necessary to obtain the required strength with the least obstruction




FIG. 12

to view. It is much more economical to use a hollow cylindrical column (*b*), because the same amount of material as in a solid column, when spread into a hollow cylinder, will sustain a much greater load. In (*c*) is shown a rectangular or box column; the sides may be equal or unequal. When unequal, the value of d , or length of a side, is always taken as the shortest side and the value of r , or radius of gyration, is figured for the smallest value of d . This section is almost as efficient for the same amount of material as the one shown in (*b*), with the advantage of being better adapted for forming beam connections. In (*d*) is shown the H section, which is very useful, especially in walls where it may be easily built into the masonry and in this way be thoroughly protected from fire. It has the advantage that all surfaces are exposed and open to inspection, so that bad spots may be easily detected and the nature of the casting known. All surfaces may be painted and protected from rust. Also, on account of its shape, it is much more easily cast, no core being required. It has, however, the disadvantage of being an uneconomical section. In (*e*) is shown a form that has the advantage of being easily cast, but it is not an economical shape. This section has been used in old practice for struts in framed structures, such as roof trusses and bridges. In (*f*) is shown a column section that is sometimes used in the construction of store fronts, and, as a cast-iron pilaster, is frequently a structural member in a building. It is not economical, but has the advantage that it is readily built into the walls and thus entirely or partially concealed.

EXAMPLE.—What is the difference in strength of two cast-iron columns, each 16 feet long, having an area of cross-section equal to 28.28 square inches, the one to be a hollow cylindrical column of 10 inches outside diameter and the other to be solid.

SOLUTION.—A solid cylindrical column whose area of cross-section is 28.28 sq. in. will have a diameter of $\sqrt{\frac{28.28}{.7854}} = 6$ in. The square of the radius of gyration for the solid column will then be $\frac{6^2}{16} = 2\frac{1}{4}$, and substituting in formula 15,

$$u = \frac{80,000}{1 + \frac{192^2}{3,600 \times 2\frac{1}{4}}} = 14,414 \text{ lb.}$$

This multiplied by 28.28 gives $14,414 \times 28.28 = 407,627.92$ lb. for the strength of the solid column.

A cylinder whose outside diameter is 10 in. and whose area is 28.28 sq. in. would have an inside diameter of

$$\sqrt{d^2 - \frac{28.28}{.7854}} = 8 \text{ in.,}$$

since
$$\frac{\pi d^2}{4} - \frac{\pi d_1^2}{4} = \frac{\pi}{4} (d^2 - d_1^2) = 28.28;$$

and
$$d_1 = \sqrt{d^2 - 28.28 \times \frac{4}{\pi}} = \sqrt{100 - 36} = 8$$

The square of the radius of gyration $r^2 = \frac{d^2 + d_1^2}{16} = 100 + 64 \div 16 = 10\frac{1}{4}$ in. Substituting in formula 15 again, we have

$$u = \frac{80,000}{1 + \frac{192^2}{3,600 \times 10\frac{1}{4}}} = 40,020 \text{ lb.}$$

This result multiplied by 28.28 gives $40,020 \times 28.28 = 1,131,765.6$ lb.

Therefore, the hollow cylindrical column is nearly three times as strong as the solid column, in this case, although no more metal has been used. Ans.

39. Column Connections.—Solid cylindrical cast-iron columns are usually fastened together by the simple flange base shown in Fig. 13 (*a*). The flange need only be broad enough to allow bolting together, the minimum bolt circle being expressed by the formula

$$d + o + \frac{1}{2} \text{ inch} \quad (22)$$

in which d = diameter of column;

o = outside diameter of nut.

The flange may be used around hollow cast-iron columns, whether rectangular or circular, as shown in (*b*). In order to reduce the machine work and get a bearing that will be more apt to be true, a design such as is shown in (*c*) has been used. This, however, is not as stiff a connection as that shown in (*b*), the bearing of the base being smaller. Sometimes, to secure a better alinement, a flange is cast on the lower column projecting into the lower end of the upper column. The two connecting flanges are faced and bolted

together as shown in (*d*), ordinary bolts being used to hold the two columns together. The connection for H columns is shown in (*e*). Here the web, forming the bearing of the




FIG. 13

column, is cast inside the vertical flanges. This is a point in favor of this style of column, because, having no projecting

flanges, the column is easily built into masonry walls. The upper column section is usually reduced in the manner shown in the figure by casting a small lip a on the base of the upper column.

The purpose of using two shells, as in (f), is for fire-protection, the outer one protecting the inner one from the effect of flames. In this case a plate, such as is shown at p , is used, bringing the columns into alinement and adjusting them to their proper position. The objection to the use of this plate is the extra number of joints, there being twice as many as in the ordinary column. Joints are very objectionable features in a column, on account of the difficulty of bringing them to a good bearing. In (g) is shown the general form of connection for the **X** shape; this shape is very little used because its form is not economical.

In all the above styles, except (d), the bolts should fit the holes tightly, this necessity in the case of (d) being obviated on account of the projecting flange or lip of the lower column into the upper column. Some constructors permit the use of tin shims in order to center the bolt, but this is objectionable because it does not hold the columns firmly in line. The best method is to have the holes machine-drilled and use machine bolts that fit the holes accurately. The holes in the bases must then be drilled to a templet to insure their alinement. In order that the bolts may hold the flanges more firmly together, the latter are usually *spot-faced*; that is, the metal around the hole is cut off until the nut has a full and even bearing. (h) shows a flat cast-iron pilaster column that it is sometimes necessary to use against masonry walls and in positions where room cannot be provided for a larger column. In calculating the strength of such a column the least radius of gyration should be used, even though the column is securely tied to the wall. In (i) is shown a connection frequently used for square columns, though it is probably more usual to put the ribs in, as shown dotted. There is little value in placing the ribs on the diagonal in this instance, from the fact that the corner could be well rounded as at a , when the necessity for the corner ribs would not exist.

The reduction of section at the different floors forms an important consideration in selecting the section of a column. The cylindrical column is generally reduced by changing the diameter. Where an abrupt change is to be made and the load carried by the upper column is considerable, great care should be taken to make the flanges at the connection strong enough to stand the shear so that the columns may not telescope.

40. In erecting columns, it frequently happens that the bases are not square to the axis of the column. This throws the column out of a vertical line, which, when brought to its proper position, causes a bearing only on one edge. In order to bring the columns to a fair bearing, sheets of paper, called *shims*, are sometimes used to fill in. If the ends have been left rough, the custom is to use lead or copper sheets between the bases. These two metals are so soft that any slight inequality in the surface of the base sinks into the soft metal, giving the column a full, square bearing.

41. **Column Bases.**—The conditions that arise in designing a column base to set on the capstone are slightly different from those met with in designing a base at a column connection. The former usually stand directly on a capstone whose unit crushing strength is much less than that of the column. The base must therefore be increased in area so as not to produce a greater pressure per square inch than is safe. Column bases are usually set on a lead or copper plate or in Portland cement. When lead or copper is used the crushing strength of the stone should be considered, as the compressive strength of these metals is greater than that of the stone. When, however, cement is used, the allowable compressive strength per square inch is not more than from 200 to 300 pounds. The Portland cement may be used neat, that is, without any sand or gravel, or it may be used in the proportion of one part cement to one or two parts sand. The strongest mixture is that of one part cement and one part of clean, sharp sand.

Such a design as is shown in Fig. 14 (*a*) is suitable for a column that rests directly on the capstone. The ribs










FIG. 14

should be so placed as to protect the corners, as at (b) and not as at (c), because the corners are the more liable to break off from the load of the column. A much better plan is to rest the column on a separate base, such as is shown in (c). This base is suitable for a cylindrical column holding only a comparatively light load. In this case the column has the same flange connection at the base that it has at the top. The advantages of this method are that the bases may be built heavier and may be set so as to give a perfectly level bearing on which to start the column. They are less awkward to handle than a column that has its base cast with it, and they are indispensable where a column is to sustain a heavy load, in order to distribute the pressure evenly over the capstone. Here, as in (a), the ribs run to the corners. In (d) is shown a base commonly used in connection with the H form of column. This base is designed to hold a heavier load than the one shown in (c). In (f) is a form of base suitable for the heaviest loads to which a cast-iron column is subjected. It is octagonal, having ribs to each angle of the octagon. The lower flange is further stiffened by a vertical rib running around the edge of the base.

A type of base that is sometimes used with advantage for supporting tiers of cast-iron columns is shown in Fig. 14 (g). This base is supported on a pier that extends through the basement floor, and the casting *a* provides a support for the first-floor columns and a connection for the first-floor beams.

In these bases, no holding-down bolts are used, as the cement is considered sufficient to stand all shocks, and when the weight of the building comes on the columns, the liability of displacement is still further reduced.

DESIGN OF CAST-IRON BRACKETS

42. The beam connections form an important feature in the selection of a column section. Some column sections are especially adaptable to this service, for example, the rectangular and the H section; while the circular columns, especially the smaller ones, are not so easily designed for

acket connections. The usual rule to be followed is that the brackets should be as near the center of the column as possible so as to carry the load to the center line of support. This is done in order to reduce the eccentric loading as much as possible. A bracket should be strong enough to support its load with safety.

The usual form of bracket is shown in Fig. 15 (*a*). The angle made by the outer edge of the vertical web of the bracket should be 30° with the axis of the column. It is sometimes desired to add to the architectural effect by making this line into a molding. The cyma reversa shown (*b*) is well adapted to this treatment, as it gives plenty of metal at the top of the bracket where it is most needed. The cyma recta (*c*), although often used, is not so well adapted to the design of a bracket because the edge is weak, and if a beam were to rest on this edge alone, it is probable that it would break off as shown in (*d*). To avoid this, the top edge may be slightly beveled so that the beam cannot rest on it. The section in (*f*) designates the manner in which the thickness of the shell adjacent to the bracket is frequently increased. This figure, it will be noticed, is somewhat similar to the section in (*d*). A very good design for a strong bracket for an architectural column is shown (*g*). Here the bed is held up by four vertical webs. In (*e*) is shown a method of supporting a wooden post on a cast-iron column, the post being slipped into the projecting part *d*. A vertical lug is usually provided to which the beams are bolted. It may be made as shown at *f* in (*e*), or, where a box girder is to be supported, the lug may be designed to slip in between the two webs of the girder, as at *g* in (*h*) and (*i*).

Necessity frequently arises for a cast-iron column that has some pretensions to architectural finish. In Fig. 16 (*a*) is shown a cast-iron column with molded brackets and an architectural cap. The main girders in the building are designated at *a*, and are composed of steel I beams. The secondary girders *b* are of $10'' \times 12''$ yellow pine. A bracket is provided at *c* for bolting the steel girder *a* securely in




FIG. 15




FIG. 16


position, while the secondary wooden beams b are held in place by lagscrews passed through the bracket d at c . The same type of column for an upper story, supporting an inclined rafter, is shown in Fig. 16 (b). The block a is separate from the column and is secured to it with bolts extending through the bracket at b .

43. Many concerns have their own standard designs for column connections and brackets. These are usually embodied in tables that give the required dimensions. Table V gives the standard dimensions of brackets on cast-iron columns for I-beam connections. The face of the shelf should have a pitch away from the column of $\frac{1}{8}$ inch to the foot to allow for the deflection of the beam. As the holes in the column are cored, it will be necessary to have the beams drilled in the field in order to insure alinement.


In this table the values given in the columns marked A, B, C , etc. are the various dimensions for brackets, these dimensions being represented by corresponding letters in the figures accompanying the table. Thus, for a 12-inch I-beam connection, the distance from the bottom of the beam flange to the center of the outside bolt of the vertical lug should be 3 inches, the pitch of the bolts, 3 inches, the projection of the bracket beyond the column, $4\frac{1}{2}$ inches, the depth of the vertical leg of the bracket, $7\frac{3}{4}$ inches, etc.

44. **Strength of Cast-Iron Brackets.**—In Fig. 15 (k), (i), (j), and (k) are shown brackets that were tested to their breaking point. The brackets in almost every case tore out the body of the column, as shown in (j). The minimum strength of the bracket shown in (k) and (i) with a distributed load was about 160,000 pounds, and with a concentrated load at the edge of the bracket, was about 95,000 pounds. The somewhat surprising result was found, in testing brackets of the dimensions of those shown in (j) and (k), that on different sized columns their strength was practically the same. It will be noticed that these brackets are practically of the same dimensions, with the exception of the height of the web, which is $5\frac{1}{2}$ inches on the 15-inch

TABLE V
DIMENSIONS, IN INCHES, OF STANDARD CONNECTIONS
TO CAST-IRON COLUMNS



Depth of Beam	A	B	C	D	E	F	G	H	K	Thick-ness of Lugs	Holes Cored for $\frac{1}{4}$ -Inch Bolts
20	5	5	6	10 $\frac{1}{2}$	1 $\frac{1}{2}$	1 $\frac{1}{2}$	2	1 $\frac{1}{2}$	2	1	
18	4	5	6	10 $\frac{1}{2}$	1 $\frac{1}{2}$	1 $\frac{1}{2}$	2	1 $\frac{1}{2}$	2	1	
15	4	3 $\frac{1}{2}$	5 $\frac{1}{2}$	9 $\frac{1}{2}$	1 $\frac{1}{2}$	1 $\frac{1}{2}$	2	1 $\frac{1}{2}$	1 $\frac{3}{4}$	1	
12	3	3	4 $\frac{1}{2}$	7 $\frac{1}{4}$	1 $\frac{1}{4}$	1 $\frac{1}{4}$	2	1 $\frac{1}{2}$	1 $\frac{1}{2}$	1	



Depth of Beam	A	B	C	D	E	F	G	H	K	Thick-ness of Lugs	Holes Cored for $\frac{1}{4}$ -Inch Bolts
10	3 $\frac{1}{4}$	3 $\frac{1}{2}$	4	7	1 $\frac{1}{4}$	1	2	1 $\frac{1}{2}$	1 $\frac{1}{2}$	1	
9	3	3	4	7	1	1	2	1 $\frac{1}{2}$	1 $\frac{1}{2}$	1	
8	2 $\frac{1}{2}$	3	4	7	1	1	2	1 $\frac{1}{2}$	1 $\frac{1}{2}$	1	
7	2 $\frac{1}{4}$	2 $\frac{1}{2}$	4	7	1	1	2	1 $\frac{1}{2}$	1 $\frac{1}{2}$	1	

column and 7 inches on the 6-inch column. When tested to destruction, the breaking strength with a distributed load for the former varied from 122,800 to 142,000 pounds, and for a concentrated load at the edge of the bracket, from 69,800 to 72,900 pounds. The breaking strength of the latter for a distributed load varied from 131,000 to 133,700 pounds, and for a concentrated load at the edge of the bracket was 49,140 pounds. The last test quoted may be discarded, since the manner of failure was by breaking off the lip of the bracket instead of tearing out, as in the other cases. If this result be neglected, it will be seen that the two brackets were practically of the same strength.

If the bracket shown in (j) were figured for shear, according to the usual method, the result would be $6 \times 1\frac{1}{4} + 5\frac{1}{2} \times 1\frac{1}{4} = 13\frac{1}{8}$ square inches. This multiplied by the shearing strength of cast iron, 18,000 pounds, gives $18,000 \times 13\frac{1}{8} = 240,375$ pounds. It is easily seen that the calculated shearing strength of the bracket is greatly in excess of the actual strength. If the allowable shearing strength of cast iron is taken at 3,000 pounds per square inch, which is the value required by the New York building laws, we find the safe bearing strength of the bracket to be $13\frac{1}{8} \times 3,000 = 41,062$ pounds. This shows that, while the theoretical factor of safety is about 6, the actual factor of safety is little more than $1\frac{2}{3}$ with a concentrated load at the edge, and about 3 with a distributed load. The following conclusions were made from the results of these tests:

1. A bracket on the usual cylindrical cast-iron column will usually fail by tearing out a portion of the body of the column; the stress that causes this failure is unknown, but it is probably a transverse stress similar to that which exists in a beam.

2. By deductions from tests, figuring the total area of the breaking surface of a bracket, the breaking strength amounts to from 5,700 to 18,000 pounds per square inch with a distributed load, and from 3,600 to 8,400 pounds with a concentrated load at the edge of the bracket.

3. A bracket projecting from 4 to 5 inches from the body of the column will carry only half as much when the load is

concentrated at the edge of the bracket as it would if the load were distributed over the bracket.

4. The bracket should be made so as to bring the load as close to the column as possible, and thus reduce the bending stress.

45. The following rules have been deduced from tests made and are probably the most reliable for calculating the strength of brackets. A bracket may fail in one or more of the three following ways: (1) by direct shear at the column; (2) by breaking off due to a transverse stress at the column; (3) by tearing out a portion of the column, leaving an approximately elliptical hole.

The First Method.—Under most conditions a bracket will not fail by this method, as most brackets are loaded so as to produce transverse stress rather than shearing. It is well, however, to calculate the strength of the bracket for this stress, assuming the load to be placed close to the column and calculating the shearing strength at 18,000 pounds per square inch of cross-section.

The Second Method.—This method of failure is quite probable, especially with brackets on columns of small diameters. The strength may be figured by applying the formula

$$W = \frac{31,000 \times I}{10 c l} \quad (23)$$

in which W = safe load on the bracket;

I = moment of inertia of section of bracket made by a plane passing through bracket and tangent to outside of column;

c = distance from neutral axis to extreme fiber;

l = distance of center of gravity of load from plane of I .

The Third Method.—The bracket is apt to fail by this method in most cases, especially with columns whose diameters are greater than 6 or 8 inches. It is practically impossible to obtain a method by which the strength of the bracket may be calculated for this kind of failure, as the failure occurs partially from transverse and partially from shearing strains.

If the section modulus of the actual break in the brackets tested could be obtained, it might be possible to find a modulus of rupture that could be utilized in calculating the breaking strength by this method. This section modulus




FIG. 17

evidently depends on the diameter and thickness of the column, the width of the ledge of the bracket, and the height of the vertical web. If it could be calculated for this form of break, it would probably be found to be less than the section modulus

obtained by the second method in columns where the diameter is greater than 6 inches, and greater than the section modulus found by the second method in columns whose diameters are less than 6 inches.

EXAMPLE.—What will be the safe load of the bracket shown in Fig. 17, if the load is concentrated $\frac{1}{2}$ inch from the outer edge, using a factor of safety of 4?

SOLUTION.—The area resisting the load by shear is $6 \times 1\frac{1}{2} + 4\frac{1}{2} \times 1\frac{1}{2} = 12.5625$ sq. in.; allowing 18,000 lb. per sq. in. shearing, we have 226,125 lb. This divided by 4 gives 56,531 lb., safe load. In measuring the height of the vertical web, $\frac{1}{2}$ inch has been allowed for breaking at the foot of the bracket.

The area at the assumed plane of fracture being 12.56 sq. in., from tables giving the properties of various sections, the distance of the neutral axis from the back of flange is

$$\frac{d^2 t + s^2 (b - t)}{2 d t} = \frac{(5\frac{1}{2})^2 \times 1\frac{1}{2}}{25.12} + \frac{1\frac{1}{2}^2 (6 - 1\frac{1}{2})}{25.12}$$

in which $c_1 = 1.783$ in., and $c = 5.750 - 1.783 = 3.967$ in.

From tables giving the properties of sections, the moment of inertia

$$\begin{aligned} \text{of the section is } I &= \frac{t c^3 + b c_1^3 - (b - t)(c_1 - s)^3}{3} \\ &= \frac{1\frac{1}{2} \times 3.967^3 + 6 \times 1.783^3 - (6 - 1\frac{1}{2})(1.783 - 1\frac{1}{2})^3}{3} = 34.502 \end{aligned}$$

Then the safe load, by formula 23, is $W \times \text{area} = \frac{31,000 \times 34.502}{10 \times 3.967 \times 4.5} \times 12.5625 = 75,262$ lb.; hence, the safe load is the smaller of these results, or 56,531 lb. **Ans.**

EXAMPLE FOR PRACTICE

What would be the shearing strength of the bracket shown in Fig. 15 (*k*), allowing $\frac{1}{8}$ inch for breaking at the foot of the bracket?

Ans. 225,000 lb.

46. Beam Connections.—Bolt holes for connecting the beams to the columns should always be drilled either in the column or in the steel beams after the latter are in place, because if the holes were cored in the casting and the holes in the beam punched at the mill, it would very likely be found, in the course of erection at the building, that the beams were supported entirely by the shear of the bolts and not by the bracket. The bolts should always fit as tightly as possible, and in the best work both holes should be drilled in the field, the bolts used being machine fit, for on these beam connections depend the rigidity of the building.

47. Inspection.—In examining castings used in building construction, to ascertain their quality and soundness several points are to be considered. The edges should be struck with a light hammer. If the blow makes a slight impression, the iron is probably of good quality, providing it be uniform throughout. If fragments fly off and no sensible indentation be made, the iron is hard and brittle. Air bubbles and blowholes should be searched for by tapping the surface of the casting all over with a hammer. Bubbles, or flaws, filled in with sand from the mold, or purposely stopped with loam, cause a dullness in the sound, leading to their detection. The metal of a casting should be free from bubbles, core nails, or flaws of any kind. The exterior surface should be smooth and clean and the edges of the casting sharp and perfect. An uneven or wavy surface indicates unequal shrinkage, caused by want of uniformity in the texture of the iron.

The surface of a fracture, examined before becoming rusty, should present a fine-grained texture, of a uniform bluish-gray color and high metallic luster.

EXAMPLE.—A long-leaf, yellow-pine, square column 20 feet long is required to sustain a load of 100,000 pounds; provided a factor of

safety of 5 is used, what must be the size of the column, according to the parabolic formula for wood columns?

SOLUTION.—In order to solve this problem it is first necessary to assume the size of the column and then determine whether the assumed size meets the requirements of the conditions imposed. In this case a $12'' \times 12''$ column is assumed. Substituting values in formula 13, $u_f = 4,000 - .8 \left(\frac{l}{d} \right)^2$, it is found that $u_f = 4,000 - .8 \left(\frac{240}{12} \right)^2 = 3,680$ lb. per sq. in., which, multiplied by the sectional area of the column, or 144 sq. in., equals 529,920 lb. Using a factor of safety of 5, the safe strength of this column is $529,920 \div 5 = 105,984$ lb., which is greater than the load to be sustained, and consequently the assumed size $12'' \times 12''$ is satisfactory and should be used. **Ans.**

EXAMPLES FOR PRACTICE

1. According to the straight-line formula, what will be the allowable load on an $8'' \times 10''$ spruce column, 12 feet long, using a factor of safety of 6, the ultimate compressive strength of spruce being 4,000 pounds per square inch? **Ans.** 43,733 lb.

2. It is required that a short, round, yellow-pine column shall carry 173,000 pounds. What must be the diameter of the column, the safe unit compressive stress of the material being 1,000 pounds? **Ans.** 15 in.

3. What will be the breaking load of a cast-iron column 20 feet long, 12 inches in diameter outside, made of 1-inch metal, according to Gordon's formula (15)? **Ans.** 1,349,248 lb.

4. The thickness of the metal in a cast-iron column is $\frac{3}{4}$ inch; if a factor of safety of 6 is used, and the length of the column is 18 feet, what must be its outside diameter to support a load of 133,000 pounds, using formula 15? **Ans.** 10.5 in.

5. Find by Gordon's formula (15), the ultimate crushing strength of a 10-inch square, outside measurement, cast-iron column; the thickness of the metal is 1 inch, and the length of the column is 20 feet. **Ans.** 1,327,176 lb.

COLUMNS AND STRUTS

(PART 2)

STEEL COLUMNS

INTRODUCTION

1. It is to the adoption of structural steel shapes in building construction that the modern high building owes its existence. Before steel construction was employed, such loads as 700 or 800 tons on one column were considered visionary, for they could not with safety be sustained by any cast-iron or wood column of practical dimensions. But now loads of 1,000 tons, or more, are often supported on a single column, and the structural steel column is superseding the cast-iron column even in buildings of moderate height.

Although the loads in buildings are generally quiescent and the liability to sudden shock is more remote than in bridges, the columns seldom receive their loads as favorably as in bridges, because in most cases they are subjected to considerable eccentricity in loading; that is, the loads on one side of a column are heavier than those on the other, thus tending to produce bending stress and materially decreasing the ultimate compressive strength of the column.

CLASSIFICATION OF STEEL COLUMNS

2. As in the case of cast-iron columns, the method of securing the ends exercises an important influence on the resistance of steel columns to bending, and consequently on their ability to resist compressive stresses. The classification adopted for structural steel columns is as shown in Fig. 1,

For notice of copyright, see page immediately following the title page

where (a) is a column with **hinged or pinned ends**, (b) a column with **flat ends**, and (c) a column with **fixed ends**.




FIG. 1

Hinged-end columns are struts that have only central points or lines of contact, such as are provided by pins passed through reinforced holes in the ends of the member, or, as

in unusual instances, resting in sockets in the form of semi-cylindrical depressions in cast-iron bearing blocks. The center of the end joints in a pin-connected member should lie on the central axis of the column.

Flat-end columns are struts that have flat ends normal to the central axis of the strut, but not rigidly secured at the base and top.

Fixed-end columns are rigidly secured at the end to the contiguous parts of the structure, or by anchor bolts to heavy masonry at the base and to portions of the steel frame at the top. In order to realize the conditions of fixed ends the column must be so secured that the attachment would not be severed if the member were subjected to the ultimate load.

FORMS OF STEEL COLUMNS

3. Conditions That Affect the Choice of a Type of Column.—There are at present numerous forms in which rolled-steel shapes are combined to make up columns for structural purposes. The type of column to be used in a building is sometimes prescribed by the owner, or the design of the building is furnished by the architect, thus leaving the engineer little latitude in his choice of design. There are, however, a number of conditions demanded by considerations, partly practical and partly theoretical, that should be carefully studied and compared before selecting the type of column for a particular purpose. In many cases it will be found that these considerations impose conditions that conflict with each other; and in order to make such a compromise as will meet this difficulty in the most satisfactory manner, there is demanded of the engineer a most careful exercise of judgment guided by practical experience. Some of the most important points to be considered in choosing the type of column to be used, in any case, are the following:

1. The cost and availability of the material.
2. The amount of labor required and the facility with which it may be performed in both shop and field.
3. The distribution of material in the column so as to give the maximum strength with the least weight.

4. The facility with which connections may be made between the column and the members which it supports.

5. The application of the connections in such a manner that they will transfer the compressive stresses directly to the axis of the column.

6. The facility with which the thickness of the metal in the different parts composing the column can be reduced in order to meet the reduced loads of the upper floors. It is not desirable to make the columns supporting the upper floors of the building very small, since the beams and girders supporting the upper floors are usually of the same dimensions as those for the lower floors, and consequently require connections as heavy and secure; it is almost impossible to make such connections to small columns, consequently, in order to reduce the weight of the column for the lighter load that it will carry, it is better to reduce the thickness of the material used and keep the section the same.

7. The facility with which fireproofing may be attached to the section. Columns of circular sections may be fireproofed more compactly than rectangular columns.

4. In regard to the cost and availability of the material, such shapes should be selected as are easily rolled and can be placed on the market at a reasonable price. I beams, channels, angles, and Z bars, together with plates, are the most common commercial sections; these are manufactured at nearly every structural steel mill, and may be obtained promptly in large orders at any locality where a skeleton-constructed building is likely to be erected. Patented sections do not fulfil this condition, and should therefore be avoided in most cases. The consideration of prompt delivery is an important one, and greatly influences the cost and facility with which the modern building is erected.

The consideration of the facility with which the labor in both shop and field can be performed is one that should receive careful attention. In the shop the complexity of the column section, and the number of pieces of which it is

composed, greatly influence the element of labor. If there are numerous small pieces, such as brackets or splice plates, each of which requires cutting, bending, and fitting together, with frequent handling, the cost of labor may be proportionately very great. The number of rivets also greatly influences the cost of a column; not only should there be as few rivets as is consistent with strength, but the construction should permit the rivets to be readily driven by machine, so as to avoid hand riveting, which is slow and expensive and now generally admitted to be inferior to machine work. These facts are also true of the labor in the field; the connections should be as simple as possible, and with as few rivets as is consistent with the strength required; they should be easy of access, so that the work on them may be executed conveniently and rapidly.

5. In connection with the question of the distribution of the material in the column so as to develop the maximum amount of strength with the least weight of material, it is




FIG. 2

Necessary to consider the facility with which economical connections may be made between the columns and floor-beams, and the directness with which the connections transfer the stresses to the central axis of the column. The

relation between these conditions may be illustrated and analyzed by comparing the sections shown in Fig. 2, where (a) represents a section of a Phoenix column, while (b) is a section of a Z-bar column. The apparent advantage of the Phoenix column is that the material composing it is placed

where it will be the most efficient, thus fulfilling the third condition of the above list in a satisfactory manner; the radius of gyration of the column is also practically the same on all of its diameters, and the metal is placed at the greatest possible distance from its center.

On the other hand, by referring to the section of the Z-bar column, it is seen that a considerable portion of the material is concentrated on the axis, a condition that gives it a relatively small radius of gyration and demands the use of a greater weight of material for a given load. This column, however, offers greater advantages for the proper connection of the floorbeams than does the other, and, owing to its open construction, the beams transmit their loads almost directly to the central axis of the column, thus avoiding the disadvantages of eccentric loading.

Thus it is seen that the section having the best theoretical distribution of material is not always the





FIG. 3

best to use, on account of these several practical considerations; in fact, the section shown in Fig. 3 is probably as much used for structural steel columns as any other, although it is not an economical section, for the reason that its radius of gyration on the axis de is very small in proportion to the weight of material used, and, since


the least radius of gyration is always used in calculating the strength of a structural column, all the material that goes to form the greater radius of gyration adds nothing to the theoretical strength.

The great advantage of this section is that it is composed of the cheapest rolled sections, which are put together with a minimum amount of labor. It is also one of the best forms for attaching the beams and girders, and, as will be seen by a study of the details of the splice shown in the figure, for making connections between two adjacent columns.


6. Sections of Columns Frequently Used in Skeleton Building Construction.—The following list shows the general forms of the principal types of steel-column sections now in use:




Larimer column (patented), 1 row of rivets.




Z-bar column without cover-plates, 2 rows of rivets.



Z-bar column with one cover-plate on each side, 6 rows of rivets.



Z-bar column with two cover-plates on each side, 6 rows of rivets.




Z-bar column, additional section obtained by the use of angles and plates, 8 rows of rivets.



Z-bar column, rectangular section, 6 rows of rivets.



Channel column with plates or lattice, 4 rows of rivets.



Box column of plates and angles, 8 rows of rivets.



Plate and angle column without cover-plate, 2 rows of rivets.




Plate and angle column with one cover-plate on each side, 6 rows of rivets.




Latticed angle column, 8 rows of rivets.




A column much used by the Pennsylvania Railroad, composed of angles and plates, 10 rows of rivets.




Keystone octagonal column (patented),
4 rows of rivets.



Four-section Phoenix column (patent expired), 4 rows of rivets.



Eight-section Phoenix column (patent expired), 8 rows of rivets.



Grey column (patented), 4 rows of rivets.

FORMULAS FOR STEEL COLUMNS

COLUMNS WITH CONCENTRIC LOADS

7. There are many forms of built-up columns, though several standard sections are preferred by practicing engineers. It becomes necessary, however, to find some general rule or formula by which the strength of columns of different sections may be calculated. The strength of a steel column depends on its length, the ultimate strength of the material, and the radius of gyration of the section.

There are four formulas that consider these factors, namely—*Gordon's* or *Rankin's*, *Euler's*, the *straight-line*, and the *parabolic*. These formulas give the strength of the column per square inch of section, and the actual strength of the column is determined by multiplying the value obtained from the formula by the area of the column section.

8. Gordon's Formula.—The strength of steel columns may be found by the following rule:

Rule.—*To find the ultimate strength per square inch of sectional area of a steel column with fixed ends, divide the ultimate strength of the material composing the column by 1 plus the quotient of the square of the length, in inches, divided by the product of the constant 36,000 and the square of the least radius of gyration of the section.*

For columns with one end fixed and the other end pin-connected use 24,000 for the constant, and for columns with both ends pin-connected use 18,000.

This rule may be expressed by the formulas given in Table I.

TABLE I
GORDON'S FORMULA FOR n

Material	Fixed Ends	Square or Pin-Connected and Fixed Ends	Pin-Connected on Both Ends
Wrought iron	$n = \frac{40,000}{1 + \frac{l^2}{40,000r^2}}$	$n = \frac{40,000}{1 + \frac{l^2}{30,000r^2}}$	$n = \frac{40,000}{1 + \frac{l^2}{20,000r^2}}$
Soft steel	$n = \frac{45,000}{1 + \frac{l^2}{36,000r^2}}$	$n = \frac{45,000}{1 + \frac{l^2}{24,000r^2}}$	$n = \frac{45,000}{1 + \frac{l^2}{18,000r^2}}$
Medium steel	$n = \frac{50,000}{1 + \frac{l^2}{36,000r^2}}$	$n = \frac{50,000}{1 + \frac{l^2}{24,000r^2}}$	$n = \frac{50,000}{1 + \frac{l^2}{18,000r^2}}$

in which u = ultimate strength of column, in pounds per square inch of section;
 l = length of columns, in inches;
 r = least radius of gyration of section.

It will be noticed from Table I that the same formula applies to columns with square ends as to those that are fixed on one end and pin-connected on the other.

9. Straight-Line Formula.—The following formulas are used in calculating the ultimate unit strength of columns whose lengths are between 50 and 150 radii of gyration:

MEDIUM STEEL		
Fixed ends	$60,000 - 210 \frac{l}{r}$	(1)
Square ends	$60,000 - 230 \frac{l}{r}$	(2)
Pin-connected ends . .	$60,000 - 260 \frac{l}{r}$	(3)
SOFT STEEL		
Fixed ends	$54,000 - 185 \frac{l}{r}$	(4)
Square ends	$54,000 - 200 \frac{l}{r}$	(5)
Pin-connected ends . .	$54,000 - 225 \frac{l}{r}$	(6)

These formulas are derived in practically the same manner as the straight-line formulas used in Fig. 7, *Columns and Struts*, Part 1, the difference being due to the fact that a higher value is used in the above for the ultimate strength of the material.

10. Euler's and the Parabolic Formulas.—As in the case of cast-iron columns, the parabolic formula covers most practical cases. However, because steel is so much stronger, columns whose lengths are great in comparison with their radii of gyration are sometimes used, in which cases Euler's formula may be applied. The limiting value of $\frac{l}{r}$ for wrought iron and steel in these formulas is given in the following table:

WROUGHT-IRON COLUMNS

$$\text{Pin-connected ends} \left\{ \begin{array}{l} \text{When } \frac{l}{r} < 170, u = 34,000 - .67 \left(\frac{l}{r} \right)^2 \quad (7) \\ \text{When } \frac{l}{r} > 170, u = \frac{432,000,000}{\left(\frac{l}{r} \right)^2} \quad (8) \end{array} \right.$$

$$\text{Flat ends} \left\{ \begin{array}{l} \text{When } \frac{l}{r} < 210, u = 34,000 - .43 \left(\frac{l}{r} \right)^2 \quad (9) \\ \text{When } \frac{l}{r} > 210, u = \frac{675,000,000}{\left(\frac{l}{r} \right)^2} \quad (10) \end{array} \right.$$

MILD-STEEL COLUMNS

$$\text{Pin-connected ends} \left\{ \begin{array}{l} \text{When } \frac{l}{r} < 150, u = 42,000 - .97 \left(\frac{l}{r} \right)^2 \quad (11) \\ \text{When } \frac{l}{r} > 150, u = \frac{456,000,000}{\left(\frac{l}{r} \right)^2} \quad (12) \end{array} \right.$$

$$\text{Flat ends} \left\{ \begin{array}{l} \text{When } \frac{l}{r} < 190, u = 42,000 - .62 \left(\frac{l}{r} \right)^2 \quad (13) \\ \text{When } \frac{l}{r} > 190, u = \frac{712,000,000}{\left(\frac{l}{r} \right)^2} \quad (14) \end{array} \right.$$

in which u = ultimate strength of column, in pounds per square inch;

l = length of column, in inches;

r = least radius of gyration, in inches.

In the above formulas, the first in each division is used when the value of $\frac{l}{r}$ is less than the given number and the second when $\frac{l}{r}$ is greater than the given number.

11. Great care is required in the proper classification of a style of column, and it sometimes requires considerable experience to judge in which class a column should be placed. Naturally there would be six divisions, according to the method of securing the ends, as follows: (1) Fixed; (2) fixed

nd square; (3) square; (4) fixed and pin-connected; (5) pin-connected; and (6) square and pin-connected; but on account of the similarity of the effect of stress on certain classes, the same formula applies in more than one case, and it is therefore only necessary to have three formulas for the three following classes: (1) Fixed, or square and fixed; (2) square, or pin-connected and fixed; (3) pin-connected, or square and pin-connected, as given in Table I. The following examples will assist the student in obtaining a clear understanding of this subject.

12. Columns With Hinged Ends.—To this class belong the compression members of a pin-connected truss,




FIG. 4

— the swinging ends of a truss, such as is shown at *a*, Fig. 4. Here the column rests on a pin that permits it to swing to and fro as the truss expands and contracts from changes of temperature.

EXAMPLE.—Using a factor of safety of 4, compute the safe strength of a strut of a pin-connected truss, the length of the strut being 12 feet from center to center of pins, and its section made up of four $6'' \times 6'' \times \frac{3}{8}''$ angles, connected as shown in Fig. 5.

SOLUTION.—Since the relation of the section to each of the axes *a b* and *d e* is the same, its moment of inertia and radius of gyration is the same about either axis, and it is therefore necessary to compute these factors for only one of these axes. From a table giving the properties

of angles the area of the section of a $6'' \times 6'' \times \frac{5}{8}''$ angle is 4.36 sq. in., and the distance of its center of gravity from the back of either leg is 1.84 in., nearly. Also from this table, it is found that the moment of inertia of one of the angles, with respect to an axis through its center of gravity parallel with the given axis, is 15.39.

From Fig. 5, the distance of the axis through the center of gravity of the angle from the axis $d e$ of the section is 2.14 in.; therefore, substituting the known values in formula 1 in *Properties of Sections*, the moment of inertia of a single angle with respect to the axis $d e$, is $I' = I + a x^2 = 15.39 + 4.36 \times 2.14^2 = 35.35$. The moment of inertia of the whole section is, therefore, $I_s = 4 I' = 4 \times 35.35 = 141.40$.




FIG. 5

The total area of the section is $4.36 \times 4 = 17.44$ sq. in.; therefore, the square of its radius of gyration, from formula 6 of *Properties of Sections*, is $r^2 = \frac{I}{A} = \frac{141.4}{17.44} = 8.1$, nearly.

According to the statement of the problem the length of the strut is 20 ft., or 240 in. Substituting in Gordon's formula for medium steel and pin-connected ends, we find the ultimate strength per square inch of section of the strut to be
$$u = \frac{50,000}{1 + \frac{240^2}{18,000 \times 8.1}} = 35,842 \text{ lb.}$$

The safe bearing strength of the strut is therefore

$$\frac{35,842 \times 17.44}{4} = 156,271 \text{ lb. Ans.}$$

13. Columns With Flat Ends or Fixed at One End and Pin-Connected at the Other.—To this class belong columns whose ends are flat and not held firmly, or where there is a single column extending from cap to foundation

as in Fig. 1 (*b*). This class also includes such posts as that shown at *a*, Fig. 6, the lower end being pin-connected and




FIG 6

The upper end securely fastened so that it will assume the shape given in Fig. 4 (*c*), in *Columns and Struts*, Part 1.

EXAMPLE.—The moment of inertia, with respect to the axis YY of the medium steel Z -bar column shown in Fig. 7, is 287.92, and, with respect to the axis XX , 337.17. The total area of the section is 21.36 square inches; what is the safe bearing strength of a column 20 feet in length having flat ends, if a factor of safety of 3 is used?




FIG 7

SOLUTION.—Using the least moment of inertia, which is that with respect to the axis YY , the square of the least radius of gyration is found

to be $r^2 = \frac{287.92}{21.36} = 13.48$, nearly; therefore, the ultimate strength per square inch of section is $u = \frac{50,000}{1 + \frac{240^2}{24,000 \times 13.48}} = 42,445$ lb. The safe

bearing strength is therefore

$$\frac{42,445 \times 21.36}{3} = 302,208 \text{ lb. Ans.}$$

14. Columns With Fixed Ends.—This type appears in buildings where the column extends through two or more stories or is rigidly secured to the structure so as to restrain its bending out of line.

EXAMPLE.—A section of the compression member of a large structural-steel roof truss is shown in Fig. 8. The ends of the member are firmly riveted to the adjacent members of the truss, and the length of the member is 15 feet; what is its safe bearing strength with a factor of safety of 4?




FIG. 8

SOLUTION.—From one of the tables giving the properties of angles, in *Properties of Sections*, the area of a $3'' \times 3'' \times \frac{1}{2}''$ angle is found to be 1.44 sq. in., and the distance from its center of gravity to the back of the flange is .84 in.; also from the same table, the moment of inertia of the angle, with respect to an axis through its center of gravity, is found to be 1.24.

In accordance with the dimensions given in the figure, the distance from the axis de to the centers of gravity of the angles is $4 - .84 = 3.16$ in. The moment of inertia of one of the angles, with respect to the axis de , is, therefore, $I' = 1.24 + 1.44 \times 3.16^2 = 15.62$. The moment of inertia of the web-plate, with respect to de , is $I' = \frac{1}{12} \times \frac{1}{8} \times 8^3 = 13.33$. The moment of inertia of the whole section, with respect to de , is $I_x = 4 \times 15.62 + 13.33 = 75.81$. The total area of the section is $4 \times 1.44 + 8 \times \frac{1}{8} = 8.26$ sq. in.; the square of its radius of gyration, with respect to de , is, therefore, $r^2 = \frac{75.81}{8.26} = 9.18$.

Referring now to the axis ab , the distance from the axis to the center of gravity of one of the angles is $.84 + \frac{1}{8} = .84 + .156 = .996$, say 1 in. The moment of inertia of the angle, with respect to ab , is, therefore, $I' = 1.24 + 1.44 \times 1^2 = 2.68$. The moment of inertia of the web-plate, with respect to ab , is $\frac{8 \times \frac{1}{8}^3}{12} = .02$.

Taking the sum of the moments of inertia of the several parts, the moment of inertia of the whole section, with respect to ab , is found to be $4 \times 2.68 + .02 = 10.74$; dividing this by the area of the section, the square of the radius of gyration, with respect to this axis, is $r^2 = \frac{10.74}{8.26} = 1.3$, nearly, which, being much less than the value of r^2

with reference to the axis de , is the value to use in computing the strength of the member.

Substituting, in Gordon's formula for medium steel and fixed ends, the ultimate strength per square inch of section is

$$s = \frac{50,000}{1 + \frac{180^2}{36,000 \times 1.3}} = 29,550 \text{ lb.}$$

and the safe bearing strength of the member is

$$29,550 \times 8.26 \div 4 = 61,021 \text{ lb. Ans.}$$

COLUMNS WITH ECCENTRIC LOADS

15. In modern buildings, nearly all columns are subjected to more or less eccentric loading; in fact, it would be difficult to find a column loaded with a perfectly concentric load. However, it is good practice to disregard the eccentric loading generally encountered in ordinary building construction, since the preceding formulas make due allowance for the slight eccentricity caused by the lack of symmetry in the arrangement of the brackets and the application of the loads with regard to the central axis of the column. For example, all the beam connections may be on one side of the column, as shown in Fig. 9, or




FIG. 9

the beams attached to one side of the column may be more heavily loaded than those attached to the other side. Some

of these conditions are usually unavoidable and tend to produce the undesirable effect of eccentric loading.

Should the eccentricity of the load be considerable and liable to produce dangerous transverse or bending stresses, it would materially diminish the ability of the column to withstand direct compressive stresses. The bending or transverse stresses should, in such a case, be calculated and an additional amount of material should be added to the section of the column in order to resist them.

16. The nature of the material in cast-iron columns forbids their use in cases where an eccentric load of any considerable amount is liable to occur. It is very important that any eccentric loading on a cast-iron column should be reduced as much as possible and that the brackets should be so designed that their load is carried as near the center line of the column as possible.

Timber columns are often subjected to an eccentric load due to the attachment of a jib crane to them. They must be calculated for this extra stress according to the rules given hereafter and the maximum stress due to the combined direct and bending stresses should not be more than 25 per cent. above the safe unit stress of the column section if subjected to the same load concentrically placed.

Steel columns are the best adapted to use in cases where eccentric loads exist because their section may be increased with little difficulty to take care of the excessive stress. In the subsequent formulas a sufficient factor of safety has been used to take care of any eccentric load of ordinary magnitude. It is for this reason that the allowable unit stress is increased 25 per cent. over the calculated stress for a concentric load.

17. Strength of Columns With Eccentric Loads. The method, considered in this Section, of proportioning columns for eccentric loads, is pursued through the following steps:

1. The allowable unit stress is determined for the column section when subjected to the entire load without regard to the eccentricity of the loading.

2. The allowable unit stress for the combined compression and bending stresses is found by taking one and one-quarter times the allowable unit stress for concentric loading, as determined in the first step of the process.

3. The unit stress to which the column is subjected by the entire load that it supports is obtained by dividing the total load on the column, in pounds, by the sectional area of the column, in inches. The fiber stress due to the eccentric load is found by dividing the product of the eccentrically placed load and its distance from the neutral axis of the section by the section modulus of the section. By adding these two stresses, the maximum unit stress due to the direct compressive stress combined with the unit stress created by the eccentric load is obtained.

4. When the maximum unit stress due to the combined effect of the direct and eccentric loads is determined, and it is found to exceed the allowable unit stress due to the combined compression and bending, as determined in the second step of the process, the column must be redesigned.

5. In order to determine the section that it is necessary to use for the revised design in case the assumed column section is not sufficient, formula 16 is employed. In this formula, W_e is the equivalent central load that will produce the same stress on the column section as the combined central and eccentric loads. For convenience in determining the approximate value of C , used in formula 16, Table II is given. If the judgment of the designer dictates that the loads require a light column, the smaller values given in this table are used; while if it is indicated by the conditions of the problem that a heavier column is needed, the greater values are employed. When the equivalent central load, or W_e , has thus been found, the required column may be selected from the tables given at the end of this Section and the column designed accordingly. For instance, if a latticed channel column 20 feet long is to support a load of 105 tons, it is found from Table XI under the column headed 20 Ft., that two 12-inch, 30-pound channels will be required for the column.

18. Formulas for Eccentric Loads.—The several steps described in the method of providing for eccentric loads on columns, as explained in the previous article, may be expressed in the following formulas; the principal formula for determining W_e is obtained as explained in the evolution given here.

Let W_c = central, or axial, load;

W_e = eccentric load;

W = total load on column = $W_c + W_e$;

W_e = equivalent central load;

e = eccentricity of load $W_e = \frac{v}{c}$;

A = area of cross-section of column, in square inches;

r = radius of gyration in direction of bending;

s_{ca} = allowable stress per square inch for direct compression on columns;

s_c = allowable stress per square inch for combined compression and bending = $1.25s_{ca}$;

s_e = unit stress due to eccentric load;

s_v = direct unit stress per square inch of section due to vertical loads;

c = distance from line passing through center of gravity of column section to extreme edge of section, in inches;









v = distance from eccentric load to line passing through center of gravity of column section, in inches;

$C = \left(\frac{c}{r}\right)^2$.

The bending moment M then equals $W_e v$; the resisting moment M_r is equal to $\frac{s_c I}{c} = s_c S$, in which I is the moment of inertia, with respect to the neutral axis, and S , the section modulus, is equal to $\frac{I}{c}$. Then, as $M = M_r$,

$$W_e v = s_c S, \text{ or } s_e = \frac{W_e v}{S} \quad (15)$$

TABLE II
APPROXIMATE VALUES OF *C* FOR VARIOUS COLUMNS

									
Axis <i>XX</i>	1.60 to 1.75	1.55	1.70 to 2.00	1.40 to 1.60	1.90	2.85 to 3.00	2.30 to 2.00	<i>C</i> ₁ 1.00 to 1.25 <i>C</i> ₂ 4.50	
Axis <i>YY</i>	6.25 to 5.50	5.00 to 4.00		2.65 to 2.85	3.25 to 3.00	3.50	3.25 to 3.00	.	

The direct stress s_e is $\frac{W_c + W_r}{A}$. The total stress then is $s_e + s_n$, and this sum may equal s_d but must not exceed it.

Assuming, therefore, that $s_d = s_e + s_n$, and multiplying this equation by A , we have the greatest allowable stress, $A s_d = A s_e + A s_n$. As $s_e = \frac{W_c + W_r}{A}$ and $s_n = \frac{W_r v}{S}$, these values may be substituted for s_e and s_n , when the equation will become $A s_d = W_c + W_r + \frac{A W_r v}{S}$; $W_c + W_r = W$; therefore, $A s_d = W + \frac{A W_r v}{S}$. Substituting $\frac{l}{c}$ for S , we have $A s_d = W + \frac{W_r A v}{l} = W + \frac{W_r A v c^2}{l c}$ after the numerator and denominator have been multiplied by c^2 .

As $l = l r^2$, $\frac{1}{r^2} = \frac{A}{I}$; also, $k = \frac{v}{c}$, as previously stated. Arranging the equation in the following form, $A s_d = W + W_r \times \frac{A}{I} \times \frac{v}{c} \times c^2$, and substituting $\frac{1}{r^2}$ for $\frac{A}{I}$ and k for $\frac{v}{c}$, we have $A s_d = W + W_r \times \frac{c^2}{r^2} \times k = W + W_r C k$, after substituting C for $\frac{c^2}{r^2}$. A , the required area of the column, then equals $\frac{W + W_r C k}{s_d}$, and as $s_d = 1.25 s_{ca}$, $A = \frac{W + W_r C k}{1.25 s_{ca}} = \frac{4(W + W_r C k)}{5 s_{ca}}$. After multiplying by s_{ca} , the equivalent central load $W_e = A s_{ca} = \frac{4 s_{ca} (W + W_r C k)}{5 s_{ca}}$, and finally

$$W_e = \frac{4}{5} (W + W_r C k) \quad (16)$$

Table II gives the values of C for various types of columns. These values are only approximate, and considerable judgment must be used in selecting them. They are given to aid the student in finding any required size of column by the formulas previously given. In the case of the two angles placed back to back, C , is the value obtained by

considering c as the distance from the axis XX to the back of the angles, while C_c is determined by taking c as the distance from the axis XX to the other extremity.

19. In order that a better understanding may be had of the several operations in the method of providing for the eccentric loading on a column, the following example is given:

EXAMPLE.—The 22-foot column shown in Fig. 10, made of four 6-inch \angle bars and one 8" \times $\frac{3}{4}$ " web-plate, is loaded with 190 tons, 50 tons of which is applied on a bracket at a distance of 8 $\frac{3}{4}$ inches from the center line of the column. (a) What will be the maximum allowable fiber stress of the column? (b) What will be the maximum fiber stress produced by the loads on the column? (c) How should the column be designed to withstand this load?




FIG. 10

SOLUTION.—(a) It is assumed that the column is of mild steel and that the conditions of loading are as designated in Fig. 11. The values of the section modulus, radius of gyration, area, etc. are taken from Table IX. In this case $A = 12 \times 22 = 264$, and $r = 3.74$;

then, $\frac{l}{r} = \frac{264}{3.74} = 70.59$, and sub-

stituting in formula 22, which is used in the tables, $s_{ca} = 15,000 - 57 \times 70.59 = 10,976$ lb., and the maximum safe fiber stress s_e under eccentric loading will be

$$s_{ca} \times 1.25 = 10,976 \times 1.25 = 13,720 \text{ lb. Ans.}$$

(b) By formula 15, in which the load given in tons is changed to pounds, the fiber stress due to the eccentric load is $\frac{50 \times 2,000 \times 8\frac{3}{4}}{76.8}$

$$= 10,905 \text{ lb.}; \text{ the direct stress is } s_e = \frac{W_c + W_e}{A} = \frac{190 \times 2,000}{34.8} = 10,920 \text{ lb.}$$

The maximum fiber stress produced by the loads is

$$10,905 + 10,920 = 21,825 \text{ lb. Ans.}$$

(c) This load is much more than the column will safely sustain. Table II shows that the approximate value of C around the

axis XX for Z -bar columns varies from 2.85 to 3; as the column required will probably be large, 3 may be assumed as the value of C . Also, on account of the increased size of the column, the value of r is assumed as $8\frac{1}{2}$ instead of $8\frac{3}{4}$, and e is increased from $6\frac{3}{8}$ to $6\frac{1}{2}$. In the substitution in the following formula the load is in tons, so that the result is likewise in tons. Then,

$$W_c = \frac{4}{5} \left(190 + \frac{50 \times 3 \times 8\frac{1}{2}}{6\frac{1}{2}} \right) = 308.92 \text{ T.}$$

From Table XVII it is found that a 6-in Z -bar column with a $\frac{1}{8}$ -inch web-plate will not be strong enough,

so that a column with cover-plates will have to be used. Referring to Table XVIII, it is found that a 6-in Z -bar column with a web-plate $8'' \times \frac{3}{4}''$

and cover-plates $12'' \times 14''$ will have a safe resistance of 313 T., which gives an excess of strength of 4 T. This column weighs 191.7 lb. per ft. of length, according to Table X.

In all such problems, the weight is an important factor and the best designer will select the lightest weight of column consistent with the required strength. If the design is changed to a plate and angle column, the value of C , as found in Table II, is assumed as 1.55, and substituting in the formula above,

$$W_c = \frac{4}{5} \left(190 + 50 \times 1.55 \times \frac{8\frac{3}{4}}{6\frac{3}{8}} \right) = 232.2 \text{ T.}$$

Assuming a plate and angle column with a web-plate of $12'' \times \frac{3}{4}''$ and four angles $6'' \times 4'' \times \frac{1}{4}''$ with $\frac{1}{16}$ in. cover-plates, the required strength is found to be 234 T., which is amply sufficient to support the load. As this column weighs only 157.5 lb. per ft. against 191.7 lb. for the Z -bar column, a saving of 34 lb. per ft., or 748 lb. for each column, is obtained.

20. Columns With Several Eccentric Loads.—When a column is loaded with a number of eccentric loads, the maximum fiber stress is equal to the algebraic sum of the stresses due to the loads on the column.

EXAMPLE.—An 8-inch channel column composed of two 8-inch, 17-pound channels and two $1'' \times 10''$ cover-plates is loaded with 80 tons, which is distributed on the brackets a, a and b, b , as shown in Fig. 12; what will be the maximum stress due to these loads, and at what part of the column will it occur?




FIG. 11

SOLUTION.—Since the maximum fiber stress is equal to the algebraic sum of the stresses due to the loads on the column, it is necessary to determine both the direct stress and the stresses due to eccentric loads.

According to the third step in the method for providing for eccentric loads, as described in Art. 17 the stress due to each eccentric load is equal to its moment about the central axis of the column divided by the section modulus of the column with respect to the same axis. If the moment of a load on one side of the axis XX is considered as being positive, the moment of the load on the other side of the same axis is negative. The same is true regarding the loads on each side of the axis YY . From Table VII, the section modulus for such a column about the axis XX is 98.2 and about the axis YY is 53.4.




FIG. 12

Consequently, the algebraic sum of the stresses due to the four eccentric loads is $\frac{35 \times 7}{98.2} - \frac{15 \times 7}{98.2} + \frac{20 \times 4.9}{53.4} - \frac{10 \times 4.9}{53.4} = 2.344$ T.

The unit stress due to the direct load is equal to the sum of the loads divided by the area of the column section. In this case, the sum of the loads = $20 + 35 + 10 + 15 = 80$ T., and the area of the column section found from Table VII is 30 sq. in., so that the direct unit stress is $\frac{80}{30} = 2.666$, which, added to the previous sum, equals $2.666 + 2.344 = 5.01$ T. per sq. in., or 10,020 lb. This stress would occur at the corner between the loads of 20 T. and 35 T. Ans.

21. Columns Under Bending Stress.—Columns are sometimes subjected to a direct bending stress; such cases are met with in columns supporting open sheds, especially where the truss is braced against the column, or the column supports a jib crane. In such cases the bending stress should be calculated and the column proportioned accordingly.

EXAMPLE.—Given a column on which a 5-ton jib crane has been attached, such as is shown in Fig. 13 (a). If the column is made up of four $6\frac{1}{2}'' \times \frac{1}{2}''$ Z bars, one $8'' \times \frac{1}{2}''$ web-plate, and two $14'' \times \frac{1}{2}''$ cover-plates, and is $22\frac{1}{2}$ feet high to the center of bearing *d*, will it be safe?




FIG. 13

SOLUTION.—From Table X, we find that the area equals 58 sq. in. The radius of gyration about axis *XX* is 4.82; the radius of gyration about axis *YY* is 3.86, the section modulus, with respect to axis *XX*, is 192.2; the section modulus, with respect to axis *YY*, is 123.5. In

this case, c is 7 in. in both directions. The ultimate strength per square inch, by Gordon's formula, Table I, for medium steel, pin-connected

and fixed ends is $u = \frac{50,000}{1 + \frac{(22.5 \times 12)^2}{24,000 \times 3.86^2}} = 41,535 \text{ lb.}$

Using a factor of safety of 4, the safe load per square inch is $\frac{41,535}{4} = 10,384 \text{ lb.}$, and for eccentric loads is $10,384 \times 1.25 = 12,980 \text{ lb.}$

In this case, the crane itself is assumed to weigh 800 lb., half of which is concentrated at each end of the I beam c . Resolving the load into its components, and considering the forces as passing through the centers of the bearings d, e , on the column, it is found, by the triangle of forces at (b) , that there is a horizontal thrust of 24,900 lb. due to the load, $10,000 + 400 = 10,400 \text{ lb.}$

Considering the column as a beam supported at a and b , and that the center line of bearing d is coincident with the center line of the beam f , then since $R : 24,900 = 51 : 252$, the reaction R at the base of the column, due to this thrust is 5,039 lb. The maximum stress on the column is:

Stress due to direct load on column,

$$52 \times 2,000 = 104000 \text{ lb.}$$

$$5 \times 2,000 = 10000 \text{ lb.}$$

$$800 \text{ lb.}$$

$$\hline 114800 \text{ lb.}$$

The stress per square inch of section $= \frac{114,800}{58} = 1,979 \text{ lb.}$

Stress due to bending,

$$10,800 \times 12 = 129600 \text{ in.-lb.}$$

$$5,039 \times 201 = 1012839 \text{ in.-lb.}$$

$$\hline 1142439 \text{ in.-lb.}$$

The stress per square inch due to bending is then $\frac{1,142,439}{S}$
 $= \frac{1,142,439}{192.2} = 5,944 \text{ lb.}$, and the total stress is $1,979 + 5,944$, or $7,923 \text{ lb.}$

Stress when the crane is at right angles to position shown in figure:

$$\text{Direct stress} = 1979 \text{ lb.}$$

Bending stress

$$(10,800 \times 12) \div 192.2 = 675 \text{ lb.}$$

$$(5,039 \times 201) \div 123.5 = 8201 \text{ lb.}$$

$$\text{Total stress} = 10855 \text{ lb.}$$

In this case, the bending stress in the column is around the axis YY , when, according to Table X, the section modulus S equals 123.5 instead of 192.2, used above.

The column will, therefore, be amply safe in both directions. Ans.

22. Factors of Safety.—The ability of a column to resist the transverse or bending stresses due to eccentric

loading decreases as its length increases, and this ability is less for columns with round or hinged ends than for those with flat or fixed ends. For these reasons it is good practice to assume a minimum factor of safety for the shortest columns or struts and increase the factor with the increase in length, making the rate of increase greater for round or hinged than for flat or fixed ends.

TABLE III
FACTORS OF SAFETY

$\frac{l}{r}$	Fixed and Flat Ends	Hinged Ends	$\frac{l}{r}$	Fixed and Flat Ends	Hinged Ends	$\frac{l}{r}$	Fixed and Flat Ends	Hinged Ends
20	3.2	3.30	110	4.1	4.65	200	5.0	6.00
30	3.3	3.45	120	4.2	4.80	210	5.1	6.15
40	3.4	3.60	130	4.3	4.95	220	5.2	6.30
50	3.5	3.75	140	4.4	5.10	230	5.3	6.45
60	3.6	3.90	150	4.5	5.25	240	5.4	6.60
70	3.7	4.05	160	4.6	5.40	250	5.5	6.75
80	3.8	4.20	170	4.7	5.55	260	5.6	6.90
90	3.9	4.35	180	4.8	5.70	270	5.7	7.05
100	4.0	4.50	190	4.9	5.85	280	5.8	7.20

Assuming a minimum factor of safety of 3 for very short struts, the factors prescribed by good practice for longer struts with flat or fixed ends are found by the formula

$$F = 3 + .01 \frac{l}{r} \quad (17)$$

and for struts with hinged ends,

$$F = 3 + .015 \frac{l}{r} \quad (18)$$

in which F = required factor of safety;

l = length of strut, in inches;

r = least radius of gyration of section.

EXAMPLE.—What is the least factor of safety that should be used with: (a) a column with flat ends, and (b) a column with hinged

ends, the length of the column being 20 feet, and its least radius of gyration, 2.5?

SOLUTION.—(a) Applying formula 17, we have

$$F = 3 + .01 \times \frac{240}{2.5} = 3.96, \text{ say } 4. \quad \text{Ans.}$$

(b) Applying formula 18,

$$F = 3 + .015 \times \frac{240}{2.5} = 4.44. \quad \text{Ans.}$$

Table III gives values for the factor of safety obtained by substituting different values of $\frac{l}{r}$ in formulas 17 and 18.




FIG. 14

These values are for columns whose length is as great as 280 times their least radius of gyration; it is not, however, good practice to use a column in which the value of $\frac{l}{r}$ is greater than 150. Another condition to be observed is that the length of the column should not exceed 45 times its least dimension.

23. Results of Tests.—Fig. 14 is a chart giving the results of tests on various forms of structural columns.

The lines showing the results of the parabolic formulas agree with the column tests to a remarkable degree of accuracy. This chart was prepared by Prof. J. B. Johnson, in order to show how closely his parabolic formula agrees with the tests made on columns.

The tests marked with a circle indicate that the test pieces were symmetrical in section with the bearing pin in the center, while those marked with two concentric circles indicate that the column tested was unsymmetrical in section with the bearing pin placed at the center of gravity. The key to the marks used in the chart is given below.

It must not be inferred from this chart that because the Phoenix columns are among the highest in their results per square inch, they are the strongest. It simply means that the columns tested were of steel with flat ends, having a value of $\frac{1}{r^2}$ varying from 40 to 130.

Wrought iron, Watertown Arsenal	Symmetrical sections, pin in center	○
	Unsymmetrical sections, pin in center of gravity	◎
Phoenix		⊗
American		I
Wrought-iron box		□
Pennsylvania Railroad solid web		⌈
Z bar		⌋
Keystone		⊕
Steel latticed channels		⌈⌋

EXAMPLES FOR PRACTICE

1. What safe load, according to Gordon's formula, can be supported by a plate and angle column made up of four $3'' \times 2\frac{1}{2}'' \times \frac{1}{2}''$ angles and one $6'' \times \frac{1}{2}''$ web-plate, the length of the column being 16 feet and the ends being pin-connected, using a safety factor of 4? Ans. 78,299 lb.

2. Using the straight-line formula, what is the ultimate strength of a 16-inch, 304.1-pound **Z**-bar column of medium steel 30 feet in height, with flat ends? Ans. 3,754,800 lb.

3. Calculate the allowable maximum fiber stress under an eccentric load of a 14-inch, 179.5-pound **Z**-bar column 26 feet long, with fixed ends, using Gordon's formula with a factor of safety of 5, the values to be taken from the tables. Ans. 10,562 lb.

4. A plate and angle column 28 feet long, fixed at the ends and of the general dimensions shown in Fig. 15, is subjected to a vertical load of 150 tons and a direct horizontal thrust of 6 tons from




FIG. 15

the knee brace of a truss 5 feet below its top, and parallel to the web-plate of the column. What will be the maximum unit stress in the flange plates *a, a*, considering both the transverse and the direct stress? Ans. 10,638 lb.

5. A 10-inch, 15-pound channel column 20 feet high, with square ends, and having $\frac{3}{8}$ -inch cover-plates, is cross-braced at one-half its height in a plane parallel to the plates of the column. What is its ultimate strength, according to the parabolic formula? Ans. 40,275 lb.


DESIGN OF STEEL COLUMNS

24. Different Column Sections.—Tables giving the properties, dimensions, and safe loads of the common forms of columns are given at the end of this Section, but a few remarks as to some of the forms may be of value at this time. The plate and angle columns are especially adapted for use when cranes or any eccentric loads are to be placed on the column, because they may be made so as to stand the strain without much increase of weight.

The **Z** bar, channel and plate, and box columns are best adapted to ordinary cases in building, where the load is distributed around the column.

The latticed channel column is used where the load is light. The channels are placed a certain distance apart, as shown in the tables at the end of this Section, and are so arranged that the center of gravity of the channels is, in both cases, the same distance from the center line of the column.

TABLE IV
SIZE OF LATTICE BARS AND STAY-PLATES TO BE USED WITH LATTICED CHANNEL COLUMNS



Depth of Channels	Dimensions of Lattice Bars		Weight of Lattice Bars per Foot	Center of Hole to End of Bar <i>a</i>	Distance Center to Center of Rivets <i>d</i>		Size of Stay-Plates at Ends of Columns		Diameter of Rivets
	Inches	Inches			Maximum	Minimum	Thickness	Inches	
			Pounds	Inches	Feet	Inches	Inch	Inches	Inch
6	1½	1½	1.28	1½	0	6½	1	7½	¾
7	1½	1½	1.49	1½	1	7½	1	10	¾
8	2	1½	2.12	1½	1	8½	1½	9	¾
9	2	1½	2.12	1½	1	9½	1½	12	¾
10	2	1½	2.55	1½	1	10½	1½	12	¾
12	2½	1½	2.87	1½	1	10½	1½	15	¾
15	2½	1½	3.19	1½	2	31½	1½	15	¾

25. Spacing of Lattice Bars.—In Table IV are given the necessary dimensions for placing the lattice bars on columns. The value of b for various columns may be found by the following formula. If f is the width of a flange of the channels, then for columns made with the flanges turned out,

$$b = 2f + d \quad (19)$$

and for columns made with the flanges turned in,

$$b = D \quad (20)$$

The values of d and D are given in the tables of safe loads for latticed channel columns at the end of this Section, and have nothing to do with the value d in Table IV.




FIG. 16

26. Clearance.—In designing columns with a central web-plate, such as Z-bar columns and plate and angle columns, the outside edge of the web-plate should be at

least $\frac{1}{8}$ inch back from the faces of the **Z** bars or angles. This clearance is allowed in order to provide for any inequality in cutting.

27. Efficiency of Section.—In order to compare the efficiency of the different sections, Fig. 16 has been prepared. This shows the comparative ultimate strength for different lengths of five forms of columns. The columns assumed are those whose greatest diameter is not over 17.4 inches nor less than 15.6 inches, and whose least outside dimension is between 12 and $12\frac{3}{4}$ inches. The area of the section has been reduced to 30 square inches. In other words, the sections are the same weight, about 100 pounds per foot of length, and have about the same limiting extreme dimensions of cross-section.

To ascertain from the diagram the ultimate strength, in tons, of a column of a given section and length, select the corresponding length from either of the horizontal rows of numbers and follow the vertical line belonging to this number until it intersects the curve of the column selected. The value, in tons, of the horizontal line drawn through this point is ascertained from the vertical rows of numbers. For instance, it is desired to find the ultimate strength of a channel column, 20 feet long, of the section indicated in the diagram. On following the 20-foot line, it is seen to have a point of intersection that happens to be common to that of the horizontal line representing 660 tons, which is the ultimate strength of this column.

The strength of a Phœnix column of the same length is seen to be about 693 tons.

The ultimate strength, in tons, has been calculated by Gordon's formula for medium steel columns with fixed ends. This shows the great economy, so far as the weight is concerned, in the use of the box and round shapes, but the advantage of weight is not always the most important consideration, as stated before.

Further, this comparison has been made on the assumption that the load is placed at the center of gravity of the

section. It does not take into consideration the problem of eccentric loading, in which case the round column is the least economical. The advantage of the round-column section is realized where floor space is desired and long columns are indispensable.

28. Column Splices and Connections.—The excellence of the detail design of structural steel columns is

largely governed by the experience and judgment of the designer, and the care with which he studies the local conditions that will be met with in nearly every new piece of work.

As the strength of a building depends almost entirely on the strength of the beam connections to the columns, great care should be taken in their design. Rigid connections for the floorbeams and girders at the several floors, and efficient splice connections between the sections of the columns on the different floors are of the utmost importance, and should be given the most careful attention. The ideal system of column construction would be to make the various columns on the several floors of one continuous set of




FIG. 17

FIG. 18

sections running from foundation to roof. It is evident, however, that this is impossible in high modern-building

construction, and therefore the next best thing is to make the spliced connections as rigid as possible.

Columns may be spliced as shown in Fig. 17. The bedplate *a* separates the two columns, and through it, by means of the angles *b b*, the columns are riveted securely together; they are also additionally secured by means of the two splice plates *c, c*.




FIG. 19

The abutting ends of structural columns should be milled or planed so as to secure a square and firm bearing and obviate the danger of their being thrown out of line when erected.

Another very good method of connecting two columns is by the use of splice plates on all sides, thus doing away with the bedplates or packing pieces between the ends; this construction is shown in Fig. 18.

In some cases the bedplate extends beyond the column and forms a rest or support for the floorbeams or girders.

This is shown by means of Fig. 19, in which (*a*) is a front elevation, (*b*) a plan view, and (*c*) a side elevation of the joint. It is here advisable to further support the bedplate *b* by a bracket *c* directly under the bearing of the beam. The beams are secured to this bedplate and also to the post by means of angle clips *d*.

If, in the same floor, the beams or girders are of different depths and are at the same level with regard to the top flange, the shallow beams may be supported by introducing cast-iron blocks *a* beneath them, as shown in Fig. 19. In this case angle clips *e* connect the beams and column.

Where the floor girders are of the built-up plate-girder type, there is no difficulty in securing a rigid connection to the column. The connection to be recommended, where the architectural features of the interior arrangement of the building do not interfere, is shown in Fig. 20. This connection is particularly




FIG. 20

efficient when the building is high and narrow, and in danger of being acted on by heavy wind pressure.

Other forms of connections, where plate girders are the principal supporting members of a floor system, are shown in Figs. 21 and 22. In Fig. 21, a filler *c* is introduced because the upper column is smaller than the lower, and it becomes necessary to pack between the splice plates. It is, however, preferable to pack equally on both sides of the

upper column whenever practicable, as this insures the central axis of the one column being over the central axis of the other.

29. Fig. 23, in which (a) is a front elevation and (b) a plan view, shows another form of column section made by riveting together four channels and two cover-plates, which makes a very efficient form of section. There are only four rows of rivets, and the column presents four good faces on which to form connections. It will be seen that a single



FIG 21

angle *a* has been placed under the 10-inch I beam to support it and take the load. With such a light beam, this is all that is necessary, but where an 18-inch girder is to be connected on the side, additional means must be provided for supporting its load. Two 3" × 3" × $\frac{5}{16}$ " angles *b* have therefore been riveted directly under the angles supporting

the beam, in order to transmit the load to the column, this size angle having been selected in order to bring the line of rivets directly under the load. In making up this column, the brack-

ets should be riveted to the outside channel before the channels are riveted together.

Fig. 24 shows a connection for a heavy column, designed to support an enormous load, and at first sight the connection seems very light, the splice plate being only $\frac{1}{2}$ inch. The column is made up of four angles with one web-plate and three cover-plates riveted to the angles on two sides of the column. The ends of the columns at such a splice must be planed off very accurately so as to give a full bearing, in order to transmit the load directly to the center of the column below. In such a case, the splice plates are only used as guides to hold the columns in line, and they bear no load. This splice should be as near

the floor connection as possible, and not more than 25 inches above the top of the beams.

A splice commonly used in connecting Phoenix columns is illustrated in Fig. 25, which shows an eight-section column in which filler plates have been used. One plate *a*, the form of which is shown in the elevation (*a*), passes directly through the column, tying the parts together and forming a web splice for the floor-beam connections, as shown in the plan view (*b*). At right angles to this plate, two other plates have been placed, which are riveted to the first one by means of angles. These plates greatly stiffen and strengthen the column, but they add inefficient material at the center of the column, which should be figured as part of the load supported.




FIG. 22

30. In Figs. 26 and 27 are shown complete detail working drawings of the first-floor columns of a building designed according to the best modern practice. Fig. 26 shows a channel column to which the floorbeams are rigidly secured at a considerable distance below the splice, which has been designed with a bedplate between the two sections. The

splice could have been made as well by the use of side-splice plates, similar to those on the other two sides, as previously explained, and would possibly have been more efficient.






FIG. 23




FIG. 24

The base of this column gives very interesting details. It is designed with side plates to distribute the weight over

the capstones. The load from the column is partly transmitted to the side plates, which again transmit the load to the $5'' \times 5''$ angles and thence to the base plate. Part of the load is also transmitted to the base plate through the side angle clips shown in the side view.




FIG. 25

In Fig. 27 is shown a Z-bar column, the principal points in the detail of which are similar to those in the channel-bar column.

In each of these examples, the shear on the rivets supporting the floorbeam brackets has been calculated to safely sustain the load carried by the floorbeams.




FIG. 26




FIG. 27

All the connections and splices to a column should be riveted together with hot rivets; this insures more rigidity against wind pressure than can be obtained by bolted connections.

In Fig. 28 is shown the usual method of forming the base for a Phoenix column. Here the web-plates come into play by helping to distribute the load equally over the bed-




FIG. 28

plate. This base is very strong and is capable of sustaining a load of 100 tons, if set in cement.

31. Assembled Designs.—Fig. 29 gives an example of a column supporting the wall of a building. In the illustration (*a*) is a sectional plan taken along line *AB* of (*c*), (*b*) a side elevation showing the surrounding brickwork in section, and (*c*) a front elevation. Four **Z** bars are riveted to separate plates between which the floor girder passes, forming a cantilever for the support of the wall. The advantages of this design are that the load supported by this girder is transmitted practically to the center of the column, and the walls may be made so as to balance the

weight of the floors and partitions. This column section is very efficient for the purpose for which it is intended.

Fig. 30 shows the details of a channel and plate column supporting two 20-inch floor girders *a, a*, a 12-inch wall






FIG. 29


beam *b*, and a 15-inch floorbeam *c*. An effort has been made to entirely eliminate eccentric loading, and with this object in view a girder has been placed on either side of the

4-6x6x1/2 Ls.
 16 Plots.
 4-8x8x1/2 Ls.
 16 Plots.





a)

Section (b)









igh A B



view. The main column b is made up of four $8'' \times 8'' \times \frac{1}{8}''$ angles and one $17'' \times \frac{5}{8}''$ web-plate, and supports two 32-inch wall girders h, h . Each of the latter is made up of four $6'' \times 4'' \times \frac{1}{2}''$ angles, and one $31\frac{3}{4}'' \times \frac{3}{8}''$ web-plate. Two floor girders i, i , made up of two 15-inch 100-pound I beams, run directly over the lower column and support the upper column c , which is made up of four $6'' \times 6'' \times \frac{1}{2}''$ angles, with one $17'' \times \frac{5}{8}''$ web-plate. An important part of the structure is the brace g , which is of $\frac{3}{4}$ -inch plate, located on each side of the column b for the purpose of connecting the latter directly with the upper column and also with the girders and the I beams. In order to stiffen the I beams sufficiently to receive the load of the upper column, four series of filler plates k_1, k_1 have been inserted, which are riveted securely to the webs of the I beams, the braces g , and the angle stiffeners of the girders h .

The load from the upper column is still further distributed over the I beams by the use of a 1-inch plate d and the vertical web-plate a . The two girders are connected by the $\frac{5}{8}$ -inch vertical plate e and the angles shown, the latter being riveted securely to the upper flanges of the girders. In order to secure the girders h, h still further against turning over, the $\frac{5}{8}$ -inch plates f are riveted to the lower flanges of the girders by means of two $6'' \times 4'' \times \frac{1}{2}''$ angles and to the lower column by two $4'' \times 4'' \times \frac{1}{2}''$ angles. To strengthen the connection between the I beams and the lower column, two 1-inch plates m, n have been riveted to the beams and the column connection.

32. Columns for Power Houses and Shops.—Fig. 32 is a detail drawing of a column designed for a power house, in which (a) is a front elevation, (b) a side elevation, and (c) a sectional plan taken on line AB in (b). The column is one of a series supporting an I beam. On top of this beam is a T rail over which the side wheels of a 50-ton crane may run. There is a similar beam supported by columns at the other side of the building supporting the other end of the crane. The load to which the column will be subjected

from the crane is 25 tons. The column supports also an upper column, which in turn supports the roof and carries about 12 tons. Its section is made up of four $6'' \times 3\frac{1}{2}'' \times \frac{1}{2}''$




FIG. 33

angles, two $28'' \times \frac{3}{4}''$ web-plates, and two $16'' \times \frac{1}{4}''$ cover-plates. For the purpose of strengthening the lower column for the load of the upper column, a diaphragm has been inserted in the interior of the lower column directly under the plinth plate. This helps to distribute the load of the upper column more evenly over the whole of the lower column. The diaphragm consists of a vertical plate stiffened by two angles riveted to its sides. Under the plate girder that supports the track for the crane, is a vertical web brace, which acts as a bracket for the crane and also as a connection for the cross-bracing that is inserted between adjacent columns.

Fig. 33 shows the connections between the post *a* and one of the adjoining posts. In this figure *b*

is the main I beam and *c* a smaller one that connects the post *a* rigidly with adjoining posts on either side; *d* is a cross-brace and *e* an additional longitudinal brace. The columns have a clear height of 44 feet, but by reason of being cross-braced to the adjacent columns, the effective height is only 22 feet.

EXAMPLE —Given the case shown in Figs 32 and 33; using Gordon's formula: (a) what is the maximum fiber stress? (b) what load will the column be able to carry, using a factor of safety of 5?

SOLUTION. —(a) The moment of inertia of the column about the short axis through the center of the column and parallel with the I beams is:

Moment of inertia of two web-plates $28'' \times \frac{3}{8}'' = 2 \times 686$. . .	1 3 7 2
Moment of inertia of four $6'' \times 3\frac{1}{2}'' \times \frac{5}{8}''$ angles, $4(20.08 + 5.55$ $\times 11.87^3)$	3 2 0 8
Moment of inertia of two $16'' \times \frac{3}{4}''$ plates, $2(.5625 + 12 \times 14\frac{3}{8}^3)$	4 9 6 0
Total moment of inertia	9 5 4 0

The area of the column section is as follows:

Two $28'' \times \frac{3}{8}''$ plates	2 1.0 sq. in.
Four $6'' \times 3\frac{1}{2}'' \times \frac{5}{8}''$ angles	2 2.2 sq. in.
Two $16'' \times \frac{3}{4}''$ plates	2 4.0 sq. in.
	<u>6 7.2 sq. in.</u>

The distance from the neutral axis to the extreme fiber is $14\frac{3}{4}$ in.;

then the section modulus is $S = \frac{9,540}{14\frac{3}{4}} = 647$.

The maximum fiber stress is $\frac{25 \times 14\frac{3}{4} - 12 \times 7}{647} + \frac{37}{67.2} = .9907$ T.

Per sq. in. = 1,981.4 lb. per sq. in. Ans.

(b) The radius of gyration about the short axis is $r = \sqrt{\frac{9,540}{67.2}}$, or
 $= \frac{9,540}{67.2}$.

The moment of inertia of the column about the long axis, at right angles to the I beams is as follows:

Moment of inertia of two web-plates, $2(.123 + 10\frac{1}{2} \times 4\frac{5}{8}^3)$.	3 9 0.8 0
Moment of inertia of four angles, $4(5.08 + 5.55 \times 5.38^3)$. .	6 6 2.8 8
Moment of inertia of two plates $16'' \times \frac{3}{4}'' = 2 \times 256$	5 1 2.0 0
Total moment of inertia	1 5 6 5.6 8

Using Gordon's formula for medium steel and for flat-ended columns,

$$u = \frac{50,000}{1 + \frac{(44 \times 12)^2}{24,000 \times \frac{9,540}{67.2}}} = \frac{50,000}{1.0818} = 46,219 \text{ lb.}$$

This is the breaking strength calculated with the shorter axis as the base of the calculations. The strength of the column about the longer axis may be determined as follows: Since the column is cross-braced at the middle in this direction, it is assumed to act as a column only half its height. The ultimate strength per square inch, therefore, is

$$u = \frac{50,000}{1 + \frac{(22 \times 12)^2}{24,000 \times \frac{1,565}{67.2}}} = \frac{50,000}{1.124} = 44,484 \text{ lb.}$$

The column therefore is weakest about this axis and its safe load will be

$$\frac{44,484 \times 67.2}{5} = 597,865 \text{ lb. Ans.}$$

33. Tables Giving the Strength and Properties of Steel Columns.—The following tables giving the safe load, in tons, for the usual column sections, will be found convenient in selecting structural steel columns for a determined load. The values in these tables have been calculated from the following formulas:

$$\begin{aligned}
 s_s \text{ for medium steel} &= \begin{cases} 12,000 \text{ for lengths up to 50 radii of} \\ \text{gyration} & (21) \\ 15,000 - 57 \frac{l}{r} \text{ for lengths over 50} \\ \text{radii} & (22) \end{cases} \\
 s_s \text{ for soft steel} &= \begin{cases} 12,000 \text{ for lengths up to 30 radii of} \\ \text{gyration} & (23) \\ 13,500 - 50 \frac{l}{r} \text{ for lengths over 30} \\ \text{radii} & (24) \end{cases}
 \end{aligned}$$


These formulas embody their own factor of safety, which varies from 4 to 5. The tables for safe loads on I-beam columns have been calculated for soft steel. The tables of safe loads for plate and angle columns, channel and plate columns, and Z-bar columns have been calculated for medium steel, which is the grade of steel that it is advisable to use for such columns.

TABLE V
PROPERTIES OF STEEL PLATE-AND-ANGLE COLUMNS




Column Section	Thickness of Plate and Angle, Inch	Area of Section Square Inches	Weight of Column in Pounds per Foot	Axis X-X			Axis Y-Y		
				Moment of Inertia	Section Modulus	Radius of Gyration Inches	Moment of Inertia	Section Modulus	Radius of Gyration Inches
One 6-Inch Plate Four 3" X 3" L's	$\frac{1}{4}$	6.74	22.9	36.3	12.09	2.32	10.4	3.32	1.24
	$\frac{3}{8}$	8.52	29.0	44.6	14.87	2.29	13.6	4.24	1.26
	$\frac{1}{2}$	11.71	39.8	59.0	19.68	2.25	21.1	6.42	1.34
	$\frac{3}{4}$	13.00	44.2	64.6	21.53	2.23	24.7	7.60	1.38
One 7-Inch Plate Four 3½" X 3½" L's	$\frac{1}{4}$	7.51	25.5	58.3	16.65	2.78	16.1	4.43	1.46
	$\frac{3}{8}$	9.43	32.1	71.9	20.55	2.76	20.8	5.59	1.49
	$\frac{1}{2}$	12.98	44.1	95.8	27.38	2.72	30.8	8.15	1.54
	$\frac{3}{4}$	14.50	49.3	105.1	30.02	2.69	36.3	9.69	1.58
One 8-Inch Plate Four 4" X 3" L's	$\frac{1}{4}$	10.86	36.9	107.5	26.88	3.14	30.3	7.30	1.67
	$\frac{3}{8}$	13.12	44.6	128.5	32.13	3.13	37.4	8.79	1.69
	$\frac{1}{2}$	14.98	50.9	144.6	36.15	3.11	44.4	10.54	1.72
	$\frac{3}{4}$	17.24	58.6	163.5	40.88	3.08	53.1	12.29	1.75
One 9-Inch Plate Four 4½" X 3" L's	$\frac{1}{4}$	19.50	66.3	182.9	45.73	3.06	61.9	14.04	1.78
	$\frac{3}{8}$	20.92	71.1	193.5	48.38	3.04	69.1	16.04	1.82
	$\frac{1}{2}$	22.83	77.6	209.4	52.44	3.55	75.3	15.64	2.01
	$\frac{3}{4}$	24.18	84.9	226.3	58.44	3.52	87.9	17.90	2.04
One 10-Inch Plate Four 5" X 3" L's	$\frac{1}{4}$	12.73	43.3	211.8	42.36	4.08	57.6	11.16	2.13
	$\frac{3}{8}$	15.35	52.2	252.7	50.54	4.06	71.9	13.68	2.17
	$\frac{1}{2}$	17.62	59.9	286.4	57.28	4.03	85.9	16.46	2.21
	$\frac{3}{4}$	20.24	68.8	326.0	65.20	4.01	102.2	19.22	2.25
One 12-Inch Plate Four 5½" X 3" L's	$\frac{1}{4}$	22.35	76.0	355.7	71.14	4.00	118.1	22.36	2.29
	$\frac{3}{8}$	24.07	84.9	392.3	78.46	3.97	136.6	25.43	2.34
	$\frac{1}{2}$	28.07	97.5	451.0	105.5	4.77	199.7	30.91	2.64
	$\frac{3}{4}$	30.94	104.9	493.4	115.6	4.75	223.4	35.49	2.69
One 12-Inch Plate Four 6" X 4" L's	$\frac{1}{4}$	34.17	116.2	560.1	126.8	4.72	255.7	36.88	2.73
	$\frac{3}{8}$	37.44	127.3	625.3	137.6	4.70	288.7	44.44	2.78
	$\frac{1}{2}$	41.44	139.4	700.4	150.4	4.68	331.4	51.44	2.84
	$\frac{3}{4}$	45.44	150.4	775.4	163.4	4.66	374.4	58.44	2.89

TABLE VI
PROPERTIES OF STEEL PLATE-AND-ANGLE COLUMNS
WITH COVER-PLATES




Column Section	Thickness of Cover-Plates Inches	Area of Section Square Inches	Weight of Col- umn in Pounds per Foot	Axis X X			Axis Y Y		
				Moment of Inertia	Section Modulus	Radius of Gyration Inches	Moment of Inertia	Section Modulus	Radius of Gyration Inches
Four 6" X 4" X 3/4" Angles One 12" X 1/2" Web-Plate Two Cover-Plates 13 Inches Wide	1/4"	41.44	140.9	1,129	174.0	5.22	366.1	56.32	2.98
	1/2"	43.07	146.5	1,199	182.6	5.27	389.0	59.84	3.00
	3/4"	44.69	152.0	1,269	192.0	5.33	411.8	63.36	3.04
	1"	46.32	157.5	1,340	200.3	5.38	434.7	66.88	3.07
	1 1/8"	47.94	163.0	1,415	209.8	5.44	457.6	70.40	3.10
	1 1/4"	49.57	168.5	1,492	219.3	5.49	480.5	73.92	3.12
	1 1/2"	51.19	174.0	1,563	227.2	5.52	503.4	77.44	3.14
	1 3/4"	52.82	179.6	1,642	237.0	5.59	526.2	81.00	3.16
	2"	54.44	185.1	1,723	246.0	5.64	549.1	84.48	3.18
	2 1/8"	56.07	190.6	1,803	256.1	5.68	572.0	88.00	3.20
	2 1/4"	57.69	196.2	1,884	264.9	5.72	594.9	91.52	3.22
	2 1/2"	59.32	201.7	1,965	274.3	5.75	617.8	95.04	3.23
	2 3/4"	60.94	207.2	2,050	283.2	5.80	640.6	98.56	3.25
	3"	62.57	212.8	2,143	292.7	5.85	663.5	102.1	3.26
Four 6" X 4" X 3/4" Angles One 14" X 1/2" Web-Plate Two Cover-Plates 15 Inches Wide	1/4"	64.19	218.3	2,224	301.8	5.88	686.4	105.6	3.27
	1/2"	65.82	223.8	2,311	311.2	5.93	709.3	109.1	3.29
	3/4"	67.44	229.3	2,400	321.3	5.98	732.2	112.6	3.30
	1"	53.94	183.2	1,981	264.1	6.05	569.5	75.93	3.25
	1 1/8"	55.82	189.8	2,088	276.2	6.12	604.6	80.61	3.30
	1 1/4"	57.69	196.7	2,195	288.3	6.17	639.8	85.30	3.33
	1 1/2"	59.57	202.6	2,304	299.8	6.22	674.9	89.98	3.37
	1 3/4"	61.44	208.8	2,417	312.8	6.28	710.1	94.66	3.40
	2"	63.32	215.3	2,533	325.3	6.32	745.2	99.36	3.44
	2 1/8"	65.19	221.6	2,645	336.2	6.36	780.4	104.0	3.46
	2 1/4"	67.07	228.1	2,765	349.4	6.41	815.5	108.7	3.49
	2 1/2"	68.94	234.4	2,885	361.4	6.48	850.7	113.4	3.52
	2 3/4"	70.82	240.8	3,004	373.2	6.51	885.9	118.1	3.54
	3"	72.69	247.1	3,131	386.1	6.57	921.0	122.8	3.56
	3 1/8"	74.57	253.6	3,251	398.4	6.61	956.2	127.5	3.58
	3 1/4"	76.44	259.9	3,383	409.7	6.66	991.3	132.2	3.60
	3 1/2"	78.32	266.3	3,510	421.6	6.70	1,026.5	136.9	3.62
	3 3/4"	80.19	272.6	3,635	433.3	6.74	1,061.6	141.5	3.64
	4"	82.07	279.1	3,770	445.2	6.79	1,096.8	146.2	3.66
	4 1/8"	83.94	285.4	3,903	459.9	6.83	1,132.0	150.9	3.68

TABLE VII
PROPERTIES OF STEEL CHANNEL COLUMNS




Designation	Weight of Each Channel in Pounds per Foot	Thickness of Cover-Plate Inches	Area of Section Square Inches	Weight of Column in Pounds per Foot	Axis X X			Axis Y Y		
					Moment of Inertia	Section Modulus	Radius of Gyration Inches	Moment of Inertia	Section Modulus	Radius of Gyration Inches
6-Inch Channel Column: Two Channels 6 Inches Deep and Two Cover-Plates 8 Inches Wide	8		8.70	29.6	64.0	19.9	2.72	46.7	11.7	2.31
	10		9.88	33.6	68.1	21.0	2.62	50.3	12.6	2.27
	10		10.88	37.0	78.2	23.6	2.68	56.0	14.0	2.27
	10		11.88	40.4	90.1	26.6	2.75	61.0	15.3	2.27
	12		12.96	44.1	98.9	29.2	2.75	71.8	18.0	2.35
	12		13.96	47.5	110.0	32.0	2.81	77.2	19.3	2.35
	12		14.96	50.9	122.0	34.9	2.86	82.5	20.6	2.35
	16		16.72	56.8	127.0	36.4	2.76	86.9	21.7	2.28
	15		17.72	60.3	138.0	39.3	2.81	92.2	23.1	2.28
	15		18.72	63.7	152.0	42.1	2.86	97.6	24.4	2.28
	17		19.70	67.0	161.0	44.4	2.86	111.0	27.8	2.38
	17		20.70	70.4	174.0	47.2	2.90	116.0	29.1	2.37
	17		21.70	73.8	188.0	50.2	2.94	122.0	30.4	2.37
	17		22.70	77.2	203.0	53.1	2.98	127.0	31.8	2.37
	17		23.70	80.6	217.0	56.0	3.02	132.0	33.1	2.36
	17		24.70	84.0	233.0	59.0	3.06	138.0	34.4	2.36
	17		25.70	87.4	248.0	62.1	3.10	143.0	35.8	2.36
7-Inch Channel Column: Two Channels 7 Inches Deep and Two Cover-Plates 9 Inches Wide	9		9.72	33.1	97.1	25.9	3.16	71.4	15.8	2.71
	9		10.85	36.9	113.0	29.7	3.23	79.0	17.6	2.70
	13		13.23	45.0	129.0	34.1	3.13	100.0	22.3	2.75
	13		14.35	48.8	146.0	37.8	3.20	108.0	24.0	2.74
	13		15.48	52.6	163.0	41.6	3.26	115.0	25.7	2.73
	13		16.60	56.4	181.0	45.4	3.33	123.0	27.4	2.72
	17		18.05	64.4	191.0	47.8	3.17	133.0	29.6	2.66
	17		20.08	68.3	209.0	51.5	3.23	141.0	31.4	2.66
	17		21.20	72.1	228.0	55.3	3.28	149.0	33.1	2.65
	17		22.33	75.9	247.0	59.1	3.33	156.0	34.7	2.65
	17		23.45	79.7	267.0	63.0	3.38	163.0	36.4	2.64
	17		24.58	83.6	288.0	66.8	3.43	171.0	38.1	2.64
	17		25.70	87.4	309.0	70.7	3.47	179.0	39.8	2.64
	17		26.83	91.2	331.0	74.7	3.51	187.0	41.5	2.64
	17		27.95	95.0	354.0	78.6	3.56	194.0	43.1	2.64

TABLE VII—(Continued)




	Designation	Weight of Each Channel in Pounds per Foot	Thickness of Cover Plates Inches	Area of Section Square Inches	Weight of Column in Pounds per Foot	Axis X X			Axis Y Y		
						Moment of Inertia	Section Modulus	Radius of Gyration Inches	Moment of Inertia	Section Modulus	Radius of Gyration Inches
8-Inch Channel Column: Two Channels 8 Inches Deep and Two Cover Plates 10 Inches Wide	10	11.0	1	37.4	141	33.3	3.58	107	21.5	3.12	
	10	12.3	1	41.7	164	38.1	3.66	118	23.6	3.09	
	13	13.9	1	47.1	179	41.6	3.59	136	27.3	3.14	
	13	15.1	1	51.3	203	46.3	3.66	147	29.3	3.12	
	13	16.4	1	55.6	227	51.2	3.73	157	31.4	3.10	
	13	17.6	1	59.8	252	56.1	3.79	167	33.5	3.08	
	17	20.0	1	67.9	265	58.7	3.64	184	36.8	3.04	
	17	21.2	1	72.1	290	63.8	3.70	194	39.0	3.03	
	17	22.5	1	76.4	317	68.2	3.76	205	40.9	3.02	
	17	23.7	1	80.7	344	73.3	3.81	215	43.0	3.02	
	17	25.0	1	84.9	372	78.2	3.86	225	45.2	3.02	
	17	26.2	1	89.1	400	83.1	3.91	236	47.2	3.00	
	17	27.5	1	93.4	430	88.3	3.96	246	49.3	2.99	
	17	28.7	1	97.7	459	93.1	4.00	257	51.4	2.99	
	17	30.0	1	101.9	488	98.2	4.04	267	53.4	2.99	
10-Inch Channel Column: Two Channels 10 Inches Deep and Two Cover Plates 12 Inches Wide	13	14.5	1	49.2	243	44.8	4.07	117	30.4	3.40	
	13	15.7	1	53.7	272	55.7	4.14	131	32.9	3.38	
	16	17.7	1	60.0	295	60.5	4.09	205	37.5	3.43	
	16	19.0	1	64.7	329	66.7	4.16	222	40.3	3.41	
	16	20.4	1	69.4	364	72.8	4.18	240	42.9	3.41	
	21	23.4	1	79.5	383	76.6	4.05	259	47.6	3.33	
	21	24.8	1	84.2	417	82.5	4.11	273	49.5	3.32	
	21	26.1	1	88.8	453	88.5	4.16	287	52.1	3.31	
	21	27.5	1	93.5	489	94.6	4.21	300	54.7	3.30	
	21	28.9	1	98.3	525	100.7	4.27	314	57.3	3.30	
	21	30.3	1	102.1	560	106.0	4.33	328	59.6	3.29	
	21	31.6	1	107.5	604	113.0	4.37	342	62.2	3.29	
	21	33.0	1	112.2	645	119.0	4.43	356	64.8	3.28	
	21	34.4	1	116.9	686	125.0	4.47	370	67.3	3.28	
	21	35.7	1	121.6	726	131.0	4.50	383	69.6	3.27	
	21	37.1	1	126.2	771	137.0	4.55	397	72.2	3.27	
	21	38.5	1	130.9	819	144.0	4.60	411	74.5	3.27	
	21	39.9	1	135.5	859	149.0	4.64	425	77.3	3.27	

TABLE VII—(Continued)




Designation	Weight of Each Channel in Pounds per Foot	Thickness of Cover-Plates Inches	Area of Section Square Inches	Weight of Column in Pounds per Foot	Axis X X			Axis Y Y		
					Moment of Inertia	Section Modulus	Radius of Gyration Inches	Moment of Inertia	Section Modulus	Radius of Gyration Inches
10-Inch Channel Column: Two 10-Inch Channels and Two Cover-Plates 12 Inches Wide	15	$\frac{1}{16}$	16.3	56.8	336	63.2	4.49	227	37.9	3.69
	15	$\frac{1}{8}$	18.2	61.9	377	70.2	4.55	245	40.9	3.67
	20	$\frac{1}{8}$	20.3	70.7	412	77.0	4.46	286	47.7	3.71
	20	$\frac{3}{16}$	22.3	75.8	457	84.0	4.53	304	50.7	3.69
	20	$\frac{1}{4}$	23.8	80.9	502	91.5	4.60	322	53.7	3.68
	25	$\frac{1}{4}$	26.7	90.8	526	95.8	4.45	348	58.0	3.61
	25	$\frac{3}{8}$	28.2	95.9	572	103.0	4.51	366	61.1	3.61
	25	$\frac{1}{2}$	29.7	101.0	619	110.0	4.56	384	64.0	3.60
	30	$\frac{1}{2}$	32.6	110.9	643	114.0	4.44	408	68.0	3.54
	30	$\frac{3}{4}$	34.1	116.0	691	122.0	4.50	426	71.0	3.53
	30	$\frac{1}{2}$	35.6	121.1	740	129.0	4.56	444	74.0	3.53
	30	$\frac{3}{4}$	37.1	126.2	790	136.0	4.62	462	77.0	3.53
	30	$\frac{1}{2}$	38.6	131.3	841	144.0	4.68	480	80.0	3.53
	30	$\frac{3}{4}$	40.1	136.4	893	150.0	4.73	498	83.0	3.52
	30	1	41.6	141.5	949	158.0	4.78	516	86.0	3.52
	30	1 $\frac{1}{8}$	44.6	151.7	1,059	172.0	4.87	552	92.0	3.52
	30	1 $\frac{1}{4}$	47.6	161.9	1,173	188.0	4.97	588	98.0	3.51
	30	$\frac{1}{2}$	50.6	172.1	1,292	203.0	5.05	624	104.0	3.51
	30	1	53.6	182.3	1,416	217.0	5.14	660	110.0	3.51
12-Inch Channel Column: Two 12-Inch Channels and Two Cover-Plates 14 Inches Wide	20	$\frac{1}{16}$	22.3	75.8	650	102.0	5.40	429	61.3	4.39
	20	$\frac{1}{8}$	24.1	81.8	724	112.0	5.48	457	65.3	4.36
	25	$\frac{1}{8}$	27.1	91.9	760	118.0	5.30	505	72.1	4.31
	25	$\frac{3}{16}$	28.8	97.9	833	128.0	5.38	534	76.3	4.31
	30	$\frac{3}{16}$	31.6	107.4	891	137.0	5.32	600	85.7	4.36
	30	$\frac{1}{4}$	33.4	113.4	964	147.0	5.37	628	89.7	4.34
	30	$\frac{1}{2}$	35.1	119.3	1,043	157.0	5.45	657	93.9	4.33
	30	$\frac{3}{4}$	36.9	125.3	1,118	168.0	5.51	686	98.0	4.31
	30	$\frac{1}{2}$	38.6	131.3	1,198	178.0	5.57	714	102.0	4.30
	35	$\frac{1}{2}$	41.6	141.5	1,234	183.0	5.44	753	108.0	4.25
	35	$\frac{3}{4}$	43.4	147.4	1,316	193.0	5.50	782	112.0	4.25
	35	1	45.1	153.3	1,396	204.0	5.56	810	116.0	4.24
	35	1 $\frac{1}{8}$	46.9	159.3	1,482	214.0	5.63	840	120.0	4.24
	35	1 $\frac{1}{4}$	48.6	165.2	1,565	224.0	5.68	867	124.0	4.22
	35	1 $\frac{3}{8}$	52.1	177.2	1,742	245.0	5.79	925	132.0	4.21
	35	1 $\frac{1}{2}$	55.6	189.0	1,922	266.0	5.90	981	140.0	4.21
	35	1 $\frac{3}{4}$	59.1	200.9	2,105	287.0	5.98	1,039	148.0	4.19
	35	1 $\frac{1}{2}$	62.6	212.7	2,302	308.0	6.08	1,096	157.0	4.19

TABLE VII—(Continued)




Designation	Weight of Channel Thickness of Cover-Plates Inches	Area of Section Square Inches	Weight of Column in Pounds per Foot	Axis X X			Axis Y Y			
				Moment of Inertia	Section Modulus	Radius of Gyration Inches	Moment of Inertia	Section Modulus	Radius of Gyration Inches	
15-Inch Channel Column, Light Section: Two 15-Inch Channels and Two Cover-Plates 17 Inches Wide	33	$\frac{1}{8}$	36.4	123.8	1,630	204	6.69	1,084	128	5.46
	33	$\frac{1}{8}$	38.5	131.0	1,767	219	6.77	1,136	134	5.43
	35	$\frac{1}{8}$	39.7	135.2	1,789	222	6.71	1,166	137	5.42
	35	$\frac{1}{8}$	41.9	142.3	1,928	237	6.79	1,217	143	5.39
	40	$\frac{1}{8}$	44.9	152.5	1,983	244	6.65	1,288	152	5.36
	40	$\frac{1}{8}$	47.0	159.7	2,124	259	6.72	1,339	158	5.34
	45	$\frac{1}{8}$	49.8	169.3	2,180	266	6.62	1,405	165	5.31
	45	$\frac{1}{8}$	51.9	176.5	2,324	282	6.69	1,456	171	5.30
	50	$\frac{1}{8}$	54.9	186.7	2,379	288	6.58	1,525	179	5.27
	50	$\frac{1}{8}$	57.0	193.9	2,527	304	6.66	1,576	185	5.26
	50	$\frac{1}{8}$	59.2	201.1	2,673	319	6.72	1,627	191	5.24
	50	$\frac{1}{8}$	61.3	208.4	2,822	335	6.79	1,678	197	5.23
	50	$\frac{1}{8}$	63.4	215.6	2,975	350	6.85	1,730	203	5.22
	50	$\frac{1}{8}$	67.7	230.0	3,288	381	6.97	1,832	216	5.21
	50	$\frac{1}{8}$	71.9	244.5	3,608	412	7.08	1,934	228	5.19
	50	$\frac{1}{8}$	76.2	258.9	3,938	444	7.19	2,037	240	5.17
	50	$\frac{1}{8}$	80.4	273.4	4,278	475	7.30	2,139	252	5.16

TABLE VIII
PROPERTIES OF HEAVY STEEL CHANNEL COLUMNS




Designation	Column Section	Thickness of Cover-Plates Inches	Area of Section Square Inches	Weight of Column in Pounds per Foot	Axis X X			Axis Y Y		
					Moment of Inertia	Section Modulus	Radius of Gyration Inches	Moment of Inertia	Section Modulus	Radius of Gyration Inches
10-Inch Extra-Heavy Channel Column	Two 10-Inch 30-Pound Channels Two Cover-Plates 12 Inches Wide and Two Web-Plates 9 In. X 1/2 In.	1 1/2	49.1	167.0	831	145	4.11	522	87	3.26
		1 3/4	50.6	172.1	881	152	4.18	540	90	3.27
		1 7/8	52.1	177.2	932	159	4.23	558	93	3.27
		2	53.6	182.3	985	166	4.30	576	96	3.28
		2 1/8	55.1	187.4	1,039	173	4.35	594	99	3.28
		2 1/4	58.1	197.6	1,149	188	4.45	630	105	3.29
		2 3/8	61.1	207.8	1,264	203	4.55	666	111	3.30
		2 1/2	64.1	218.0	1,384	218	4.65	702	117	3.31
		2 7/8	67.1	228.2	1,507	233	4.75	738	123	3.31
		3	70.1	238.4	1,637	247	4.84	774	129	3.32
		3 1/8	73.1	248.6	1,766	263	4.92	810	135	3.33
		3 1/4	76.1	258.8	1,910	279	5.00	846	141	3.33
		3 3/8	79.1	269.0	2,057	293	5.10	882	147	3.34
		3 1/2	82.1	279.2	2,208	311	5.19	918	153	3.34
		3 7/8	85.1	289.4	2,361	326	5.27	954	159	3.34
12-Inch Extra-Heavy Channel Column	Two 12-Inch 35-Pound Channels Two Cover-Plates 14 Inches Wide and Two Web-Plates 11 In. X 1/2 In.	1 1/2	58.1	197.6	1,402	208	4.91	927	132	3.99
		1 3/4	59.9	203.5	1,478	217	4.97	956	136	3.99
		1 7/8	61.6	209.4	1,563	228	5.05	985	141	4.00
		2	63.4	215.4	1,646	237	5.10	1,013	145	4.00
		2 1/8	65.1	221.3	1,729	247	5.15	1,041	149	4.00
		2 1/4	68.6	233.3	1,907	268	5.28	1,099	157	4.00
		2 3/8	72.1	245.1	2,090	288	5.38	1,156	165	4.01
		2 1/2	75.6	257.0	2,272	309	5.49	1,213	173	4.01
		2 7/8	79.1	269.0	2,466	329	5.59	1,271	181	4.01
		3	82.6	280.8	2,665	349	5.69	1,328	189	4.02
		3 1/8	86.1	292.7	2,876	371	5.78	1,385	198	4.02
		3 1/4	89.6	304.7	3,081	391	5.86	1,442	206	4.02
		3 3/8	93.1	316.5	3,313	415	5.97	1,499	214	4.02
		3 1/2	96.6	328.4	3,538	435	6.05	1,557	222	4.02
		3 7/8	100.1	340.4	3,773	458	6.15	1,614	231	4.02

TABLE VIII—(Continued)



Designation	Column Section	Thickness of Cover-Plates Inches	Area of Section Square Inches	Weight of Column in Pounds per Foot	Axis X X			Axis Y Y		
					Moment of Inertia	Section Modulus	Radius of Gyration Inches	Moment of Inertia	Section Modulus	Radius of Gyration Inches
15-Inch Extra-Heavy Channel Column	Two 15-Inch 50-Pound Channels Two Cover-Plates 17 Inches Wide and Two Web-Plates 14 In. X 1 In.	$\frac{3}{4}$	75.9	258.1	2,722	330	5.99	1,920	226	5.03
		$1\frac{1}{8}$	78.0	265.3	2,870	345	6.06	1,971	232	5.03
		$1\frac{1}{4}$	80.2	272.5	3,016	360	6.14	2,022	238	5.02
		$1\frac{3}{8}$	82.3	279.8	3,165	375	6.20	2,074	244	5.02
		1	84.4	287.0	3,318	390	6.27	2,125	250	5.02
		$1\frac{1}{8}$	88.7	301.4	3,631	420	6.40	2,227	262	5.01
		$1\frac{1}{4}$	92.9	315.9	3,951	452	6.52	2,330	274	5.01
		$1\frac{3}{8}$	97.2	330.3	4,281	482	6.64	2,432	286	5.00
		$1\frac{1}{2}$	101.4	344.8	4,621	513	6.75	2,534	298	5.00
		$1\frac{3}{4}$	105.7	359.2	4,970	545	6.86	2,637	310	5.00
		$1\frac{7}{8}$	109.9	373.7	5,328	576	6.96	2,739	322	4.99
		2	114.2	388.1	5,696	608	7.06	2,841	334	4.99
		$2\frac{1}{8}$	118.4	402.6	6,075	640	7.16	2,944	346	4.99
		$2\frac{1}{4}$	122.7	417.0	6,463	672	7.26	3,046	358	4.98
		$2\frac{3}{8}$	126.9	431.5	6,864	704	7.36	3,148	370	4.98

TABLE IX
PROPERTIES AND DIMENSIONS OF STANDARD Z-BAR COLUMNS



Designation	Section of Column	Thickness of Z Bars and Web Plate	Area of Section Square Inches	Weight of Column in Pounds per Foot	Axis X-X'			Axis Y-Y'			Dimensions		
					Moment of Inertia	Section Modulus	Radius of Gyration Inches	Moment of Inertia	Section Modulus	Radius of Gyration Inches	A	B	C
12-Inch Z-Bar Column	Four Z-Bars 6 Inches Deep and One Web-Plate 8 Inches Wide	21.4	72.7	287	46.5	3.67	337	46.5	3.97	19.1	6.1	7.1	
		25.1	85.2	347	55.2	3.72	391	54.0	3.95	19.1	6.1	7.1	
		28.1	97.8	409	64.1	3.77	445	61.3	3.92	19.1	6.1	7.1	
		31.2	106.2	427	67.9	3.69	469	66.4	3.88	18.1	6.1	7.1	
		34.8	118.5	489	76.8	3.74	518	73.4	3.86	19	6.1	7.1	
		38.5	130.9	556	85.9	3.79	567	80.0	3.83	19.1	6.1	7.1	
		40.5	137.6	562	88.2	3.72	579	84.2	3.78	18.1	6.1	6.1	
		44.1	149.9	629	97.3	3.77	624	90.7	3.76	18.1	6.1	6.1	
10-Inch Z-Bar Column	Four Z-Bars 5 Inches Deep and One Web-Plate 7 Inches Wide	47.7	162.1	700	106.6	3.82	664	96.5	3.73	19	6.1	6.1	
		15.8	53.7	149	29.0	3.08	197	30.1	3.54	16.1	5.1	6.1	
		19.0	64.7	186	35.5	3.13	235	35.8	3.52	16.1	5.1	6.1	
		22.3	75.6	225	42.0	3.17	272	42.1	3.50	16.1	5.1	6.1	
		24.5	83.3	236	44.9	3.10	290	45.5	3.44	16.1	5.1	6.1	
		27.7	94.2	275	51.5	3.16	324	50.8	3.42	16.1	5.1	6.1	
		30.9	105.2	312	58.4	3.21	358	56.1	3.40	16.1	5.1	6.1	
		32.7	111.2	320	59.9	3.13	365	59.0	3.34	16.1	5.1	6.1	
8-Inch Z-Bar Column	Four Z-Bars 4 Inches Deep and One Web-Plate 6 Inches Wide	34.8	121.8	363	66.8	3.18	393	63.5	3.32	16.1	5.1	6.1	
		39.0	132.6	411	74.3	3.25	428	69.2	3.30	16.1	5.1	6.1	
		11.3	38.4	68.7	16.6	2.47	123	20.0	3.31	14.1	4.1	6.1	
		14.2	48.2	89.8	21.3	2.52	152	24.6	3.28	5	4.1	6.1	
		17.1	58.1	113	26.1	2.57	184	29.8	3.28	5	4.1	6.1	
		19.0	64.5	118	28.1	2.49	198	33.1	3.23	4.1	4.1	6	
		21.9	74.4	142	32.9	2.54	225	37.6	3.21	4.1	4.1	6	
		24.7	83.9	167	37.8	2.59	252	41.9	3.19	4.1	4.1	6	
6-Inch Z-Bar Column	Four Z-Bars 3 Inches Deep and One Web-Plate 6 Inches Wide	26.3	89.4	167	38.8	2.52	258	44.3	3.13	4.1	4.1	5.1	
		29.0	98.6	193	43.8	2.53	281	48.4	3.11	4.1	4.1	5.1	
		31.9	108.3	221	49.0	2.63	305	52.4	3.09	4.1	4.1	5.1	
		9.4	31.9	32.3	10.3	1.86	86.7	15.6	3.04	12.1	3.1	5.1	
		11.8	40.1	42.8	13.3	1.91	108	19.3	3.02	12.1	3.1	5.1	
		13.7	46.6	48.0	15.1	1.87	121	22.3	2.97	12.1	3.1	5.1	
		16.1	54.7	59.5	18.1	1.92	140	25.8	2.95	12.1	3.1	5.1	
		17.8	60.5	63.6	19.6	1.89	150	28.3	2.91	12.1	3.1	5.1	
4-Inch Z-Bar Column	Four Z-Bars 2 Inches Deep and One Web-Plate 4 Inches Wide	20.1	68.3	76.0	22.7	1.94	168	31.7	2.89	12.1	3.1	5.1	

14-Inch 2-Bar Column		14	66.9	227.5	1,018	223.2	4.92	979.3									
Four 6" X 1" Z-Bars One 10" X 1" Web-Plate Two Cover-Plates 16 Inches Wide		1	68.7	233.5	1,711	234.0	4.99	1,007.0	139.7	3.83	20 1/8	7 1/4	7				
		1 1/8	70.5	239.7	1,805	244.8	5.06		143.8	3.84	20 1/4	7 1/8	7				
		1 1/4	72.2	245.2	1,901	255.7	5.13	1,035.0	147.9	3.84	20 5/16	7 3/8	7				
		1 1/2	74.0	251.6	1,999	266.5	5.20	1,064.0	152.0	3.84	20 7/8	7 7/8	7				
		1 3/4	75.7	257.3	2,098	277.5	5.26	1,092.0	156.2	3.84	20 1/2	7 1/2	7				
		1 7/8	77.5	263.3	2,198	288.3	5.32	1,121.0	160.2	3.85	20 3/8	7 9/8	7				
		1 5/8	79.2	269.4	2,300	299.1	5.39	1,150.0	164.2	3.85	20 1/4	7 3/4	7				
		1 1/2	81.0	275.4	2,405	310.4	5.45	1,178.0	168.2	3.85	20 3/8	7 1/2	7				
		1 1/4	82.7	281.2	2,510	321.3	5.51	1,207.0	172.5	3.86	20 7/8	7 3/4	7				
		1						1,236.0	176.5	3.86	21	7 1/2	7				
Four 6" X 1" Z-Bars One 10" X 1" Web-Plate Two Cover-Plates 16 Inches Wide		1	81.4	276.8	2,298	303.8	5.31	1,726.0	216.2	4.60	22	7 1/8	8				
		1 1/8	83.4	283.7	2,413	316.5	5.38	1,769.0	221.6	4.60	22 1/8	7 3/8	8				
		1 1/4	85.4	290.4	2,531	329.5	5.44	1,811.0	226.8	4.60	22 3/8	7 1/2	8				
		1 1/2	87.4	297.2	2,650	341.9	5.50	1,854.0	232.2	4.60	22 1/4	7 3/4	8				
		1 3/4	89.4	304.1	2,771	354.4	5.56	1,897.0	237.6	4.60	22 3/8	7 1/2	8				
		1 7/8	91.4	310.8	2,895	367.6	5.62	1,939.0	242.9	4.60	22 7/8	7 3/8	8				
		1 5/8	93.4	317.6	3,019	380.4	5.69	1,982.0	248.2	4.60	22 9/8	7 1/2	8				
		1 1/2	95.4	324.5	3,146	393.3	5.74	2,025.0	253.6	4.60	22 5/8	8	8				
		1 1/4	97.4	331.2	3,275	406.3	5.80	2,067.0	258.9	4.60	22 1/8	8 1/8	8				
		1 1/8	99.4	338.0	3,406	419.2	5.86	2,110.0	264.1	4.60	22 3/8	8 1/4	8				
		1 3/8	101.4	344.9	3,539	432.3	5.91	2,153.0	269.4	4.61	22 7/8	8 1/8	8				
		1 1/2	103.4	351.7	3,674	445.5	5.96	2,195.0	274.8	4.61	23	8 1/4	8				
		1 1/4	105.4	358.4	3,811	458.5	6.01	2,238.0	280.1	4.61	23 1/8	8 5/8	8				
		1 1/8	107.4	365.2	3,951	471.8	6.06	2,280.0	285.4	4.61	23 1/4	8 3/8	8				
		1 3/4	109.4	372.0	4,092	485.0	6.12	2,323.0	290.8	4.61	23 3/8	8 7/8	8				
		1 1/2	111.4	378.8	4,235	498.3	6.17	2,366.0	296.2	4.61	23 7/8	8 1/2	8				
		1 1/8	113.4	385.7	4,381	511.7	6.21	2,409.0	301.4	4.61	23 7/8	8 1/2	8				
		2	115.4	392.5	4,528	524.9	6.26	2,451.0	306.8	4.61	23 1/2	8 5/8	8				
		2 1/8	117.4	399.2	4,679	538.6	6.31	2,494.0	312.2	4.61	23 5/8	8 1/2	8				
		2 1/4	119.4	406.1	4,831	552.1	6.36	2,537.0	317.4	4.61	23 1/4	8 3/4	8				
		2 1/2	121.4	412.8	4,985	565.3	6.41	2,579.0	322.9	4.61	23 1/8	8 1/2	8				

TABLE XI


SAFE LOADS FOR STEEL, LATTICED, CHANNEL COLUMN



Safe Load, in Tons of 2,000 Pounds, for Columns With Square Ends and the Following Unsupported Lengths																	
Depth of Channel Inches	Weight of Channel Pounds per Foot	d Inches	l Inches	Area of Section Square Inches	Least Radius of Gyration Inches	Length of Column											
						8 Ft or Less	9 Ft	10 Ft	11 Ft	12 Ft	14 Ft	16 Ft	18 Ft	20 Ft	22 Ft	24 Ft	26 Ft
5	6	2.8	4.6	3.52	1.93	21	21	20	20	19	18	16	15	14			
5	7	2.7	4.5	4.11	1.86	25	24	23	23	22	20	19	17	16			
5	8	2.7	4.4	4.70	1.82	28	27	26	25	24	23	21	19	17			
5	9	2.6	4.3	5.18	1.93	31	31	30	29	28	26	24	23	21			
5	10	2.5	4.1	5.77	1.89	34	34	33	32	31	29	27	24	22			
5	12	2.3	4.0	6.95	1.82	42	41	39	38	35	32	30	28	27			

6	8	3.5	5.6	4.70	2.33	28	28	27	26	24	23	22	20	19	.	
6	9	3.4	5.4	5.29	2.28	32	32	30	29	27	25	24	22	20		
6	10	3.3	5.3	5.88	2.23	35	35	33	31	30	28	26	24	23		
6	12	3.2	5.8	6.96	2.32	42	42	40	38	36	34	31	29	27		
6	13	3.1	5.7	7.55	2.28	45	45	42	40	37	35	33	31	28		
6	15	2.9	5.5	8.72	2.21	52	52	49	47	44	41	39	36	33		
6	17	2.8	5.9	9.70	2.28	58	58	56	53	50	47	44	41	38		
6	18	2.7	5.9	10.3	2.26	62	62	59	56	53	50	46	43	40		
6	20	2.6	5.8	11.5	2.22	69	69	65	61	58	54	51	47	44		
7	9	4.3	6.3	5.22	2.70	31	31	31	30	28	27	26	24	23	22	20
7	10	4.1	6.1	5.81	2.64	35	35	35	33	32	30	29	27	26	24	23
7	12	4.0	6.0	6.98	2.55	42	42	41	39	37	35	33	32	30	28	26
7	13	4.0	6.4	7.60	2.69	46	46	45	43	41	39	37	36	34	32	30
7	15	3.7	6.2	8.78	2.60	53	53	52	50	47	45	43	40	38	36	33
7	17	3.6	6.1	9.95	2.53	60	60	58	55	53	50	48	45	42	40	37
						12 Ft. or Less	14 Ft.	16 Ft.	18 Ft.	20 Ft.	22 Ft.	24 Ft.	26 Ft.	28 Ft.	30 Ft.	
8	10	5.0	7.1	6.00	3.08	36	36	32	31	29	28	26	25			
8	11	4.9	6.9	6.59	3.01	39	39	34	33	31	30	28	27			
8	12	4.8	6.8	7.18	2.96	42	42	37	35	34	32	31	29			
8	13	4.9	7.2	7.60	3.07	45	45	40	38	37	35	34	32			
8	15	4.7	7.0	8.78	2.97	52	52	46	44	42	39	37	35			
8	17	4.5	6.8	9.97	2.90	58	58	51	48	46	44	41	39			

TABLE XI—(Continued)



Depth of Channel Inches	Weight of Channel Pounds per Foot	d Inches	D Inches	Area of Section Square Inches	Least Radius of Gyration Inches	13 Ft. or Less	14 Ft.	16 Ft.	18 Ft.	20 Ft.	22 Ft.	24 Ft.	26 Ft.	28 Ft.	30 Ft.	32 Ft.	34 Ft.	36 Ft.	40 Ft.
9	13	5.7	7.9	7.60	3.46	46	46	45	44	42	41	39	38	36	35	33	30	30	
9	14	5.6	7.8	8.19	3.40	49	49	48	45	43	42	41	39	37	36	35	31	31	
9	15	5.5	7.7	8.79	3.36	53	53	51	49	47	45	43	42	41	39	37	34	34	
9	16	5.4	8.1	9.40	3.48	56	56	50	54	52	50	49	47	45	43	41	38	41	
9	18	5.3	8.0	10.6	3.40	64	64	62	61	58	56	54	52	50	47	45	41	46	
9	21	5.1	7.7	12.4	3.30	74	74	72	69	67	64	62	59	57	54	51	46	51	

Safe Load, in Tons of 4000 Pounds, for Columns With Square Ends
and the Following Unsupported Lengths

10	15	6.3	8.9	8.80	3.89	53	53	53	24 Ft.	26 Ft.	28 Ft.	30 Ft.	32 Ft.	36 Ft.	40 Ft.	44 Ft.	48 Ft.	52 Ft.
10	17	6.1	8.7	10.1	3.77	60	60	59	24 Ft.	26 Ft.	28 Ft.	30 Ft.	32 Ft.	36 Ft.	40 Ft.	44 Ft.	48 Ft.	52 Ft.
10	18	6.0	8.6	10.7	3.73	64	64	63	24 Ft.	26 Ft.	28 Ft.	30 Ft.	32 Ft.	36 Ft.	40 Ft.	44 Ft.	48 Ft.	52 Ft.
10	20	6.0	8.9	11.8	3.81	71	71	69	24 Ft.	26 Ft.	28 Ft.	30 Ft.	32 Ft.	36 Ft.	40 Ft.	44 Ft.	48 Ft.	52 Ft.
10	25	5.7	8.6	14.7	3.65	88	88	85	24 Ft.	26 Ft.	28 Ft.	30 Ft.	32 Ft.	36 Ft.	40 Ft.	44 Ft.	48 Ft.	52 Ft.
10	30	5.4	8.4	17.6	3.53	106	106	101	24 Ft.	26 Ft.	28 Ft.	30 Ft.	32 Ft.	36 Ft.	40 Ft.	44 Ft.	48 Ft.	52 Ft.
						18 Ft. or Less	20 Ft.	22 Ft.	24 Ft.	26 Ft.	28 Ft.	30 Ft.	32 Ft.	36 Ft.	40 Ft.	44 Ft.	48 Ft.	52 Ft.
12	20	7.7	10.4	11.8	4.59	71	71	67	24 Ft.	26 Ft.	28 Ft.	30 Ft.	32 Ft.	36 Ft.	40 Ft.	44 Ft.	48 Ft.	52 Ft.
12	23	7.4	10.2	13.6	4.47	82	81	77	24 Ft.	26 Ft.	28 Ft.	30 Ft.	32 Ft.	36 Ft.	40 Ft.	44 Ft.	48 Ft.	52 Ft.
12	25	7.3	10.0	14.8	4.39	89	88	83	24 Ft.	26 Ft.	28 Ft.	30 Ft.	32 Ft.	36 Ft.	40 Ft.	44 Ft.	48 Ft.	52 Ft.
12	27	7.4	10.5	15.8	4.54	95	95	90	24 Ft.	26 Ft.	28 Ft.	30 Ft.	32 Ft.	36 Ft.	40 Ft.	44 Ft.	48 Ft.	52 Ft.
12	30	7.1	10.2	17.6	4.42	106	105	100	24 Ft.	26 Ft.	28 Ft.	30 Ft.	32 Ft.	36 Ft.	40 Ft.	44 Ft.	48 Ft.	52 Ft.
12	33	7.0	10.1	19.4	4.34	116	115	109	24 Ft.	26 Ft.	28 Ft.	30 Ft.	32 Ft.	36 Ft.	40 Ft.	44 Ft.	48 Ft.	52 Ft.
12	35	6.9	10.0	20.6	4.29	123	122	116	24 Ft.	26 Ft.	28 Ft.	30 Ft.	32 Ft.	36 Ft.	40 Ft.	44 Ft.	48 Ft.	52 Ft.
15	33	9.5	12.7	19.4	5.64	116	116	116	24 Ft.	26 Ft.	28 Ft.	30 Ft.	32 Ft.	36 Ft.	40 Ft.	44 Ft.	48 Ft.	52 Ft.
15	35	9.4	12.5	20.6	5.53	124	124	124	24 Ft.	26 Ft.	28 Ft.	30 Ft.	32 Ft.	36 Ft.	40 Ft.	44 Ft.	48 Ft.	52 Ft.
15	40	9.1	12.2	23.6	5.40	142	142	141	24 Ft.	26 Ft.	28 Ft.	30 Ft.	32 Ft.	36 Ft.	40 Ft.	44 Ft.	48 Ft.	52 Ft.
15	45	8.9	12.0	26.4	5.29	158	158	157	24 Ft.	26 Ft.	28 Ft.	30 Ft.	32 Ft.	36 Ft.	40 Ft.	44 Ft.	48 Ft.	52 Ft.
15	50	8.7	11.8	29.4	5.21	176	176	174	24 Ft.	26 Ft.	28 Ft.	30 Ft.	32 Ft.	36 Ft.	40 Ft.	44 Ft.	48 Ft.	52 Ft.

TABLE XII
SAFE LOADS FOR STEEL I BEAMS USED AS COLUMNS. BEAMS SUPPORTED
AGAINST YIELDING SIDEWISE

Safe Load, in Tons of 2,000 Pounds, for Columns With Square Ends and the Following Unsupported Lengths																		
Depth of Beam Inches	Weight of Beams per Foot Pounds	Area of Section Square Inches	Radius of Gyration Inches	Length of Column, in Feet														
				12 Ft. or Less	14 Ft.	16 Ft.	18 Ft.	20 Ft.	22 Ft.	24 Ft.	26 Ft.	28 Ft.	30 Ft.	32 Ft.	34 Ft.	36 Ft.	38 Ft.	40 Ft.
20	90	26.4	7.55	159.0	159.0	159.0	159.0	158.0	156.0	154.0	151.0	149.0	147.0	145.0	143.0	141.0	139.0	137.0
20	80	23.5	7.55	141.0	141.0	141.0	141.0	140.0	138.0	136.0	134.0	132.0	130.0	128.0	127.0	125.0	123.0	121.0
20	75	22.1	7.53	133.0	133.0	133.0	133.0	132.0	130.0	128.0	126.0	125.0	123.0	121.0	119.0	118.0	116.0	114.0
20	65	19.1	7.76	115.0	115.0	115.0	115.0	114.0	113.0	111.0	109.0	108.0	106.0	105.0	104.0	102.0	101.0	99.0
18	80	23.5	6.94	141.0	141.0	141.0	140.0	138.0	136.0	134.0	132.0	130.0	128.0	126.0	124.0	122.0	120.0	118.0
18	70	20.6	6.87	124.0	124.0	124.0	123.0	121.0	119.0	117.0	116.0	114.0	112.0	110.0	108.0	107.0	105.0	103.0
18	65	19.1	6.81	115.0	115.0	115.0	114.0	112.0	110.0	109.0	107.0	105.0	104.0	102.0	100.0	99.0	97.0	95.0
18	60	17.6	6.94	106.0	106.0	106.0	105.0	104.0	102.0	101.0	99.0	97.0	96.0	94.0	93.0	91.0	89.0	88.0
18	55	16.2	7.08	97.0	97.0	97.0	97.0	96.0	94.0	93.0	91.0	90.0	89.0	87.0	86.0	85.0	83.0	82.0
15	80	23.5	5.64	141.0	141.0	139.0	136.0	134.0	131.0	129.0	126.0	124.0	121.0	119.0	116.0	114.0	111.0	109.0
15	75	22.1	5.72	133.0	133.0	131.0	128.0	126.0	124.0	121.0	119.0	117.0	114.0	112.0	110.0	107.0	105.0	103.0
15	60	17.6	6.02	106.0	106.0	106.0	105.0	103.0	101.0	98.0	96.0	94.0	93.0	91.0	89.0	87.0	86.0	84.0
15	55	14.7	6.00	88.0	88.0	87.0	86.0	85.0	83.0	82.0	80.0	79.0	77.0	76.0	74.0	73.0	71.0	70.0
15	42	12.4	5.90	74.0	74.0	74.0	72.0	71.0	70.0	69.0	67.0	66.0	65.0	64.0	62.0	61.0	60.0	58.0

TABLE XIII

SAFE LOADS FOR STEEL I BEAMS USED AS COLUMNS. BEAMS NOT END RESTED AGAINST YIELDING SIDEWISE

Depth of Beam Inches	Weight per Foot-Pounds	Area of Section Square Inches	Radius of Gyration, Inches	Safe Load, in Tons of 2000 Pounds, for Columns With Square Ends and Unsupported for the Length of																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																								
				2 Ft. or Less				3 Ft.				4 Ft.				5 Ft.				6 Ft.				7 Ft.				8 Ft.				9 Ft.				10 Ft.				11 Ft.				12 Ft.				13 Ft.				14 Ft.				15 Ft.				16 Ft.																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																
20	99	26.4	1.27	158.0	158.0	153.0	147.0	141.0	135.0	128.0	122.0	116.0	110.0	103.0	97.1	90.9	84.6	78.4																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																										

12	65	10.1	1.23	114.0	114.0	116.0	106.0	101.0	96.4	91.7	87.1	82.4	77.8	73.1	68.5	63.8	59.2	54.5
12	55	16.2	1.25	97.2	97.2	93.8	89.9	86.0	82.1	78.2	74.4	70.5	66.6	62.7	58.8	54.9	51.0	47.1
12	50	14.7	1.15	88.2	87.7	83.9	80.0	76.2	72.4	68.6	64.7	60.9	57.1	53.2	49.4	45.6	41.8	37.9
12	40	11.8	1.20	70.8	70.8	67.9	64.9	62.0	59.0	56.1	53.1	50.2	47.2	44.3	41.3	38.4	35.4	32.5
12	35	10.3	1.01	61.8	60.4	57.3	54.3	51.2	48.2	45.1	42.1	39.0	36.0	32.9	29.9	26.8	23.8	20.7
12	31½	9.3	1.04	55.8	54.7	52.1	49.4	46.7	44.0	41.3	38.6	36.0	33.3	30.6	27.9	25.2	22.5	19.9
				1 Ft.	2 Ft.	3 Ft.	4 Ft.	5 Ft.	6 Ft.	7 Ft.	8 Ft.	9 Ft.	10 Ft.	11 Ft.	12 Ft.	13 Ft.	14 Ft.	15 Ft.
10	40	11.8	1.07	70.8	70.8	69.9	66.5	63.2	59.9	56.6	53.2	49.9	46.6	43.3	40.0	36.6	33.3	30.0
10	35	10.3	1.09	61.8	61.8	61.0	58.2	55.4	52.5	49.7	46.8	44.0	41.2	38.3	35.5	32.7	29.8	27.0
10	30	8.8	.96	52.8	52.8	51.1	48.4	45.6	42.9	40.1	37.4	34.6	31.9	29.1	26.4	23.6	20.9	18.1
10	25	7.3	.99	43.8	43.8	42.6	40.4	38.2	36.0	33.8	31.6	29.3	27.1	24.9	22.7	20.5	18.3	16.1
9	33	9.7	1.03	58.2	58.2	57.0	54.2	51.4	48.6	45.7	42.9	40.1	37.2	34.4	31.6	28.8	25.9	23.1
9	27	7.9	1.07	47.4	47.4	46.7	44.5	42.2	40.0	37.8	35.6	33.4	31.2	29.0	26.7	24.5	22.3	20.1
9	25	7.3	.91	43.8	43.8	42.1	39.7	37.2	34.8	32.4	30.0	27.6	25.2	22.8	20.3	17.9	15.5	13.1
9	21	6.2	.95	37.2	37.2	36.0	34.0	32.1	30.1	28.2	26.2	24.2	22.3	20.3	18.4	16.4	14.4	12.5
8	27	7.9	.93	47.4	47.4	45.7	43.2	40.6	38.1	35.5	33.0	30.4	27.9	25.3	22.8	20.2	17.7	
8	22	6.4	.97	38.4	38.4	37.3	35.3	33.3	31.3	29.3	27.4	25.4	23.4	21.4	19.4	17.5	15.5	
8	18	5.2	.87	31.2	31.2	29.7	27.9	26.1	24.3	22.5	20.8	19.0	17.2	15.4	13.6	11.8	10.0	
7	20	5.7	.92	34.2	34.2	32.9	31.0	29.2	27.3	25.5	23.6	21.7	19.9	18.0	16.2	14.3		
7	15	4.4	.84	26.4	26.4	25.0	23.4	21.8	20.2	18.7	17.1	15.5	14.0	12.4	10.8	9.3		
6	15	4.4	.79	26.4	26.3	24.7	23.0	21.3	19.7	18.0	16.3	14.7	13.0	11.3				
6	12	3.6	.73	21.6	21.3	19.8	18.4	16.9	15.4	13.9	12.4	11.0	9.5	8.0				
5	13	3.8	.72	22.8	22.5	20.9	19.3	17.7	16.2	14.6	13.0	11.4	9.8					
5	9½	2.9	.67	17.4	17.0	15.7	14.4	13.1	11.8	10.5	9.2	7.9	6.6					
4	10	2.9	.55	17.4	16.4	14.8	13.3	11.7	10.1	8.5								
4	7½	2.2	.56	13.2	12.5	11.3	10.2	9.0	7.8	6.6								
4	6	1.8	.47	10.8	9.8	8.7	7.5	6.3	5.2	4.0								

SAFE LOAD FOR STEEL PLATE-AND-ANGLE COLUMNS

[illegible]

TABLE XV

SAFE LOAD FOR STEEL PLATE-AND-ANGLE COLUMNS WITH COVER-PLATES

Thickness of Plate and Angles Inches	Safe Load, in Tons of 2,000 Pounds, for Columns With Square Ends and Unsupported Lengths of												
	12 Ft. or Less	14 Ft.	16 Ft.	18 Ft.	20 Ft.	22 Ft.	24 Ft.	26 Ft.	28 Ft.	30 Ft.	32 Ft.	36 Ft.	40 Ft.
$\frac{1}{8}$	248	244	235	225	216	206	197	187	178	168	159	140	
$\frac{1}{4}$	259	255	245	235	225	215	205	196	186	176	166	146	
$\frac{3}{8}$	268	265	255	245	235	225	215	205	194	184	174	154	
$\frac{1}{2}$	277	276	266	255	245	234	224	213	203	192	182	161	
$\frac{5}{8}$	288	286	275	265	254	243	233	222	212	201	190	169	
$\frac{3}{4}$	298	296	285	274	263	252	241	231	220	209	198	176	
$\frac{7}{8}$	307	306	295	284	273	261	250	239	228	217	205	183	
1	317	316	305	293	282	270	259	247	236	224	213	190	
$1\frac{1}{8}$	328	327	315	303	292	280	268	256	244	232	221	197	173
$1\frac{1}{4}$	337	337	325	313	301	289	277	265	253	241	229	205	178
$1\frac{3}{8}$	345	345	334	322	310	297	285	273	261	249	236	212	188
$1\frac{1}{2}$	356	356	345	333	321	308	296	283	270	257	244	219	194
$1\frac{3}{4}$	365	365	354	341	328	316	303	290	277	264	252	226	200
$1\frac{7}{8}$	375	375	364	351	338	325	312	299	286	273	260	234	208
2	385	385	375	361	348	334	321	307	294	280	267	240	213
$2\frac{1}{8}$	395	395	384	371	357	342	330	316	302	289	275	248	221
$2\frac{1}{4}$	405	405	394	380	366	353	338	324	310	296	282	254	226
	14 Ft. or Less	16 Ft.	18 Ft.	20 Ft.	22 Ft.	24 Ft.	26 Ft.	28 Ft.	30 Ft.	32 Ft.	36 Ft.	40 Ft.	44 Ft.
$\frac{1}{8}$	324	313	302	290	279	268	256	245	234	222	200	177	
$\frac{1}{4}$	335	326	314	300	291	280	268	256	245	233	210	187	
$\frac{3}{8}$	346	338	326	314	302	291	279	267	255	243	220	196	
$\frac{1}{2}$	357	350	338	326	314	302	290	277	265	253	229	205	
$\frac{5}{8}$	368	363	351	338	326	313	301	288	276	263	238	213	
$\frac{3}{4}$	380	374	361	349	336	324	311	298	286	273	248	223	
$\frac{7}{8}$	391	386	373	360	347	334	321	308	296	283	257	231	
1	402	398	385	372	358	345	332	319	306	293	266	240	
$1\frac{1}{8}$	413	409	396	382	369	356	342	329	315	302	275	249	222
$1\frac{1}{4}$	425	421	407	394	380	366	353	339	325	312	285	257	230
$1\frac{3}{8}$	436	433	419	405	391	377	363	349	335	322	294	266	238
$1\frac{1}{2}$	447	445	431	417	402	388	374	360	346	331	303	274	246
$1\frac{3}{4}$	458	457	443	428	414	399	385	370	356	341	312	283	254
$1\frac{7}{8}$	470	469	454	439	424	410	395	380	365	350	320	291	261
2	481	481	466	451	436	421	405	390	375	360	330	299	269
$2\frac{1}{8}$	492	492	478	463	447	432	416	401	385	370	339	308	277
$2\frac{1}{4}$	503	503	489	473	458	442	426	411	395	380	348	317	286

TABLE XVI

SAFE LOAD FOR STEEL CHANNEL COLUMNS WITH COVER-PLATES

Designation		Weight of Each Channel Pounds per Foot	Thickness of Cover Plate Inches	Safe Load, in Tons of 2,000 Pounds, for Columns With Square Ends and Unsupported Lengths of															
				10 Ft. or Less	11 Ft.	12 Ft.	13 Ft.	14 Ft.	15 Ft.	16 Ft.	18 Ft.	20 Ft.	22 Ft.	24 Ft.	26 Ft.	28 Ft.	30 Ft.		
6-Inch Channel Columns:																			
Two Channels 6 Inches Deep and Two Cover-Plates 8 Inches Wide				8	52	51	49	48	47	44	42	39	37	34	32	29			
		10	59	57	55	53	51	50	47	44	41	38	35	32	30				
		10	65	63	62	61	59	55	52	49	45	42	39	36					
		12	71	69	67	66	64	61	57	53	50	46	43	39					
		12	78	76	74	72	71	67	63	59	55	51	47	43					
		12	84	81	79	77	75	71	67	63	58	54	50	46					
		14	90	87	84	82	80	76	71	67	62	58	53	49					
		14	100	98	95	92	90	85	80	75	70	65	60	55					
		15	106	104	101	98	95	89	84	79	73	68	63	58					
		15	112	109	106	103	100	95	89	84	78	73	67	62					
		17	118	116	113	110	107	102	96	91	85	80	74	69					
		17	124	121	119	116	113	107	101	95	90	84	78	72					
		17	130	127	124	121	118	112	106	100	94	88	82	76					
		17	136	132	128	125	122	116	110	104	97	91	85	79					
		17	142	138	134	131	128	122	115	108	102	95	89	82					
		17	148	144	141	137	134	127	120	113	106	99	92	85					
		17	154	150	147	144	140	132	124	117	110	102	95	88					
8-Inch Channel Columns:																			
Two Channels 8 Inches Deep and Two Cover-Plates 9 Inches Wide				9	58	57	56	54	52	50	47	45	43	40	38	36	34		
		9	65	63	61	60	57	55	53	50	47	45	42	39	37				
		13	79	77	75	74	71	68	65	62	59	56	53	50	47				
		13	86	84	82	80	77	74	71	67	64	60	57	53	50				
		13	93	92	90	89	85	81	77	73	69	66	62	58	54				
		13	100	98	96	94	90	86	82	78	74	70	66	62	58				
		17	114	112	109	107	102	98	93	88	83	79	74	69	64				
		17	122	119	116	113	108	103	98	93	88	83	78	73	68				
		17	127	124	122	119	114	109	103	98	93	87	82	76	71				
		17	134	131	129	126	120	114	109	103	97	92	86	81	75				
		17	140	136	133	130	124	118	112	106	100	94	88	82	76				
		17	148	145	142	139	132	125	119	113	107	100	94	88	82				
		17	154	150	147	144	138	131	125	118	112	105	99	93	86				
		17	161	157	154	150	143	137	130	123	116	110	103	96	89				
		17	168	164	161	157	150	143	136	129	121	114	107	100	93				

Safe Load, in Tons of 2,000 Pounds, for Columns With Square Ends and Unsupported Lengths of														
Thickness of Cover-Plate Inches	Length of Column in Feet													
	12 Ft. or Less	13 Ft.	14 Ft.	16 Ft.	18 Ft.	20 Ft.	22 Ft.	24 Ft.	26 Ft.	28 Ft.	30 Ft.	32 Ft.	34 Ft.	36 Ft.
1	66	66	66	64	62	60	57	54	52	49	46	44	41	39
1 1/4	74	74	73	70	67	65	62	59	57	54	51	49	46	43
1 1/2	83	83	83	80	77	74	71	68	65	62	59	56	53	50
1 3/4	91	91	90	87	84	80	77	74	70	67	64	60	57	54
2	98	98	97	94	90	87	83	79	76	72	69	65	62	58
2 1/4	106	106	105	102	98	94	90	86	82	78	74	70	66	62
2 1/2	120	120	118	114	110	105	101	96	92	87	82	78	73	69
2 3/4	127	127	126	120	115	110	106	101	96	91	87	83	78	73
3	135	135	133	128	123	117	112	107	102	97	92	87	82	77
3 1/4	142	142	140	135	129	123	118	113	108	102	97	92	86	81
3 1/2	150	150	147	141	136	130	125	119	114	108	103	97	92	86
3 3/4	157	157	155	149	143	137	131	125	119	113	107	101	95	89
4	165	165	162	156	150	144	137	131	125	118	112	106	99	93
4 1/4	172	172	169	163	156	150	143	136	130	123	117	110	104	97
4 1/2	180	180	177	171	164	157	150	143	136	129	122	115	108	101
4 3/4														
5	187	187	184	177	170	163	156	149	142	135	128	121	114	107
5 1/4	195	195	192	185	178	171	164	157	150	143	136	129	122	115
5 1/2	203	203	200	193	186	179	172	165	158	151	144	137	130	123
5 3/4	211	211	208	201	194	187	180	173	166	159	152	145	138	131
6	219	219	216	209	202	195	188	181	174	167	160	153	146	139
6 1/4	227	227	224	217	210	203	196	189	182	175	168	161	154	147
6 1/2	235	235	232	225	218	211	204	197	190	183	176	169	162	155
6 3/4	243	243	240	233	226	219	212	205	198	191	184	177	170	163
7	251	251	248	241	234	227	220	213	206	199	192	185	178	171
7 1/4	259	259	256	249	242	235	228	221	214	207	200	193	186	179
7 1/2	267	267	264	257	250	243	236	229	222	215	208	201	194	187
7 3/4	275	275	272	265	258	251	244	237	230	223	216	209	202	195
8	283	283	280	273	266	259	252	245	238	231	224	217	210	203

TABLE XVI—(Continued)

Designation		Weight of Each Channel Pounds per Foot	Thickness of Cover-Plates Inches	Safe Load, in Tons of 2,000 Pounds, for Columns With Square Ends and Unsupported Lengths of															
				15 Ft or Less	16 Ft.	18 Ft.	20 Ft.	22 Ft.	24 Ft.	26 Ft.	28 Ft.	30 Ft.	32 Ft.	34 Ft.	36 Ft.	40 Ft.			
10-Inch Channel Column. Two Channels 10 Inches Deep and Two Cover-Plates 12 Inches Wide				1 1/8	100	100	97	94	91	88	85	82	79	76	73	70	64		
				1 1/8	109	109	106	103	100	97	93	90	86	83	79	75	68		
				1 1/8	125	125	121	117	113	110	106	102	98	94	90	87	79		
				1 1/8	135	135	130	126	122	118	114	109	105	101	97	93	85		
				1 1/8	143	143	139	135	130	126	121	117	113	108	104	99	90		
				1 1/8	160	160	155	150	145	139	134	129	124	119	114	109	99		
				1 1/8	169	169	163	157	152	147	141	136	131	126	121	115	104		
				1 1/8	178	178	172	166	160	155	149	143	138	132	126	121	110		
				1 1/8	196	193	187	180	174	168	162	156	149	143	137	131	119		
				1 1/8	205	202	196	189	183	176	169	163	156	150	144	137	124		
				1 1/8	211	212	206	199	192	185	178	171	164	157	150	143	129		
				1 1/8	223	221	214	207	200	192	185	178	171	163	156	149	135		
12-Inch Channel Column. Two Channels 12 Inches Deep and Two Cover-Plates 14 Inches Wide				1 1/8	232	230	222	215	208	200	192	185	178	170	163	155	140		
				1 1/8	240	238	230	223	215	207	199	192	184	176	168	161	145		
				1 1/8	250	247	239	231	223	215	207	198	190	182	174	166	150		
				1 1/8	268	265	256	247	239	230	222	213	204	196	187	179	162		
				1 1/8	286	283	273	264	255	245	236	227	218	208	199	190	171		
				1 1/8	304	301	290	280	271	261	251	242	232	222	213	203	184		
				1 1/8	322	318	308	297	287	277	266	256	245	235	225	214	193		
				1 1/8	334	332	320	308	297	286	275	264	253	242	231	220	200		
				1 1/8	343	340	328	315	303	291	280	268	257	245	234	222	202		
				1 1/8	353	349	336	323	310	297	285	273	261	249	237	225	205		
				1 1/8	363	359	345	331	317	303	290	277	264	251	238	224	206		
				1 1/8	373	368	353	338	323	308	294	280	266	252	238	223	209		

TABLE XVI—(Continued)

Designation	Weight of Each Channel Pounds per Foot	Thickness of Cover-Plates Inches	Safe Load, in Tons of 2,000 Pounds, for Columns With Square Ends and Unsupported Lengths of															
			22 Ft or Less	24 Ft	26 Ft	28 Ft	30 Ft	32 Ft	34 Ft	36 Ft	38 Ft	40 Ft	44 Ft	48 Ft	52 Ft			
			22 Ft or Less	24 Ft	26 Ft	28 Ft	30 Ft	32 Ft	34 Ft	36 Ft	38 Ft	40 Ft	44 Ft	48 Ft	52 Ft			
15-Inch Channel Column, Light Section: Two 15-Inch Channels and Two Cover-Plates 17 Inches Wide			218	218	214	209	205	200	196	191	186	182	173	164	155			
	33	1 1/8	231	231	226	221	216	211	207	202	197	192	182	173	163			
	35	1 1/8	238	238	233	228	223	218	213	208	203	198	188	178	168			
	35	1 1/8	251	250	245	240	234	229	224	218	213	208	197	186	176			
	40	1 1/4	269	268	262	256	250	245	239	233	228	222	210	199	187			
	40	1 1/4	282	280	274	268	262	256	250	244	238	232	220	208	196			
	45	1 1/2	299	296	290	284	277	271	264	258	252	245	232	219	207			
	45	1 1/2	311	309	302	295	289	282	275	269	262	255	242	229	215			
	50	1 3/4	329	326	319	312	305	298	290	283	276	269	255	240	226			
	50	1 3/4	342	338	331	324	316	309	301	294	287	279	265	250	235			
	50	1 3/4	355	351	343	335	328	320	312	304	297	289	273	258	243			
	50	1 3/4	368	363	355	347	339	331	323	315	307	299	283	267	251			
	50	1 3/4	380	376	367	359	351	342	334	326	318	309	293	276	260			
	50	1 3/4	406	401	392	383	374	365	356	348	339	330	312	294	277			
	50	1 3/4	431	426	416	407	397	388	378	369	359	350	331	312	293			
50	1 3/4	457	450	440	430	420	410	400	390	379	369	349	329	308				
50	1 3/4	482	475	464	454	443	432	422	411	400	390	368	347	326				
15-Inch Channel Column, Heavy Section: Two 15-Inch Channels, Two Cover-Plates 17 Inches Wide and Two Web-Plates 14" x 1/2"			455	455	445	435	425	414	404	394	383	363	342	322	301			
	50	1 3/4	468	468	458	447	436	426	415	405	394	373	352	330	309			
	50	1 3/4	481	481	470	459	448	437	426	416	404	383	361	339	318			
	50	1 3/4	494	494	482	471	460	449	438	427	415	393	371	348	326			
	50	1 3/4	506	506	495	483	472	460	449	438	426	403	380	357	334			
	50	1 3/4	532	532	520	508	496	484	471	459	447	423	399	375	351			
	50	1 3/4	557	557	544	532	519	506	494	481	468	443	418	392	367			
	50	1 3/4	583	583	569	556	543	529	516	503	490	463	437	410	384			
	50	1 3/4	608	608	594	580	566	552	539	525	511	483	455	428	400			
	50	1 3/4	633	633	619	604	590	575	561	547	532	503	474	445	416			
	50	1 3/4	658	658	644	629	614	598	583	568	553	523	493	463	433			
	50	1 3/4	683	683	668	653	637	621	606	590	575	543	512	481	449			
	50	2	711	709	693	677	661	644	628	612	596	563	531	498	466			
	50	2	736	735	718	701	684	667	651	634	617	583	550	516	482			
	50	2	761	760	743	725	708	690	673	656	638	603	568	534	499			

TABLE XVI—(Continued)

Designation	Column Section	Thickness of Cover-Plates Inches	Safe Load, in Tons of 2,000 Pounds, for Columns With Square Ends and Unsupported Lengths of																	
			14 Ft or Less	16 Ft	18 Ft	20 Ft	22 Ft	24 Ft	26 Ft	28 Ft	30 Ft	32 Ft	34 Ft	36 Ft	40					
10-Inch Extra-Heavy Channel Column	Two 10-Inch 45-Pound Channels, Two Cover-Plates 12 Inches Wide and Two Web-Plates 9" X 1/4"	1	295	286	275	265	255	245	234	224	214	203	193	183	173					
		1 1/4	304	295	284	273	263	252	242	231	221	210	200	189	179					
		1 1/2	313	304	293	282	271	260	249	238	227	216	205	194	184					
		1 3/4	321	312	300	288	277	266	255	244	233	222	211	200	190					
		2	331	322	310	299	287	276	264	253	241	230	218	207	197					
		2 1/4	340	340	329	317	305	291	279	267	255	243	231	218	207					
		2 1/2	367	358	345	333	320	307	295	282	269	257	244	231	219					
		2 3/4	385	375	361	348	335	322	309	296	283	270	257	243	230					
		3	403	393	381	367	353	339	325	311	297	283	269	255	242					
		3 1/4	421	410	396	381	367	353	338	324	310	295	281	267	253					
		3 1/2	439	427	412	397	382	367	352	337	322	308	293	278	264					
		3 3/4	457	445	429	414	398	383	367	352	336	320	305	289	274					
		4	475	463	446	430	414	398	382	366	350	334	318	301	286					
		4 1/4	493	481	465	448	431	415	398	382	365	348	331	314	298					
		4 1/2	511	500	484	466	448	431	413	396	378	361	343	326	309					
12-Inch Extra-Heavy Channel Column	Two 12-Inch 45-Pound Channels, Two Cover-Plates 14 Inches Wide and Two Web-Plates 11" X 1/4"	1	349	346	336	326	316	306	296	286	266	246	226	206	186					
		1 1/4	359	357	346	336	326	316	306	296	275	254	233	212	191					
		1 1/2	370	368	356	345	334	324	313	303	283	262	241	220	199					
		1 3/4	381	378	367	357	346	335	324	313	292	270	248	226	204					
		2	391	388	377	366	355	344	332	320	298	276	254	232	210					
		2 1/4	411	409	398	387	375	364	352	340	316	292	268	245	222					
		2 1/2	433	431	419	407	395	382	370	358	333	308	283	258	233					
		2 3/4	454	452	439	426	413	400	387	374	348	322	296	270	244					
		3	476	473	459	445	432	418	405	391	364	337	310	283	256					
		3 1/4	496	493	478	464	450	436	422	408	380	352	324	296	268					
		3 1/2	518	515	501	487	472	457	443	428	398	369	339	309	280					
		3 3/4	539	536	520	504	489	474	458	443	413	382	352	321	291					
		4	560	556	541	526	510	494	478	462	430	398	366	334	302					
		4 1/4	580	577	561	545	529	512	496	479	446	413	380	347	314					
		4 1/2	602	598	581	565	547	530	513	495	461	427	393	359	325					

TABLE XVII
SAFE LOAD FOR STEEL Z-BAR COLUMNS

Safe Load, in Tons of 2,000 Pounds, for Columns With Square Ends and Unsupported Lengths of																								
Thickness of Z-Bar and Web-Plate inches	8 Ft. or Less	9 Ft.	10 Ft.	11 Ft.	12 Ft.	13 Ft.	14 Ft.	16 Ft.	18 Ft.	20 Ft.	22 Ft.	24 Ft.	26 Ft.	28 Ft.	30 Ft.	32 Ft.	34 Ft.	36 Ft.	38 Ft.	40 Ft.	42 Ft.	44 Ft.	46 Ft.	48 Ft.
		56	55	53	52	50	48	46	43	39	36	32	29	27	24	21	18	16	14	12	10	8	6	4
$\frac{1}{8}$	56	55	53	52	50	48	46	43	39	36	32	29	27	24	21	18	16	14	12	10	8	6	4	2
$\frac{1}{4}$	71	70	68	66	64	61	59	55	51	47	42	38	34	30	26	22	19	16	14	12	10	8	6	4
$\frac{3}{8}$	83	79	77	74	72	69	67	62	57	53	48	43	39	34	30	26	22	19	16	14	12	10	8	6
$\frac{1}{2}$	97	94	91	88	85	83	80	74	69	63	57	51	46	41	36	31	27	23	20	17	14	12	10	8
$\frac{5}{8}$	107	104	100	97	94	91	89	83	75	70	63	57	51	46	41	36	31	27	23	20	17	14	12	10
$\frac{3}{4}$	121	118	115	112	107	103	100	93	86	80	73	66	60	54	48	42	37	32	28	24	20	17	14	12
$\frac{1}{8}$	11 Ft. or Less	12 Ft.	13 Ft.	14 Ft.	16 Ft.	18 Ft.	20 Ft.	22 Ft.	24 Ft.	26 Ft.	28 Ft.	30 Ft.	32 Ft.	34 Ft.	36 Ft.	38 Ft.	40 Ft.	42 Ft.	44 Ft.	46 Ft.	48 Ft.	50 Ft.	52 Ft.	54 Ft.
		67	66	64	63	59	56	53	50	47	44	41	38 <td>35</td> <td>32</td> <td>29</td> <td>26</td> <td>23</td> <td>20</td> <td>18</td> <td>16</td> <td>14</td> <td>12</td> <td>10</td>	35	32	29	26	23	20	18	16	14	12	10
$\frac{1}{8}$	67	66	64	63	59	56	53	50	47	44	41	38	35	32	29	26	23	20	18	16	14	12	10	8
$\frac{1}{4}$	85	83	81	79	76	72	68	64	60	57	53	49	45	41	37	33	29	25	22	19	16	14	12	10
$\frac{3}{8}$	103	101	99	97	92	88	83	78	74	69	65	60	56	51	46	42	37	33	29	25	21	18	16	14
$\frac{1}{2}$	114	111	108	106	100	95	90	85	80	74	69	64	60	55	50	45	40	36	31	27	23	20	17	14
$\frac{5}{8}$	131	128	125	122	117	111	105	99	93	87	82	76	71	66	61	56	51	46	41	37	32	28	24	20
$\frac{3}{4}$	149	146	142	139	133	126	120	113	107	100	94	87	81	76	71	66	61	56	51	46	41	37	32	28
$\frac{7}{8}$	158	155	151	148	140	133	126	119	111	104	97	90	84	78	73	67	62	57	52	47	42	37	32	28
$\frac{15}{16}$	174	171	166	162	155	147	140	132	125	117	110	102	96	90	84	78	73	67	62	57	52	47	42	37
$\frac{15}{16}$	191	189	185	181	172	164	156	148	140	131	123	115	108	101	94	87	81	75	70	64	59	53	48	42
$\frac{1}{8}$	13 Ft. or Less	14 Ft.	16 Ft.	18 Ft.	20 Ft.	22 Ft.	24 Ft.	26 Ft.	28 Ft.	30 Ft.	32 Ft.	34 Ft.	36 Ft.	38 Ft.	40 Ft.	42 Ft.	44 Ft.	46 Ft.	48 Ft.	50 Ft.	52 Ft.	54 Ft.	56 Ft.	58 Ft.
		95	95	91	88	84	81	77	75	71	66	63	60	56 <td>52</td> <td>48</td> <td>44</td> <td>40</td> <td>36</td> <td>32</td> <td>28</td> <td>24</td> <td>20</td> <td>16</td>	52	48	44	40	36	32	28	24	20	16
$\frac{1}{8}$	95	95	91	88	84	81	77	75	71	66	63	60	56	52	48	44	40	36	32	28	24	20	16	12
$\frac{1}{4}$	114	114	110	106	101	97	93	89	85	81	76	72	68	64	60	56	52	48	44	40	36	32	28	24
$\frac{3}{8}$	134	134	129	124	119	114	109	104	99	94	90	85	80	76	71	67	62	58	54	50	46	42	38	34
$\frac{1}{2}$	147	146	141	135	130	124	119	113	108	102	97	91	86	81	76	72	67	63	59	55	51	47	43	39
$\frac{5}{8}$	166	166	160	154	148	142	135	129	123	117	111	105	99	94	88	83	78	74	69	65	61	57	53	49
$\frac{3}{4}$	185	185	179	172	164	158	151	145	138	131	126	119	113	107	101	96	91	86	82	77	73	69	65	61
$\frac{7}{8}$	196	195	188	181	173	166	159	152	145	138	130	123	116	110	104	98	93	88	83	78	74	70	66	62
$\frac{15}{16}$	215	213	204	198	190	183	174	167	160	152	145	137	130	123	116	110	104	98	93	88	83	78	74	70
$\frac{15}{16}$	234	234	226	218	210	201	193	185	177	169	160	152	144	137	130	123	116	110	104	98	93	88	83	78
$\frac{1}{8}$	16 Ft. or Less	18 Ft.	20 Ft.	22 Ft.	24 Ft.	26 Ft.	28 Ft.	30 Ft.	32 Ft.	34 Ft.	36 Ft.	38 Ft.	40 Ft.	42 Ft.	44 Ft.	46 Ft.	48 Ft.	50 Ft.	52 Ft.	54 Ft.	56 Ft.	58 Ft.	60 Ft.	62 Ft.
		128	125	120	116	112	108	104	100	96	92	88	84	80 <td>76</td> <td>72</td> <td>68</td> <td>64</td> <td>60</td> <td>56</td> <td>52</td> <td>48</td> <td>44</td> <td>40</td>	76	72	68	64	60	56	52	48	44	40
$\frac{1}{8}$	128	125	120	116	112	108	104	100	96	92	88	84	80	76	72	68	64	60	56	52	48	44	40	36
$\frac{1}{4}$	150	146	141	137	132	128	123	119	114	109	105	101	96	92	88	84	80	76	72	68	64	60	56	52
$\frac{3}{8}$	173	170	165	160	154	149	144	138	133	128	123	117	112	107	102	97	92	87	82	77	72	67	62	57
$\frac{1}{2}$	187	182	177	171	165	159	153	147	141	135	130	124	118	113	107	102	97	92	87	82	77	72	67	62
$\frac{5}{8}$	209	204	198	191	185	178	172	165	159	152	146	140	133	127	121	115	110	104	99	93	88	83	77	72
$\frac{3}{4}$	231	227	220	214	207	200	193	186	180	172	165	158	151	145	138	132	126	120	114	108	102	96	90	84
$\frac{7}{8}$	243	237	230	222	215	207	200	192	185	177	170	162	155	148	141	134	127	121	115	109	103	97	91	85
$\frac{15}{16}$	265	258	250	242	234	226	218	210	202	194	186	178	170	162	154	146	138	131	124	117	110	103	96	90
$\frac{15}{16}$	286	280	271	262	253	245	236	227	218	209	201	192	184	176	168	160	152	144	136	128	120	112	104	96

COLUMNS AND STRUTS

§ 16

TABLE XVIII

SAFE LOAD FOR STEEL Z-BAR COLUMNS WITH COVER-PLATES

Safe Load, in Tons of 2,000 Pounds, for Columns With Square Ends and Unsupported Lengths of		Lengths of Columns in Feet															
		16 Ft or Less	18 Ft	20 Ft	22 Ft	24 Ft	26 Ft	28 Ft	30 Ft	32 Ft	34 Ft	36 Ft	38 Ft	40 Ft	42 Ft	44 Ft	46 Ft
Four 2 Bars 6" x 1/4" One Web Plate 8" x 1/4" Two Cover Plates 14 Inches Wide	1	306	300	291	282	273	264	255	246	237	228	219	210	201	192	183	174
	1 1/2	317	311	301	292	283	273	264	254	245	235	226	216	207	198	189	180
	2	327	321	311	302	292	282	273	263	253	244	234	224	215	206	197	188
	2 1/2	338	332	323	313	303	293	283	273	263	253	243	233	223	214	205	196
	3	348	342	332	322	311	301	291	281	270	260	250	240	229	220	211	202
	3 1/2	358	352	342	331	321	310	300	289	279	268	258	247	237	228	219	210
	4	368	362	352	342	331	321	310	300	288	277	266	255	244	235	226	217
	4 1/2	380	374	363	352	341	329	318	307	296	285	274	262	251	241	231	222
	5	389	384	372	361	350	338	327	315	304	293	281	270	258	248	237	227
	5 1/2	401	393	381	370	358	346	334	322	310	298	286	274	262	251	240	229
Four 2 Bars 6" x 1/4" One Web Plate 8" x 1/4" Two Cover Plates 14 Inches Wide	1	412	404	392	380	368	355	343	331	318	306	294	282	270	258	246	234
	1 1/2	422	415	402	390	377	365	352	340	328	315	303	290	278	266	254	242
	2	433	426	413	400	388	375	362	349	336	324	311	298	285	273	261	249
	2 1/2	444	436	423	410	397	384	371	357	344	331	318	305	292	279	267	254
	3	454	446	433	419	407	393	380	366	353	339	326	312	299	286	273	260
	3 1/2	465	457	443	430	416	402	388	375	361	348	334	321	307	294	281	268
	4	475	467	454	440	426	412	398	384	370	356	342	328	314	300	287	273
	4 1/2	486	477	463	449	434	420	406	392	377	363	349	335	321	307	293	279
	5	496	487	472	457	443	428	414	399	385	370	356	341	327	312	298	283
	5 1/2	507	497	482	467	452	437	422	407	392	377	362	347	332	317	302	287
Four 2 Bars 6" x 1/4" One Web Plate 10" x 1/4" Two Cover Plates 16 Inches Wide	1	488	476	464	452	440	428	416	404	392	380	368	356	344	332	320	308
	1 1/2	501	488	475	463	450	439	427	415	402	390	378	365	353	341	329	317
	2	513	501	488	475	463	450	438	425	412	400	387	374	362	350	338	326
	2 1/2	525	513	500	487	474	461	448	435	422	409	396	383	370	357	345	333
	3	537	523	510	497	484	470	457	444	431	418	404	391	378	365	352	339
	3 1/2	548	534	522	509	495	482	468	455	441	428	414	401	387	374	361	348
	4	561	548	534	520	506	493	479	465	451	437	424	410	396	382	369	355
	4 1/2	573	559	545	531	517	503	489	475	460	446	432	418	404	390	376	362
	5	585	571	556	542	527	513	498	484	470	455	441	426	412	397	383	369
	5 1/2	597	583	568	553	539	524	509	494	479	464	450	435	420	405	390	376
	6	609	594	579	564	549	534	519	504	489	474	459	444	429	414	399	384
	6 1/2	621	607	592	577	561	546	530	515	500	484	469	454	439	424	409	394
	7	633	618	602	587	571	556	540	525	509	494	478	463	447	432	417	402
	7 1/2	645	631	616	600	584	568	552	536	520	504	488	472	456	441	425	410
	8	657	643	626	610	593	577	561	544	528	512	496	480	464	448	432	416
	8 1/2	669	654	637	621	603	587	570	554	538	521	505	488	472	456	440	424
	9	681	666	648	631	615	598	581	565	548	531	514	498	481	465	448	432
	9 1/2	693	677	659	642	625	608	591	574	557	540	523	506	489	472	455	438
	10	705	689	671	654	636	619	601	584	567	549	532	514	497	480	463	446
	10 1/2	717	701	682	664	647	629	612	594	576	559	541	524	506	489	472	455
	11	729	713	694	676	658	640	622	604	586	568	550	532	514	497	480	463

DETAILS OF CONSTRUCTION

RIVETS AND PINS

INTRODUCTION

1. Rivets and pins are the elements by which the different sections and members of a steel structure are connected.

Pins are also used in the better class of timber construction, in which case the tension members are usually made of steel or wrought iron.

Where plates or rolled shapes are joined by pins or rivets, as in Fig. 1, there is friction between the parts, which tends to prevent their being pulled apart. This is especially true when rivets are driven close against the plates while hot; in cooling, they contract between the heads and bind the plates tightly together. The friction




FIG. 1

between plates connected by rivets and pins, however, is an uncertain quantity and should not be considered in calculating the strength of the joint.

For notice of copyright, see page immediately following the title page

RIVETED CONNECTIONS

RIVETS

2. Structural rivets are made either of steel or of wrought iron. Those used in the shop are made of soft steel, but those used in the field are of wrought iron, because this material is less likely to be damaged in heating, and also because considerable heat is lost in passing the rivets from the forge to the riveters, thus reducing them to a temperature that would be too low to work on steel.

3. **Sizes.**—Rivets used in structural work vary in diameter from $\frac{1}{2}$ inch to 1 inch, being made in $\frac{1}{2}$ -, $\frac{3}{8}$ -, $\frac{5}{8}$ -, $\frac{7}{8}$ -, and 1-inch sizes. The $\frac{1}{2}$ - and $\frac{3}{8}$ -inch rivets are most generally used, the smaller sizes being employed only on unimportant details, or where the clearance will not allow the insertion of larger ones, and those larger than $\frac{7}{8}$ inch are used only where there are very thick plates or very great stresses. Field rivets should never be more than $\frac{7}{8}$ inch.

On account of the difficulty of punching holes of less diameter than the thickness of the plate, the diameter of the rivet should not be less than the thickness of the thickest plate through which the rivet passes. Sections with small flanges necessitate the use of small rivets so as to allow sufficient distance from the edge of the piece and enough space for the tool in driving the rivet.

When the size cannot be determined by the above conditions, such a size should be used as will resist the existing stresses and be economical. It is cheaper to use the same size rivets throughout a piece, and the smaller rivets are more economical as they reduce the weight and the cost of punching and driving. The standard sizes, from the Cambria Steel Company's handbook, to be used in I beams, channels, and angles are given in Table I.

4. **Diameter of Hole.**—The diameter of the rivet hole when drilled should be $\frac{1}{16}$ inch larger than the rivet, as the latter is inserted while hot, and when driven, is upset, thus

TABLE I
MAXIMUM SIZE OF RIVETS IN BEAMS, CHANNELS, AND ANGLES

I Beams						Channels			Angles			
Depth of Beam Inches	Weight per Foot Pounds	Size of Rivet Inches	Depth of Beam Inches	Weight per Foot Pounds	Size of Rivet Inches	Depth of Channel Inches	Weight per Foot Pounds	Size of Rivet Inches	Length of Leg Inches	Size of Rivet Inches	Length of Leg Inches	Size of Rivet Inches
3	5.50	$\frac{3}{8}$	15	42.00	$\frac{3}{8}$	3	4.00	$\frac{3}{8}$	$\frac{3}{8}$	$\frac{3}{8}$	$2\frac{1}{2}$	$\frac{3}{8}$
4	7.50	$\frac{3}{8}$	15	60.00	$\frac{3}{8}$	4	5.25	$\frac{3}{8}$	1	$\frac{3}{8}$	$2\frac{3}{4}$	$\frac{3}{8}$
5	9.75	$\frac{3}{8}$	15	80.00	$\frac{3}{8}$	5	6.50	$\frac{3}{8}$	$1\frac{1}{2}$	$\frac{3}{8}$	3	$\frac{3}{8}$
6	12.25	$\frac{3}{8}$	18	55.00	$\frac{3}{8}$	6	8.00	$\frac{3}{8}$	$1\frac{3}{4}$	$\frac{3}{8}$	$3\frac{1}{2}$	1
7	15.00	$\frac{3}{8}$	20	65.00	1	7	9.75	$\frac{3}{8}$	$1\frac{7}{8}$	$\frac{3}{8}$	4	1
8	17.75	$\frac{3}{8}$	20	80.00	1	8	11.25	$\frac{3}{8}$	$1\frac{7}{8}$	$\frac{3}{8}$	$4\frac{1}{2}$	1
9	21.00	$\frac{3}{8}$	24	80.00	1	9	13.25	$\frac{3}{8}$	$1\frac{7}{8}$	$\frac{3}{8}$	5	1
10	25.00	$\frac{3}{8}$				10	15.00	$\frac{3}{8}$	2	$\frac{3}{8}$	6	1
12	31.50	$\frac{3}{8}$				12	20.50	$\frac{3}{8}$	$2\frac{1}{2}$	$\frac{3}{8}$	7	1
12	40.00	$\frac{3}{8}$				15	33.00	$\frac{3}{8}$	$2\frac{3}{4}$	$\frac{3}{8}$		

completely filling the hole, but when the hole is punched, it is well to allow $\frac{1}{8}$ inch excess of diameter of hole over diameter of rivet. Holes are not drilled except in very important work, or when hard steel is used.

5. Rivet Heads.—The round head or full head, also called button head, is a spherical segment slightly less than a hemisphere.

Countersunk heads are countersunk into the surrounding material so that they are flush on top with the surface of the plate into which they are sunk. These are used when a button head would interfere with the bearing, as at the base of a column where it rests on the bearing block or capstone.

Flattened heads are made by flattening the button heads and are used in extreme cases where a round head would be too high.

6. Dimensions of Heads.—The height and diameter of a rivet head bear the following relations to the diameter of the rivet.




FIG. 2

For button heads the standard height of head is six-tenths the diameter of the rivet and the radius of the head is three-fourths of the diameter of the rivet plus $\frac{1}{8}$ inch. These dimensions are shown in Fig. 2.

For countersunk heads, the diameter of the head is the same as for a button head, and its bevel is 60° ; from these data the height, or depth, of the head can be determined. A simple rule is to make the depth equal to one-half of the diameter of the rivet. Countersunk rivets should not be used in plates of less thickness than one-half the diameter of the rivet. Where economy is to be considered, their use should be avoided if possible, as the extra work required in countersinking makes them expensive.

For flattened heads, the height is never less than $\frac{1}{8}$ inch.

7. Clearance.—When one riveted section is close to another, it is necessary to keep them a certain distance apart to allow a clearance for the driven rivets. This clearance is $\frac{1}{8}$ inch for $\frac{3}{4}$ -inch rivets and $\frac{1}{4}$ inch for $\frac{1}{2}$ -inch rivets. It is always better to provide for a head $\frac{1}{8}$ inch higher than the figured height, to allow for the upsetting of the rivet and discrepancies in the material.

8. Length or Grip.—In order to drive tight rivets, it is necessary to keep them within a certain length or grip. The maximum grip, or distance between heads, is generally accepted as not more than four times the diameter of the rivet. In

determining the length to be given in ordering rivets, first find the grip, which is considered as the thickness of the parts joined plus $\frac{1}{32}$ inch for each joint between plates; this $\frac{1}{32}$ inch is to allow for unevenness in the surfaces of the plates which might prevent their being in close contact. This grip must be increased in the ratio of the area of the hole to the area of the rivet section, to allow for upsetting, the hole being $\frac{1}{16}$ inch larger in diameter than the rivet. To this result must be added the height required for the head, and the sum is the length of rivet under the formed head. Assume a $\frac{3}{4}$ -inch button-head rivet with a grip of $2\frac{1}{8}$ inches. Increasing this grip in the ratio of the area of the hole to the area of the rivet, or $\frac{(\frac{13}{16})^2 \times .7854}{(\frac{3}{4})^2 \times .7854} = \frac{169}{144}$ (since $\frac{.7854}{16^2}$ is common to both numerator and denominator), gives $2\frac{1}{2} \times \frac{169}{144}$, or about $2\frac{1}{2}$ inches. Adding $1\frac{1}{8}$ inches for the head, the length of rivet required is found to be $2\frac{1}{2} + 1\frac{1}{8} = 3\frac{5}{8}$ inches. Table II gives the length required to form one head, including the increase due to excess of area of hole over area of rivet.

TABLE II
LENGTH OF RIVET SHANK REQUIRED TO FORM ONE RIVET HEAD

Grip Inches	Button Head					Countersunk Head				
	Diameter of Rivet. Inches					Diameter of Rivet. Inches				
	$\frac{1}{2}$	$\frac{5}{8}$	$\frac{3}{4}$	$\frac{7}{8}$	1	$\frac{1}{2}$	$\frac{5}{8}$	$\frac{3}{4}$	$\frac{7}{8}$	1
$\frac{1}{2}$ to $1\frac{3}{8}$	1	$1\frac{1}{4}$	$1\frac{3}{8}$	$1\frac{1}{2}$	$1\frac{5}{8}$	$\frac{5}{8}$	$\frac{3}{4}$	$\frac{3}{4}$	$\frac{7}{8}$	$\frac{7}{8}$
$1\frac{1}{2}$ to $2\frac{7}{8}$	$1\frac{1}{8}$	$1\frac{3}{8}$	$1\frac{1}{2}$	$1\frac{5}{8}$	$1\frac{3}{4}$	$\frac{5}{8}$	$\frac{3}{4}$	$\frac{7}{8}$	$\frac{7}{8}$	1
3 to $4\frac{3}{8}$	$1\frac{1}{4}$	$1\frac{1}{2}$	$1\frac{5}{8}$	$1\frac{3}{4}$	$1\frac{7}{8}$	$\frac{3}{4}$	$\frac{7}{8}$	1	1	$1\frac{1}{8}$
$4\frac{1}{2}$ to $5\frac{1}{2}$	$1\frac{3}{8}$	$1\frac{5}{8}$	$1\frac{3}{4}$	$1\frac{7}{8}$	2				1	$1\frac{1}{8}$

Rivets are ordered in even eighths of an inch. Table III shows the lengths of rivets required for the different grips.

SPACING OF RIVETS

9. Pitch.—The pitch, or distance from center to center of rivets, should be at least three diameters of the rivet. If spaced closer, the material is likely to fracture or become otherwise injured. For members in compression, the pitch in the direction of the stress should not be greater than 6 inches, or sixteen times the thickness of the thinnest outside plate. If possible, the pitch should be kept in even inches, making it either 2, 3, 4, 5, or 6 inches, as the case may require, especially when the rows are long.

It is usual to space the rivets closer at the joints and foot of a column than in the body; when $\frac{3}{4}$ -inch rivets are used, it is customary to space them 3 inches on centers at the joints and bottom, and from $4\frac{1}{2}$ to 6 inches on centers in the remainder of the column; when the rivets are $\frac{7}{8}$ -inch, they should be spaced about 4 inches at the joints and 6 inches throughout the length of the column.

In Table IV are given the maximum and minimum pitches of the different sized rivets and the minimum and usual distances from the end.

TABLE IV
RIVET SPACING

Size of Rivet Inch	Minimum Pitch Inches	Maximum Pitch at Ends of Compression Members Inches	Maximum Pitch in Flanges of Chords and Girders Inches	Distance From End of Piece to Center of Rivet Inches	
				Minimum	Usual
$\frac{1}{4}$	$\frac{3}{4}$				
$\frac{3}{8}$	$1\frac{1}{8}$				
$\frac{1}{2}$	$1\frac{1}{2}$				
$\frac{5}{8}$	$1\frac{7}{8}$	$2\frac{1}{2}$	4	$1\frac{5}{8}$	$1\frac{1}{4}$
$\frac{3}{4}$	$2\frac{1}{4}$	3	4	$1\frac{1}{8}$	$1\frac{1}{2}$
$\frac{7}{8}$	$2\frac{5}{8}$	$3\frac{1}{2}$	4	$1\frac{5}{16}$	$1\frac{3}{4}$
1	3	4	4	$1\frac{1}{2}$	2


TABLE V
STANDARD SPACING OF RIVETS AND BOLTS THROUGH FLANGES AND CONNECTION ANGLES OF
I BEAMS, AND TANGENT DISTANCES BETWEEN FILLETS MEASURED ALONG THE WEB



Depth of Beam Inches	Weight Pounds per Foot	" Inches	a Inches	b Inches	T Inches	Depth of Beam Inches	Weight Pounds per Foot	a Inches	b Inches	T Inches
3	5.50	1 1/4	4 3/4	1 1/4	1 1/8	12	55.0	3	5 1/4	1 1/4
3	6.50	1 1/4	4 3/4	1 1/4	1 1/8	13	42.0	3	4 1/2	1 1/4
3	7.50	1 1/4	4 3/4	1 1/4	1 1/8	15	45.0	3	4 1/2	1 1/4
4	7.50	1 1/4	4 1/4	1 1/4	2 1/4	15	50.0	3	5 1/4	1 1/4
4	8.50	1 1/4	4 1/4	1 1/4	2 1/4	15	55.0	3	5 1/4	1 1/4
4	9.50	1 1/4	4 1/4	1 1/4	2 1/4	15	60.0	3	5 1/4	1 1/4
4	10.50	1 1/4	4 1/4	1 1/4	2 1/4	15	65.0	3 1/2	5 1/4	1 1/4
5	9.75	1 1/4	4 1/4	1 1/4	3 1/4	15	70.0	3 1/2	5 1/4	1 1/4
5	12.25	1 1/4	4 1/4	1 1/4	3 1/4	15	75.0	3 1/2	5 1/4	1 1/4
5	14.75	1 1/4	5	1 1/4	3 1/4	15	80.0	3 1/2	5 1/4	1 1/4
6	12.25	2	4 1/4	1 1/4	4 1/4	15		3 1/2	5 1/4	1 1/4

6	14.75	2	437	11	414	15	80.0	31	516	132	1018
6	17.25	2	431	38	416	15	85.0	31	513	132	1018
7	15.00	21	41	38	53	15	90.0	31	51	132	1018
7	17.50	21	437	38	53	15	95.0	31	513	132	1018
7	20.00	21	431	38	53	15	100.0	31	516	176	1018
8	18.00	21	437	13	618	18	55.0	31	431	11	1518
8	20.25	21	437	16	618	18	60.0	31	516	11	1518
8	22.75	21	416	16	618	18	65.0	31	51	33	1518
8	25.25	21	582	16	618	18	70.0	31	572	33	1518
9	21.00	21	437	16	716	20	65.0	31	5	33	1618
9	25.00	21	432	16	716	20	70.0	31	532	33	1618
9	30.00	21	516	15	716	20	75.0	31	532	33	1618
9	35.00	21	532	15	716	20	80.0	4	532	33	1618
10	25.00	25	413	15	716	20	85.0	4	532	33	1618
10	30.00	25	416	1	716	20	90.0	4	51	33	1618
10	35.00	25	532	1	716	20	95.0	4	516	33	1618
10	40.00	25	51	17	716	20	100.0	4	53	16	1618
12	31.50	24	437	17	92	21	80.0	4	5	33	2018
12	35.00	24	416	17	92	21	85.0	4	516	33	2018
12	40.00	24	516	14	92	21	90.0	4	51	7	2018
12	40.00	3	431	33	916	21	95.0	4	518	7	2018
12	45.00	3	532	33	916	21	100.0	4	51	7	2018
12	50.00	3	516	33	916	21		4		7	


TABLE VI
STANDARD SPACING OF RIVETS AND BOLTS IN FLANGES
AND CONNECTION ANGLES OF CHANNELS, AND
TANGENT DISTANCES BETWEEN FILLETS
MEASURED ALONG THE WEB

[illegible]

10. Distance From End.—In order to avoid the danger of fracturing the material, rivets should not be placed too near the edge or end of the plate. (Owing to the greater strength of wrought iron in the direction of the fiber, rivets in wrought iron may be placed nearer the edge than the end.) According to practice, the distance between the edge of any piece and the center of the rivet hole should not be less than $1\frac{1}{4}$ inches for $\frac{3}{4}$ -inch and $\frac{7}{8}$ -inch

TABLE VII

STANDARD SPACING OF RIVETS AND BOLTS IN ANGLES,
WITH MAXIMUM SIZE OF RIVETS TO BE USED



Length of Leg Inches	<i>m</i> Inches	Diameter of Rivet Inches	Length of Leg Inches	<i>m</i> Inches	Diameter of Rivet Inches	Length of Leg Inches	<i>m</i> Inches	Diameter of Rivet Inches
$\frac{3}{4}$	$\frac{7}{16}$	$\frac{1}{4}$	2	$1\frac{1}{8}$	$\frac{5}{8}$	$3\frac{1}{2}$	Variable, depending on diameter of rivet, thickness of metal, and length of leg.	1
1	$\frac{9}{16}$	$\frac{3}{8}$	$2\frac{1}{4}$	$1\frac{1}{4}$	$\frac{3}{4}$	4		1
$1\frac{1}{4}$	$1\frac{1}{8}$	$\frac{1}{2}$	$2\frac{5}{8}$	$1\frac{1}{4}$	$\frac{3}{4}$	$4\frac{1}{2}$		1
$1\frac{5}{8}$	$\frac{3}{4}$	$\frac{1}{2}$	$2\frac{1}{2}$	$1\frac{3}{8}$	$\frac{3}{4}$	5		1
$1\frac{3}{8}$	$\frac{3}{4}$	$\frac{1}{2}$	$2\frac{3}{4}$	$1\frac{1}{2}$	$\frac{3}{4}$	6		1
$1\frac{1}{2}$	$1\frac{3}{8}$	$\frac{1}{2}$	3	$1\frac{3}{4}$	$\frac{7}{8}$	7		1
$1\frac{3}{4}$	$1\frac{5}{8}$	$\frac{5}{8}$						

rivets, except in bars less than $2\frac{1}{2}$ inches wide; when practicable, it should be at least two diameters of the rivet for all sizes and should not exceed eight times the thickness of the plate. A simple rule is to make the end distance twice the diameter of the rivets and the side distance $\frac{1}{4}$ inch less than this.

11. Clearance.—A certain amount of clearance is required for tools in forming the heads of rivets in shapes having short flanges. For a $\frac{7}{8}$ -inch rivet, the distance from

TABLE VIII
STANDARD SPACING OF RIVETS AND BOLTS IN T BARS,
WITH MAXIMUM SIZE OF RIVETS TO BE USED



Width of Flange Inches	Depth of Bar Inches	Weight Pounds per Foot	<i>m</i> Inches	Maximum Diameter of Rivet in Stem Inches	<i>n</i> Inches	Maximum Diameter of Rivets in Flange Inches
3½	3½	9.30	2	1	1½	5⁄8
3	3	7.80	1½	7⁄8	1½	½
3	3	6.60	1½	7⁄8	1½	½
2½	2½	5.50	1½	¾	1½	½
2½	2½	4.90	1½	¾	1½	½
2½	2½	4.10	1½	¾	1½	½
2	2	4.30	1½	¾	1	½
2	2	3.70	1½	¾	1	½
1½	1½	1.85	¾	½	5⁄8	¼
1½	1½	1.61	11⁄10	½	5⁄8	¼
1½	1½	1.53	5⁄8	½	5⁄8	¼
1½	1½	1.39	9⁄10	½	5⁄8	¼
1	1	.89	9⁄16	3⁄8	5⁄8	¼
3½	4	9.90	2½	1	1½	5⁄8
5	3	13.60	1¾	7⁄8	2½	¾
3	2½	7.20	1¾	¾	1½	½
2½	1½	2.90	1½	½	1½	½
1½	1½	1.49	9⁄16	3⁄8	1	¼

the center of the rivet to the back of the angle should not be less than $1\frac{1}{4}$ inches; and for a $\frac{3}{4}$ -inch rivet, this distance should not be less than $1\frac{1}{8}$ inches. The perpendicular distance between the center line of a rivet in one leg of an angle and the top of a rivet head on the other leg should not be less than $1\frac{1}{8}$ inches.

Tables V and VI give the standard spacing (adopted by the Cambria Steel Company) of rivets and bolts in flanges and connection angles of I beams and channels, and the tangent distances between fillets measured along the web. In Tables VII and VIII are given the standard spacings of rivets and bolts in angles, T bars, and Z bars, with the maximum size of rivets to be used.

ANALYSIS OF RIVETED JOINTS

12. Every riveted joint is one of two kinds: a *lap joint*, as shown in Fig. 3, or a *butt joint*, as in Fig. 4, either of which may be single-, double-, triple-, or quadruple-riveted. When there is more than one row,




FIG. 3



*With Single Cover Plate**With Double Cover Plate*

FIG. 4

the riveting may be either *chain* or *zigzag*, usually called *staggered*.

The one most frequently used is the butt joint, it being more symmetrical and more effective. It is always preferable to the lap joint, which is made use of only in unimportant details.


TABLE IX
STANDARD SPACING OF RIVETS AND BOLTS IN 2 BARS,
WITH MAXIMUM SIZE OF RIVETS TO BE USED



Depth of Bar Inches	Weight Pounds per Foot	<i>m</i> Inches	Maximum Diameter of Rivets Inches
3 to $3\frac{1}{8}$	6.7 to 14.2	$1\frac{5}{8}$	$\frac{3}{4}$
4 to $4\frac{1}{8}$	8.2 to 23.0	$1\frac{3}{4}$	$\frac{7}{8}$
5 to $5\frac{1}{8}$	11.6 to 28.3	$1\frac{7}{8}$	$\frac{7}{8}$
6 to $6\frac{1}{8}$	15.6 to 34.6	2	1

13. Joints in Tension.—A simple lap joint in tension with only one rivet, as shown in Fig. 5, will first be considered. This joint is liable to fail:

1. By one or both bars tearing across, as in Fig. 6.
2. By the rivet being sheared, as in Fig. 7.
3. By the rivet cutting into the bar, or the bar cutting into the rivet, as in Fig. 8, according to which metal is the softer.
4. By the bar being sheared by the rivet, as in Fig. 9.



In order to secure a good joint, therefore, it is necessary to calculate the stresses coming upon the joint and to

arrange the number, size, position, and pitch of rivets and the dimensions of the plates to effectively resist those stresses.

The cause of the first method of failure is the inability of the net section of the bar to resist the stress. To find the net section, deduct the diameter of the rivet hole from the width of the bar and multiply by the thickness. Table X gives the areas to be deducted to obtain the net sections of riveted plates when the thickness of plate and diameter of rivet hole are given. Therefore, to insure strength, the area of this net section multiplied by the safe tensile strength of the steel per square inch must equal the tensile stress on the joint.

14. Bearing Value on Plates.—When the diameter of the rivet is large in proportion to the thickness of the plate, the joint or connection is liable to fail by the crippling of the plate, as shown in Fig. 10. This occurs when the resistance of the plate to crushing or crimping is less than the resistance of the rivet to shear.




FIG. 10

Considering the second method of failure, the strength depends on the bear-

ing value of the plate or rivet, and as this varies with the bearing area of the rivet on the plate, which is assumed to be $t d$, the bearing value B of the plate is expressed by the formula,

$$B = t d r_b \quad (1)$$

in which t = thickness of plate;

d = diameter of rivet;

r_b = safe bearing resistance per square inch.


15. The condition of the plates in the joint shown in Fig. 11 (a) is called *ordinary bearing*, while the plate m connected as shown in (b) is said to be in *web bearing*. This distinction is important, because the bearing value of a web-plate is greater than that of an outside plate, the value for

Size of Hole, Inches

Thickness of Plates Inches

Inches of Plates	$\frac{1}{16}$	$\frac{1}{8}$	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{5}{8}$	$\frac{3}{4}$	$\frac{7}{8}$	1	1 $\frac{1}{8}$	1 $\frac{1}{4}$	1 $\frac{1}{2}$	1 $\frac{3}{4}$	2		
$\frac{1}{16}$.27	.28	.30	.31	.33	.34	.36	.38	.39	.41	.42	.44	.45	.47	.48	.50
$\frac{1}{8}$.33	.35	.37	.39	.41	.43	.45	.47	.49	.51	.53	.55	.57	.59	.61	.63
$\frac{3}{16}$.40	.42	.45	.47	.49	.52	.54	.56	.59	.61	.63	.66	.68	.70	.73	.75
$\frac{1}{4}$.46	.49	.52	.55	.57	.60	.63	.66	.68	.71	.74	.77	.79	.82	.85	.88
$\frac{5}{16}$.53	.56	.59	.63	.66	.69	.72	.75	.78	.81	.84	.88	.91	.94	.97	1.00
$\frac{3}{8}$.60	.63	.67	.70	.74	.77	.81	.84	.88	.91	.95	.98	1.02	1.05	1.09	1.13
$\frac{7}{16}$.66	.70	.74	.78	.82	.86	.90	.94	.98	1.02	1.05	1.09	1.13	1.17	1.21	1.25
$\frac{1}{2}$.73	.77	.82	.86	.90	.95	.99	1.03	1.07	1.12	1.16	1.20	1.25	1.29	1.33	1.38
$\frac{3}{4}$.80	.84	.89	.94	.98	1.03	1.08	1.13	1.17	1.22	1.27	1.31	1.36	1.41	1.45	1.50
$1\frac{1}{16}$.86	.91	.96	1.02	1.07	1.12	1.17	1.22	1.27	1.32	1.37	1.42	1.47	1.52	1.57	1.63
$1\frac{1}{8}$.93	.98	1.04	1.09	1.15	1.20	1.26	1.31	1.37	1.42	1.48	1.53	1.59	1.64	1.70	1.75
$1\frac{1}{4}$	1.00	1.05	1.11	1.17	1.23	1.29	1.35	1.41	1.46	1.52	1.58	1.64	1.70	1.76	1.82	1.88
1	1.06	1.13	1.19	1.25	1.31	1.38	1.44	1.50	1.56	1.63	1.69	1.75	1.81	1.88	1.94	2.00
$1\frac{1}{8}$	1.13	1.20	1.26	1.33	1.39	1.46	1.53	1.59	1.66	1.73	1.79	1.86	1.93	1.99	2.06	2.13
$1\frac{1}{4}$	1.20	1.27	1.34	1.41	1.48	1.55	1.62	1.69	1.76	1.83	1.90	1.97	2.04	2.11	2.18	2.25
$1\frac{3}{8}$	1.26	1.34	1.41	1.48	1.56	1.63	1.71	1.78	1.86	1.93	2.00	2.08	2.15	2.23	2.30	2.38
$1\frac{1}{2}$	1.33	1.41	1.48	1.56	1.64	1.72	1.80	1.88	1.95	2.03	2.11	2.19	2.27	2.34	2.42	2.50
$1\frac{5}{8}$	1.39	1.48	1.56	1.64	1.72	1.80	1.89	1.97	2.05	2.13	2.21	2.30	2.38	2.46	2.54	2.63
$1\frac{3}{4}$	1.46	1.55	1.63	1.72	1.80	1.89	1.98	2.06	2.15	2.23	2.32	2.41	2.49	2.58	2.66	2.75
$1\frac{7}{8}$	1.53	1.62	1.71	1.80	1.89	1.98	2.07	2.16	2.25	2.34	2.43	2.52	2.61	2.70	2.79	2.88
2	1.59	1.69	1.78	1.88	1.97	2.06	2.16	2.25	2.34	2.44	2.53	2.63	2.72	2.81	2.91	3.00
$2\frac{1}{16}$	1.66	1.76	1.86	1.95	2.05	2.15	2.25	2.34	2.44	2.54	2.64	2.73	2.83	2.93	3.03	3.13
$2\frac{1}{8}$	1.73	1.83	1.93	2.03	2.13	2.23	2.34	2.44	2.54	2.64	2.74	2.84	2.95	3.05	3.15	3.25
$2\frac{1}{4}$	1.79	1.90	2.00	2.11	2.21	2.32	2.43	2.53	2.64	2.74	2.85	2.95	3.06	3.16	3.27	3.38
$2\frac{1}{2}$	1.86	1.97	2.08	2.19	2.30	2.41	2.52	2.63	2.73	2.84	2.95	3.06	3.17	3.28	3.39	3.50
$2\frac{3}{8}$	1.93	2.04	2.15	2.27	2.38	2.49	2.61	2.72	2.83	2.95	3.06	3.17	3.29	3.40	3.51	3.63
$2\frac{1}{2}$	1.99	2.11	2.23	2.34	2.46	2.58	2.70	2.81	2.93	3.05	3.16	3.28	3.40	3.52	3.63	3.75
$2\frac{5}{8}$	2.06	2.18	2.30	2.42	2.54	2.66	2.79	2.91	3.03	3.15	3.27	3.39	3.51	3.63	3.75	3.88
2	2.13	2.25	2.38	2.50	2.63	2.75	2.88	3.00	3.13	3.25	3.38	3.50	3.63	3.75	3.88	4.00

web bearing being about one-third greater than that for ordinary bearing. Owing to the support that the material around the hole receives from the rest of the plate, its bearing value is greater than the compressive strength of the material when not so supported. The safe bearing strength of the rivet on the plate, for ordinary bearing, is assumed to be one and one-half times its compressive strength, and for



(a)



(b)

FIG 11

web bearing the safe bearing strength is assumed to be double the compressive strength of the material.

In deducting the rivet holes, to ascertain the net section of a riveted plate, the diameter of the hole is taken as $\frac{1}{8}$ inch larger than the diameter of the rivet.

As the tensile strength of iron and steel used in the manufacture of rivets, pins, and plates for structural work is more easily determined by tests, and, therefore, better known than either its compressive or shearing strength, it is customary to use this as a basis from which to calculate the bearing value of plates and the shearing strength of rivets and pins.

Good practice assumes that the compressive strength of steel or high-test iron is about thirteen-fifteenths of its tensile strength; that is, if the safe tensile strength of the material per square inch of section is 15,000 pounds, the safe compressive strength may be taken as thirteen-fifteenths of 15,000 = 13,000 pounds.

The bearing strength of the rivet on the plate, for ordinary bearing, is found to be 1.8 times the shearing strength of the rivet, according to the assumptions made in this and the following paragraphs, but it is common in practice to consider the bearing value as twice that for shear, as shown in Table XIII.

16. Shearing Strength of Rivets.—When a rivet shears, the tendency is to cut straight through it across its section, as shown in Fig. 12 (a) and (b). The resistance of the rivet to shear depends on the area of its cross-section.




FIG. 12

The shearing strength is considered to be five-sixths of the compressive strength. For example, the tensile strength is 15,000 pounds and the compressive strength 13,000 pounds, the shearing strength becomes five-sixths of 13,000, or 10,833 pounds per square inch of section.

Where there are only two plates connected, as shown in Fig. 12 (a), the tendency is to cut the rivet on the single plane *a b*. A rivet in this position is said to be in *single shear*.

At (b), the tendency is to cut through the rivet on both the planes *a b* and *c d*; under these conditions the rivet is in *double shear*, and it is evident that, since the rivet will shear across at two places, it will be twice as strong as when the tendency is to shear through only one section.

17. Shearing of Plate.—To prevent the fourth method of failure, the lap should be sufficient to prevent the plate from shearing, as shown in Fig. 9. Since two surfaces have to be sheared, each having an area of $t \times \frac{l}{2}$ (in which *l* equals

the lap), the resistance to shear is $2t \times \frac{l}{2} \times r$, or tlr , where r is the shearing strength of the plate per square inch.

18. A butt joint with a single cover-plate may be considered as two lap joints placed close together, its strength depending on the number of rivets on one side of the butt, or half the entire number of rivets. The cover-plate should have at least the same thickness as the plates to be joined.

19. In a butt joint with two cover-plates, the thickness of each cover-plate should be at least half the thickness of the plates joined. The only difference in the strength of this joint and that having one cover-plate is that the rivets have twice as much shearing resistance.




FIG. 13

It must also be remembered that as the plates connected are in web bearing, they have a greater bearing value than the cover-plates, which are in ordinary bearing.

The methods of calculation are the same for double-, triple-, or quadruple-riveted joints, the entire bearing value and shearing value depending on the number of rivets used.

20. Tensile Strength of Plates.—In Fig. 13, the tensile strength of the plate depends on the net section through the outside row of rivets, as it does also in Fig. 14. The first method, therefore, weakens the plates more than the second by one rivet hole, but both have the same bearing value and the same




FIG. 14

shearing strength, since the number of rivets in each case is the same. In Fig. 15, the bearing and shearing values are the same as in the previous cases, but the plates joined are stronger, since they are weakened by only one rivet hole, for,

before the plate can tear across the section $A-A$, the leading rivet a must fail by shearing or bearing. This counterbalances the weakening of the plate caused by one rivet hole, so that the section $A-A$ is really only weakened by one rivet hole and is as strong as the one through the leading




FIG. 15

rivet a . It will also be seen that the section through d, e , and f is even stronger than either of the other two, since before it can fail the three rivets a, b , and c must fail.

21. The cover-plates, however, have their section reduced by three rivet holes and must therefore be thicker than half the thickness of the plates joined. Knowing the tensile strength of the plate, its breadth, the diameter of the rivet holes, and the unit tensile strength of the steel or iron, the thickness of the cover-plates to be used in a case like Fig. 15 can be found by the formula,

$$t' = \frac{R_t}{2(b - 3d)r_t} \quad (2)$$

in which t' = thickness of one cover-plate;

R_t = tensile strength of the plate;

b = breadth of plate;

d = diameter of rivet hole;

r_t = safe unit tensile strength of steel or iron.

22. Rivets in Single Shapes.—The difficulty in using single shapes for tension members is to provide proper connections at the ends. The arrangement of the rivets should be such as to make the net area as great as possible, so that the efficiency of the metal will be maximum. The rivets, therefore, should be placed symmetrically with respect to the axis of the piece, and the cross-section should be reduced as little as possible, as in Fig. 16 (a), where the cross-section of the plate is reduced by only one or two rivet holes.

When the rivets are arranged as shown in Fig. 16 (*b*), a section is at right angles to the axis of the member cuts two and in most cases three rivet holes, and consequently this design is not as efficient as the one shown in (*a*).




FIG. 16

Angle irons should be attached through both legs to develop the greatest strength and the rivets should be arranged symmetrically as in plates. Fig. 17 shows the detail as it is usually made.

23. Rivets in Compound Sections.—Sections composed of two or more simple shapes riveted together are




FIG. 17

used in cases where the member requires special stiffness. If the end attachment is made by means of a pin, the built member is usually reinforced by pin plates, which reduce the unit pressure on the pin.

In designing pin plates in important members, they are often made strong enough to realize the utmost working capacity of

the member and not merely for the total stress to which the member will be subjected.

24. Joints in Compression.—If it were possible to fit a joint perfectly, the compressive stress would be transmitted across the joint entirely by the plates and the only

TABLE XI
SHEARING VALUE OF RIVETS
Shearing value = area of rivet X allowable shearing stress per square inch

Diameter of Rivet Inch	Area in Square Inches	Single Shear at 6,000 Pounds per Square Inch	Double Shear at 12,000 Pounds per Square Inch	Single Shear at 6,750 Pounds per Square Inch	Double Shear at 13,500 Pounds per Square Inch	Single Shear at 7,500 Pounds per Square Inch	Double Shear at 15,000 Pounds per Square Inch	Single Shear at 9,000 Pounds per Square Inch	Double Shear at 18,000 Pounds per Square Inch	Single Shear at 10,000 Pounds per Square Inch	Double Shear at 20,000 Pounds per Square Inch
$\frac{3}{8}$.1105	663	1,325	746	1,491	828	1,657	994	1,989	1,105	2,209
$\frac{1}{2}$.1964	1,178	2,356	1,325	2,651	1,473	2,945	1,767	3,535	1,964	3,927
$\frac{5}{8}$.3068	1,841	3,682	2,071	4,142	2,301	4,602	2,761	5,522	3,068	6,136
$\frac{3}{4}$.4418	2,651	5,301	2,982	5,964	3,313	6,627	3,976	7,952	4,418	8,836
$\frac{7}{8}$.6013	3,608	7,216	4,059	8,118	4,510	9,020	5,411	10,823	6,013	12,026
1	.7854	4,712	9,425	5,301	10,603	5,891	11,781	7,068	14,137	7,854	15,708

Where the rivets are arranged as shown in Fig. 16 (b), a section at right angles to the axis of the member cuts two and in most cases three rivet holes, and consequently this design is not as efficient as the one shown in (a).




FIG. 16

Angle irons should be attached through both legs to develop the greatest strength and the rivets should be arranged symmetrically, as in plates. Fig. 17 shows the detail as it is usually made.

23. Rivets in Compound Sections.—Sections composed of two or more simple shapes riveted together are




FIG. 17

used in cases where the member requires special stiffness. If the end attachment is made by means of a pin, the built member is usually reinforced by pin plates, which reduce the unit pressure on the pin.

In designing pin plates in important members, they are often made strong enough to realize the utmost working capacity of

the member and not merely for the total stress to which the member will be subjected.

24. Joints in Compression.—If it were possible to fit a joint perfectly, the compressive stress would be transmitted across the joint entirely by the plates and the only

In Table XII, the bearing values between the lower and upper zigzag heavy lines in each group are greater than single shear and less than double shear for the corresponding dimensions, so that in case of single shear, the single-shearing value governs, and in case of double shear, the bearing value governs the design.

The bearing values above and to the right of the upper zigzag heavy lines are greater than double shear for the corresponding dimensions, so that in these cases the shearing values govern the design.

The bearing values below and to the left of the lower zigzag heavy lines are less than single shear, and in these cases the bearing values govern the design.

TABLE XIII
ALLOWABLE STRAINS ON RIVETED WORK

Rivets	Shearing Pounds per Square Inch	Bearing Pounds per Square Inch
Iron rivets in railroad bridges	6,000	12,000
Iron rivets in highway bridges and build- ings	7,500	15,000
Steel rivets in railroad bridges	7,500	15,000
Steel rivets in highway bridges and build- ings	9,000	18,000

EXAMPLE 1.—Two pieces of structural steel are joined by rivets, as shown in Fig. 19. If the tensile strength of the steel is 60,000 pounds per square inch, and a factor of safety of 4 is used, what is the safe strength of this joint?

SOLUTION.—The safe tensile strength of the steel is $60,000 \div 4 = 15,000$ lb. per sq. in. The width of the pieces connected is $2\frac{1}{2}$ in., from which is to be deducted 1 in. for the rivet hole, leaving a net width of $1\frac{1}{2}$ in., which, multiplied by the thickness of the plate, gives a net area of $1\frac{1}{2} \times \frac{3}{8} = .5625$ sq. in. Then, $.5625 \times 15,000 = 8,437$ lb., the strength of the plate.

To determine whether the strength of the rivets is equal to the net section of the plate: Taking the compressive value of the plate as

	1,400	1,750	2,100	2,450	2,800	3,150	3,500	3,850	4,200	4,550	4,900	5,250	5,600	5,950	6,300	6,650	7,000	7,350	7,700	8,050	8,400	8,750	9,100	9,450	9,800	10,150	10,500	10,850	11,200	11,550	11,900	12,250	12,600	12,950	13,300	13,650	14,000	14,350	14,700	15,050	15,400	15,750	16,100	16,450	16,800	17,150	17,500	17,850	18,200	18,550	18,900	19,250	19,600	19,950	20,300	20,650	21,000	21,350	21,700	22,050	22,400	22,750	23,100	23,450	23,800	24,150	24,500	24,850	25,200	25,550	25,900	26,250	26,600	26,950	27,300	27,650	28,000	28,350	28,700	29,050	29,400	29,750	30,100	30,450	30,800	31,150	31,500	31,850	32,200	32,550	32,900	33,250	33,600	33,950	34,300	34,650	35,000	35,350	35,700	36,050	36,400	36,750	37,100	37,450	37,800	38,150	38,500	38,850	39,200	39,550	39,900	40,250	40,600	40,950	41,300	41,650	42,000	42,350	42,700	43,050	43,400	43,750	44,100	44,450	44,800	45,150	45,500	45,850	46,200	46,550	46,900	47,250	47,600	47,950	48,300	48,650	49,000	49,350	49,700	50,050	50,400	50,750	51,100	51,450	51,800	52,150	52,500	52,850	53,200	53,550	53,900	54,250	54,600	54,950	55,300	55,650	56,000	56,350	56,700	57,050	57,400	57,750	58,100	58,450	58,800	59,150	59,500	59,850	60,200	60,550	60,900	61,250	61,600	61,950	62,300	62,650	63,000	63,350	63,700	64,050	64,400	64,750	65,100	65,450	65,800	66,150	66,500	66,850	67,200	67,550	67,900	68,250	68,600	68,950	69,300	69,650	70,000	70,350	70,700	71,050	71,400	71,750	72,100	72,450	72,800	73,150	73,500	73,850	74,200	74,550	74,900	75,250	75,600	75,950	76,300	76,650	77,000	77,350	77,700	78,050	78,400	78,750	79,100	79,450	79,800	80,150	80,500	80,850	81,200	81,550	81,900	82,250	82,600	82,950	83,300	83,650	84,000	84,350	84,700	85,050	85,400	85,750	86,100	86,450	86,800	87,150	87,500	87,850	88,200	88,550	88,900	89,250	89,600	89,950	90,300	90,650	91,000	91,350	91,700	92,050	92,400	92,750	93,100	93,450	93,800	94,150	94,500	94,850	95,200	95,550	95,900	96,250	96,600	96,950	97,300	97,650	98,000	98,350	98,700	99,050	99,400	99,750	100,100	100,450	100,800	101,150	101,500	101,850	102,200	102,550	102,900	103,250	103,600	103,950	104,300	104,650	105,000	105,350	105,700	106,050	106,400	106,750	107,100	107,450	107,800	108,150	108,500	108,850	109,200	109,550	109,900	110,250	110,600	110,950	111,300	111,650	112,000	112,350	112,700	113,050	113,400	113,750	114,100	114,450	114,800	115,150	115,500	115,850	116,200	116,550	116,900	117,250	117,600	117,950	118,300	118,650	119,000	119,350	119,700	120,050	120,400	120,750	121,100	121,450	121,800	122,150	122,500	122,850	123,200	123,550	123,900	124,250	124,600	124,950	125,300	125,650	126,000	126,350	126,700	127,050	127,400	127,750	128,100	128,450	128,800	129,150	129,500	129,850	130,200	130,550	130,900	131,250	131,600	131,950	132,300	132,650	133,000	133,350	133,700	134,050	134,400	134,750	135,100	135,450	135,800	136,150	136,500	136,850	137,200	137,550	137,900	138,250	138,600	138,950	139,300	139,650	140,000	140,350	140,700	141,050	141,400	141,750	142,100	142,450	142,800	143,150	143,500	143,850	144,200	144,550	144,900	145,250	145,600	145,950	146,300	146,650	147,000	147,350	147,700	148,050	148,400	148,750	149,100	149,450	149,800	150,150	150,500	150,850	151,200	151,550	151,900	152,250	152,600	152,950	153,300	153,650	154,000	154,350	154,700	155,050	155,400	155,750	156,100	156,450	156,800	157,150	157,500	157,850	158,200	158,550	158,900	159,250	159,600	159,950	160,300	160,650	161,000	161,350	161,700	162,050	162,400	162,750	163,100	163,450	163,800	164,150	164,500	164,850	165,200	165,550	165,900	166,250	166,600	166,950	167,300	167,650	168,000	168,350	168,700	169,050	169,400	169,750	170,100	170,450	170,800	171,150	171,500	171,850	172,200	172,550	172,900	173,250	173,600	173,950	174,300	174,650	175,000	175,350	175,700	176,050	176,400	176,750	177,100	177,450	177,800	178,150	178,500	178,850	179,200	179,550	179,900	180,250	180,600	180,950	181,300	181,650	182,000	182,350	182,700	183,050	183,400	183,750	184,100	184,450	184,800	185,150	185,500	185,850	186,200	186,550	186,900	187,250	187,600	187,950	188,300	188,650	189,000	189,350	189,700	190,050	190,400	190,750	191,100	191,450	191,800	192,150	192,500	192,850	193,200	193,550	193,900	194,250	194,600	194,950	195,300	195,650	196,000	196,350	196,700	197,050	197,400	197,750	198,100	198,450	198,800	199,150	199,500	199,850	200,200	200,550	200,900	201,250	201,600	201,950	202,300	202,650	203,000	203,350	203,700	204,050	204,400	204,750	205,100	205,450	205,800	206,150	206,500	206,850	207,200	207,550	207,900	208,250	208,600	208,950	209,300	209,650	210,000	210,350	210,700	211,050	211,400	211,750	212,100	212,450	212,800	213,150	213,500	213,850	214,200	214,550	214,900	215,250	215,600	215,950	216,300	216,650	217,000	217,350	217,700	218,050	218,400	218,750	219,100	219,450	219,800	220,150	220,500	220,850	221,200	221,550	221,900	222,250	222,600	222,950	223,300	223,650	224,000	224,350	224,700	225,050	225,400	225,750	226,100	226,450	226,800	227,150	227,500	227,850	228,200	228,550	228,900	229,250	229,600	230,000	230,350	230,700	231,050	231,400	231,750	232,100	232,450	232,800	233,150	233,500	233,850	234,200	234,550	234,900	235,250	235,600	235,950	236,300	236,650	237,000	237,350	237,700	238,050	238,400	238,750	239,100	239,450	239,800	240,150	240,500	240,850	241,200	241,550	241,900	242,250	242,600	242,950	243,300	243,650	244,000	244,350	244,700	245,050	245,400	245,750	246,100	246,450	246,800	247,150	247,500	247,850	248,200	248,550	248,900	249,250	249,600	250,000	250,350	250,700	251,050	251,400	251,750	252,100	252,450	252,800	253,150	253,500	253,850	254,200	254,550	254,900	255,250	255,600	255,950	256,300	256,650	257,000	257,350	257,700	258,050	258,400	258,750	259,100	259,450	259,800	260,150	260,500	260,850	261,200	261,550	261,900	262,250	262,600	262,950	263,300	263,650	264,000	264,350	264,700	265,050	265,400	265,750	266,100	266,450	266,800	267,150	267,500	267,850	268,200	268,550	268,900	269,250	269,600	270,000	270,350	270,700	271,050	271,400	271,750	272,100	272,450	272,800	273,150	273,500	273,850	274,200	274,550	274,900	275,250	275,600	275,950	276,300	276,650	277,000	277,350	277,700	278,050	278,400	278,750	279,100	279,450	279,800	280,150	280,500	280,850	281,200	281,550	281,900	282,250	282,600	282,950	283,300	283,650	284,000	284,350	284,700	285,050	285,400	285,750	286,100	286,450	286,800	287,150	287,500	287,850	288,200	288,550	288,900	289,250	289,600	290,000	290,350	290,700	291,050	291,400	291,750	292,100	292,450	292,800	293,150	293,500	293,850	294,200	294,550	294,900	295,250	295,600	295,950	296,300	296,650	297,000	297,350	297,700	298,050	298,400	298,750	299,100	299,450	299,800	300,150	300,500	300,850	301,200	301,550	301,900	302,250	302,600	302,950	303,300	303,650	304,000	304,350	304,700	305,050	305,400	305,750	306,100	306,450	306,800	307,150	307,500	307,850	308,200	308,550	308,900	309,250	309,600	310,000	310,350	310,700	311,050	311,400	311,750	312,100	312,450	312,800	313,150	313,500	313,850	314,200	314,550	314,900	315,250	315,600	315,950	316,300	316,650	317,000	317,350	317,700	318,050	318,400	318,750	319,100	319,450	319,800	320,150	320,500	320,850	321,200	321,550	321,900	322,250	322,600	322,950	323,300	323,650	324,000	324,350	324,700	325,050	325,400	325,750	326,100	326,450	326,800	327,150	327,500	327,850	328,200	328,550	328,900	329,250	329,600	330,000	330,350	330,700	331,050	331,400	331,750	332,100	332,450	332,800	333,150	333,500	333,850	334,200	334,550	334,900	335,250	335,600	335,950	336,300	336,650	337,000	337,350	337,700	338,050	338,400	338,750	339,100	339,450	339,800	340,150	340,500	340,850	341,200	341,550	341,900	342,250	342,600	342,950	343,300	343,650	344,000	344,350	344,700	345,050	345,400	345,750	346,100	346,450	346,800	347,150	347,500	347,850	348,200	348,550	348,900	349,250	349,600	350,000	350,350	350,700	351,050	351,400	351,750	352,100	352,450	352,800	353,150	353,500	353,850	354,200	354,550	354,900	355,250	355,600	355,950	356,300	356,650	357,000	357,350	357,700	358,050	358,400	358,750	359,100	359,450	359,800	360,150	360,500	360,850	361,200	361,550	361,900	362,250	362,600	362,950	363,300	363,650	364,000	364,350	364,700	365,050	365,400	365,750	366,100	366,450	366,800	367,150	367,500
--	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	--------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------	---------

use of the rivets would be to hold the plates together. But as a perfect fit cannot be insured, the entire stress is assumed to be transmitted by the rivets, and the calculations are the same as for rivets in tension joints. The only



FIG. 18

difference is that there is no deduction made from the cross-section for rivet holes, as the rivet completely fills up the hole and transmits the stress.

It is necessary sometimes to have the longitudinal pitch less than in tension joints to avoid the danger of buckling the plates between the rivets, as in Fig. 18.

25. Tables of Bearing Values of Riveted Plates and Shearing Values of Rivets.—In order to avoid the necessity of calculating the shearing value of the rivets and the bearing value of the riveted plates and rolled sections, Tables XI and XII have been prepared. It will be noticed that the areas and shearing values for both double and single shear are given in Table XI for rivets from $\frac{3}{8}$ inch to 1 inch in diameter, using unit allowable shearing stresses of 6,000, 6,750, 7,500, and 9,000 pounds for single shear, and double these amounts for double shear.

Table XII gives the bearing values of riveted plates for different thicknesses of plate and unit allowable bearing stresses of 12,000, 13,500, 15,000, and 18,000 pounds.

The usual allowable strains, in pounds per square inch, on riveted work are given in Table XIII.

26. In designing a riveted joint, it is necessary to calculate the number of rivets required to resist the shear and the number required to provide sufficient bearing on the plate. The greater value must be adopted as the number of rivets to be used. By dividing the total tensile stress in the bar by the values taken from Tables XI and XII, the number of rivets required for bearing and the number for shearing are obtained.

In Table XII, the bearing values between the lower and upper zigzag heavy lines in each group are greater than single shear and less than double shear for the corresponding dimensions, so that in case of single shear, the single-shearing value governs, and in case of double shear, the bearing value governs the design.

The bearing values above and to the right of the upper zigzag heavy lines are greater than double shear for the corresponding dimensions, so that in these cases the shearing values govern the design.

The bearing values below and to the left of the lower zigzag heavy lines are less than single shear, and in these cases the bearing values govern the design.

TABLE XIII
ALLOWABLE STRAINS ON RIVETED WORK

Rivets	Shearing Pounds per Square Inch	Bearing Pounds per Square Inch
Iron rivets in railroad bridges	6,000	12,000
Iron rivets in highway bridges and build- ings	7,500	15,000
Steel rivets in railroad bridges	7,500	15,000
Steel rivets in highway bridges and build- ings	9,000	18,000

EXAMPLE 1.—Two pieces of structural steel are joined by rivets, as shown in Fig. 19. If the tensile strength of the steel is 60,000 pounds per square inch, and a factor of safety of 4 is used, what is the safe strength of this joint?

SOLUTION.—The safe tensile strength of the steel is $60,000 \div 4 = 15,000$ lb. per sq. in. The width of the pieces connected is $2\frac{1}{2}$ in., from which is to be deducted 1 in. for the rivet hole, leaving a net width of $1\frac{1}{2}$ in., which, multiplied by the thickness of the plate, gives a net area of $1\frac{1}{2} \times \frac{3}{8} = .5625$ sq. in. Then, $.5625 \times 15,000 = 8,437$ lb., the strength of the plate.

To determine whether the strength of the rivets is equal to the net section of the plate: Taking the compressive value of the plate as

thirteen-fifteenths of 15,000 lb., or 13,000 lb. per sq. in., and the rivets being in ordinary bearing, the safe bearing strength is $13,000 \times 1\frac{1}{4} = 19,500$ lb. per sq. in. of bearing area. The bearing area is $\frac{7}{8} \times \frac{3}{4} = .328$ sq. in.; therefore, the safe bearing strength for one rivet is $19,500 \times .328 = 6,396$ lb., and for the two it is $2 \times 6,396 = 12,792$ lb.

The shearing strength of the steel is five-sixths of 13,000 = 10,833 lb. per sq. in. The area of a $\frac{7}{8}$ -in. rivet is .601 sq. in., which, multiplied by 10,833, gives 6,510 lb., the shearing strength of one rivet. The total resistance to shear of the rivets in the joint is, therefore, $6,510 \times 2 = 13,020$ lb.

The safe resistance of the three elements entering into the strength of the joint is, therefore, as follows: Resistance of net section of the plate = 8,437 lb., bearing value of the plate = 12,792 lb.; shearing strength of the two rivets = 13,020 lb.; from which it is easily seen that the strength of the joint is that of the net section of the plate, 8,437 lb. Ans.

Since the bearing value of the plate and the shearing strength of the rivets are considerably in excess of this amount, it appears that the rivets are large for the joint, and it is probable that $\frac{3}{4}$ -in. rivets would give better results.




FIG 19

EXAMPLE 2.—Determine the safe strength of the riveted joint shown in Fig. 20, in which the plates and rivets each have a safe tensile strength of 16,000 pounds per square inch.

SOLUTION.—The safe tensile strength of the material being 16,000 lb., the safe compressive strength is thirteen-fifteenths of 16,000 lb., or 13,867 lb., and the shearing strength of the rivets is five-sixths of 13,867, or 11,556 lb. per sq. in. of section. The area of the section of a $\frac{7}{8}$ -in. rivet is .601 sq. in.; therefore, the total shearing strength of the three rivets, each of which is in double shear, is $2 \times .601 \times 11,556 \times 3 = 41,670$ lb.

The two outside plates are in ordinary bearing, and their bearing

value is $1\frac{1}{2} \times 13,867 = 20,800$ lb. per sq. in. There are three rivet holes in each plate, each with a bearing area of $\frac{3}{8} \times \frac{7}{8} = .328$ sq. in.; the total bearing strength of the two plates is, therefore, $20,800 \times .328 \times 3 \times 2 = 40,934$ lb.

The bearing value of the central or web-bearing plate at one rivet hole is $2 \times 13,867 = 27,734$ lb. per sq. in., and the bearing area is $\frac{3}{4} \times \frac{7}{8} = .656$ sq. in.; the total bearing strength for the three rivets is, therefore, $27,734 \times .656 \times 3 = 54,580$ lb.




FIG. 20

The safe tensile strength of the central plate is equal to its net section multiplied by 16,000, the safe unit tensile strength of the material. The net width of the plate is $3 - 1 = 2$ in., and its net area, $2 \times \frac{3}{4} = 1.5$ sq. in.; therefore, the safe strength is $1.5 \times 16,000 = 24,000$ lb. The strength of the two outside plates, calculated in the same manner, is found to be 24,000 lb. also; therefore, it is evident that, since the strength of the net section of the plate is much less than either the strength of the rivets or the bearing value of the plates, it determines the strength of the joint, which is 24,000 lb. Ans.

EXAMPLE 3.—The lower chord of a roof truss is made up of two angles, as shown in Fig. 21. A butt joint in this member is reinforced by the vertical splice plates *a*, *b*, and *d*, and a horizontal plate *c*. Calculate the number of $\frac{3}{4}$ -inch rivets to be used, the full safe strength of the material being realized, using a unit tensile stress of 15,000 pounds, for angles and plates.

SOLUTION.—The sectional area of a $4'' \times 3\frac{1}{2}'' \times \frac{3}{8}''$ angle is 2.67 sq. in. The cross-section of the two angles is $2.67 \times 2 = 5.34$ sq. in. If the rivets are staggered in the two legs of the angles, their section will be reduced by two rivet holes, or $2 \times \frac{7}{8} \times \frac{3}{8} = .65625$ sq. in. This leaves a net sectional area of 4.68375 sq. in. Since the unit tensile stress is 15,000 lb., the total stress in the joint is $4.68375 \times 15,000 = 70,256$ lb., which stress must be taken up by the four plates *a*, *b*, *c*, and *d*.

First determine the number of rivets in the horizontal plate *c*. The net section of this plate = $(7\frac{1}{4} \times \frac{3}{8}) - (2 \times \frac{7}{8} \times \frac{3}{8}) = 2.0625$ sq. in., and

its resistance is $2.0625 \times 15,000 = 30,937$ lb. Using the usual unit shearing stress of iron rivets in buildings, which is 7,500 lb., the value of a $\frac{3}{4}$ -in. rivet in single shear will be found, from Table XI, to be 3,313. Therefore, the number of rivets required in the plate c is $30,937 \div 3,313 \approx 9$; but to make the joint symmetrical, ten rivets must be used, five being placed on each side, at a pitch of 4 in., the end distance being $1\frac{1}{2}$ in., and the distance from center of rivet to the butt joint $1\frac{1}{2}$ in., as in Fig. 21.




FIG. 21

Next ascertain whether the resistance of plates a , b , and d is sufficient to resist the remaining stress, not taken up by c . This equals $70,256 - 30,937 = 39,319$ lb. The net section of plate $d = (4 \times \frac{3}{4}) - (\frac{1}{2} \times \frac{3}{4}) = 1.172$ sq. in. The net section of a and $b = 2 \times [(3.5 \times \frac{3}{4}) - (\frac{1}{2} \times \frac{3}{4})] = 1.968$ sq. in. The total net section of these three plates is, therefore, $1.968 + 1.172 = 3.14$ sq. in., and their resistance equals $3.14 \times 15,000 = 47,100$ lb., which more than equals the stress 39,319 lb.

Now calculate the number of rivets through the vertical flanges and plates. The bearing values of these vertical members, taken from Table XII, are as follows:

Three splice plates	d in web bearing $4,219 \times 1\frac{1}{2} =$	5,625 lb.
	a and b in ordinary bearing	8,438 lb.
	Sum	14,063 lb.
Two angle legs in web bearing		11,250 lb.
Rivets	in double shear in one plate d	6,627 lb.
	in single shear in two plates a and b	6,627 lb.
	Sum	13,254 lb.
Rivet in double shear in two angle legs		13,254 lb.

From the above, it will be seen that the value 11,250 is the least and therefore it governs the design. The number of rivets through these members is $47,100 \div 11,250 = 4$, which are staggered with respect to those in the horizontal members.

EXAMPLE 4.—Fig. 22 represents the lower end of the main strut in a Fink roof truss, which is connected by means of a pin to the tension members. Each channel is reinforced by a pin plate, as shown. Determine the number of $\frac{3}{4}$ -inch rivets to be used in each pin plate, the allowable unit shearing stress being 7,500 pounds.

The detailing is to be done for the actual stress to which the member is subjected, the total compressive stress in the member being 48,000 pounds.

SOLUTION.—The distribution of stresses between the pin plate and channel is in direct proportion to their respective bearings on the pin. Hence, the amount of stress in one pin plate = $\frac{3 \times .5625}{3 \times (.5625 + .32)} \times \frac{48,000}{2} = 15,288$ lb., the thickness of the channel web being .32 in.

The shearing value of a $\frac{3}{4}$ -in. rivet in single shear is found, from Table XI, to be 3,313 and the bearing value from Table XII of a $\frac{3}{4}$ -in. rivet in ordinary bearing in a $\frac{5}{16}$ -in., or .3125-in. plate, which is nearly the thickness of the web, is 3,516. From this it will be seen that the shearing value is less than the bearing value and therefore governs the design. The number of rivets, then, is $15,288 \div 3,313 = 4.6$, or 5; hence, in order to make the joint symmetrical, six rivets in three rows will be used, two rows above the pin and one below, as shown in Fig. 22. Ans.

EXAMPLES FOR PRACTICE

1. What are the safe strengths of $\frac{7}{8}$ -, $\frac{3}{4}$ -, and $\frac{5}{8}$ -inch rivets, in double shear, and also in single shear,




FIG. 22

assuming that the safe tensile strength of the material used in their manufacture is 15,000 pounds per square inch of section?

ANS. {	DIAMETER OF RIVET	DOUBLE SHEAR	SINGLE SHEAR
	INCH	POUNDS	POUNDS
{	$\frac{1}{2}$	13,028	6,514
	$\frac{3}{8}$	9,572	4,786
	$\frac{5}{16}$	6,648	3,324

2. What pulling force will two pieces of $\frac{3}{4}'' \times 2\frac{1}{2}''$ bar safely resist, provided that they are connected at the ends by two $\frac{3}{4}$ -inch rivets, as shown in Fig. 23? The safe tensile strength of the material in rivets and bars is 15,000 pounds.




FIG. 23

material is 20,000 pounds per square inch? Ans. 245,400 in.-lb.

4. It is necessary to construct the connection of a tension member as shown in Fig. 24. What is the safe load that this member will




FIG. 24

carry, if the safe tensile strength of the material in both the rivets and bars is 18,000 pounds per square inch? Ans. 11,250 lb.

PIN CONNECTIONS

COMPARISON WITH RIVETED CONNECTIONS

27. While riveted connections make a stiffer structure and one that is less liable to accident from the failure of a single member, pin connections can be more satisfactorily designed since they are almost free from secondary stresses. The riveted system generally requires more material than

the pin system and the latter requires more skilled workmanship. The pin system is the cheaper for a long span but for a short span it is sometimes more expensive. Good results can be obtained by either system, and the item of cost will usually be the controlling factor.

METHODS OF FAILURE

28. A pin is subject to strain in three ways: by shearing, by bending, and by crushing of the plates. Frequently, the first is not considered, as the size of pin required to resist the bending and bearing stresses generally exceeds that required for the shear.

The usual stresses allowed for pins, in pounds per square inch, are given in Table XIV.

TABLE XIV
ALLOWABLE STRESSES ON PINS

Kind of Pin	Shearing Pounds per Square Inch	Bearing Pounds per Square Inch	Bending Pounds per Square Inch
Iron pins, railroad bridges	7,500	12,000	15,000
Iron pins, highway bridges and buildings	9,000	15,000	18,000
Steel pins, railroad bridges	9,000	15,000	18,000
Steel pins, highway bridges and buildings	11,250	18,000	22,500

CALCULATIONS FOR RESISTANCE

29. Shearing.—As the shearing strength of a pin depends on its cross-section, the method of calculating this value is the same as for rivets, and the maximum shear at any section on the pin is equal to the square root of the sum of the squares of the horizontal and vertical shears at that point.

The shearing values of pins of different diameters are given in Table XV, the allowable stresses given in the previous article being used.

TABLE XV
SHEARING VALUES OF PINS

Shearing value = area of pin × shearing stress per square inch

Diameter of Pin Inches	Area of Pin Square Inches	Shearing Value at 1,000 Pounds per Square Inch Pounds	Shearing Value at 7,500 Pounds per Square Inch Pounds	Shearing Value at 9,000 Pounds per Square Inch Pounds	Shearing Value at 11,250 Pounds per Square Inch Pounds
1 ⁷ / ₈	1.62	1,620	12,150	14,600	18,200
1 ¹¹ / ₁₆	2.24	2,240	16,800	20,200	25,200
1 ¹³ / ₁₆	2.95	2,950	22,100	26,550	33,200
2 ¹ / ₈	3.76	3,760	28,200	33,800	42,300
2 ¹ / ₁₆	4.67	4,670	35,000	42,000	52,500
2 ¹ / ₈	5.67	5,670	42,500	51,000	63,800
2 ¹ / ₄	6.78	6,780	50,850	61,000	76,300
3 ¹ / ₈	7.98	7,980	59,850	71,800	89,800
3 ¹ / ₄	9.28	9,280	69,600	83,500	104,400
3 ¹ / ₂	10.68	10,680	80,100	96,100	120,150
4 ¹ / ₈	12.18	12,180	91,350	109,600	137,000
4 ¹ / ₄	15.03	15,030	112,700	135,300	169,100
4 ¹ / ₂	16.80	16,800	126,000	151,200	189,000
5 ¹ / ₈	18.66	18,660	140,000	167,900	209,900
5 ¹ / ₄	22.69	22,690	170,150	204,200	255,200
5 ¹ / ₂	24.85	24,850	187,000	224,000	280,000
6 ¹ / ₈	27.11	27,110	203,000	244,000	305,000
6 ¹ / ₄	28.27	28,270	212,000	254,000	318,000
6 ¹ / ₂	30.68	30,680	230,000	276,000	345,000
7 ¹ / ₈	33.18	33,180	249,000	299,000	373,000
7 ¹ / ₄	35.79	35,790	268,000	322,000	403,000
7 ¹ / ₂	38.48	38,480	289,000	346,000	433,000
8 ¹ / ₈	44.18	44,180	331,000	398,000	497,000
8 ¹ / ₄	50.27	50,270	377,000	452,000	568,000
8 ¹ / ₂	56.75	56,750	426,000	511,000	638,000
9 ¹ / ₈	63.62	63,620	477,000	573,000	716,000
9 ¹ / ₄	70.88	70,880	532,000	638,000	797,000
10 ¹ / ₈	78.54	78,540	589,000	707,000	884,000
11 ¹ / ₈	95.03	95,030	712,000	855,000	1,069,000
12 ¹ / ₈	113.10	113,100	848,000	1,018,000	1,272,000

30. Bending.—Pins, when used to connect the several members of a structure, besides being subjected to shearing in the same manner as rivets, may be required to resist heavy bending stresses; they may then be regarded as solid cylindrical beams and calculated to resist the greatest bending moment that may come on them.

Take, for example, the pin in Fig. 25, which connects the three tension bars *a*, *a*, and *c*; the pull of the two bars *a*, *a*,




FIG. 25

both acting in the same direction, is transmitted to the bar *c* by means of the pin. The stress on each bar *a* is 30,000 pounds, consequently the stress on the bar *c* must be 60,000 pounds. Assuming a maximum unit stress of 15,000 pounds per square inch, it is desired to find what diameter of pin is required to resist the bending moment produced by the stresses exerted on it.




FIG. 26

In calculating the bending moment on a pin, the forces acting on it through the several members are considered as being applied at the center of the bearings. In Fig. 25, the distance between the centers of the bearings of the members is 4 inches, and by referring to the diagram, Fig. 26, it is seen that the greatest bending moment, which is at *c*, is equal to $30,000 \times 4 = 120,000$ inch-pounds.

Having found the greatest bending moment on the pin, it is necessary to determine its diameter, in order that its resisting moment may equal the moment of the bending stresses.

In Table I in *Properties of Sections*, the section modulus of a circular section is found to be

$$S = \frac{\pi d^3}{32} = .098 d^3$$

the allowable unit stress on the material is $s = 15,000$ pounds per square inch, and the bending moment is $M = 120,000$ inch-pounds; substituting these values in the formula $M = sS$, gives $120,000 = 15,000 \times .098 d^3$, from which

$$d^3 = \frac{120,000}{15,000 \times .098} = 81.63$$

The diameter of the pin is, therefore, $d = \sqrt[3]{81.63} = 4.338 = 4\frac{3}{8}$ inches, nearly.

31. Table of Maximum Bending Moments on Pins.

To avoid the necessity of calculating the resisting moment of pins, Table XVI, Maximum Bending Moments on Pins, will be found convenient. This table gives the resisting moments of pins from $1\frac{1}{8}$ to 12 inches in diameter, calculated for allowable fiber stresses of 1,000, 15,000, 18,000, and 22,500 pounds per square inch.

The values for a stress of 1,000 pounds per square inch are given so that the values for other fiber stresses may be determined. For instance, it is desired to find the bending moment on a $4\frac{3}{8}$ -inch pin for a fiber stress of 20,000 pounds per square inch. The bending moment for a fiber stress of 18,000 pounds per square inch is 147,960 and for 1,000 pounds it is 8,220; then the bending moment, allowing a fiber stress of 20,000 pounds per square inch, is $147,960 + 8,220 \times 2 = 164,400$ inch-pounds.

32. Resultant Moment of Several Stresses.

—When a pin is used at a joint at which several members, extending in different directions, meet, as shown in Fig. 27, it is necessary to combine the stresses so as to find the resultant that

TABLE XVI

MAXIMUM BENDING MOMENTS ON PINS

*Bending moment = diameter³ × .0982 × allowable fiber stress
per square inch*

Diameter of Pin Inches	Area of Pin Square Inches	Moments, in Inch-Pounds, for Fiber Stresses of				Diameter of Pin Inches
		1,000 Pounds per Square Inch	15,000 Pounds per Square Inch	18,000 Pounds per Square Inch	22,500 Pounds per Square Inch	
1 ⁷ / ₁₆	1.62	291	4,370	5,240	6,550	1 ⁷ / ₁₆
1 ¹¹ / ₁₆	2.24	471	7,070	8,480	10,610	1 ¹¹ / ₁₆
1 ¹⁵ / ₁₆	2.95	713	10,700	12,840	16,050	1 ¹⁵ / ₁₆
2 ³ / ₁₆	3.76	1,026	15,400	18,480	23,110	2 ³ / ₁₆
2 ⁷ / ₁₆	4.67	1,420	21,310	25,580	31,970	2 ⁷ / ₁₆
2 ¹¹ / ₁₆	5.67	1,904	28,570	34,280	42,850	2 ¹¹ / ₁₆
2 ¹⁵ / ₁₆	6.78	2,487	37,310	44,770	55,960	2 ¹⁵ / ₁₆
3 ³ / ₁₆	7.98	3,178	47,670	57,200	71,500	3 ³ / ₁₆
3 ⁷ / ₁₆	9.28	3,986	59,790	71,750	89,680	3 ⁷ / ₁₆
3 ¹¹ / ₁₆	10.68	4,920	73,810	88,570	110,710	3 ¹¹ / ₁₆
3 ¹⁵ / ₁₆	12.18	5,990	89,860	107,830	134,790	3 ¹⁵ / ₁₆
4 ³ / ₈	15.03	8,220	123,300	147,960	185,000	4 ³ / ₈
4 ⁵ / ₈	16.80	9,713	145,700	174,800	218,500	4 ⁵ / ₈
4 ⁷ / ₈	18.66	11,373	170,600	204,700	255,900	4 ⁷ / ₈
5 ³ / ₈	22.69	15,246	228,700	274,400	343,000	5 ³ / ₈
5 ⁵ / ₈	24.85	17,473	262,100	314,500	393,100	5 ⁵ / ₈
5 ⁷ / ₈	27.11	19,906	298,600	358,300	447,900	5 ⁷ / ₈
6	28.27	21,206	318,100	381,700	477,100	6
6 ¹ / ₄	30.68	23,966	359,500	431,400	539,300	6 ¹ / ₄
6 ¹ / ₂	33.18	26,960	404,400	485,300	606,600	6 ¹ / ₂
6 ³ / ₄	35.79	30,193	452,900	543,500	679,400	6 ³ / ₄
7	38.48	33,673	505,100	606,100	757,700	7
7 ¹ / ₂	44.18	41,420	621,300	745,500	931,900	7 ¹ / ₂
8	50.27	50,266	754,000	904,800	1,131,000	8
8 ¹ / ₂	56.75	60,293	904,400	1,085,200	1,356,600	8 ¹ / ₂
9	63.62	71,566	1,073,500	1,288,200	1,610,300	9
9 ¹ / ₂	70.88	84,173	1,262,600	1,515,100	1,893,900	9 ¹ / ₂
10	78.54	98,173	1,472,600	1,767,100	2,208,900	10
11	95.03	130,673	1,960,100	2,352,100	2,940,100	11
12	113.10	169,646	2,544,700	3,053,600	3,817,000	12

gives the greatest bending moment. This is conveniently done by first resolving the stresses on each member into vertical and horizontal components, and calculating the bending moments produced in each of these directions by all the corresponding components. The maximum bending moment is then given by the resultant of these two bending moments.




FIG 27

The details of the method for finding the maximum bending stress on a pin, will be made clear by a study of the following illustrative example:

Fig. 28 shows one of the lower joints of a roof truss. At this joint there are four sets of members, two of which act in a horizontal, while one acts in a vertical direction; since they already act in the directions of the required components, these forces need not be resolved. However, there is one inclined member in which there is a compressive stress of 40,000 pounds, which stress must be resolved into its vertical and horizontal components. Draw the line ab parallel to the strut and of such a length as to represent the magnitude of the stress. From a , draw the horizontal line ac intersecting the vertical line at the point c . The

direction of the forces around the triangle is shown by the arrows. On measuring the line ac , the horizontal component of the stress in ab is found to be 20,000 pounds, while the vertical component of the stress is found to be 34,650 pounds.

Having determined these components, a diagram showing all the horizontal stresses acting on the pin and tending to




FIG. 28

bend it, and also another showing all the vertical forces, should be drawn as illustrated in Fig. 29 (a) and (b), the distance from center to center of the members being taken from the detail plan of the joint, Fig. 28. It must always be remembered that, in accordance with the principles of equilibrium, the sum of the resultants of the forces acting on the pin in any one direction must equal the sum of all

the resultants acting in the opposite direction; otherwise, the pin will move in the direction of the greater sum, and the structure will fail. Thus, from Fig. 28, it is seen that the vertical component of the stress in BC acts in an opposite direction to the stress in the member CD , while the horizontal component acts in opposition to the stress in the member AB and in the same direction as the stress in DE . This makes the algebraic sum of all the components

in either the horizontal or vertical direction equal to zero, and fulfills the condition of equilibrium.

The resultant of the vertical and horizontal bending moments may also be calculated by the rule given for finding the length of the hypotenuse of a right-triangle; for example, in this case the lengths of the sides are represented by the horizontal bending moment of 40,000 inch-pounds, and the vertical bending




FIG. 29

moment of 69,300 inch-pounds; the resultant bending moment is, therefore, $\sqrt{40,000^2 + 69,300^2} = 80,015$ inch-pounds.

In order to determine the required size of pin for this joint, assume a safe fiber stress of 15,000 pounds per square inch; then, by referring to Table XVI, it is seen that a pin $3\frac{1}{8}$ inches in diameter, under a fiber stress of 15,000 pounds per square inch, has a resisting moment of 89,860 inch-pounds, which is slightly greater than the value required by the conditions.

The pin must also be proportioned for the bearing value, as explained in Art. 34.

33. The Graphic Method of Obtaining Bending Moment.—This method will be explained by applying it to the pin-connected joint shown in Fig. 28. A diagrammatic representation of the pin with the loads upon it is shown in isometric perspective in Fig. 30 (a), ab being laid off at an angle of 45° with the horizontal. The distances between




FIG. 30

loads are laid off on ab to the scale $\frac{1}{4}$ inch = 1 inch. In (b), the horizontal load line is laid off from 1 to 2, 2 to 3, 3 to 1, 1 to 4, 4 to 5, and 5 to 1, the scale being $\frac{1}{8}$ inch = 800 pounds. The vertical load line is laid off from 1 to 6, 6 to 7, and from 7 to 6. Take a line H , located in a

[The page contains several lines of extremely faint, illegible text.]

The polygon for the vertical bending moment is obtained in a similar manner, kj and kl being drawn parallel to $7a$ and $6a$ respectively. The maximum vertical bending moment occurs at the point k , or the center of the pin, and it is evident that the greatest resultant moment is at this point. It is equal to the resultant of kj and kl , or kk , multiplied by H . Measuring kk , it is found to equal 4 inches, and $20,000 \times 4 = 80,000$ inch-pounds. This result is practically correct, for the amount obtained by computation, in Art. 32, was 80,015 inch-pounds.

34. Bearing Value.—The bearing or crushing value of a pin depends on its bearing area on the bars or plates composing the joint. This area is considered as the product of the diameter of the pin and the thickness of the plate.

TABLE XVII
BEARING VALUES OF PIN PLATES FOR 1 INCH
THICKNESS OF PLATE
Bearing value = diameter of pin × thickness of plate × stress per square inch

Diameter of Pin Inches	Bearing Value at 1,000 Pounds per Square Inch Pounds	Bearing Value at 12,000 Pounds per Square Inch Pounds	Bearing Value at 15,000 Pounds per Square Inch Pounds	Bearing Value at 18,000 Pounds per Square Inch Pounds	Diameter of Pin Inches
1 ⁷ / ₈	1,437.5	17,200	21,600	25,900	1 ⁷ / ₈
1 ¹¹ / ₈	1,687.5	20,200	25,300	30,400	1 ¹¹ / ₈
1 ⁵ / ₈	1,937.5	23,200	29,100	34,900	1 ⁵ / ₈
2 ³ / ₈	2,187.5	26,200	32,800	39,400	2 ³ / ₈
2 ⁷ / ₈	2,437.5	29,200	36,600	43,900	2 ⁷ / ₈
2 ¹ / ₈	2,687.5	32,200	40,300	48,400	2 ¹ / ₈
2 ⁵ / ₈	2,937.5	35,200	44,100	52,900	2 ⁵ / ₈
3 ³ / ₈	3,187.5	38,200	47,800	57,400	3 ³ / ₈
3 ⁷ / ₈	3,437.5	41,200	51,600	61,900	3 ⁷ / ₈
3 ¹ / ₈	3,687.5	44,200	55,300	66,400	3 ¹ / ₈
3 ⁵ / ₈	3,937.5	47,200	59,100	70,900	3 ⁵ / ₈
4 ³ / ₈	4,375.0	52,500	65,600	78,750	4 ³ / ₈
4 ⁵ / ₈	4,625.0	55,500	69,400	83,300	4 ⁵ / ₈
4 ⁷ / ₈	4,875.0	58,500	73,100	87,750	4 ⁷ / ₈
5 ³ / ₈	5,375.0	64,500	80,600	96,750	5 ³ / ₈
5 ⁵ / ₈	5,625.0	67,500	84,400	101,250	5 ⁵ / ₈
5 ⁷ / ₈	5,875.0	70,500	88,100	105,750	5 ⁷ / ₈
6	6,000.0	72,000	90,000	108,000	6
6 ¹ / ₄	6,250.0	75,000	93,800	112,500	6 ¹ / ₄
6 ¹ / ₂	6,500.0	78,000	97,500	117,000	6 ¹ / ₂
6 ³ / ₄	6,750.0	81,000	101,300	121,500	6 ³ / ₄
7	7,000.0	84,000	105,000	126,000	7
7 ¹ / ₂	7,500.0	90,000	112,500	135,000	7 ¹ / ₂
8	8,000.0	96,000	120,000	144,000	8
8 ¹ / ₂	8,500.0	102,000	127,500	153,000	8 ¹ / ₂
9	9,000.0	108,000	135,000	162,000	9
10	10,000.0	120,000	150,000	180,000	10
11	11,000.0	132,000	165,000	198,000	11
12	12,000.0	144,000	180,000	216,000	12

Table XVII gives the bearing values of pins on a plate 1 inch thick, using allowable bearing values of 1,000, 12,000, 15,000, and 18,000 pounds per square inch. The use of the column giving bearing values at 1,000 pounds per square inch is similar to that of the corresponding column in Table XVI, as previously explained. The application of this table may be illustrated by the following example. In Fig. 28, assume the thickness of the horizontal bars resisting 60,000 pounds to be $1\frac{1}{2}$ inches and those having a stress of 40,000 pounds to be $\frac{3}{4}$ inch. The bearing value for a 1-inch plate will be one and one-third times as great as that for a $\frac{3}{4}$ -inch plate; hence, $(40,000 \div 2) \times 1\frac{1}{3} = 26,667$ pounds represents the bearing value for a 1-inch plate corresponding to 20,000 pounds for a $\frac{3}{4}$ -inch plate. From Table XVII, it is seen that a $1\frac{1}{8}$ -inch pin, having a safe unit fiber stress of 15,000 pounds, is sufficient to provide the required bearing, and as a $3\frac{1}{8}$ -inch pin is to be used, it will give ample bearing value. For a $1\frac{1}{2}$ -inch plate, the bearing value is one and one-fourth times as much as for a 1-inch plate, and therefore, the value corresponding to the bearing that would be required for a 1-inch plate is $(60,000 \div 2) \div 1\frac{1}{2} = 24,000$ pounds. Assuming a fiber stress of 15,000 pounds, the size of pin required to provide the bearing is $1\frac{1}{4}$ inches. In the same manner, the size of pin required to give the bearing value for each plate may be determined.

35. As an example in the design of a pin, the joint shown in Fig. 31 will be considered. It is first necessary to determine the horizontal and vertical components of the oblique forces. These components may be obtained graphically or by computation, but in this case the latter method will be followed.

The member *b* in the frame diagram of the joint shown in Fig. 32 (*a*), is at an angle of 15° with the horizontal. The vertical component of this force will be equal to the product of the sine of 15° and the stress in the member, while the horizontal component will equal the stress multiplied by





FIG. 31





FIG. 32

the cosine of 15° . From a table of natural sines and cosines, the following values are obtained:

$$\sin 15^\circ = .258819$$

$$\cos 15^\circ = .965926$$

Then the vertical component of the force is $120,000 \times .258819 = 31,058$ pounds, and the horizontal component equals $120,000 \times .965926 = 115,910$ pounds. The values for the other angles, obtained from the table, are:

$$\sin 30^\circ = .500000$$

$$\cos 30^\circ = .866025$$

$$\sin 45^\circ = .707107$$

$$\cos 45^\circ = .707107$$

The components of the oblique force of 18,480 pounds are:

$$\text{Vertical component} = 18,480 \times .866025 = 16,004 \text{ pounds}$$

$$\text{Horizontal component} = 18,480 \times .500000 = 9,240 \text{ pounds}$$

For the oblique force of 66,556 pounds the horizontal and vertical components are equal, their amount being $66,556 \times .707107 = 47,062$ pounds.

The action of the horizontal forces and components on the pin is illustrated in Fig. 32 (*b*), and from this diagram the horizontal bending moment may be computed. The bending moment about the point *b* due to the horizontal forces is equal to $29,804 \times 1\frac{5}{8} = 48,432$ inch-pounds; about the point *c*, the bending moment is $(29,804 \times 2\frac{1}{8}) - (57,955 \times 1\frac{5}{8}) = 11,483$ inch-pounds; and about the point *d*, the horizontal bending moment is $(57,955 \times 2\frac{3}{8}) - [(29,804 \times 4) + (4,620 \times 1\frac{1}{8})] = 13,518$ inch-pounds.

There is no vertical bending moment about the points *a* and *b*, as will be observed from the diagram at (*c*), but about the points *c* and *d* it is as follows:

$$\text{About } c, 15,529 \times 1\frac{5}{8} = 20,382 \text{ inch-pounds}$$

$$\text{About } d, (15,529 \times 2\frac{3}{8}) + (8,002 \times 1\frac{1}{8}) = 45,383 \text{ inch-pounds}$$

It is readily determined by observation that the maximum bending moment will be the horizontal moment of


48,432 inch-pounds at the point *b*, or the resultant of the horizontal and vertical moments at the point *d*. This resultant equals $\sqrt{13,518^2 + 45,383^2} = 47,353$ inch-pounds; consequently, this is the maximum bending moment and it occurs at the point *d*. The size of pin required to resist this bending moment may be determined by the method explained in Art. 30, or from Table XVI. Considering a safe fiber stress of 22,500 pounds per square inch, it is found from the table that a $2\frac{1}{8}$ -inch pin must be used to supply the required resisting moment. It is readily observed that the shear between the points *a* and *b* is equal to 29,804 pounds; between *b* and *c* it is the resultant of the horizontal shear of $57,955 - 29,804 = 28,151$ pounds and the vertical shear of 15,529 pounds. Between *c* and *d* the vertical and horizontal shears are each equal to 23,531 pounds and their resultant, or $\sqrt{2} \times 23,531 = 33,278$ pounds, the maximum shear on the pin. From Table XV, it is found that a $2\frac{3}{8}$ -inch pin having a safe unit shearing strength of 11,250 pounds will be sufficient to resist the shear.

It is next necessary to consider the bearing value of the pin on the different members of the joint. In the member carrying 120,000 pounds, there are two $1\frac{7}{8}$ -inch bars, each having 60,000 pounds stress. The bearing value of such a bar will be equivalent to that of a 1-inch bar having a stress of $60,000 \div 1\frac{7}{8} = 32,000$ pounds. Therefore, referring to Table XVII, it is seen that a $1\frac{1}{8}$ -inch pin having a safe unit bearing value of 18,000 pounds will supply the required resistance. The size of pin necessary to give the bearing value required by the other members of the joint may be computed, but it will be found that a $1\frac{1}{8}$ inch pin is sufficient in each case. From these calculations for bending moment, shear, and bearing value, it is found that a $2\frac{1}{8}$ -inch pin will be required for this joint.

DETAILS OF DESIGN

36. Position of Pins.—Pins are not placed at the centers of gravity of the horizontal sections or those inclined to the horizontal less than 45° , through which they pass, but at a

TABLE XVIII
STANDARD PINS AND NUTS



<i>D</i> Diameter of Pin Inches	<i>T</i> Diameter of Thread Inches	<i>S</i> Length of Thread Inches	<i>A</i> Short Diameter of Nut Inches	<i>B</i> Long Diameter of Nut Inches	Weight of One Nut Pounds
$1\frac{3}{8}$	1	$1\frac{1}{2}$	$1\frac{3}{4}$	2	
$1\frac{7}{8}$	1	$1\frac{1}{2}$	$1\frac{3}{4}$	2	
$1\frac{1}{2}$	$1\frac{1}{8}$	$1\frac{1}{2}$	$3\frac{1}{4}$	$3\frac{3}{4}$	1.5
$1\frac{5}{8}$	$1\frac{1}{4}$	$1\frac{1}{2}$	$3\frac{1}{4}$	$3\frac{3}{4}$	1.5
$2\frac{1}{8}$	$1\frac{1}{2}$	$1\frac{1}{2}$	$3\frac{1}{4}$	$3\frac{3}{4}$	1.5
$2\frac{3}{8}$	$1\frac{3}{4}$	$1\frac{1}{2}$	$3\frac{1}{4}$	$3\frac{3}{4}$	1.5
$2\frac{1}{2}$	2	$1\frac{1}{2}$	$3\frac{1}{4}$	$4\frac{1}{4}$	2.5
$2\frac{5}{8}$	$2\frac{1}{4}$	$1\frac{1}{2}$	$4\frac{1}{2}$	$5\frac{1}{4}$	3.0
$3\frac{1}{8}$	$2\frac{1}{2}$	$1\frac{1}{2}$	$4\frac{1}{2}$	$5\frac{1}{4}$	2.8
$3\frac{3}{8}$	$2\frac{3}{4}$	$1\frac{1}{2}$	$4\frac{1}{2}$	$5\frac{1}{4}$	2.8
$3\frac{1}{2}$	$2\frac{3}{4}$	$1\frac{1}{2}$	$4\frac{3}{4}$	$5\frac{1}{2}$	3.0
$3\frac{5}{8}$	3	$1\frac{1}{2}$	$4\frac{3}{4}$	$5\frac{1}{2}$	3.0
$4\frac{1}{8}$	$3\frac{1}{2}$	$1\frac{1}{2}$	$5\frac{1}{2}$	$6\frac{1}{4}$	3.8
$4\frac{3}{8}$	$3\frac{1}{2}$	$1\frac{1}{2}$	$5\frac{1}{2}$	$6\frac{1}{4}$	3.8
$4\frac{7}{8}$	4	$1\frac{1}{2}$	6	7	6.7
$5\frac{1}{8}$	4	2	6	7	6.7
$5\frac{3}{8}$	4	2	7	8	9.1
7	5	$2\frac{1}{4}$	8	$9\frac{1}{4}$	12.0
8	6	$2\frac{1}{4}$	$10\frac{1}{2}$	12	22.8
9	7	$2\frac{1}{4}$	$10\frac{1}{2}$	12	18.8

TABLE XIX
STANDARD SCREW THREADS AND NUTS

Diameter of Rod or Bolt	Threads per Inch	Diameter at Root of Thread	Area of Rod or Bolt at Root of Thread	Short Diameter of Nuts	Long Diameter, Hexagon Nuts	Long Diameter, Square Nuts	Thickness of Nuts
$\frac{1}{16}$	20	.185	.026	$\frac{1}{16}$	$\frac{3}{16}$	$\frac{1}{8}$	$\frac{1}{16}$
$\frac{1}{8}$	18	.240	.045	$\frac{1}{8}$	$\frac{1}{4}$	$\frac{1}{8}$	$\frac{1}{8}$
$\frac{3}{16}$	16	.294	.067	$\frac{3}{16}$	$\frac{1}{2}$	$\frac{3}{16}$	$\frac{3}{16}$
$\frac{1}{2}$	14	.344	.092	$\frac{1}{2}$	$\frac{3}{4}$	$\frac{1}{2}$	$\frac{1}{2}$
$\frac{5}{8}$	13	.400	.125	$\frac{5}{8}$	1	$\frac{5}{8}$	$\frac{5}{8}$
$\frac{3}{4}$	12	.454	.161	$\frac{3}{4}$	$1\frac{1}{4}$	$1\frac{1}{4}$	$1\frac{1}{4}$
$\frac{7}{8}$	11	.507	.201	$1\frac{1}{8}$	$1\frac{7}{8}$	1	$1\frac{7}{8}$
1	10	.620	.301	1	$1\frac{7}{8}$	$1\frac{3}{4}$	1
$1\frac{1}{8}$	9	.731	.419	$1\frac{7}{8}$	$2\frac{1}{2}$	$2\frac{1}{2}$	$1\frac{7}{8}$
$1\frac{1}{4}$	8	.837	.550	1	2	$2\frac{1}{4}$	1
$1\frac{3}{8}$	7	.940	.693	$1\frac{3}{8}$	$2\frac{3}{4}$	$2\frac{3}{4}$	$1\frac{3}{4}$
$1\frac{1}{2}$	7	1.065	.890	2	$2\frac{1}{2}$	$2\frac{3}{4}$	$1\frac{1}{2}$
$1\frac{3}{4}$	6	1.160	1.056	$2\frac{3}{4}$	$2\frac{1}{2}$	$3\frac{1}{2}$	$1\frac{3}{4}$
$1\frac{7}{8}$	6	1.284	1.294	2	2	$3\frac{3}{4}$	$1\frac{7}{8}$
2	$5\frac{1}{2}$	1.389	1.515	$2\frac{7}{8}$	$2\frac{3}{4}$	3	2
$2\frac{1}{8}$	5	1.491	1.746	2	$3\frac{1}{8}$	$3\frac{1}{2}$	$2\frac{1}{8}$
$2\frac{1}{4}$	5	1.616	2.051	$2\frac{1}{2}$	$3\frac{1}{2}$	$4\frac{1}{2}$	$2\frac{1}{4}$
$2\frac{3}{8}$	$4\frac{1}{2}$	1.712	2.301	$3\frac{1}{8}$	$3\frac{5}{8}$	$4\frac{3}{4}$	2
$2\frac{1}{2}$	$4\frac{1}{2}$	1.962	3.023	$3\frac{1}{2}$	$4\frac{1}{4}$	$4\frac{1}{2}$	$2\frac{1}{2}$
$2\frac{3}{4}$	4	2.176	3.718	$3\frac{3}{4}$	4	$5\frac{1}{4}$	$2\frac{3}{4}$
3	4	2.426	4.622	4	$4\frac{3}{4}$	6	3
$3\frac{1}{8}$	$3\frac{1}{2}$	2.629	5.428	$4\frac{1}{2}$	5	$6\frac{1}{2}$	$3\frac{1}{8}$
$3\frac{1}{4}$	$3\frac{1}{2}$	2.879	6.509	5	$5\frac{1}{2}$	$7\frac{1}{8}$	$3\frac{1}{4}$
$3\frac{3}{8}$	$3\frac{1}{4}$	3.100	7.547	$5\frac{3}{8}$	$6\frac{1}{4}$	$7\frac{3}{8}$	$3\frac{3}{8}$
$3\frac{1}{2}$	3	3.318	8.641	$5\frac{1}{2}$	$6\frac{3}{4}$	8	$3\frac{1}{2}$
4	3	3.567	9.993	6	$7\frac{3}{4}$	$8\frac{1}{2}$	4

distance below the center, so that the stress acting along the neutral axis will produce a moment that will counteract, or neutralize, the moment due to the weight of the member itself.

The distance from the edge of the pinhole to the end of the plate must be great enough to prevent splitting along the line of the least net section.

37. Pin Plates.—Pin plates should be used at all pinholes in built-up members and should extend at least 6 inches within the member, to provide for at least two transverse rows of rivets at that place. The net section through the pinhole should be 40 per cent. more than the net section through the body of the member, and the net section outside of the pinhole along the center line of stress should equal the net section of the body.

38. Packing of Joints.—The members of a pin-connected joint should be packed so as to produce the least bending moment on the pin and should be arranged symmetrically on both sides of the center line. Sufficient clearance should be allowed for inaccuracies in manufacture. Interior vacant spaces must be filled with steel fillers if their omission will permit the members to move on the pin. All bars must be, as nearly as possible, parallel to the central plane of the truss.

39. Standard Sizes of Pins.—Table XVIII gives standard sizes and dimensions of pins and nuts. These sizes have been fixed on by the several steel companies in the United States and are standard in this country.

40. Standard Screw Threads and Nuts.—Table XIX gives the proportions for United States standard screw threads and nuts.

EXAMPLES FOR PRACTICE

1. One of the tension members in a structure is connected as shown in Fig. 33. The tension bars are made of structural steel with a safe tensile strength of 15,000 pounds per square inch. (a) What is the bearing value of the bar *c*? (b) What is the bearing value of the two bars *a*?

Ans. $\begin{cases} (a) & 104,000 \text{ lb.} \\ (b) & 97,500 \text{ lb.} \end{cases}$




FIG. 33



FIG. 34





FIG. 36

2. In Fig. 34 is shown a pin connection, the pull on the tension bar a being 140,000 pounds. If the safe shearing strength of the material in the pin is 10,000 pounds per square inch, and the safe fiber stress in bending is 15,000 pounds per square inch: (a) what size of pin will be required to resist the shear? (b) what size will be required to resist the bending?

Ans. $\begin{cases} (a) 3\frac{3}{8} \text{ in. in diameter} \\ (b) 4\frac{3}{8} \text{ in. in diameter} \end{cases}$

3. (a) What is the maximum resultant bending moment on the pin used in the connection shown in Fig. 35? (b) What size pin is required for this connection when the highest unit strength values given in the tables are assumed?

Ans. $\begin{cases} (a) 71,480 \text{ in.-lb.} \\ (b) 3\frac{3}{8} \text{-in. pin} \end{cases}$

GRAPHICAL ANALYSIS OF STRESSES

(PART 1)

INTRODUCTION

1. The **graphical analysis of stresses** is the study, by means of diagrams, of the stability or equilibrium of structures and the relation between the external forces and the stresses created in the members of the frame. It is founded on the principle that any force may be designated, both as to direction and intensity, by a straight line by letting the direction of the line be identical with that of the force and adjusting its length according to an arbitrary unit adopted for the forces under consideration. The advantage existing in the use of graphical statics for the solution of stresses in framed structures is that when the principles are correctly applied no important error can exist, and though the stresses determined by this means will not be extremely accurate, they cannot be radically wrong. The approximations obtained by the diagrams give results as nearly accurate as the practical design of any member in the structure can be.

2. Definitions.—Before studying this subject the meaning of several terms should be thoroughly understood. Other terms, which require an extensive explanation, will be defined when first introduced.

A **force**, in graphical statics, is understood to be a weight or pressure applied in a certain direction at a particular point. It may be either an external or internal, or a concurrent or non-concurrent, or even a coplanar, or non-coplanar force.

For notice of copyright, see page immediately following the title page

An **external force** on any structure represents either a weight or a reaction; for instance, the vertical dead or snow loads on a roof truss are external forces, as are also the reactions created by the resistance of the piers or abutments beneath the ends of the roof trusses.

An **internal force** is the stress created in any member of a framed structure. Sometimes it is denominated as a strain, but this is incorrect for strain is now generally understood to mean the distortion, or amount of change of form created in a piece of material by a stress or the force that must exist before the change of form is accomplished. In a roof truss, the internal forces are the compression in the rafter members and struts, and the tension in the tie-rods.




FIG 1

Concurrent forces are those forces that act or meet at a single point, as in Fig. 1 (a).

Non-concurrent forces comprise any system of forces that do not meet at a single point, as in Fig. 1 (b). While *a* and *b* meet at a certain point, and *c* and *d* can be extended until they meet, the four forces cannot act at one point.

Coplanar and non-coplanar forces are the forces that act in the same plane, and in different planes, respectively. Fig. 2 (a) illustrates the first force and (b) the second.

Equilibrium exists in any structure when there is no tendency for the structure to move; or if it is moving uniformly, there is no tendency for the rate or direction of the motion to change. In graphical statics, which term is

derived from the study of the equilibrium of structures, when a body is said to be in equilibrium, it is inferred that there is no tendency for the body or structural frame to change from a state of rest to one of motion; nor from a state of motion to one of rest. A body may be in equilibrium against motion either in a lateral direction or in a rotary direction.

Equilibrium of translation is a term that has been applied to a body in equilibrium against lateral motion.

Rotary equilibrium is applied to a body that is in equilibrium about a particular point; that is, the condition that exists in a body that has no rotary tendency about a fixed point.

Complete equilibrium can only be considered to exist when there is no tendency for a body toward translatory or




FIG. 2

rotary motion; that is, when both the conditions of translatory equilibrium and rotary equilibrium are fulfilled.

A **couple** is the term given to two equal and opposing forces not coincident with respect to their line of action; or, in the terms of the definitions, two equal and opposing non-concurrent forces form a couple.

The **moment** of a force about any point not located in its line of action is its tendency to rotate about that point; the amount of the moment is obtained by multiplying the intensity, or amount, of the force by its lever arm, or the perpendicular distance from the line of action of the force to the point around which it tends to rotate, this point being termed the center of moments. The moment of any force is never expressed in either units of weight or units of

length, but by a combination of the two, as inch-pounds, foot-pounds, and foot-tons.

The resultant of any system of forces is any force that by its direction and amount, will equal in its effect on a body or structure the effect of all the forces of the system. Any force that will destroy the action of all the forces of the system is equal and opposed to the resultant; such force might be termed **resultant reaction**. Where the resultant of a system of forces equals zero, the system is in translatory equilibrium, while if the moment of the resultant about any point equals zero, the system is in rotary equilibrium. Where any system of forces is resolved into a couple, that is, two equal and opposing non-concurrent forces, the system cannot be in complete equilibrium and no single force will replace the two non-concurrent forces.

FUNDAMENTAL PRINCIPLES OF GRAPHICAL ANALYSIS

EFFECTS OF A FORCE

3. The effect of a force on a body may be compared with another force when the three following conditions are fulfilled in regard to both forces:

1. The point of application, or point at which the force acts on the body, must be known.
2. The direction of the force, or the straight line along which the force tends to move the point of application, must be known.
3. The magnitude, or value, of the force, when compared with a given standard, must be known.

The unit of magnitude of forces will be taken as 1 pound throughout this Course, and all forces spoken of as a certain number of pounds.

4. The fundamental principles of the relations between force and motion, which were first stated by Sir Isaac Newton and are called "Newton's Three Laws of Motion" are as follows:

Law I.—*All bodies continue in a state of rest, or of uniform motion in a straight line, unless acted on by some external force that compels a change.*

Law II.—*A force acting on a body in motion or at rest, produces the same effect whether it acts alone or with other forces.*

Law III.—*To every action there is always opposed an equal and contrary reaction.*

From the first law of motion, it is inferred that a body once set in motion by any force, no matter how small, will move forever in a straight line, and always with the same velocity, unless acted on by some force that compels a change.

The deduction from the second law is that, if two or more forces act on a body, their final effect on that body will be in proportion to their magnitude and to the directions in which they act. Thus, if the wind is blowing due west, with a velocity of 50 miles per hour, and a ball is thrown due north, with the same velocity, the wind will carry the ball just as far west as the force of the throw carried it north, and the combined effect will be to cause it to move northwest.



FIG. 3

The amount of departure from due north will be proportional to the force of the wind, and independent of the velocity due to the force of the throw.

The third law states that action and reaction are equal and opposite. A man cannot lift himself by his boot straps, for the reason that he presses downward with the same force that he pulls upward; the downward reaction equals the upward action, and is opposite to it.

5. A force may be represented by a line; thus, in Fig. 3, let A be the point of application of the force, let the length of the line AB represent its magnitude, and let the arrow-head indicate the direction in which the force acts, then the line AB fulfils the three required conditions and shows the point of application, the direction, and the intensity of the force.

THE COMPOSITION OF FORCES

6. Parallelogram of Forces.—When two forces act on a body at the same time, but at different angles, their final result may be obtained as follows:

In Fig. 4, let A be the common point of application of two forces, and let AB and AC represent the magnitude and direction of the forces. The final effect of the movement due to these two forces will be the same whether they act singly or together. For instance, let the line AB represent the distance that the force AB would cause the body to move; similarly, let AC represent the distance that the force



FIG. 4

AC would cause the body to move, when both forces were acting separately. The force AB , acting alone, would carry the body to B ; if the force AC were now to act on the body, it would carry it along the line BD , parallel to AC , to a point D , at a distance from B equal to AC . Join C and D , then CD is parallel to AB , and $ABDC$ is a parallelogram. Draw the diagonal AD .

According to the second law of motion the body will stop at D whether the forces act separately or together, but if they act together, the path of the body will be along AD , the diagonal of the parallelogram. Moreover, the length of the line AD represents the magnitude of a force, which acting at A in the direction AD , would cause the body to move from A to D ; in other words, AD measured to the same scale as AB and AC , represents the magnitude and direction of the combined effect of the two forces AB and AC , and is called the resultant. Suppose that the scale used was 50 pounds to the inch, then, if $AB = 50$ pounds, and $AC = 62\frac{1}{2}$ pounds, the length of AB would be $\frac{50}{50} = 1$ inch, and the length of AC would be $\frac{62.5}{50} = 1\frac{1}{4}$ inches. If AD , or the resultant, measures $1\frac{3}{4}$ inches, its magnitude would be $1\frac{3}{4} \times 50 = 87\frac{1}{2}$ pounds. Therefore, a

A force of $87\frac{1}{2}$ pounds, acting on a body at A , in the direction AD , will produce the same result as the combined effects of a force of 50 pounds acting in the direction AB , and a force of $62\frac{1}{2}$ pounds acting in the direction AC .

7. This method of finding the resulting action of two forces acting on a body at a common point, is correct for forces of any direction and magnitude. Hence, to find the resultant of two forces when their common point of application, their direction, and magnitudes are known:

Rule.—Through an assumed point, draw two lines parallel with the direction of the two forces. With any scale, measure from the point of intersection, in the direction of the forces, distances corresponding to the magnitudes of the respective forces, and from the points thus obtained complete the parallelogram. Draw the diagonal of the parallelogram from the point of intersection of the two forces; this diagonal will be the resultant, and its direction will be away from the point of intersection of the two forces. Its magnitude must be measured with the same scale that was used to lay off the two forces.

This method is called the **graphical method of the parallelogram of forces**.

EXAMPLE.—If two forces act on a body at a common point, both acting away from the body, and the angle between them is 80° , what is the value of the resultant, the magnitude of the two forces being 60 and 90 pounds, respectively.

SOLUTION.—Draw two indefinite lines having an angle of 80° between them. With any convenient scale, say 10 lb. to the inch, measure off $AB = 60 \div 10 = 6$ in., and $AC = 90 \div 10 = 9$ in., as shown in Fig. 5 (a). Through B draw BD parallel to AC , and through C




FIG. 5

draw CD parallel to AB . Then draw AD , which will be the resultant; its direction is toward the point D , as shown by the arrow.

Measuring AD , its length is found to be 11.7 in. Hence, $11.7 \times 10 = 117$ lb. Ans.

8. Triangle of Forces.—The above example might also have been solved by the method called the **triangle of forces**, which is as follows: In Fig. 5 (*b*), suppose that the two forces AB and BC act separately, first from A to B , and then from B to C , in the direction of the arrows. Connect A and C ; then AC is the resultant of the forces AB and BC . It will also be noticed in following the direction of the forces around the triangle, that the direction of the resultant AC is opposite to that of AB and BC . Hence, to find the resultant of two forces acting on a body at a common point, by the method of triangle of forces:

Rule.—*Draw the lines of action of the two forces as if each force acted separately, the lengths of the lines being proportional to the magnitude of the forces. Join the extremities of the two lines by a straight line, which will be the resultant; its direction will be opposite to that of the two forces.*

When the resultant is spoken of as being opposite in direction to the other forces around the polygon, it is meant that, starting from the point where the drawing of the polygon was commenced, and tracing each line in succession, the pencil will have the same general direction around the polygon as if passing around a circle, from left to right or from right to left, but the closing line or resultant must have an opposite direction; that is, the two arrowheads, the one on the resultant and the other on the last side, must point toward the intersection of the resultant and the last side.

9. Resultant of Several Forces.—When three or more forces act on a body at a given point, their resultant may be found by the following rule:

Rule.—*Find the resultant of any two forces; treat this resultant as a single force, and combine it with a third force to find a second resultant. Combine this second resultant with a fourth force, to find a third resultant, etc. After all the forces have*

been thus combined, the last resultant will be the resultant of all of the forces, both in magnitude and direction.

EXAMPLE.—Find the resultant of all the forces acting on the point O in Fig. 6, the length of the lines being proportional to the magnitude of the forces.

SOLUTION.—Draw OE parallel and equal to AO , and EF parallel and equal to BO , then OF is the resultant of these two forces, and its direction is from O to F , opposed to OE and EF . Treat OF as if OE and EF did not exist, and draw FG parallel and equal to CO ; OG will be the resultant of OF and FG ; but OF is the resultant of OE and EF ; hence, OG is the resultant of OE , EF , and FG , and therefore of AO , BO , and CO . Likewise draw GL parallel




FIG. 6

and equal to DO . Join O and L , and OL will be the resultant of all the forces AO , BO , CO , and DO (both in magnitude and direction), acting at the point O . If $L'O$ were drawn parallel and equal to OL , and having the same direction, it would represent the effect produced on the body by the combined action of the forces AO , BO , CO , and DO .

10. In Fig. 6, it will be noticed that OE , EF , FG , GL , and LO are sides of a polygon $OELFG$, in which LO , the resultant, is the closing side, and that its direction is opposed to that of all the other sides. This fact is made use of in what is called the method of the polygon of forces. To find the resultant of several forces acting on a body at the same point by this method:

Rule.—Through any point, draw a line parallel to one of the forces, and having the same direction and magnitude. At the end of this line, draw another line, parallel to, and having the same direction and magnitude as a second force; at the end of the second line, draw a line parallel and equal in magnitude and direction to a third force. Thus continue until lines have been drawn parallel and equal in magnitude and direction to all of the forces.

The straight line joining the free ends of the first and last lines will be the closing sides of the polygon; mark it opposite in direction to that of the other forces around the polygon, and it will be the resultant of all the forces.




FIG 7

EXAMPLE.—If five forces act on a body at angles of 60° , 120° , 180° , 240° , and 270° , toward the same point, and their respective magnitudes are 60, 40, 30, 25, and 20 pounds, find the magnitude and direction of their resultant by the method of polygon of forces.*

SOLUTION —From a common point O , Fig. 7, draw the lines of action of the forces, making the given angles with a horizontal line through O , and mark them as acting toward O , by means of arrowheads, as shown. Choose some convenient scale, such that the whole figure may be drawn in a space of the required size on the drawing. Select any one of the forces, as AO , and draw OF parallel to it, and equal in length

*All the angles in the figure are measured from a horizontal line in a direction opposite to the movement of the hands of a watch, from 1° up to 360° .

to 30 lb. on the scale. It must also act in the same direction as $A O$. At F , draw $F G$ parallel to $B O$, and equal to 40 lb. In a similar manner, draw $G H$, $H I$, and $I K$ parallel to $C O$, $D O$, and $E O$, and equal to 60, 20, and 25 lb., respectively. Join O and K by $O K$, and $O K$ will be the resultant of the combined action of the five forces; its direction is opposite to that of the other forces around the polygon $O F G H I K$, and its magnitude = $55\frac{3}{4}$ lb. Ans. .

11. If the resultant $O K$, Fig. 7, were to act alone on the body in the direction shown by the arrowhead with a force of $55\frac{3}{4}$ pounds, it would produce exactly the same effect as




FIG. 8

the combined action of the five forces. If $O F$, $F G$, $G H$, $H I$, and $I K$ represent the distances and directions that the forces would move the body, if acting separately, $O K$ is the direction and distance of movement of the body when all the forces act together. It is evident, therefore, that any number of forces acting on a body at the same point, or having their lines of action pass through the same point, can be replaced by a single force (resultant), whose line of action shall pass through that point.

Heretofore, it has been assumed that the forces acted on a

single point on the surface of the body, but it will make no difference where they act, so long as the lines of action of all the forces intersect at a single point either within or without the body, only so that the resultant can be drawn through the point of intersection. If two forces act on a body in the same straight line and in the same direction, their resultant is the sum of the two forces; but if they act in opposite directions, their resultant is the difference of the two forces, and its direction is the same as that of the greater force. If they are equal and opposite, the resultant is zero, or one force just balances the other.

EXAMPLE.—Find the resultant of the forces whose lines of action pass through a single point, as shown in Fig. 8.

SOLUTION.—Take any convenient point g , and draw a line gf , parallel to one of the forces, say the one marked 40, making it equal in length to 40 lb. on the scale, and indicate its direction by the arrowhead. Take some other force—the one marked 37 will be convenient, the line fe represents this force. From the point e draw a line parallel to some other force, say the one marked 29, and make it equal in magnitude and direction to it. So continue with the other forces, taking care that the general direction around the polygon is not changed. The last force drawn in the figure is ah , representing the force marked 25. Join the points a and g , then, ag is the resultant of all the forces shown in the figure. Its direction is from g to a , opposed to the general direction of the others around the polygon. It does not matter in what order the different forces are taken, the resultant will be the same in magnitude and direction, if the work is done correctly.

These various methods of finding the resultant of several forces are all grouped under one head: The Composition of Forces.

THE RESOLUTION OF FORCES

12. Since two forces can be combined to form a single resultant force, a single force may also be treated as if it were the resultant of two or more forces, whose action on a body will be the same as that of the single force. Thus, in Fig. 9, the force OA may be resolved into two forces, OB and BA , whose directions are opposed to OA . If the force OA acts on a body, moving or at rest on a horizontal plane, and the resolved force OB is vertical, and BA

Horizontal, OB , measured to the same scale as OA , is the magnitude of that part of OA that pushes the body downwards, while BA is the magnitude of that part of the force OA , which is exerted in pushing the body in a horizontal direction. OB and BA are called the **components** of the force OA , and when these components are vertical and horizontal, as in the present case, they are called the *vertical component* and the *horizontal component* of the force OA . These components may be drawn in any direction and the angle at their intersection is not necessarily a right angle.

13. It frequently happens that the position, magnitude, and direction of a certain force are known, and that it is desired to know the effect of the force in some direction other than that in which it acts. Thus, in Fig. 9, assume that OA represents, to some scale, the magnitude, direction, and line of action of a force acting on a body at A , and that it is desired to know what effect OA produces in the direction BA , which may be any direction. To find the value of the component of OA that acts in the direction BA , it is necessary to employ the following rule:




FIG. 9

Rule.—*From one extremity of the line representing the given force, draw a line parallel to the direction in which it is desired that the component shall act; from the other extremity of the given force, draw a line perpendicular to the component first drawn, and intersecting it. The length of the component, measured from the point of intersection to the intersection of the component with the given force, will be the magnitude of the effect produced by the given force in the required direction.*

Thus, suppose that OA , Fig. 9, represents a force acting on a body resting on a horizontal plane, and that it is desired to know what vertical pressure OA produces on the body.

Here the desired direction is vertical; hence, from one extremity, as O , draw OB parallel to the desired direction (vertical in this case), and from the other extremity draw AB perpendicular to OB , and intersecting OB at B . Then OB , when measured to the same scale as OA , will be the value to the vertical pressure produced by OA .




FIG. 10

EXAMPLE.—If a body weighing 200 pounds rests on an inclined plane whose angle of inclination to the horizontal is 18° , what force does it exert perpendicular to the plane, and what force does it exert parallel to the plane, tending to slide downwards?

SOLUTION.—Let ABC , Fig. 10, be the plane, the angle A being equal to 18° , and let W be the weight. Draw a vertical line $FD = 200$ lb., to represent the magnitude of the weight. Through F , draw FE parallel to AB , and through D draw DE perpendicular to FE , the two lines intersecting at E . FD is now resolved into two components, one FE tending to pull the weight downwards, and the other ED acting as a perpendicular pressure on the plane.

On measuring FE with the same scale by which the weight FD was laid off, its intensity is found to be about 61.8 lb., and the perpendicular pressure ED on the plane is found to measure 190.2 lb. Ans.

EQUILIBRIUM

14. When a body is at rest, all of the forces that act on it must balance one another; the forces are then said to be in equilibrium. The most important of the forces acting on the body is gravity, which acts on every particle. But a force that must be considered when determining the equilibrium of framed structures is the wind pressure.

A body is in *stable equilibrium* when, if slightly displaced from its position of rest, the forces acting on it tend to return it to that position; for example, a cube, a cone resting on its base, a pendulum, etc.

A body acted on by a system of forces is in *unstable equilibrium* when the application of a small force is sufficient to produce motion; for example, a cone standing on its apex, an egg balanced on end, etc.

Since two kinds of motion may be produced in a body acted upon by external forces, the following conditions must be fulfilled in order that a body be in equilibrium:

1. The resultant of all the forces tending to move the body in any direction must be zero.
2. The resultant of all the forces tending to turn the body about any center must be zero.

But, if either of the two following conditions prevails the body will be in unstable equilibrium or unrest:

1. If the forces acting on a body create or influence motion of the body in the direction of the line of action of the force.
2. If the force acting on the body tends to move or rotate the body around some fixed point, which point is always necessarily outside the line of action of the force.

EQUILIBRIUM AT THE JOINTS OF A STRUCTURE

15. The several forces acting at any joint of a framed structure must theoretically be concurrent, and a single joint can, in consequence, be subjected only to translatory motion. But, where several forces meet at a joint in any stable structure there must be no translatory motion, for if the joint could move in any direction it would fail and cause the destruction of the frame.

In Fig. 11 (*a*) are shown five concurrent forces that act in the directions indicated by the arrows. By drawing the stress diagram for these forces, as shown at (*b*), their resultant is determined by the line *bc*, which force is the combined effect, both in direction and in intensity, of all of the concurrent forces acting at the joint *c*. Since this line *bc* is the resultant of the system of forces, it is evident that if no other force is substituted at the joint, it will move in the oblique direction indicated by the arrow on this line in the stress diagram. In order to produce equilibrium in the joint, a force *cb* in (*a*) acting in opposition to *ca*, and of the same amount, must be applied to the joint *c*, as shown. Consequently, the joint is in unstable equilibrium and can never be in equilibrium of translation until the points *c* and *b* in the stress diagram coincide.

The stress diagram of the five concurrent forces, acting on the joint shown in Fig. 11 (*c*), is shown in (*d*). It will be observed that there is no resultant, but that the polygon closes at the point *c*, the end of the last force *f c* coinciding with the beginning of the first force *a c*. It is evident, therefore,




FIG. 11

since the resultant of all the forces about the joint *c* is zero, that no force need be substituted in the frame diagram to produce equilibrium of translation, and in consequence the joint in the structure will be stable and no failure of the frame, through weakness at this joint, can exist.

16. In order to analyze the conditions that create equilibrium of translation in any system of concurrent forces, resolve each of the forces of the system shown at Fig. 11 (*c*) into vertical and horizontal components, as shown in Fig. 12, by the method explained under The Resolution of Forces. The forces *ac* and *ec*, Fig. 11 (*c*), are horizontal and *fc* is vertical, but the forces *bc* and *dc* are oblique and may be resolved into vertical and horizontal components, as shown by *y* and *y*₁, *x* and *x*₁, respectively, Fig. 12. By scaling the horizontal components *x* and *x*₁, it is found that *x* = 2,100 pounds and *x*₁ = 6,300 pounds, and it will also be observed that the direction of the component *x* is opposed to the




FIG. 12

direction of the force *ac*, and *x*₁ is opposed to the force *ec*. By studying the diagram, Fig. 12, it will be observed that the horizontal forces acting toward the left are exactly equal to the horizontal forces acting toward the right, and that they act and react so as to completely annul all action in a horizontal direction. In other words, the algebraic sum of all of the horizontal forces acting at the joint is zero, or, as it might be stated, $x + ec = x_1 + ac$ and $(x + ec) - (x_1 + ac) = 0$.

Again, the vertical components *y*₁ and *y* of the forces *bc* and *dc* both act in opposition to the force *fc* and the algebraic sum of all the vertical forces is equal to zero, for the sum of *y* and *y*₁ is equal to 5,600, as may be proved by

scaling the diagram. The algebraic sum of all the vertical forces at the joint is consequently equal to zero. From these deductions the condition of equilibrium at a joint may therefore be expressed by the following rule:

Rule.—*In order that any joint in a frame, or any system of concurrent forces, shall be in equilibrium of translation, the algebraic sum of all the horizontal and vertical forces and all the horizontal and vertical components of the oblique forces shall equal zero.*

17. The conclusion that in order to have equilibrium of translation the algebraic sum of the several forces at a joint must equal zero, can be reached in another way. For instance, it has been stated and proved that the resultant of any system of concurrent forces must equal zero and it is evident that when all of the forces about a joint are resolved into their horizontal and vertical components, the final resultant is the hypotenuse of the triangle formed by the resultants of the components. In Fig. 13 (a), the several oblique forces have been resolved into their components x, x, x , and y, y, y , and x_1 and y_1 are the algebraic sums of these components, as may be proved by scaling the diagram. By laying off x_1 and y_1 , as indicated, and drawing the hypotenuse R , the resultant is obtained. This resultant is therefore $\sqrt{\Sigma x^2 + \Sigma y^2}$, in which x and y equal, respectively, the horizontal and vertical components of each force about the joint. The components x_1 and y_1 may also be obtained directly from the stress diagram, Fig. 13 (b), by resolving the resultant R into its vertical and horizontal components.

The direction of the resultant R can be determined by obtaining the tangent of the angle that R makes with the horizontal or vertical components. The tangent of the angle marked z in Fig. 13 (a), is equal to $\frac{y_1}{x_1}$. Where, therefore, the vertical and horizontal components of each of the forces are considered, their direction being represented by V and H , respectively,

$$\tan z = \frac{\Sigma y}{\Sigma x}, \text{ or } \frac{\Sigma V \text{ components}}{\Sigma H \text{ components}}$$




FIG. 13

But, from a previous statement and deduction, the resultant R of any system of concurrent forces in equilibrium must equal zero, so that $R^* = (\sum H \text{ components})^* + (\sum V \text{ components})^* = 0$. R having an inappreciable amount, consequently, has no direction and it is conclusively shown that for equilibrium of translation the sum of the horizontal and vertical components must equal zero. This condition must therefore exist at every joint in a framed structure in order to secure the equilibrium or stability of the entire structure.

EQUILIBRIUM OF THE ENTIRE FRAME

18. Any framed structure, besides having each joint at which concurrent forces occur in equilibrium, must be in equilibrium with regard to the action of the external forces, which are usually non-concurrent. The external forces on any frame, such as a roof truss, are the loads and their reactions. On a roof truss, or other exposed structure, the external forces consist of the vertical loads due to the weight of the structure and snow, and the horizontal or oblique forces due to the wind pressure. The reactions occur at the abutments or supports of the structure and act in opposition to the loads, to hold the structure in equilibrium. It is sometimes necessary to introduce in the analysis of stresses imaginary or assumed reactions and forces that replace the resistance to bending offered by some member; this is due to the fact that a transverse stress cannot be shown in a diagram in conjunction with direct stresses.

Fig. 14 (*a*) shows an iron bracket resting on the ledge a , tied into the wall at b , and supporting, at its end, a weight W . As the external, or non-concurrent, forces alone are to be taken into account, the members of the bracket may be disregarded and the structure considered as a solid triangular body held in equilibrium by the four forces W , C , D , and E , as shown in (*b*). The force W acts vertically while C , which is a tensile stress, acts horizontally; D and E may be regarded as reactions. For the frame to be in equilibrium, the sum of the vertical forces must equal zero, as must also the sum

of the horizontal forces. W is known, both in direction and intensity, and since E is negative with respect to the force W , their algebraic sum must be $W - E = 0$; therefore, $W = E$. Since the resultant of the horizontal forces must equal zero, $C - D = 0$, or $C = D$, thus proving that the triangular frame is in translatory equilibrium; that is, there is no tendency for the frame to move laterally in any direction.

The conditions of complete equilibrium are not fulfilled unless equilibrium of both translation and rotation exists about any point of the structure. Assume the point c as the center of moments. The force C acts about this point with a lever arm equal to y and the weight W tends to rotate in the opposite direction with a lever arm equal to x . Since the forces E and




FIG. 14

D intersect at the center of moments c , there is no tendency for them to rotate the structure about this point, for their lever arm is zero; so that $D \times 0 = 0$, as does $E \times 0 = 0$.

$W \times x$ must equal $C \times y$ in order to produce rotary equilibrium; therefore, $W \times x - C \times y = 0$. The algebraic sum of the moments of all the forces acting about c and tending to rotate the triangular frame is consequently equal to zero.

THE FORCE AND EQUILIBRIUM POLYGON

19. Since, in order for any structure to be in equilibrium the algebraic sum of the forces acting on the structure must equal zero, when a structure supports a number of

parallel loads, the reactions at the ends of the structure, which are coincident with the line of action of the loads, must equal, when added together, the sum of the loads.

If the loads are not all parallel, but exert their forces along different lines of action, and the reactions in consequence do not coincide with the line of action of the several forces, the sum of the reactions does not equal the sum of the loads; but, in order for the structure to be in equilibrium, the sum of the vertical and horizontal components of all the forces must equal the sum of the vertical and horizontal components of the reaction.




FIG 15

Assume that in Fig. 15 (a), a beam loaded at the center with the weight W is held in equilibrium by the reactions R_1 and R_2 ; or, designating them by the usual system of notation, the forces AZ and BZ . Suppose, now, that instead of a beam that has a certain transverse strength, which cannot be represented graphically, the load W is supported by a flexible cord attached at R_1 and R_2 . This cord might have any length and consequently might drop any distance below the beam, but no matter what this drop may be, the vertical reactions R_1 and R_2 will always be the same, for the sum of R_1 and R_2 equals the sum of the vertical components of all of the forces acting in one direction on the cord, while W , or the amount of the load, must be equal and act in the opposite

direction to fulfil the condition that the algebraic sum of the vertical loads shall equal zero. Besides the reactions R_1 and R_2 , in order to create equilibrium in the cord supporting the load W , there must be horizontal forces A and B at each end of the cord to prevent their approaching each other. These two forces could as well be supplied by a horizontal strut extending between the ends of the cord, and could be considered as the compressive strength of the beam.

It is evident, therefore, since there are horizontal and vertical forces at each end of the beam, that a single force equal to their resultant could be applied to the ends of the cord in order that equilibrium might be maintained. These oblique resultants C and D of the vertical and horizontal components must, therefore, in order that they may alone create equilibrium, have their line of action coincident with the direction of the cord, as shown. Assume that the cord, instead of occupying the position designated in Fig. 15 (*a*), is considerably longer and that the weight is applied at twice the distance below the beam, as in Fig. 15 (*b*). The directions of the oblique reactions coincident with the present direction of the cord are indicated by the lines ce and fg . But it was stated that the vertical reactions, which are the vertical components of these oblique forces and are represented by the vertical lines cd and fh , Fig. 15 (*b*), must always be of the same amount when the load W is located in the center of the cord; that is, their sum must equal the load. It is evident, then, that if the vertical component at R_1 is laid off from c to d , and de is drawn horizontally from d , de will equal the horizontal component of the oblique force at this abutment. It will also be noticed that when the oblique reaction C , Fig. 15 (*a*), is designated by the dotted line ce_1 , Fig. 15 (*b*), de_1 is the horizontal component for the oblique reaction at R_1 . As seen in Fig. 15 (*b*), the horizontal reaction of the cord having the lesser drop is much greater than the horizontal reaction of the cord having the greater drop, and it is therefore evident that as the drop of the cord becomes greater, the horizontal component of the oblique force becomes less. Likewise, that the greater the drop of the cord, the less will

be the oblique reaction until when the oblique reaction approaches verticality the thrust or horizontal force will become zero while the reaction will equal one-half of the load.

20. Assume that to the beam shown in Fig. 16 (a) is applied a load W equal to 1,000 pounds. Lay off in the




FIG 16

diagram at (b) a line ab equal, by scale, to 1,000 pounds. Choose any point, or pole, such as o , and draw lines from a and b to this point. From the point A in (a), extend a line AO parallel with ao in (b). Extend the line of action

of the force W acting on the beam until it intersects this line just drawn at the point O . From the point O thus found, draw a line OB parallel with ob in (b) and designate the point of intersection of this line and the line of action of the reaction R_2 , as B . Connect the points A and B just found in this diagram, and returning to the diagram (b), extend from the pole, or point o , a line coincident in direction with the line AB in (a). Where this line intersects the line ab , designate the point as z . Fig. 16 (b) is known as the *force polygon*, while Fig. 16 (a) is known as the *equilibrium*, or *funicular, polygon*.

On analyzing these diagrams, it is found that the distances oz and za are equal and since ab represents the amount of the load and bz and za are one-half of the load, it is evident that these two forces represent, in amount and direction, the reactions R_1 and R_2 . No matter where the pole o had been chosen or assumed, the result would have been the same, for the line oz is always drawn parallel with the line AB found in the equilibrium polygon. On scaling the lines ao and bo in Fig. 16 (b), the amount of the oblique forces necessary to create equilibrium, when acting in the direction shown, is found, and oz is the thrust exerted or the compression produced in the strut introduced between A and B in (a).

A few explanations at this point may help the student in understanding the meaning of the various lines in force and funicular polygons. When the line ab , Fig. 16 (b), representing the total load W , has been laid off, and a pole o selected, from which the lines oa and ob are drawn, the force ab has been resolved into the components ao and bo . This construction is based on the triangle of forces, with this difference, that here the resultant ab is given and the components found. It is clear that there is a great latitude as to the selection of location of the point o , and therefore of the direction and magnitude of these components.

In a force polygon, any of the components may be resolved into other components, the direction of which may have been given. For instance, in Fig. 16 (b) it is desired to resolve the forces ao and ob into components, two of which will be

vertical and two parallel with the line AB in the funicular polygon. The line oz , Fig. 16 (*b*), was drawn parallel with AB and constitutes a component that will be common both to ao and ob ; the other component for ao will be az and for ob will be bz . The force triangle, or polygon, $ao b$ has thus been divided into two smaller triangles, in one of which the force ao has been resolved into the two components az and oz , while the other force ob has been resolved into the components oz and bz . It is evident that the force oz can be resolved into other components and these again into others; in fact, this process may be carried on indefinitely.

In constructing the funicular polygon in Fig. 16 (*a*), only the total load $W = ab$ and its components ao and ob were given. The known component of R_1 , that is, ao , which is also one of the components of W , was drawn through the point A and intersected the line of action of the force W at O . From this point, a line was drawn parallel with the component ob in the force polygon, and intersecting the line of action of the reaction R_2 at B . The lines AO and OB represent the components of the load W , the directions and magnitudes of which were determined by the selection of the point o in Fig. 16 (*b*). As the lines of action and magnitude of the other components of the reactions R_1 and R_2 must be the same, they must of necessity be located on the line connecting the points A and B . The line oz in the force polygon parallel with AB , will determine the magnitude of the other components of the reactions R_1 and R_2 , az being the vertical reaction R_1 , bz the other reaction R_2 , and oz the components along the line AB .

To illustrate the locations and actions of the various components more clearly, Fig. 16 (*c*) has been introduced. In it AA_1 and AO represent the components of the reaction R_1 , AO and OB , those of the load W , and OB and BB_1 , those of the reaction R_2 . In general, it is understood that the lines of action of the components AA_1 and BB_1 are located along the line AB and it is therefore unnecessary to show them separately, as has been done in this case.

The directions in which the various components act are

found from the force polygon in the manner described, but it is necessary to bear in mind that when a certain force in a polygon is to establish equilibrium, its direction conforms to that of the other forces, but if it is to serve as a resultant, it must act in the opposite direction.

Considering the structure in (a) as a cord suspending a weight with its ends separated by a compression member in the position of AB , it is evident that the force polygon (b) contains the reaction diagram giving the reactions az and zb for each end of the equilibrium polygon. In Fig. 16 (d), which represents the weighted cord, the reactions R_1 and R_2 coincident in direction with the lines of action of the cord, are the only forces required at the ends of the cord to preserve equilibrium. These reactions are represented in the force polygon by ao and bo , and are equal to the tension in the cord. For the reactions, the two components could be substituted as shown in (d) by the dotted lines; without the reactions these forces would create equilibrium. The components of the oblique reaction R_1 in (d) are represented in the force polygon by za and oz , while the corresponding components of R_2 are bz and zo .

Another pole could have been chosen and the force polygon drawn as at (e), in which case the equilibrium polygon would have changed correspondingly, assuming the form shown in (f). It will be noticed from (e) that the vertical components bz and za of the oblique reactions always remain the same length and consequently the same amount when oz is drawn parallel with AB in the diagram (f). The direction of the reactions coincident with the direction of the cords and the oblique components of this reaction are alone changed.

21. Assume the conditions of loading shown in Fig. 17 (a). The load W of 1,000 pounds is not centrally placed on the beam; consequently, the principle of moments involved in the theory of beams makes the reaction R_1 considerably less than R_2 . Lay off in the force polygon, Fig. 17 (b), to a scale of $\frac{1}{4}$ inch equals 100 pounds, the line ab equal

to 1,000 pounds. Intersecting at any pole o draw ao and bo . From the point A , in (a), extend a line parallel with ao and intersecting the line of action of the weight or the force W extended, at the point O . From O , draw a line parallel with bo , Fig. 17 (b), intersecting the reaction R_1 at B . Connect A and B as before, and from o in (b) draw a line parallel with AB in the equilibrium polygon and intersecting ab . By measuring bx and xa , the reactions R_1 and R_2 will be found to equal 770 and 230 pounds, respectively.

The student should not be guided by the size of these diagrams, as the size of those employed in practice for solving graphical problems should be considerably larger to give




FIG. 17

accurate results. The stress diagram would be laid out to a scale of from 500 pounds to 5,000 pounds to 1 inch, while the scale used for the frame diagram would be from $\frac{1}{8}$ inch to $\frac{1}{2}$ inch to the foot.

22. The application of the force and equilibrium polygons for determining the reactions of non-concurrent forces is not limited to a beam or structure supporting one weight, for they can be used for obtaining the reactions of a simple beam supporting any number of loads acting in any direction. For example, assume that a beam, Fig. 18 (a), supports the two loads W_1 and W_2 , which are placed at the position fixed

by the given dimensions. In order to determine the reactions R_1 and R_2 , lay off the force polygon (b) by drawing the load line ac and, measuring with some convenient scale, make ab and bc equal, respectively, to W_1 and W_2 . Choose any pole o and connect it with the points a , b , and c by radial lines. Draw the equilibrium polygon by commencing at A and drawing AO parallel with ao of the force polygon, intersecting the line of action of the load W_1 at O . From this point, draw a line parallel with the line ob in the force polygon, intersecting the line of action of the load W_2 at B . Finally, draw from B a line parallel with oc in the force polygon and intersecting the reaction R_2 at C . Connect A and C , as explained in the previous cases, and from o in the force polygon draw a line parallel with AC , intersecting the load line at z ; the reactions R_1 and R_2 are found by scaling za and cz . If, in the equilibrium polygon, AO and CB are extended until they intersect at the point O_1 , a vertical line drawn upwards from O_1 will divide AC into two such parts that the ratio of X to X_1 will be inversely proportional to the ratio of R_1 to R_2 ; the amount of R_1 and R_2 may be found by designating AC equal to the sum of the loads W_1 and W_2 , when R_1 will have the same ratio to the total load as X_1 to the whole distance AC , and R_2 will bear the same relation to the total load as X to AC .




FIG. 18

23. The example shown in Fig. 19 (a) is similar to the one just described with the exception that several loads are

applied and there are vertical loads also at each end of the beam. The force polygon, Fig. 19 (b), is drawn as in the previous cases, and in drawing the equilibrium polygon the lines of action of the several forces are extended as shown by the dotted lines. In drawing this equilibrium polygon, however, it will be noticed that the line marked 1 is parallel with the second line from the top of the force polygon or




FIG 19

$b o$, and that the first line of the force polygon $a o$ is represented in the equilibrium polygon by $A O$, while reference to the right-hand end of the figure will show that the line marked 5 in the equilibrium polygon is parallel with the line marked o in the force polygon. The reason for this is that the loads W_1 and W_6 are coincident with the reactions R_1 and R_2 , respectively. When the load W_1 , represented in the force polygon by the force $a b$, is resolved into its two

components oa and ob , these should, as already explained, be laid off on either side of the line of action of the load W_1 , one intersecting the reaction R_1 , and the other the line of action of load W_2 . In this case the forces W_1 and R_1 being coincident, only the component ob can be drawn. The same conditions prevail at the load W_2 . While the loads W_1 and W_2 , on account of their position, produce no stress in the girder, yet they add their share to the total load and will therefore have to be included among the forces in the force polygon, in this manner affecting the position of the point z and, as a consequence, the amount of the vertical reactions R_1 and R_2 . If the forces ab , bc , . . . fg were combined, they would equal the total load and would be represented by the line ag , the components of which would be oa and og . If AO and OB were drawn parallel with these components they would intersect at the point O , which would be located on the line of action of a load, the location and magnitude of which would be such that it would have the same effect as the six loads. The point of intersection O of the lines AO and BO is the center of action of the loads; that is, a vertical force equal and opposed to the loads when located at this point will just balance the loads and create rotary equilibrium, or conversely, it is the position at which a weight, equal to the weights on the beam, suspended from the point O on a cord fastened at A and B will produce the same reactions as the weights on the beam. The reactions at the end of the beam, which are found by measuring za and gz , are represented in the equilibrium polygon by R_1 and R_2 . The construction of the equilibrium polygon as described usually exists where there are two end loads on the beam or structure, and the student should always bear in mind the fact that the equilibrium polygon is contained between the lines of action of the reactions, and that in the equilibrium polygon there exists the same number of lines as radiate from the pole o in the force polygon.

24. The solution of the complicated problem shown in Fig. 20 (*a*) is as readily accomplished as in the simpler






FIG. 20

cases previously assumed. The several loads need not be laid off in the force polygon in the regular order, as shown in Fig. 20 (*b*); but in whatever order they are laid off in the force polygon, the same sequence must be observed in laying out the equilibrium polygon. Hence, the load line of the force polygon may be obtained by laying off the loads W_1, W_2, W_3, W_4 , and W_5 , as shown in Fig. 20 (*c*); and by connecting the points at the ends of the load line, as designated by the line ab , the direction of the reactions at the ends of the beam is found. Choose any pole o and draw radial lines to the end of each force on the load line. The reactions R_1 and R_2 in the equilibrium polygon will then lie in the direction of the line ab in either force polygon, and both equilibrium polygons will be included between these two lines.

Both equilibrium polygons are shown in Fig. 20 (*a*); the one corresponding to the force polygon at (*b*) is shown with solid lines, while the one described from the force polygon (*c*) is shown with dot-and-dash lines. In drawing the latter, commence at the point A on the line of action of the reaction R_1 and draw the line marked 1 of the equilibrium polygon parallel with the first radial line in the force polygon. This line in the force polygon connects the intersection of the reaction line az and the force or load w_1 with the pole o and should, consequently, be drawn in the equilibrium polygon from the line of action of the reaction R_1 to the line of action of W_1 . From this intersection, draw line 2 parallel with the line in the force polygon similarly marked; this extends to the line of action of the force W_2 , since line 2 in the force polygon connects the intersection of loads w_1 and w_2 to the pole o .

Draw from this intersection, line 3 parallel with the ray 3 in the force polygon, intersecting at W_3 extended. Proceed in this manner around the entire equilibrium polygon until the point B has been obtained. From B in the equilibrium polygon draw a line to the point A and draw from o in the force polygon a line parallel to AB intersecting the line of the reactions at z . The required reactions are measured

from b to z and from z to a , and are equal, by measurement, to R_1 and R_2 , respectively.

The system of non-concurrent forces W_1, W_2, W_3 , etc. can be held in equilibrium by either one of two systems of reactions: first, by reactions acting in the direction of BO and AO in the equilibrium polygon and equal in amount to the forces determined by measuring ob and oa in the force polygon (c); second, by the reactions R_1 and R_2 and the thrusts h_1 and h_2 , these forces being the components of ao and ob in (c).

It is shown in this solution, by comparing the diagrams (b) and (c), that the reactions have the same amount and direction no matter in what order the loads are taken, if the same sequence is followed in drawing the equilibrium polygon. To make this clearer, it may be further stated that in drawing the equilibrium polygon, all that need be observed is that, commencing at the point A , the lines 1, 2, 3, 4, etc. of the equilibrium polygon are laid off between the lines of action of the several forces and extended in the direction determined by the ray in the force polygon relating to the particular force in the equilibrium polygon from which it is drawn. Thus, the line 1 in the equilibrium polygon, extending between the lines of action of the reaction R_1 and the load W_1 , corresponds with line 1 in the force polygon drawn from the intersection of the line az , which represents the reaction R_1 , and the load line w_1 . The line 2 in the equilibrium polygon corresponds with ray 2 in the force polygon and is drawn from the point of intersection of line 1 and the line of action of W_1 extended. Likewise, line 3 in the equilibrium polygon coincides in direction with ray 3 in the force polygon and is drawn from the intersection of line 2 with the line of action of W_2 extended.

The reason for this method of constructing the equilibrium polygon from the force polygon, Fig. 20 (c), is easily seen when it is remembered what was stated in Art. 23 regarding the components of each of the forces on the load line ab . In each of the force triangles into which the force polygon has been divided, the two rays are components of the force

that constitutes the third side. Lines drawn in the equilibrium polygon parallel with these components should in each case intersect on the line of action of that load or force that, in the force polygon, is represented by the third side of the triangle in which the components are located.

The lines in the equilibrium polygons, which are drawn through the points O and O_1 in the direction of the reactions, give the positions on the lines AB and AB_1 , respectively, at which it would be necessary to apply a force equal to the sum of the reactions and acting in their direction, to balance the loads and to produce both rotary and translatory equilibrium. In this instance, these lines are coincident and pass through both points O and O_1 .

The results obtained from the two force polygons will be the same, though probably it is always more convenient to take the forces in the order in which they occur. The student should thoroughly familiarize himself with the principles involved in the application of the equilibrium and force polygons; and that he may understand the usefulness of this system of analysis, he should work out for himself by the graphical method the problems called for in the following examples.

EXAMPLES FOR PRACTICE

1. A main girder, having a span of 40 feet, is subjected to the superimposed loads shown in Fig. 21; determine the amount of the reaction at both ends, by the graphical method. Ans. $\begin{cases} R_1 = 7,184 \\ R_2 = 5,516 \end{cases}$




FIG. 21

2. A steel I beam is required to sustain the foot of a slanting column or strut forming one of the supports of a water tank, as

shown in Fig. 22; what will be the direction of the reactions on the walls and their amounts, by the graphical determination, provided the compression in the strut equals 3,000 pounds?




FIG. 22

from a hoist and traveler, as shown in Fig. 23; what direction and

Ans. { Direction: same as load
Amounts: $R_1 = 1,275$
 $R_2 = 1,725$

3. A pair of light steel channels in a machine shop is subjected to the pull of several belts and is also required to sustain a load




FIG. 23

amounts will the graphical method give the reactions at the column supports?

Ans. { Direction: approximately
13° with vertical axis
Amounts: $R_1 = 2,050$
 $R_2 = 5,050$

APPLICATION OF GRAPHICAL ANALYSIS

SCOPE OF GRAPHICAL SOLUTIONS

25. The study of the composition of forces has shown that the final effect of two forces can be represented by a third force having a different direction and intensity; and also that any oblique force can be resolved into its vertical and horizontal components. Therefore, when the direction and intensity of one of three forces acting at a joint or connection in a framed structure are given, the other forces can be obtained, provided that the directions or amounts of both, or




FIG. 24

the direction and amount of one are known; for instance, the forces ab in Fig. 24 (a), (b), and (c) are known both as to intensity and direction. It is assumed in the case shown in (a) that the amount of each of the two unknown forces is given and that in order to determine these forces it is necessary to know the direction in which they act. To find the unknown directions of the two forces the dividers should be set to scale for one of the forces and an arc struck from a , as designated. The dividers being then set for the other

force, an arc is struck from b and their intersection at c determines the direction of ac and cb . In (b) the directions of the two unknown forces are known either from the fact that they are parallel with another line already determined, or because the angle that they make with ab is known. Assuming that the angle that the unknown force extending from a makes with the line ab is 60° , the line representing this force may be extended indefinitely, as shown. If the angle of the force drawn from b , with reference to ab , is equal to 45° , it is evident that a line drawn at this angle from b will intersect the other force at c . Then by scaling ac and bc the two unknown forces are completely determined, that is, both their direction and intensity are known. In (c) the direction and intensity of both ab and ac are known; therefore, the point c can be located by scale and bc drawn. Consequently, both the direction and amount of bc may be obtained in this manner.

26. From the foregoing it has been determined that the following statements are true of any system of three forces:

1. That the unknown direction of two forces can be obtained when their amounts and the amount and direction of the third force are known.
2. That the amount of two unknown forces may be found when their direction and the amount and direction of the third force are known.
3. That the direction and amount of a force may be obtained when the direction and the amounts of the other two forces are known.

In the application of graphical statics, the truth conveyed by the first statement is seldom employed, but the second and third principles form the basis of the science of graphical statics as applied in the solution of stresses in framed structures.

In Fig. 25 (a) is shown a diagrammatical figure that represents a panel point, or joint, on the rafter member of a roof truss. The known stresses about this point are the

compression in the lower portion of the rafter member and the vertical force W that represents the load at the panel point applied through the purlin that is secured to the frame at this position. These two known forces are shown by heavy lines, while the unknown stresses exist in the upper portion of the rafter member and the strut, the latter being designated by light lines.

Assume that the weight W is equal to 1,000 pounds and that the stress in the lower portion of the rafter member is 6,000 pounds. The problem is to determine the stress in the upper portion of the rafter member and in the strut. In (b), lay off on a line parallel with the rafter member, a distance equal, by scale, to 6,000 pounds. It is known that the direction of the stress in this member is upwards




FIG. 25

toward the joint, so that the line just drawn extends from a to b in the direction of the arrow, as shown. From b , the line bc is laid off equal, by the same scale, to the amount of W or 1,000 pounds, and downwards. The resultant of these two forces will extend, as shown by the dotted line, from a to c . Let this resultant, therefore, represent the base line on which the two unknown forces are to be constructed; that is, let it represent the line ac shown in Fig. 24 (a), (b), and (c). The length and amount of this resultant ac is known.

By applying, therefore, the second principle stated above, the amount of the two unknown forces may be found. In order to determine these forces, draw from c a line parallel with the rafter member and from a a line parallel with the strut. Then,

by measuring with the same scale to which ab and bc were laid off, the stress in the strut can be found from ad , while the stress in the upper portion of the rafter member is found by measuring cd . The polygon of forces around the entire joint extends from a to b , from b to c , from c to d , and from d to a ; since the polygon closes, the joint is in equilibrium of translation, and because the forces are concurrent, the joint has no rotary tendency. Though it was not necessary




FIG 26

to draw the resultant ac , this was done to show that every force polygon is made up of a series of triangles of forces, and the resultant of any number of forces of the system is obtained by a line connecting the end of any force with the point of commencement of the polygon. For instance, the resultant of ab and bc is ac , while the resultant of ab , bc , and cd is da ; in the same manner the resultant of bc , cd , and da is ab .

The application of the third principle is usually employed where it is necessary to determine one of the unknown forces by means of calculation, as will be further explained; it is also used in drawing the reaction diagrams. In explanation of

the latter, assume that in order to hold the foot of the roof truss designated diagrammatically in Fig. 26, there necessarily exists a vertical force, as shown by R_1 , and a horizontal thrust, as designated by H_1 . It is desired to determine the resultant of these two forces, in order to find at what position on the base line this force will intersect, so that it may be decided whether the abutment is in equilibrium. The amount of the thrust H_1 is laid off to scale, as shown. The reaction

R_1 is known and the points a and b are consequently located. The resultant will therefore extend from a to b , and when drawn from the center of the foot of the truss, the effect of these two forces on the abutment is determined and exists as shown.

DIAGRAMS

27. In the application of graphical statics to the determination of stresses in roof trusses and framed structures, the direction of all internal and external forces, excepting the reactions, are known, and the solution resolves itself into the determination of the amounts of the forces only. In order, therefore, that the direction of the several external and internal forces that are known may be applied in drawing the diagram for obtaining the stresses, it is necessary that an accurate outline of the truss or framed structure shall be laid out to scale. In this diagram, which is drawn according to the principal dimensions, the exact direction of all the external forces and the internal members, that represent the internal forces, are accurately designated. Such a diagram, which is practically the preliminary sketch or study of the structure, is called the **frame diagram**, from the fact that it represents the framework, or skeleton, of the structure. The diagram that is drawn in order to determine the stresses and in which each line represents graphically, in its relation with the other lines of the diagram, the several forces exerted on the structure, either internally or externally, is called the **stress diagram**, though sometimes erroneously termed *strain diagram*.

The frame diagram for a simple roof truss is shown in Fig. 27 (*a*); while the stress diagram is shown in (*b*) of the same figure. The frame diagram is drawn to a convenient scale of a certain number of inches to the foot, but since lines in the stress diagram represent forces in direction and intensity, the stress diagram is always drawn to a convenient scale of pounds equal to some unit of linear measurement, such as 1 inch; for instance, the frame diagram shown in the figure may be drawn to a scale of $\frac{1}{4}$ inch = 1 foot, while the

stress diagram may be laid out to such a scale that every inch in the length of the line represents 1,000 pounds, or if a tenth scale is used each $\frac{1}{10}$ inch equals 100 pounds. The lines in the frame diagram representing the forces are never drawn to scale, as they simply show the direction of the forces. Sometimes, however, it is customary to lay out a stress diagram upon or connected with the frame diagram in order to obtain, possibly, the vertical or horizontal components of an oblique force, or to find the resultant reaction




FIG. 27

for a system of forces representing the independent reactions due to different external forces acting on the structure; for example, in Fig. 28 is shown, in light lines, a stress diagram drawn in conjunction with the frame diagram. Here it was deemed expedient to determine one force, such as R_1 , that would equal in effect the horizontal force H_1 , the vertical force V_1 ,

and the oblique force O_1 . The direction and amount of the resultant R_1 was found by laying off, to scale, the amounts of V_1 , H_1 , and O_1 on their respective coincident or parallel lines, ab , bc , and cd , the resultant R_1 being equal in intensity and direction to da . When this force R_1 is introduced instead of the three forces, the equilibrium of the structure is still maintained.

In drawing the frame diagram, any usual scale, as $\frac{1}{8}$, $\frac{1}{4}$, $\frac{3}{8}$, $\frac{1}{2}$, or $\frac{3}{4}$ inch to the foot, can be used, though probably the $\frac{1}{8}$ - and $\frac{1}{4}$ -inch scale will be found most convenient. In laying out stress diagrams, the tenth scale can be more

readily employed than the usual inch scale divided into 8ths and 16ths.

28. The frame and stress diagrams are often called *reciprocal diagrams*, from the fact that for every system of forces in the frame diagram there exists in the stress diagram a series of lines that are respectively parallel with the lines of the forces in the frame diagram; and for every joint at which a system of concurrent forces exists in the frame diagram, there is a corresponding polygon of forces in the stress diagram. In determining the stresses on any framed structure, it is usually necessary to draw several stress




FIG. 28

diagrams; for instance, to find the stresses existing in the truss, it is customary to draw at least a vertical-load diagram and a wind-load diagram, and sometimes it is advisable to draw also a snow-load diagram and even a stress diagram for the wind load on one side of the roof and the snow load on the other. For each stress diagram, the frame diagram remains the same, with the exception that the direction and amounts of the loads at the panel points, as well as the reactions, change. Oftentimes, one outline of the framed structure embodies all of the forces acting on the truss, though where a number of stress diagrams are to be drawn,

considerable confusion is usually avoided by drawing separate frame diagrams. In the design of all roof trusses, the wind and vertical loads should be considered separately, though the less conservative engineers do not consider the separate effects of the wind and snow on spans of less than 100 feet.

NOTATION

29. In order that the external forces or the internal stresses exerted in the frame diagram may be intelligently designated in the stress diagram, so that by inspection one may know that a particular line in the stress diagram designates the amount and intensity of the stress in a particular member in the frame diagram, some convenient notation must be employed. A notation should be used such that, in analyzing the stresses around a single joint, the polygon of forces may be readily traced and the completion of the polygon of forces will be immediately known when the point from which the polygon was started has been finally reached. The system of lettering, or notation, commonly used in graphical statics, consists in placing a capital letter in every space throughout the frame diagram between the several members and the forces acting externally. The lettering is usually commenced at the left-hand end of the diagram and runs around the figure in the direction traveled by the hands of a clock; the internal spaces are then lettered in alphabetical order, commencing likewise at the left-hand end of the figure. The middle point of the diagram, or that space included between the two principal reactions, is usually denominated by the letter *Z*.

In Fig. 29 (*a*) is shown a frame diagram lettered with the notation just described. The first vertical load at the left-hand end of the truss is known as the load, or force, *AB*; the second load as *BC*, etc. The three divisions of the tie-member beginning at the left are designated as *GZ*, *IZ*, and *KZ*, while the several portions of the rafter members are known as *GB*, *CH*, *JD*, and *EK*. The struts are *GH* and *JK*, while the tension rods are denominated *HI* and *IJ*.

The stress diagram that would be laid out in order to analyze the stresses in the frame diagram at (a) is shown at (b); the same letters designate the stresses or forces similarly marked in the frame diagram, with the exception that small, or lower-case, letters are used instead of capitals; for instance, ab represents to scale the force AB ; bc represents the direction and intensity of the force BC ; cd




FIG. 29

likewise stands for CD in the frame diagram. The reaction R_1 is designated in the stress diagram by za , while fz will give, on measuring, the amount of the reaction R_2 .

The convenience of this notation consists in the fact that the frame and stress diagrams bear a peculiar relation to each other in that where any system of forces in the frame diagram acts at a single point, there is a corresponding closed polygon represented in the stress diagram. For

example, the apex of the truss is a point at which five forces meet: they are the vertical load CD , the stress in the right-hand rafter member DJ , the stress in the oblique tension member JI , and the stresses in the left-hand rafter member and tension member, respectively, designated as II' and $I'H$. In the stress diagram these forces do not meet at a single point, but form the polygon $cdjth$, the last line hc of the polygon making a closed figure. On the other hand, any closed figure in the frame diagram, such as the triangular space including the letter G , is designated in the stress diagram by a number of lines meeting at a common point; that is, the space G in the frame diagram is enclosed by the members of the frame designated as BG , GZ , and GH , while in the stress diagram the lines that represent the stresses in these several members meet at the point g , and are bg , gz , and gh .

It is not absolutely necessary to use this system of lettering, for any letters or numbers may be employed, so long as no two spaces in the truss are marked alike. It is well, however, to have some definite system in engineering work, and the foregoing, being as convenient as any that can be suggested, is universally adopted.

DETERMINATION OF EXTERNAL FORCES

30. Before the stress diagram for any framed structure can be drawn, it is necessary to complete the polygon of external forces, which consists of the loads on the frame and their reactions. This step is one of the most important in graphical solutions; for if this polygon is incorrectly laid out, it will be impossible to close the stress diagram. The loads supported on a frame are always considered as concentrated at the joints of the frame; in designing roof trusses, the purlins are either located at the joints along the rafter members or else the loads are considered as being transmitted to these points by the transverse strength of the member between the panel points. In Fig. 30 is shown a simple roof truss with its loads and reactions. The panel

points, at which the loads on the rafter members are considered as being concentrated, are a , b , c , d , and e . The load at a is the portion of the wind pressure or the weight of the roof supported by one-half of the portion of the rafter member between a and b , while the load on the joint b would be the wind pressure, or the weight of the roofing material supported by one-half of the rafter member, or one-half of ab and bc . The load at the apex of the roof is equal to the weight on one-half that portion of the truss included between bc and cd .

The principal difficulty in determining the polygon of external forces is to find the amount of the reactions, or the forces opposed to the loads, in order to create equilibrium in the structure. When the frame or truss is symmetrical and the




FIG. 30

line of action of the reactions is parallel with the direction of the loads, the reactions are obtained by inspection, for they are each equal to one-half the sum of the loads on the truss or frame. Should the truss or frame, however, be unsymmetrically loaded or should the reactions be other than parallel with the line of action of the loads, their direction must be assumed and their amounts determined by calculation, or both their amounts and direction may usually be found by the graphical method.

DETERMINING THE REACTIONS BY CALCULATION

31. The method of determining, by calculation, the reactions for any framed structure involves the principle of moments. If the frame will always be regarded as a solid section or body acted on by external forces, in this way

eliminating the internal members or stresses, little difficulty will be experienced in determining the method of procedure for finding the reactions.

In Fig. 31 (*a*), (*b*), and (*c*) is shown a type of simple roof truss loaded in several different ways. In each instance, to determine the reactions by calculation, it is first necessary to evolve the formula and then, deciding on certain values, make the necessary calculations.

In (*a*) is shown a truss unsymmetrically loaded, that is, corresponding loads each side of the center line are not of the same amount, so that the reactions will not each be equal to one-half of the total load on the truss, though from the fact that the reactions coincide with the direction of the loads, it is known that the sum of the reactions is equal to the sum of the loads.

In order to determine the reaction R_1 , the truss is considered as being hinged at the point c and the algebraic sum of the moments of all the external forces about this point should equal zero, or the sum of the moments of the loads equals the moment of the reaction R_1 , the latter moment being the product of R_1 and the length S . If the sum of the moments due to the loads is divided by the lever arm of R_1 , the amount of R_1 will be determined. If the loads on this truss are represented by w_1, w_2, w_3 , etc., and their respective lever arms about the point c designated by x_1, x_2 , etc., the algebraic sum of the moments about the point c will equal $w_1 x_1 + w_2 x_2$, etc.; and since the lever arm of R_1 is equal to the span of the truss, or S , the amount of R_1 may be determined by the expression

$$R_1 = \frac{w_1 x_1 + w_2 x_2 + w_3 x_3 + w_4 x_4}{S} \quad (1)$$

As the load w_1 is coincident with the reaction R_1 , its moment is zero and is therefore not included in the formula.

For example, assume that the span of the truss is equal to 40 feet and that the distances x_1, x_2, x_3, x_4 are equal, respectively, to 10, 20, 30, and 40 feet; w_1 equals 1,000 pounds; w_2 equals 2,000 pounds; w_3 equals 2,500 pounds; w_4 equals 800 pounds; w_5 equals 600 pounds.




FIG 31

Since the calculation for moments can best be systematically arranged by tabulation, the sum of the moments of the loads will be expressed as follows:

$$w_1 x_1 = 2,000 \text{ lb.} \times 10 \text{ ft.} = 20,000 \text{ ft.-lb.}$$

$$w_2 x_2 = 2,500 \text{ lb.} \times 20 \text{ ft.} = 50,000 \text{ ft.-lb.}$$

$$w_3 x_3 = 800 \text{ lb.} \times 30 \text{ ft.} = 24,000 \text{ ft.-lb.}$$

$$w_4 x_4 = 600 \text{ lb.} \times 40 \text{ ft.} = 24,000 \text{ ft.-lb.}$$

$$\text{Total moment about } c = 118,000 \text{ ft.-lb.}$$

The moment of R_c about the point c must equal the sum of the moments of the loads, and hence the reaction R_c equals $118,000 \div 40$, or 2,950 pounds. The sum of the reactions must equal the sum of the loads, and since the sum of the loads equals 6,900, the amount of R_c will equal $6,900 - 2,950$, or 3,950 pounds.

The polygon of external forces, as designated at (a_1) , may now be laid out, and because all the external forces on the truss are coincident in direction, the force polygon will extend in a straight line. This polygon will be laid out from a to b , from b to c , from c to d , from d to e , from e to f , and back from f , locating the point z , by scale, at a distance from f equal to the reaction R_c , or 2,950 pounds, as determined by the calculation. If the polygon of the external forces has been accurately laid out, the distance za will, on scaling, be found to equal the reaction R_c , or, as determined, 3,950 pounds.

32. In Fig. 31 (*b*) is shown the frame diagram of a roof truss sustaining on the left-hand rafter member, at the several panel points, the wind loads P_1 , P_2 , and P_3 . It is considered that the roof truss is securely fixed to a wall or other support at both ends, and under such conditions the reactions coincide with the direction of the normal wind loads. Since this is similar to the preceding case, the sum of the reactions is equal to the sum of the loads, but the reactions, by inspection, are evidently not equal to each other.

The amount of R_c may be determined by considering the moments of the external forces with the point c as the center of moments. The lever arms of the loads P_1 , P_2 , are not, as

before, horizontal, but being at right angles with the line of action of the wind pressure, which is normal to the slope, they are parallel with the rafter member or slope. The reaction R , does not act, in this instance, with a leverage equal to the span of the truss, but exerts its force through a lever arm at right angles to its action, as represented by S_1 , and this distance may be obtained by extending the line of action of R , and scaling, or it may be calculated. The distance S_1 is always equal to the span of the truss divided by the secant of the angle x ; or expressed algebraically, where S = the span of the truss, $S_1 = \frac{S}{\sec x}$. In

case a secant table is not at hand, S_1 can also be found by means of the cosine of the angle x , as follows: $S_1 = S \cos x$.

The equation for determining the reaction R , of the roof truss shown in (b) may then be expressed by the formula

$$R = \frac{P_1 x_1 + P_2 x_2}{S_1}$$

which is the same as

$$R = \frac{(P_1 x_1 + P_2 x_2) \sec x}{S}$$

or

$$R = \frac{P_1 x_1 + P_2 x_2}{S \cos x} \quad (2)$$

To apply this information it will be assumed that it is desirable to obtain the amount of R , when $P_1 = 2,000$ and $P_2 = 1,000$ pounds, the distances x_1 and x_2 being equal, respectively, to 11.43 and 22.86 feet. The angle x is, approximately, 29° ; then S_1 equals the secant of 29° , or 1.14335 divided into the span, or 40 feet, which gives 34.98 feet. When this value has been obtained, the calculation for the reaction R , will be as follows:

Positive moments of wind pressure about the point c are:

$$P_1 x_1 = 2,000 \text{ lb.} \times 11.43 \text{ ft.} = 22860 \text{ ft.-lb.}$$

$$P_2 x_2 = 1,000 \text{ lb.} \times 22.86 \text{ ft.} = 22860 \text{ ft.-lb.}$$

Total moment due to wind pressure = 45720 ft.-lb.

This moment, in order that the frame may be held in equilibrium, must be equal to the moment of R , about the point c , and by dividing the amount just obtained by S_1 , R , is

found to be equal to $45,720 \div 34.98$, or 1,307 pounds. The amount of R_1 is found by deducting the amount of R_2 from the sum of the loads; therefore, if P_1 equals 1,000 pounds, R_1 equals $4,000 - 1,307$, or 2,693 pounds.

The stress diagram, or polygon of external forces, for the frame shown in (b) is designated in (b₁). The load line in this instance is oblique, since it must coincide with the direction of the external forces, and when the forces $a b$, $b c$, and $c d$ have been laid off and the amount of the calculated reaction R_1 measured from d , thus locating the point z , the length measured from z to a , by scale, will check the calculations, if it equals R_1 . Having in this manner located the point z , the polygon of external forces will extend from a to b , from b to c , from c to d , from d back to z , and from z to the starting point, thus completing the figure.

33. The frame shown in Fig. 31 (c) is loaded with several oblique panel loads caused by the wind pressure; the moments of these loads about the point c are determined in the same manner as were the moments of the loads shown in (b). In this instance, however, the truss is considered as being supported on a roller bearing at the right-hand end in order to allow lateral play for the contraction and expansion of the metallic frame. This bearing is regarded as frictionless, so that there is no horizontal resistance whatever, in consequence of which condition the reaction R_1 under a roller bearing is always considered as vertical in direction. Hence, the problem resolves itself into the determination of the amount of this reaction R_1 . The sum of the moments due to the several wind loads on the rafter members is the same as for the frame in (b) and is equal to $P_1 x_1 + P_2 x_2$. The leverage of R_1 , since it acts vertically about the point c , is equal to the span of the truss, so that the amount of the reaction R_1 is determined from the formula

$$R_1 = \frac{P_1 x_1 + P_2 x_2}{S} \quad (3)$$

For example, assume that P_1 and P_2 equal, respectively, 2,000 and 1,000 pounds, while x_1 and x_2 equal 11.43 and

22.86 feet; the span, as before, being equal to 40 feet, then

$$R_2 = \frac{2,000 \times 11.43 + 1,000 \times 22.86}{40} = 1,143 \text{ pounds}$$

The other reaction, or R_1 , is not vertical, because the truss is fixed at the end, and in consequence the actual sum of the reactions is not equal to the sum of the loads.

It is known, however, that for any frame to be in equilibrium, the algebraic sum of the vertical and horizontal components of all the forces acting on that frame must equal zero. The reaction R_2 is vertical, and consequently has no horizontal component. It is evident, therefore, that the reaction R_1 must have a horizontal component equal to the horizontal components of all the loads, in order that the algebraic sum of the horizontal components of all the loads acting on the truss may be equal to zero. Each of the wind loads P_1 , P_2 , and P_3 may be regarded as one side of a triangle in which its components constitute the remaining sides. Knowing that the angle x_1 is equal to the angle x , the value of either of the components may be found by means of one of the trigonometric functions. Thus, the horizontal component is equal to $P \sin x_1$, and the sum of the horizontal components of the three oblique forces on the rafter member will equal $(P_1 + P_2 + P_3) \sin x_1$. The sine of 29° is equal to .48481, and the sum of the loads P_1 , P_2 , and P_3 is equal to 4,000 pounds, so that the sum of the horizontal components of the oblique forces, or H , equals $4,000 \times .48481$, or 1,939 pounds.

Having in this manner obtained the horizontal component that R_1 must possess in order to equal the horizontal components of the loads, it is necessary in a similar manner to determine the vertical component of R_1 . Since R_1 acts vertically, its amount must be subtracted from the sum of the vertical components of the oblique forces P_1 , P_2 , and P_3 . Trigonometrically, the sum of the vertical components of the pressures equals $(P_1 + P_2 + P_3) \cos x_1$, or substituting the values, the vertical component $V = 4,000 \times .87462$, or 3,498 pounds. From this must be deducted the entire amount of R_2 , and when this is done there remains for a

vertical component of R , an amount equal to $3,498 - 1,143 = 2,355$ pounds.

It is now evident that since both the vertical and horizontal components of R , have been obtained, the amount and direction of R , may be found.

The amount of R , may be found by considering the vertical and horizontal components as the two sides of a right triangle and calculating the hypotenuse by the rule of Pythagoras, that is, by taking the square root of the sum of the squares of the vertical and horizontal components.

Employing this method, $R = \sqrt{2,355^2 + 1,939^2}$, or 3,050. The direction of this reaction is still to be determined. The angle y that it makes with the vertical may be found by either

of the following trigonometric functions: $\secant y = \frac{R}{V} = \frac{3,050}{2,355}$, or $\cosine y = \frac{V}{R} = \frac{2,355}{3,050}$. In the absence of a

secant table, the latter formula is used. It will be found from the above that $\secant y$ equals 1.295, and $\cosine y$ equals .7721, either of which corresponds to an angle of about $39^\circ 30'$; therefore, the reaction R , will be of the intensity calculated, or 3,050 pounds, and will extend in a direction to the right of the vertical at an angle of $39^\circ 30'$.

The calculations for R , need not have been made, for both its intensity and direction could be obtained graphically by laying out the polygon of external forces. Fig. 31 (a, b, c) shows the polygon of external forces for the frame shown in (c). The load line extends from a to b , from b to c , from c to d , and then, since the reaction R , is the vertical distance from d to the point z , the distance from d to z is made equal to the amount of the reaction R , or 1,143 pounds. When the point z has been located, the amount of the reaction R , and its direction may be determined by a line connecting the points z and a . If this line in the particular example that has been considered measures, to scale, 3,050 pounds and extends in a direction of $39^\circ 30'$ with the vertical, it will coincide with the values obtained by the calculation and will check the diagram. The polygon of external forces in this

case will then extend from a to b , from b to c , from c to d , from d vertically to the point z , and from z back to the starting point of the polygon or a .

GRAPHICAL METHOD OF OBTAINING THE REACTIONS

34. The reaction of a system of forces acting on a framed structure may be entirely determined by the graphical method. It is assumed that the roof truss shown in Fig. 32 (a) is loaded with the vertical loads AB, BC , etc. at each panel point and that it is desired to obtain the




FIG. 32

amount of the reactions R_1 and R_2 . If the loads had been symmetrical in amount on each side of the truss, these reactions would have been equal and would have corresponded in amount with one-half the load on the truss. It will be noted, however, that the right-hand half of the truss is more heavily loaded than the left-hand portion, and therefore the reactions will not be equal. Before the stress diagram can be drawn, the unknown external forces R_1 and R_2 must be obtained in

order that the location of the point z in the stress diagram may be determined. These reactions can be calculated by the principles of moments explained in Art. 31, or they can be determined by the graphical method. This method consists in drawing the force polygon (b), and from this constructing the equilibrium, or funicular, polygon (c).

In laying out the force polygon, lay off the load line designated from a to f . While it is more systematic to lay off the loads on this line in the order in which they occur around the truss, it is not necessary that this procedure should be followed, for these loads may be laid off in any convenient succession. Each portion, however, of the load line must truly represent, to scale, the amount of the force that it designates and its direction. Any point or pole o is selected and lines are drawn from it to the several divisions on the load line. The figure will then appear as shown, with the exception that the line oz has not as yet been determined, for the direction of this line is what is required in order to find the amount of the reactions R_1 and R_2 . Having completed the force polygon (b), proceed with the equilibrium polygon (c). In drawing this polygon, first extend the line of action of all the forces acting on the frame, as shown by the dotted lines, and commence the diagram at the left-hand end by drawing the line 1 parallel with bo in the force polygon and from the intersection of the line 1 with the line of action of the force BC draw line 2 parallel with co in the force polygon; and where this line intersects the line of action of CD draw the line 3 parallel with do . Likewise, from the intersection of 3 with the line of action of DE , draw 4 parallel with eo in the force polygon. This latter line will intersect the line of action of R_2 , and from this intersection f_2 draw f_2o in the same direction as of in the force polygon, while from a_1 , the left-hand end of the equilibrium polygon, extend the line a_1o parallel with ao in the force polygon. Connect the points f_2 and a_1 in the equilibrium polygon and draw from o in the force polygon a line parallel with f_2a_1 . The intersection of this line oz , or 6 in the force polygon, will divide the vertical load line into

fz and za , which, to the scale to which the force polygon was laid out, represent the reactions R_1 and R_2 , respectively.

In the equilibrium polygon, the lines 1, 2, 3, and 4 represent the form that a cord or string would assume if it supported the loads BC , CD , and DE at the several points where it changes direction, and its ends were attached at a_1 and f_1 . In order that the system might be in equilibrium, the cord would require either the oblique reactions marked P_1 and P_2 , or a compression member exerting a compressive stress as represented by the line a_1f_1 , and the vertical reactions R_1 and R_2 . It is evident from this that P_1 and P_2 , or their equivalents, the forces a_1o_1 and f_1o_1 in the equilibrium polygon, are the resultants of two sets of components R_1 and f_1a_1 , and R_2 and a_1f_1 , respectively. A force designated by two letters should be read in the direction in which the force acts; that is, the letter toward which the arrow representing the direction of the force points should be read last. In this instance, a_1f_1 represents a compressive stress and when speaking with reference to the point a_1 , the force is designated as f_1a_1 , while if the point f_1 is being considered, the force should be read a_1f_1 . In the force polygon, ao corresponds with the force P_1 in the equilibrium polygon and of with P_2 . The components of ao in the force polygon are az and zo , while the components of the force of are fz and zo . By measuring fz to the scale to which the load line was laid out, it will be found to equal, approximately, 3,300 pounds, while za , measured with the same scale, equals 2,900 pounds.

To prove, or check, the diagrams, the moments of the several external forces may be calculated about the point of application of either R_1 or R_2 . Considering the loads on the roof truss as giving positive moments about c_1 , their sum is obtained by the following calculation:

Moment of AB	$=$	$800 \text{ lb.} \times 0 \text{ ft.}$	$=$	$0 \ 0 \ 0 \ 0 \ 0$	ft.-lb.
Moment of BC	$=$	$1,000 \text{ lb.} \times 15 \text{ ft.}$	$=$	$1 \ 5 \ 0 \ 0 \ 0$	ft.-lb.
Moment of CD	$=$	$2,000 \text{ lb.} \times 30 \text{ ft.}$	$=$	$6 \ 0 \ 0 \ 0 \ 0$	ft.-lb.
Moment of DE	$=$	$1,500 \text{ lb.} \times 45 \text{ ft.}$	$=$	$6 \ 7 \ 5 \ 0 \ 0$	ft.-lb.
Moment of EF	$=$	$900 \text{ lb.} \times 60 \text{ ft.}$	$=$	$5 \ 4 \ 0 \ 0 \ 0$	ft.-lb.

The sum of moments $= 1 \ 9 \ 6 \ 5 \ 0 \ 0$ ft.-lb.

The leverage of R_1 about c , is equal to 60 feet, and consequently the value of R_1 is found by dividing the sum of the positive moments by this distance; by the calculation it equals 3,275 pounds, while the value of R_2 is the difference between this amount and the sum of the loads, or 2,925 pounds, which corresponds, approximately, with the values obtained by the diagram, thus proving the correctness of the graphical solution.




FIG. 33

35. In Fig. 33 (a) is shown a similar roof truss of the same dimensions, but supporting a wind load only on its left-hand portion. These wind stresses act parallel with each other and normal to the slope of the roof, so that if the truss is fixed at the ends, the reactions R_1 and R_2 will coincide in direction with these forces.

To determine the amount of the wind reactions R_1 and R_2 , construct the force polygon (b). Lay off the load line from a to d and represent to the proper scale the forces ab , bc ,

and $c d$, which correspond with the wind loads AB , BC , and CD . Connect any point or pole o with the several divisions on the load line, thus obtaining the oblique lines ao , bo , co , and do . Commence the equilibrium polygon (c) at any point on the left-hand wind reaction, as a_1 , and draw line 1 parallel with bo , line 2 parallel with co , and line 3 parallel with do , this last line intersecting the reaction R_1 at the point d_1 ; $a_1 o_1$ is drawn parallel with ao and line 3 is extended until it intersects $a_1 o_1$ at the point o_1 . By connecting the points d_1 and a_1 in the equilibrium polygon and drawing in the force polygon, from o , a line parallel with the line just described, the point z is located and the reaction R_1 is found by measuring $d_1 z$, while the amount of R_2 is known by scaling $z a$.

It will be noticed in drawing this diagram that the lines 1, 2, and 3 were drawn between the lines of action of the forces AB , BC , and CD , and that the force 3 coincides with the reaction component $d_1 o_1$. The reason that the last force 2 does not close on the line of action of the reaction R_2 is because there is no force on the right-hand portion of the truss. If there had been a force corresponding with AB , the reaction component $d_1 o_1$ would have been distinct from the force 3 and the diagram to the right would have been similar to the portion at the left. On being measured, $d_1 z$ and $z a$ are found to equal, respectively, 1,350 and 2,650 pounds.

36. In Fig. 34 is shown the method just described applied to a roof truss supporting both the vertical dead and snow loads, and the oblique loads due to the wind on the left-hand portion of the truss. The truss is considered fixed at the ends, but neither the amount nor the direction of the reactions R_1 and R_2 is known, so that these must be determined by the graphical method. As in the previous cases, the force polygon is laid out as shown at (b). Commence this diagram by laying off the load line, which extends from a to k . In designating the several forces making up this line, they were for convenience taken in sequence, that is, in the order in which they occur around the truss. For

instance, in the force polygon ab represents AB in the frame diagram; bc , the oblique wind force BC ; cd , the vertical load CD ; de , the oblique wind load DE ; etc. Since the forces in the load line are not coincident with regard to direction, their resultant will not lie along the load line, but




FIG. 34

will extend from a to k . This line will represent, by scale, the sum of the reactions R_1 and R_2 , and its direction coincides with the direction of the reactions. It is then in order to determine what percentage of the length of this line will represent R_1 , and what percentage will represent R_2 ; to do this, the equilibrium polygon (c) must be drawn.

Before commencing this polygon, connect some pole or point o , in the force polygon, with each point on the load line, as shown by the oblique lines ao, bo, co, do, eo , etc.; also, extend the line of action of each of the forces acting on the truss, as shown by the dotted lines. Start the equilibrium polygon from any point a , on the line of action of R_1 by drawing line 1 parallel with bo in the force polygon. This line should be drawn until it intersects the line of action of BC . The line 2 is drawn from this intersection in a direction parallel with co in the force polygon and of such a length that it intersects the line of action of the force CD . From this intersection, line 3 is drawn parallel with do in the force polygon until it intersects DE extended. From this intersection, line 4 is drawn parallel with eo , and where this line intersects the force EF extended, line 5 is drawn parallel with fo intersecting FG , and from this point line 6 is drawn parallel with go intersecting the force GH extended. Line 7 is drawn from this intersection parallel with oh , and from the intersection of line 7 with the extended force HI , line 8 is drawn parallel with io , intersecting IJ , and finally, line 9 is drawn in a direction parallel with jo , intersecting the line of action of the reaction R_2 at the point k . From this point, line 10 is drawn parallel with ko in the force polygon and intersecting at o , line 11 drawn from a , parallel with ao in the force polygon.

37. The reactions for the several frames described in connection with Figs. 32, 33, and 34 can be found from the equilibrium polygon. In each case a line yy drawn through the point o , and parallel with the reactions will divide the cord connecting the points on the two reactions into two such parts as to inversely represent the amount of the reactions; for instance, in the equilibrium polygon in Fig. 32, the line yy divides the line af_1 into two such parts that if the entire line af_1 is considered as representing the sum of the reactions R_1 and R_2 , yf_1 will equal R_1 and ay will equal R_2 . Again, in the equilibrium polygon, Fig. 33, the line yy drawn through o , parallel with the load line divides the line ad_1

into two such parts that the portion to the right equals the amount of the reaction R_1 , while the portion to the left equals the amount of the reaction R_2 , considering that the entire length of the line represents the sum of the




FIG 35

reactions. Again, in Fig. 34, the line yy coincides with the direction of the reactions and divides a, k , into such proportion of parts that $y k : a, k = R_1 : R_1 + R_2$, and $a, y : a, k = R_2 : R_1 + R_2$.

EXAMPLES FOR PRACTICE

1. Determine, by calculation, the amount of the reactions R_1 and R_2 for the frame shown in Fig. 35 (a).

$$\text{Ans. } \begin{cases} R_1 = 5,600 \\ R_2 = 6,000 \end{cases}$$

2. Calculate the amount of the reactions R_1 and R_2 of the frame shown in Fig. 35 (b).

$$\text{Ans. } \begin{cases} R_1 = 5,432 \\ R_2 = 2,568 \end{cases}$$

3. Find the amount of R_2 , by calculation, for the frame in Fig. 35 (c), and determine the amount and direction of R_1 by drawing the polygon of external forces. The right-hand end of the truss is on rollers, and the left-hand end is fixed.

$$\text{Ans. } \begin{cases} R_1 = 4,566 \\ R_2 = 1,600 \end{cases}$$

4. Determine, by the graphical method, the direction and the amount of the reactions for a frame loaded as shown in Fig. 35 (d).

$$\text{Ans. } \begin{cases} R_1 = 8,000 \\ R_2 = 9,500 \\ \text{Direction: } 11^\circ \text{ with vertical} \end{cases}$$

5. Employ the graphical method in determining the reactions for the scissor truss, shown in Fig. 35 (e), when loaded with vertical loads and oblique forces as designated.

$$\text{Ans. } \begin{cases} R_1 = 2,950 \\ R_2 = 5,050 \\ \text{Direction: } 26^\circ \text{ with vertical} \end{cases}$$

6. In Fig. 35 (f) is shown a hammer-beam roof truss. Find the vertical and horizontal components of the resultant reactions at both ends, either graphically or by calculation.

$$\text{Ans. } \begin{cases} H_1 = 1,275 \\ H_2 = 1,875 \\ V_1 = 1,525 \\ V_2 = 2,150 \end{cases}$$

DETERMINATION OF INTERNAL STRESSES


METHOD BY SOLUTION OF JOINTS

38. Maxwell's Method.—The method generally adopted for determining the internal stresses of a framed structure is known as **Maxwell's method**. After the reactions have been found, either analytically or graphically, the force polygon for each joint in the frame is found. The assembled polygons of forces, which are laid out for each joint, form the stress diagram, which it is usual to commence at the left-hand end of the frame and work around consecutive

joints. It is not always possible, however, to follow this order, for often the joint in sequence contains more than two unknown stresses, in which case it becomes necessary to analyze some other joint in the frame around which there are only two unknown forces. In working around the frame it is usual to begin at the left-hand end of the truss and proceed off and lay out the stresses around the joint in the same direction as the movement of the hands of a watch. It would be possible to work around each joint in the opposite direction, that is, in a direction opposite to the movement of the hands of a watch. But whatever may be the direction of the first joint analyzed it must be followed in analyzing the others.

In order that this important method, which will be used extensively in the application of graphical statics in analyzing the internal stresses of a framed structure may be thoroughly understood, the example illustrated in Fig. 36 will be assumed. In this figure is shown the frame and vertical load stress diagrams for a quadrilateral truss. The first procedure in the analysis of any frame by the graphical method is to determine all the external forces. In this instance the loads are given, and since the truss is symmetrically loaded, the reactions are each equal to one-half of the loads on the truss, so that R_1 and R_2 are each equal in amount to 2,100 pounds, and are designated, respectively, as $1/2 AB$ and $1/2 CD$, when the notation explained in Art. 29 is employed. The polygon of external forces, since all of these forces are coincident in direction, is contained within a straight line, which is represented in the stress diagram from a to f . This load line is determined by laying off the force ab equal in amount to $1/2 AB$ in the frame diagram; likewise, bc equal to BC ; and following around the truss in this manner until the point f has been located. When f has been determined, measure upwards on the load line an amount equal to R_1 , or 2,100 pounds to scale, in this manner locating the point e , so that fe represents, by scale, the amount of the reaction R_1 . The distance from e to a should then measure, by scale, an amount equal to R_2 . The polygon of external forces will now

sed figure and will extend, beginning at the left-hand
the truss and taking the forces in consecutive order
the right, from the point a in the stress diagram to b ,



Frame Diagram




FIG. 36

to c , from c to d , from d to e , from e to f , and from f onwards, corresponding with the direction of R_2 , and from a onwards to a , likewise corresponding in direction to R_1 ,

the last line thus closing the polygon. It is important to remember that before the stress diagram can be attempted, the polygon of external forces must be completed. If this polygon is incorrectly drawn or does not close, the diagram cannot be correctly laid out.

Having determined the polygon of external forces, the joint $ABGZ$ in the frame diagram can be analyzed. At this point in the frame there are only two unknown stresses, BG and GZ . The known stresses, AB and ZA , are already laid out in the stress diagram and are correspondingly lettered. To find the stresses in the members BG and GZ , draw an indefinite line from the point b in the stress diagram parallel with BG in the frame diagram, and from z draw a line parallel with GZ . The point of intersection of these two lines will be the point g and the polygon for the system of forces meeting at the extreme left-hand joint of the truss will read, in the stress diagram, from a to b , from b to g , from g to z , and from z back to a , the point of commencement.

39. Determination of the Kind of Stress.—In drawing the stress diagram the question naturally arises as to the direction in which these lines should be drawn, since a line might be drawn from b upwards, as shown by the dotted line, being still parallel with BG in the frame diagram; and in like manner the line zg might be drawn in a direction from z toward the right instead of toward the left. It is quite evident, however, that if the lines were drawn as suggested and shown dotted, they would not intersect and the polygon for the system of forces around the left-hand joint of the frame would not close. It is clear, therefore, that the lines that represent the stresses in the members BG and GZ can be drawn only in one direction and the direction in which they are read determines the kind of stress that exists in the member. For instance, in drawing the polygon for the stresses around the joint $ABGZ$, the force ab in the stress diagram is downwards. The stress from b to g is likewise downwards and may be designated by an arrow on BG in the frame diagram; gz is to the right,

likewise shown by the arrow on this member in the frame diagram, the final line of the polygon being upwards from z to a and thus representing the amount of the reaction R_1 .

As the stresses are read, their direction should be marked with arrows on the frame diagram; this shows the direction of the stress and designates whether it is compression or tension. Forces acting away from a joint are always tensile stresses; those acting toward a joint are always compressive stresses.




FIG. 37

If there is tension at one end of a member, it is evident there must be an equal amount of tension at the other end; if there is compression at one end of a member, there is an equal amount at the other.

An easy way to remember whether the arrows designate compression or tension by their direction, as shown on the members in a frame diagram, may be seen by referring to Figs. 37 and 38. The member DZ , Fig. 37, is a tension member; the arrows point away from the joints and toward each other, and resemble the form of an elastic material, stretched, as shown at A , Fig. 38; while in the compression member BD , the arrows act toward the joints, or away from each other, and resemble the form that a plastic material assumes on being compressed, as shown at B , Fig. 38.




FIG. 38

each other, and resemble the form that a plastic material assumes on being compressed, as shown at B , Fig. 38.

40. Proceeding with the solution of the frame diagram shown in

Fig. 36, the joint $BCHG$ may next be analyzed. Around this joint the only unknown forces are the stresses in the members CH and HG . To find the amount of these stresses, draw a line in the stress diagram from the point c

parallel with CH , and from g draw a line upwards parallel with GH ; the point of intersection will be h . The polygon of forces about the joint under consideration will then extend in the stress diagram from b to c , from c to h , from h to g , from g back to the starting point b . The joint $CDJIH$ cannot as yet be analyzed, for there are three unknown forces represented by the members DJ , JI , and IH , but the joint marked $GHIZ$ can be analyzed, for the only unknown stresses exist in the members HI and IZ . To analyze this joint, draw from the point h , already determined, an indefinite line parallel with HI in the frame diagram, and from z a line parallel with IZ , intersecting this first line at i ; thus, the polygon of forces around the joint $GHIZ$ is complete and extends in the stress diagram from g to h , from h to i , from i to z , and from z back to g . In analyzing this last joint, the stress in the member hi was determined, so that there now exist only two unknown forces at the joint $CDJIH$. By analyzing this joint, the polygon of external forces will be found to extend in the stress diagram from c to d , from d to j , from j to i , from i to h , and from h back to the point c , and it will be found that the stress diagram will begin to repeat on the lower side of the line zi . If the frame diagram is further analyzed, it will be found that the stress diagram is balanced on the line zi and is symmetrical about this axis, showing that the truss is symmetrically loaded. Since this is the case, only one-half of the stress diagram need be drawn, for the stresses in the members on each side of the center line of the frame diagram marked yy are the same, owing to the fact that the truss is symmetrically loaded.

The stresses in the several members may now be determined by measuring their respective lines in the stress diagram, and a tabulation of these stresses will give a convenient table for designing the several members to sustain tensile and compressive stresses.

GRAPHICAL STATICS BY THE METHOD OF SECTIONS

41. Another method of drawing the stress diagrams for any framed structure is by the method of sections, and while it differs somewhat from the method just explained, the results are the same. In general, this method consists of passing a plane through any section of the frame in such a manner that it will intersect only two members in which the forces are unknown, these two unknown stresses being obtained by completing the polygon of forces necessary to produce equilibrium in that portion of the frame lying to one side or the other of the plane. Since the method is more readily explained by an application of its principles to an example, the frame diagram of a quadrangular truss, shown in Fig. 39, will be analyzed. It is necessary to lay off the load line in the same manner as in the analysis of the joints of the frame by considering the forces about the joints. The load line for the frame diagram, Fig. 39, will then be a vertical line extending from a to b , b to c , etc., from f back to z , giving the reaction R_1 , and from z to the point a , the length of the latter line being equal to the reaction R_1 . Commencing at the left-hand joint of the frame diagram, pass a plane through the frame, cutting the several members along the line ab . The portion of the frame to the left of this plane is held in equilibrium by the reaction R_1 , the force AB , and the stresses in the members BG and GZ , the only two unknown forces about the joint consisting of the latter. These four forces form a system that acts on the portion of the truss to the left of the line ab , as is shown in (a). The direction of the unknown forces being known, they may be drawn in the stress diagram as shown, and their point of intersection will be g . Another plane is now passed through the frame, cutting the members along the line cd and the left-hand portion of the truss is held in equilibrium by the reaction R_1 , the loads AB and BC , and the stresses CH , HG , GZ . The portion of the frame held in equilibrium by these forces to the left of the line cd is shown in (b). The only two unknown forces acting on the left-hand portion

the frame are CH and HG , for all the other forces have been shown in the stress diagram. To find these forces, then, and close the polygon for this portion of the frame, all




FIG. 39

that it is necessary to do is to draw the lines ch and hg in the stress diagram, thus locating the point h . Again, assume that a plane is passed through the frame along the line

he left-hand portion of the frame will be held in equilibrium by the forces shown in (c), which are the reaction R_1 , the load AB , and the stresses in the members BG , GH , HI , and IZ . The two unknown stresses are HI and IZ , and their amounts are determined when the lines hi and iz have been drawn in the stress diagram, and the polygon of forces for the left-hand portion of the truss has been completed. A separate line has been used in the stress diagram to represent the polygon of forces in each case, in order that the solution of each section may be clear.

This system can be continued throughout the truss, and it will be found on comparison of the frame diagram with the stress diagram, that any plane, such as gh , will cut the truss in such a manner that each portion will be in equilibrium; and that when the stress diagram has been entirely completed the polygon will close for either portion of the frame diagram cut by the plane. This system of graphical statics is preferred by many, but the other is generally practiced.



GRAPHICAL ANALYSIS OF STRESSES

(PART 2)

DIAGRAMS FOR SIMPLE FRAMES

1. The principles stated in *Graphical Analysis of Stresses*, Part 1, may be used to analyze the stresses in any framed structure and will be applied in this Section principally to the determination of stresses in the members of roof trusses. An effort will be made to include in the applications all the principal types of trusses, and when special features of the solution are introduced they will be explained so that they may be used advantageously elsewhere than in the particular type under discussion.


2. In Fig. 1 is shown a simple frame, in which the compression member BD and the tension members AD and DC form a triangular structure that supports the downward pull of 1,000 pounds; the triangular frame is supported, in turn, by the reactions AB , BC . The problem consists in drawing the stress diagram to determine the stress in the various members.

With a scale of 40 pounds to $\frac{1}{16}$ inch, draw the vertical line ca , in the stress diagram, equal to 1,000 pounds. This line represents the force CA in the frame diagram. Working around the joint ADC in the direction of the dotted arrow, the first member encountered is AD ; hence, from a in the stress diagram, draw a line parallel to AD in the frame diagram. DC being the next member met, from c in the stress diagram draw a line parallel to it. The point of


For notice of copyright, see page immediately following the title page

2 GRAPHICAL ANALYSIS OF STRESSES §27

intersection of these two lines is d . This done, go around the joint again, to see that none of the members have been omitted, and also to get the direction in which the stresses act. Starting at c in the stress diagram, and going around



Frame Diagram



Stress Diagram
(b)

FIG 1

the joint CAD , the polygon of forces is from c to a to d , and from d back to c , thus arriving at the point from which the start was made. The next joint in the frame diagram is ABD . The point b on the line ca is not known, but may

be determined by calculating the reactions AB and BC by the principles of moments. The load of 1,000 pounds is located on the frame 6 feet from the reaction BC . The moment about CB is $1,000 \times 6 = 6,000$ foot-pounds, while the reaction at AB equals $6,000 \div 13 = 461$ pounds. Knowing that the force AB is 461 pounds and that it acts upwards, the point b can easily be located by measuring from a on the line ac in the stress diagram; then the line bd may be drawn and if found parallel to the member BD in the frame diagram, the stress diagram is correct. In this case, however, it is not necessary to calculate the reactions AB and BC , for the point d having been already determined and it being known that the line db must be parallel to DB , all that is needed is to draw a line from d parallel to DB , and the point where it cuts the line ca is b . Having drawn the line db , go around the joints ABD and CDB , marking the direction of the stress by the arrowheads, as shown in the frame diagram. Around the joint ABD the polygon of forces is from a to b , from b to d , and from d back to a . Working around the joint CDB , the polygon of forces is from c to d , from d to b , and from b back to c . This completes the stress diagram; the amount of the stress in the several members of the frame diagram is found by measuring the corresponding lines in the stress diagrams.

3. Diagram for a Small Roof Truss.—Fig. 2 is the frame diagram for a small roof truss, in which the two rafter members EB and CE are connected at their foot by the tension member EZ ; the loads and their reactions are as shown in the frame diagram. The problem is to determine the stresses in the several members composing the truss.

Draw the vertical line ad , shown in the stress diagram, Fig. 2. Lay off to any scale, say, 400 pounds to $\frac{1}{16}$ inch, the loads ab , bc , and cd . From the point d , the reaction dz acts upwards, with a force of 8,000 pounds, which determines the point z . Going around the joint $ABEZ$, the reaction ZA acts upwards and AB downwards. Then, from the point b in the stress diagram draw the line be parallel to BE in the

frame diagram, and from z draw the line ez parallel to the member EZ in the frame diagram. The point of





FIG. 2

intersection will be e . Having gone thus far, again go around the joint, to get the direction of the stresses in the members and to see whether the polygon of forces is correctly drawn. Go, for instance, from z to a upwards; a to b downwards; then from b to c , and from c back to z , the starting point. The next joint in the frame diagram is BCE . The force bc being already determined, from point c draw the line cc parallel to CE in the frame diagram; this line will pass through the point e if the diagram has been drawn correctly.

The polygon of forces at EBC is from b to c downwards, then from c to e , and back from e to b , the starting point. The next joint in the frame diagram is $ECDZ$, and

the polygon of forces in the stress diagram is from e to c , already drawn, from c to d , d to z , and back to e .





FIG. 3

The stress diagram being completed, all that remains is to measure the various lines, in the stress diagram, that represent the corresponding members in the frame diagram. Thus, eb measures $17\frac{1}{2}$ inches, the scale being 400 pounds to $\frac{1}{10}$ inch; the stress in this member is 7,000 pounds; the line ez measures about $\frac{14\frac{1}{4}}{10}$ inches, and the stress in the member ez is 5,700 pounds. Thus, the stress in any member may be determined.

4. Diagram for a Jib Crane.

A jib crane, proportioned as in Fig. 3, has a load of 30,000 pounds suspended at the end of the jib; what are the stresses in the guy ropes, and in the different members of the jib, and what are the reactions CA and DA ?

In the stress diagram draw the vertical line bc equal to 16,500 pounds, and from the point c , draw the line ce parallel to CE in the frame diagram. Then from b draw the line eb parallel to EB in the frame diagram. Going around the joint to check the polygon of forces, it is found to be from c to b , from b to e , and from e back to c . The next joint encountered is EDB . Hence, from e , draw ed upwards parallel to ED , and from b draw db parallel to DB , the point where these two lines intersect being d . The polygon of forces about the joint EDB is from b to e to d , and from d back to b , the starting point. Next, in the joint $CAD E$, continue bc upwards indefinitely; then from d draw ad parallel to AD in the frame diagram; where the lines just drawn intersect will be the point a ; de and ec have already been drawn. The remaining joint to work around is ABD . The stress diagram shows that the forces around this joint have already been determined, and the stress diagram is complete.

The stresses in the members may be determined by measuring the lines corresponding to them in the stress diagram, with the scale to which the diagram has been drawn.

5. Roof Truss With a 40-Foot Span.—Fig. 4 (*a*) shows the frame diagram for a roof truss having a 40-foot span. The loads are as shown, the compression members being indicated by heavy lines, and the tension members by light lines; required, to draw the stress diagram for this truss.

First draw the vertical line af , as shown in the stress diagram at (*b*); mark the point a and lay off on this vertical line, to any scale, using, in this case, 1,500 pounds to $\frac{1}{16}$ inch, the loads ab , bc , cd , de , and ef , corresponding to the loads AB , BC , CD , DE , and EF in the frame diagram. The truss being symmetrically loaded, the loads are the same, in amount, on both sides of the center line; the reactions R_1 and R_2 are, therefore, each equal to one-half the load, in this case, 16,500 pounds. Hence, za may be laid off on the vertical line, and as R_1 equals R_2 , za must equal zf ; consequently, z is located centrally between a and f , or between

and d . The point z having been determined, proceed with the diagram by going around the joint $A B G Z$. Draw $b g$ in the stress diagram parallel to $B G$ in the frame diagram;





FIG. 4

then from z draw $g z$ parallel to $G Z$, the point where the two lines intersect being g . The next joint is $B C H G$; as $b c$ in the stress diagram is already known, draw $c h$ parallel to $C H$ and $h g$ parallel to $H G$. Then the polygon of forces around this joint will be from b to c to h to g , and from g back to b . It is now expedient to analyze the joint $C D I H$; in the stress diagram, $h c$ and $c d$ have already been obtained; then, from d , draw $d i$ parallel to $D I$, and from the point h , already known, draw $i h$ parallel to $I H$. The polygon of forces around this joint will be from c to d to i to h to c , the starting point; arrowheads on the members in the frame diagram always

draw $i h$ parallel to $I H$. The polygon of forces around this joint will be from c to d to i to h to c , the starting point; arrowheads on the members in the frame diagram always

mark the direction in which the stresses act in the stress diagram. Of the forces around the joint $GHIJZ$, zg , gh , and hi have been obtained. Then from the point i , ij is drawn parallel to IJ ; and from z , zj , parallel to JZ ; the point j is found to fall on the point g , while the polygon of forces around this joint is from z to g to h to i to j , and from j back to z , the starting point. Of the stresses in the members around the joint $IDEJ$, ji , id , and de are known; then from e draw ej parallel to EJ . The polygon of forces around this joint will then be from i to d to e to j , and from j back to i .

The only remaining joint is $JEFZ$. The stress diagram shows that the stresses in these members have been determined, while the polygon of forces around this joint is from j to e to f to z , and back from z to j .

The stress diagram being completed, the amount of the stresses may be determined by measuring the various lines with the scale to which the diagram has been drawn.

HOWE ROOF TRUSS

6. In Fig. 5 is shown a frame suitable for timber construction with iron tension members known as a **Howe truss** when constructed as in the figure, and as a **Pratt truss** when the vertical members are made to resist compression and the oblique members, tension. In this problem it is desired to draw the stress diagrams for the dead load and the wind load; also, to design and properly proportion the roof truss to resist the stresses that the various members may be required to sustain.

Draw the frame diagram for the vertical load shown in Fig. 5, and mark the dead load coming on the different panel points, or joints, in the truss. The truss being symmetrically loaded, the reactions R_1 and R_2 are each equal to half the load on the truss.

Draw the stress diagram for the dead load to the scale of, say, 800 pounds to $\frac{1}{8}$ inch. Draw the vertical load line aj , and determine the point z . Then draw the stress diagram by the methods previously given. Only one-half the diagram

need be drawn, as the stresses obtained on one side of the center of the truss apply to the other side; for instance, FQ is the same as PE . Having completed half the stress diagram for the dead load, redraw the frame diagram for the wind load. The direction and amount of the wind pressure at the several panel points, or joints, of the truss are shown in the frame diagram.

As both ends of the truss are secured against sliding, the reactions act in a parallel direction to the wind pressure. If the left-hand side of the truss be secured and the right-hand side placed on rollers, to allow for expansion, as is sometimes the case with iron or structural steel trusses, the right-hand reaction, instead of being parallel to the direction of the wind, will be vertical. This makes considerable difference in the stress diagram, as will be explained subsequently.

To determine the amount of the reactions R_1 and R_2 , let c be the center around which the moment of R_2 is taken; then the perpendicular distance between the line of action of R_2 and the point c will be 71.22 feet. Extend the left-hand rafter until it cuts the line of action of the force R_2 at the point y' . Regard this extension and the rafter as a beam, and calculate the amount of the reactions R_1 and R_2 by the principle of moments.


The moments about the point c are as follows:

$$\begin{array}{rcl} 2,800 \times 11.18 & = & 31304 \text{ foot-pounds} \\ 2,800 \times 22.36 & = & 62608 \text{ foot-pounds} \\ 2,800 \times 33.54 & = & 93912 \text{ foot-pounds} \\ 1,400 \times 44.72 & = & 62608 \text{ foot-pounds} \\ \text{Total,} & & \underline{250432} \text{ foot-pounds} \end{array}$$


and $250,432 \div 71.22 = 3,516$ pounds, the reaction R_2 . Having found R_2 , find R_1 by subtracting R_2 from the sum of the loads.

The sum of the loads is: $1,400 + 2,800 + 2,800 + 2,800 + 1,400 = 11,200$ pounds. Then, $11,200 - 3,516 = 7,684$ pounds, the reaction R_1 .

7. Next, lay out the wind stress diagram by drawing the load line af parallel to the direction of the wind in the frame diagram for the wind load. Lay off to scale (in this case



(n)



(h)

FIG. 5





FIG. 5

400 pounds to $\frac{1}{16}$ inch) the forces ab , bc , cd , de , and ef equal to AB , BC , CD , DE and EF , in the frame diagram. Then from a , lay off az equal to the reaction ZA , or R_1 . If the other forces or loads have been laid off accurately, az should, on measurement, be found equal to the right-hand reaction R_2 .

The first joint to analyze is $ABKZ$. Start at b and draw the line bk parallel to BK in the frame diagram; then from z draw zk parallel to KZ ; where the two lines intersect is the point k . The polygon of forces around this joint is from a to b to k to z , and from z back to the starting point a . The next joint to analyze is $BCLK$. From the point c draw the line cl parallel to CL in the frame diagram and from k draw the line kl parallel to the member LK , the point of intersection being l . The polygon of forces around this joint is from b to c to l to k , and from k back to b .

To analyze the joint $KLMZ$: kl being already known, the next member is LM ; so from the point l draw the line lm parallel to LM in the frame diagram. As the next member around this joint is MZ , to which mz in the stress diagram is parallel, the point m is located where the line lm intersects the line mz ; this completes the joint, the polygon of forces around it being from k to l to m to z , and from z back to k .

To determine the stresses in the members around the joint $CDNML$, draw, from the point d , the line dn , parallel to the member DN in the frame diagram; then, from the point m draw mn parallel to NM . The polygon of forces around this joint is from c to d to n to m to l , and from l back to c .

To analyze the forces around the joint $MNOZ$, draw from n the line no upwards, parallel to NO in the frame diagram; as the next member OZ is horizontal, the point o must be at the intersection no and oz . This completes the joint, and the polygon of forces around it is from m to n to o to z , and from z back to m , the starting point.

Now analyze the joint $DEPON$. From e draw the line ep parallel to EP in the frame diagram, and from o draw the line op parallel to PO . The intersection of these lines determines the point p , and the polygon of forces around this

joint is from *d* to *e* to *p* to *o* to *n*, and from *n* back to *d*, the starting point.

The analysis of the joint *OPQZ* is made by drawing the vertical line *pq* from the point *p*; the point where *pq* intersects *bk* is *q*. Then the polygon of forces around this joint is from *o* to *p* to *q* to *z*, and from *z* back to *o*. The members shown in dotted lines do not sustain any stresses from the pressure of the wind when it strikes the left-hand side of the truss.

TABLE I

Member	Dead-Load Diagram	Wind-Load Diagram	Total of Both
<i>BK</i>	27,000 +	12,000 +	39,000 +
<i>CL</i>	23,500 +	10,000 +	33,500 +
<i>DN</i>	19,500 +	7,600 +	27,100 +
<i>EP</i>	16,000 +	5,680 +	21,680 +
<i>KZ</i>	24,000 −	13,300 −	37,300 −
<i>MZ</i>	21,000 −	10,000 −	31,000 −
<i>OZ</i>	17,500 −	7,000 −	24,500 −
<i>LK</i>	4,000 +	3,500 +	7,500 +
<i>NM</i>	5,000 +	4,400 +	9,400 +
<i>PO</i>	6,500 +	5,400 +	11,900 +
<i>ML</i>	1,600 −	1,500 −	3,100 −
<i>ON</i>	3,500 −	3,000 −	6,500 −
<i>QP</i>	10,600 −	4,500 −	15,100 −
<i>FQ</i>	16,000 +	6,600 +	22,600 +

The final joint to go around, completing the stress diagram, is *EFQP*. The only unknown force around this joint is the stress in the member *FQ*. A line drawn from *f* in the stress diagram, parallel with the member *FQ*, should pass through the point *q*; if it does not, the diagram has been inaccurately drawn. This is always a test of the accuracy of the stress diagram, and if the last line in this diagram does not close on the proper point, when drawn parallel to the member it represents, the stress diagram should be redrawn,

to determine whether the loads and reactions have been laid out correctly, and whether any of the joints or members in the structure have been omitted.

8. The two diagrams being completed, measure the different lines and obtain the stresses in the various members, as given in Table I. It must be noticed, however, that while the wind, acting on one side of a truss, does not create stresses in those members shown dotted on the opposite side of the frame, these members should be proportioned like the others, because the wind is just as likely to blow on this side of the roof and reverse the conditions.

The values given in this table represent the stresses, in round numbers, on the various members in the truss, as obtained from the dead-load and wind-stress diagrams. The + sign after a value, signifies that the stress is compressive, while the - sign shows that it is a tensile stress.

SCISSORS ROOF TRUSS

9. The type of roof truss shown in Fig. 6 (*a*) is known as the **scissors truss**; it is used for spans of from 20 to 35 feet, and is generally constructed of wood. An inspection of the frame diagram in (*a*) shows that the space *H* is a quadrangle, so that underloading the frame as constructed is liable to cause distortion and make it impossible for the vertical loads and the reactions R_1 and R_2 to keep it in equilibrium. If it is not clear that the space *H* is liable to distortion from the vertical loads and their reaction, a rough bristol-board model, hinged at the joints, should be made and notice taken of the change of form created by any vertical load applied to the truss.

To prove that such a condition exists and that it is necessary to introduce some member in order to prevent the distortion of the truss, the diagram shown in (*b*) is made. The load line is represented by the line *af*, and the several vertical loads on the rafter member of the truss are marked off, by scale, from *a* to *b* to *c* to *d* to *e* to *f*. Since the truss is symmetrically loaded and the reactions R_1 and R_2 ,

are equal, the point z will be located midway between the points a and f , or it will divide the space cd into halves.

Around the joint $ABGZ$ there are but two unknowns;






FIG. 6

therefore, the stresses in the members may be solved by drawing from b , in the stress diagram, a line parallel with BG , and from z a line parallel with GZ in the frame



diagram. The point g will be located at the intersection of these lines, and the polygon of forces around this joint will extend from a to b to g to z , and from z back to a , the starting point.

The stresses in the members of the joint $BCHG$ are represented in the stress diagram when the lines ch and gh are drawn parallel, respectively, to their members in the frame diagram.




In analyzing the next joint CDH , a difficulty is encountered, as the point h is already located, and it is impossible to draw in the stress diagram a line from d to h and parallel with that member in the frame diagram, but a line can be drawn from d to such a point as h_1 , which will be parallel with the right-hand rafter member of the truss. In fact, when the point h_1 has been found, the other half of the diagram may be completed as shown dotted, for it is exactly similar to the stress diagram for the left-hand portion of the truss. Even though the diagrams can be drawn in this way, the polygon of forces is incomplete around this joint, for in tracing its stresses, there is no closed polygon and equilibrium is not maintained. If, however, the points h and h_1 in the stress diagram are connected, the polygon of forces about the apex joint of the truss will be complete. This line of stress hh_1 is represented in the frame diagram of the truss by introducing the vertical member HH_1 , as shown in (c). The truss could be held in equilibrium by inserting a member between the joints $BCHG$ and $DEIH$, or by placing a tie between the feet of the roof truss at R_1 and R_2 . It is not unusual for carpenters to construct this truss as shown in (a). This is radically wrong, for, unless the walls will withstand a side thrust, the stability of the truss depends on the transverse strength of the rafter members at the joints $BCHG$ and $DEIH$.

10. The scissors truss shown in Fig. 7 (a) can be analyzed without the insertion of another member, provided there is sufficient stability at the feet of the truss to resist an oblique thrust. That this thrust is fixed in direction and amount may

GRAPHICAL ANALYSIS OF STRESSES



Scale $\frac{1}{30}$ inch = 300 lb.



be determined by drawing the stress diagram shown at (b). Commence the analysis of the truss, instead of at the lower right- or left-hand joint, at the apex or the joint CDH . Lay off the load line, as designated from a to l , and draw from the points c and d lines parallel with the members CH and DH , respectively, in the frame diagram, thus locating the point h .

The joints $BCHG$ and $DEIH$ can be analyzed by drawing the lines in the stress diagram designated by bg , ei , gh , and ih . Having the points g and i , the stress lines gz and iz can be found by drawing, from the points g and i , lines parallel with the members ZG and IZ , respectively. Having determined the point z , by connecting the points a and l with z , the reactions za and lz are obtained, both in direction and in amount; and it is evident that since the diagram closes and the polygons of both the external and internal forces are complete, the truss is in equilibrium when R_1 and R_2 are inclined, as shown. The inclined reactions R_1 and R_2 are the oblique resultants of the vertical reactions of 4,000 pounds shown in Fig. 6 (a) and horizontal thrusts introduced at A , and A_1 , as designated in Fig. 7 (a).

The reaction diagram is shown in Fig. 7 (c). Here aa_1 is equal to 4,000 pounds, or the vertical reaction. The horizontal thrust at each abutment is measured by the length of the line a_1z and the oblique resultants of these two forces, which are R_1 and R_2 in the frame diagram in (a), are shown from a to z and from l to z . These lines, it will be noticed, coincide with the same lines in the stress diagram in (b). The resultants, or the oblique reactions R_1 and R_2 , are shown dotted, in the frame diagram (a), at each abutment.

11. While the fact that the diagram (b) closes is sufficient proof of its correctness and the accuracy with which it has been drawn, it is interesting to check the reactions R_1 and R_2 , by calculating the moments of the external forces about some point, such as c .

Regard the left-hand portion of the truss as being held in rotatory equilibrium about the point c by the forces designated in the diagram (d). Here the member CH of the

frame diagram (*a*) is replaced by a force CH , the amount of which may be found, assuming that the stress diagram has not as yet been drawn, by laying off in the vertical direction of the force CD , from the point c shown in (*e*), a line equal in length to one-half of CD , or 1,000 pounds, and by intersecting a horizontal line from d by a line drawn parallel with CH in the frame diagram. On measuring the length of ch in (*e*), the amount of the stress, or force, CH , designated in diagram (*d*), is found.

The forces AB , BC , and CH in this figure, acting through lever arms about the point c , are opposed by the moment of the reaction R , or ZA about the same point. The sum of the moments of the forces AB , BC , and CH is found from the following:

$$\begin{aligned} \text{Moment of } AB &= 1,000 \times 25 = 25\,000 \text{ foot-pounds} \\ \text{Moment of } BC &= 2,000 \times 12.5 = 25\,000 \text{ foot-pounds} \\ \text{Moment of } CH &= 2,000 \times 8.75 = 17\,500 \text{ foot-pounds} \\ \text{Sum of positive moments} &= 67\,500 \text{ foot-pounds} \end{aligned}$$

The leverage of R , is equal to 8.75 feet, so that its amount equals $67,500 \div 8.75$, or 7,714 pounds. By scaling the lines az or fz in either the stress diagram (*b*) or in the reaction diagram (*c*) it will be found to correspond with the result just found.

12. Dead-Load Diagram.—Fig. 8 (*a*) is the frame diagram of a scissors roof truss of which the stress diagrams for the dead load and wind pressures are to be found.

First draw the stress diagram, Fig. 8 (*b*), for the dead load. As the dead loads on the truss are symmetrical, both in amount and location with regard to the center line of the truss, the reactions are the same at either end of the truss, and each is equal in amount to one-half the load, in this case, 7,575 pounds. Before going around the joints, draw the vertical line af in the stress diagram; then starting at the point a , lay off to the scale of, say, 400 pounds to every $\frac{1}{16}$ inch, the force ab equal to AB in the frame diagram; then lay off bc equal to BC , cd equal to CD , de equal to DE , and ef equal to EF . Then, as the truss is symmetrically loaded, the





FIG. 8

point z is located midway between the points a and f . If the truss were not symmetrically loaded, the reactions would have to be calculated by the principle of moments.

Having located the loads and their reactions on the vertical line af , obtain the stresses in the members around the joint $ABGZ$ from the point b , by drawing a line bg parallel to BG in the frame diagram; then from z draw the line gz parallel to GZ ; the intersection of these lines will be the point g . The polygon of forces around this joint is from b to g to z to a , from a back to b , the starting point. Bear in mind that the forces in the stress diagram, representing the reactions, must have the same direction as the reactions in the frame diagram. The lines determining the stresses around the joint $BCHG$ should next be drawn; bc having been determined from c , draw a line ch parallel to CH , and from g draw a line gh parallel to HG , the intersection of these two lines determining the point h , while the polygon of forces is from b to c to h to g , and from g back to b .

Now work around the joint $CDIH$; cd being already known, from the point d draw the line di , parallel to DI , and from the point h draw the line hi , parallel to IH , the intersection of the two lines being the point i . In going around the joint $GHIJZ$, the stresses in the members zg , gh , hi , have already been determined and drawn in the stress diagram. Then, from the point i draw the line ij parallel to IJ , and from z draw the line zj parallel to JZ , and the intersection of these two lines will be the point j . The polygon of forces around this joint is from z to g to h to i to j , and from j back to z , the starting point.

The next joint to analyze, in going around the truss, is $DEJI$; ji , id , and de being known, the only remaining force to determine is the stress in the member EJ . The point e being fixed, draw the line ej parallel to EJ in the frame diagram, and if this line, which completes the diagram, passes through the point j , the diagram is correct and accurately drawn. The stresses around the right-hand heel of the truss are all known, the line ej just drawn having been the only unknown member at this joint. The polygon of

forces around the joint $DEJI$ is from d to e to j to i , and from i to d , the starting point. The polygon of forces around the joint $EFZJ$ is from e to f to z to j , and from j back to e , completing the stress diagram for the dead or vertical load on the roof truss.

13. The wind-load diagram, however, remains to be drawn. Redraw the frame diagram, as shown in Fig. 9. The wind is always considered as acting normally, or at right angles, to the roof, the amount of its pressure at the different joints of the truss being shown on the frame diagram. As the heels of the trusses are fixed, the reactions act in lines parallel with the wind pressure.

To estimate the amount of the reactions R_1 and R_2 , consider the left-hand rafter member as a beam, and R_1 and R_2 as the reactions supporting it. The moments due to the wind pressure BC and CD acting about R_1 are:

$$\begin{array}{rcl} \text{At } BC, & 6,556 \times 19.5 & = 127,842 \text{ foot-pounds} \\ \text{At } CD, & 1,950 \times 29.66 & = 57,837 \text{ foot-pounds} \\ \text{Total,} & & \underline{185,679} \text{ foot-pounds} \end{array}$$

The lever arm with which R_2 resists the wind pressure acting at the joints is 29 feet 8 inches, so $185,679 \div 29.66 = 6,260$ pounds, the amount of the reaction at R_2 . The sum of the loads being $4,600 + 6,556 + 1,950 = 13,106$ pounds, the reaction at R_1 is $13,106 - 6,260 = 6,846$ pounds.

First draw, in the stress diagram, the load line ad parallel to the direction of the wind pressure and the reactions. Lay off to the scale to which the stress diagram is drawn—in this case, 400 pounds to $\frac{1}{8}$ inch—the force ab equal to AB in the frame diagram, then lay off bc equal to BC , and cd equal to CD . From d lay off the amount of the reaction R_2 , or dz , which determines the point z , and the distance za , according to scale, equals in amount the left-hand reaction R_1 . The polygon of external forces is, then, from a to b to c to d to z , and from z back to a , the starting point, forming a straight line, as in all cases so far analyzed.



Continue the stress diagram by going around the joint $ABGZ$; from the point b draw the line bg , and from the

point z draw the line zg parallel to the corresponding members in the frame diagram, the point where the two lines intersect being g . The polygon of forces around this point is from a to b to g to z , and from z back to a .

The next joint is $BCHG$; bc having already been obtained, from the point c draw the line ch parallel to CH , and from g draw the line gh parallel to HG , h being the point where these two lines intersect. Disregard the two members in the frame diagram shown in dotted lines, which do nothing toward sustaining the wind pressure. Now work around the joint $HCDZ$, of which cd and dz are known; draw, from z , the line zh parallel with ZH in the frame diagram; if this closing line of the diagram passes through the point h , the diagram has been drawn accurately. The polygon of forces around the joint $BCHG$ is from b to c to h to g , and from g back to b . The polygon of forces around the joint $CDZH$ is from c to d to z to h , and from h back to c . The polygon of forces around the joint ZGH is from z to g to h , and from h to z , the starting point.

The stress diagrams for both the dead and the wind load being complete, the stress in each member of the truss is obtained by determining, by scale, the stress due to both the dead and wind loads in each member, adding the two together for the maximum load in the member. To determine, for instance, the stress in the strut HG , measure the length of the line hg in the stress diagram, Fig. 8, for the dead load, and obtain its amount; then measure the same line hg in the stress diagram for the wind load, Fig. 9; find the sum of the two measurements, and determine the maximum stress in the strut hg from the assumed scale of the drawing.

It must be remembered that while the wind acting on one side of a truss does not create stresses in all the members on the opposite side, these members should be proportioned in a like manner to the other members, because the wind is quite as likely to blow on this side of the roof and reverse the conditions.



Scale $\frac{1}{30}$ inch = 300 lb.





FIG. 7

carry considerable weight, which is transmitted to the joints MZ and ZN .

By introducing these loads suspended from the panel points on the lower chord, no confusion need result in drawing the stress diagram if these loads and the correct reactions are introduced in the load line of the stress diagram, which represents the force polygon of the external forces. The sum of the reactions R_1 and R_2 must equal the sum of the loads on the frame, including the weights suspended from the lower chord, and as the truss is symmetrically loaded the reactions R_1 and R_2 are equal, and each is half the entire load. The system of lettering for the designation of the forces on the frame may be followed in alphabetical order, the letter Z being used to designate the space below the lower chord of the truss. The external forces on the frame diagram of Fig. 10 will then read, on the load line, downwards from a to b to c to d to e to f ; then upwards from f to n , which distance is laid off to equal, in this instance, the reaction R_1 , or 7,000 pounds. The force polygon will now continue from n to z downwards, thus designating the suspended weight of 3,000 pounds on the right-hand portion of the lower chord. The force zm is now laid off, also, downwards, in order to designate the suspended weight of 3,000 pounds on the left-hand portion of the lower chord. When m has been located on the load line, the reaction R_2 is laid off upwards equal to 7,000 pounds and is represented in the stress diagram by ma . It will be noticed in laying off the polygon of external forces in the stress diagram that the point n lies at the same place as the point b and that the point m coincides with the point e . This duplicate designation of a point is frequently necessary, and especially so when weights are suspended from points on the lower chord.

In this case, the polygon of external forces is actually a single straight line, but, nevertheless, it is a many sided figure, being made up of the several forces around the truss. That it has no appreciable area or shape is due to the fact that all the external forces are vertical and, coinciding with one another, form a straight line.

In drawing the stress diagram for the vertical loads, commence at b and draw bg of indefinite length, and parallel with the member BG in the frame diagram. From m draw a line parallel with MG in the frame diagram, thus obtaining the point g at the intersection of the two lines. The polygon of forces about the joint $ABGM$ will then read from a to b to g to m and from m back to the starting point a . From this it will be observed that the stress in BG at its lower end acts toward the joint, and, consequently, this member is in compression, while the stress at the left-hand end of the member GM is represented in the stress diagram by a line drawn in a direction away from the joint, so that this member is in tension. Having proceeded this far, one may hesitate as to whether to proceed with the joint $BCHG$ or $GHJZM$. An inspection of the latter joint, however, will show that there are a number of members gathered at this point and that so far only two of the forces are known.

It will be observed, however, that $BCHG$ contains only two unknown forces, and that when this joint has been solved, $GHJZM$ is likewise solvable. These two joints may then be represented in the stress diagram by the polygons $bchg$ and $ghjzm$. In this manner the stresses in the members GH , HJ , and CH , together with JZ , are determined and the stresses in all the members of the truss obtained. Since the loads are symmetrical, the stress diagram will be the same on both sides of the line zj .

15. If, after determining the stresses in GM and GH , there had still remained three unknown forces about the joint $GHJZM$, it would have been necessary to figure the stress in JZ by taking the moments about the apex of the truss. This stress will equal the algebraic sum of the moments of the external forces about the apex divided by the perpendicular distance between that point and the member JZ , or the rise of the truss. All vertical loads on the left-hand side of the truss tend to turn this half of the truss in a downward direction, while the reaction R , acts in opposition to these forces and tends to revolve it in an

upward direction. The moments of the several forces AB , BC , and MZ are equal to their amount multiplied by the perpendicular, which, in this case, is the horizontal distance from their line of action to the apex of the truss, while the moment of R , about the apex of the truss is equal to its amount multiplied by one-half the span. The several distances entering into the calculation of moments for these forces are given in the figure, and the calculations are as follows.

Negative moments, due to the vertical loads on the truss around the apex, equal:

$$\begin{aligned}\text{Moment of } AB, 1,000 \times 18 &= 18\,000 \text{ foot-pounds} \\ \text{Moment of } BC, 2,000 \times 9 &= 18\,000 \text{ foot-pounds} \\ \text{Moment of } MZ, 3,000 \times 6.76 &= 20\,280 \text{ foot-pounds} \\ \text{Sum of negative moments} &= 56\,280 \text{ foot-pounds}\end{aligned}$$

Positive moments about the same point equal:

$$\text{Moment of } MA = 7,000 \times 18 = 126,000 \text{ foot-pounds}$$

The algebraic sum of these moments equals $126,000 - 56,280 = 69,720$ foot-pounds. It will be observed that the force CD does not exert a moment about the apex of the truss, so that, in figuring the negative moments, this force is neglected. The perpendicular distance from the member JZ to the apex of the truss is 9 feet, so that the stress in this member is equal to $69,720 \div 9 = 7,746$ pounds, which is proved to be correct by scaling the line JZ in the stress diagram.

The stress in the member CH can be checked by figuring the moments about the joint $GHJZM$. The negative moments about this joint, due to the vertical loads to the left, equal:

$$\begin{aligned}\text{Moment of } AB, 1,000 \times 11.24 &= 11\,240 \text{ foot-pounds} \\ \text{Moment of } BC, 2,000 \times 2.24 &= 4\,480 \text{ foot-pounds} \\ \text{Total of negative moments} &= 15\,720 \text{ foot-pounds}\end{aligned}$$

The positive moment about the same point equals $7,000 \times 11.24 = 78,680$, and the algebraic sum of the moments about the joint is $78,680 - 15,720 = 62,960$. The perpendicular distance from CH to the joint $GHJZM$, according to

the frame diagram, is 4 feet 6 inches, and the stress in the member CH is found by dividing 62,960 by 4.5, which is found to equal 13,991 pounds. This amount is approximately the stress found on scaling the line ch in the stress diagram.

16. Wind-Load Diagram.—The frame and stress diagrams of the wind load for the same truss are shown in Fig. 11. It is first necessary to calculate the reactions R_1 and R_2 . Since the truss is fixed at both ends, these reactions coincide in direction with the normal wind pressures at each panel point. The amount of R_1 may be calculated by taking the moments about c and finding the algebraic sum of all the external forces. If the normal wind loads acting at each panel point on the rafter member are considered as exerting negative moments about c , the reaction R_1 exerts a positive moment about the same point, and the moments of the several forces are as given in the following calculation. It must be remembered in these calculations that the moment of any force is obtained by multiplying the amount of the force by the perpendicular distance between its line of action and the point around which it tends to rotate.

Moment of BC , $2,400 \times 10.06 = 24\,144$ foot-pounds

Moment of CD , $1,200 \times 20.12 = 24\,144$ foot-pounds

Sum of negative moments = 48\,288 foot-pounds

Since the amount of R_1 multiplied by its lever arm must equal the sum of the products of each force on the rafter member multiplied by its lever arm, it is evident, since the lever arm of R_1 is known, that R_1 will equal the sum of the negative moments divided by the perpendicular distance between the line of action of R_1 and the point c . This distance, from the dimensions given in the frame diagram, is 32.18 feet and the value of R_1 is equal to 48,288 divided by 32.18, or 1,500 pounds. Since the directions of all the external forces coincide, it is evident that the condition of translatory equilibrium is fulfilled when the algebraic sum of the reactions and the loads equals zero, so that if one of the reactions is known the other can be found by deducting the known reaction from the sum of the loads; hence, R_2 equals

4,800 - 1,500, or 3,300 pounds. In this way all the external forces necessary to produce equilibrium in the truss have been determined and the load line and polygon of




FIG 11

external forces may be drawn. This force polygon is drawn from a to b to c to d . Then the amount of the right-hand reaction, or R_2 , is laid off from d upwards and the point z

located. The distance za , according to scale, should equal, in amount, the value of R , previously found.

There will be no difficulty encountered in drawing the stress diagram for the wind load except, possibly, in concluding the diagram. It will be observed, however, in working around the last joint $CDJH$ that the members JK and KL will be subjected to no stress, so that they may be disregarded in drawing the diagram. When a stress diagram is closed without certain members of the frame being represented, it shows that no stresses exist in these members under the condition of loading presented. For instance, in the stress diagram of Fig. 11, it is manifestly impossible to represent the stress in the member JK , for a line drawn from d parallel with the member DK intersects the line drawn from h parallel with the member HJ at a point which, if the stress HJ is to be represented, must be the point j , and no line can be drawn from j parallel with the member JK that will give a point k on a line representing the member DK . Having no point k , kl cannot be drawn.

Frequently, the useless members in a frame may be determined by inspection. Consider the right-hand rafter member DK of the frame diagram shown in Fig. 11. This member extends in a straight line from the apex to the heel of the truss and represents a force acting in the direction of its axis. It is evident that any force, such as KL , applied laterally to the force DK , will not be opposed by any portion of the force DK , but will, if the rafter member is joined at the point q , push or deflect the rafter member out of line, as designated by the dotted lines. Evidently, therefore, no force KL can exist and the member KL is consequently useless with the wind acting on the left-hand slope of the truss.

The forces around the last joint of the frame are the stresses in the members HC , DJ , JH , and the force CD . The strut and tie being omitted, the letters K and L are neglected and the entire space, as sectioned, can be designated as J , so that the stress diagram for the wind loads will be closed by working around the joint at the apex of the truss.

If the reactions have been carefully calculated and the stress diagram accurately drawn, the polygon of forces around this last joint of the truss will read, in the stress diagram, from *c* to *d* to *j* to *h*, and from *h* to *c*, the starting point.






FIG. 12

17. Diagram for Cambered Truss.—Figs. 12 and 13 show the graphical analysis for the stresses of a frame diagram that differs somewhat from the one described. It is an excellent design for roof trusses of small span. The lower chord of this truss is cambered, that is, it does not

extend in a straight line, but is raised at the center; besides, the rafter member is supported at two places instead of one. The stress diagrams for this frame should be laid out as an



Stress Diagram
(b)

FIG. 13

exercise. In the solution, no difficulty will be experienced in laying out the stress diagram, Fig. 12, for the vertical loads on the truss.

The stress diagram, Fig. 13, for the wind loads cannot so readily be drawn, from the fact that the reactions R_1 , R_2 must be determined by the principle of moments. After the reactions have been determined and the stress

diagram drawn, with the exception of the lines representing the stresses around the apex of the truss, the frame diagram should be studied to determine which members in the right-hand portion of the truss are useless when the wind blows

from the left-hand side. By inspection, it will be perceived that OP and PQ are of no use in resisting the wind loads, so that the entire space that is section-lined can be designated by the single letter P . When this has been determined, the joint at the apex of the truss can be analyzed by drawing a line from c , in the stress diagram, parallel with the direction of the right-hand rafter member and a line from x parallel with the tension member NP ; the point of intersection of these two lines will be P . The analysis of this joint, however, does not complete the diagram, from the fact that the stress has not been determined for the member pz . This stress may be found by connecting the points p and z in the stress diagram, and unless this line coincides in direction with the member PZ , the stress diagram is incorrectly drawn, either on account of inaccuracy or because the amounts of the reactions have been incorrectly determined.

In reading the several stresses in the polygon of forces last determined, it will be found that ZN and NP , as well as PZ , are subjected to tensile stresses. It will be observed, also, on inspection of the stress diagram, that ZK sustains a greater stress than PZ , but as the wind is as likely to blow on one side of the roof as on the other, the member KZ and the corresponding member on the right-hand portion of the truss must be proportioned for the maximum stress. The small stress in the member PZ , owing to this consideration, should be disregarded. Likewise, since the lower portion of the rafter member BK must be proportioned for the maximum stress, the stress determined for EP should be disregarded, from the fact that if BK is proportioned for the maximum stress, the rafter member throughout its length will be capable of sustaining any minor stress. The only necessity, therefore, for finishing the diagram is the desirability of checking the accuracy of the work by having the diagram closed, that is, by determining whether the last line in the diagram connecting two points, otherwise determined, lies in a direction coincident with the final member of the truss that it represents.

QUEEN-POST TRUSS

18. In Fig. 14 is shown a type of truss known as the **queen post**, from the fact that the vertical members, shown dotted, are made of timber, and are so constructed as to resemble posts. These members, FG and GH , are theoretically useless when the truss is loaded at its upper panel points with vertical loads equal in amount and symmetrical as to location about the center of the truss. Disregarding





FIG. 14

these members, therefore, and denominating all of the section-lined space as G , the stress diagram is drawn by laying out the load line ae and constructing the polygon of external forces that is enclosed by ab , bc , cd , de , ez , and za . From b the line bf is drawn parallel with BF in the frame diagram, the inter-

section f being found by extending from z , which coincides with the point c since the truss is symmetrically loaded, a horizontal line parallel with GZ in the frame diagram.

In analyzing the next joint BCG , it is found that when a line bg is drawn parallel with the member BG , it will be identical with the line bf , already drawn in the stress diagram; BC is already known. It will be found that the stress in the member CG must lie on the line zf in the stress

diagram; consequently, it is proved that there can be no force in the member FG , for the vertical distance between cg and gz , in the stress diagram, is zero. The stresses in the members FG and GH being nothing, the stress diagram can be finished by drawing, from d upwards, a line parallel with DG in the frame diagram. If the interior space of the frame is not regarded as one space, but is maintained in three portions, such as F , G , and H , the point k will be coincident with f and g .




FIG. 15

By inspection of the stress diagram we observe that the stresses in CG and GZ are equal, though they differ in kind, for CG is in compression and GZ is in tension. By referring to the frame diagram, it will be observed that the space G is a rectangle, and, on consideration, it is evident that a rectangle hinged at the corners, which is the condition assumed in all framed structures, is liable to distortion. This cannot occur when the vertical loads are symmetrically placed, and when corresponding loads on each side of the vertical center line of the truss are equal, for a tendency of one to distort the frame is counteracted by the other, which tends to produce distortion in the opposite direction. If, however, there is a great variation between the vertical loads

BC and CD , the frame will be distorted, as shown in Fig. 15 (a), provided it is hinged at the joints. In practice,




FIG. 16

though the distortion would tend toward that shown in the figure, the lower tie-member, or chord, has considerable transverse strength and will be deflected as shown in (b).

That this type of truss under unequal loads is unstable, and that equilibrium cannot be obtained without the introduction of another member, will be demonstrated by the failure of an effort to draw the stress diagram under such a condition of loading. For instance, in laying out the stress diagram for the truss loaded as shown in Fig. 16 (*a*), the load line or polygon of external forces is laid off the same as that for the stress diagram previously completed. No difficulty is experienced in drawing the stresses around the joint $BCGF$, but when the joint FGZ is analyzed it is found that the point g in the stress diagram cannot be connected with z by a line parallel to GZ in the frame diagram. So, it is clear that under these conditions the stress diagram cannot be drawn in such a manner as to make a closed polygon, and, in consequence, equilibrium cannot be maintained without the introduction of another force or its equivalent, a member exerting a stress. The question then arises what member must be placed in the frame diagram of the queen-post truss in order to obtain equilibrium? Since a rectangular frame is not a stable form and because a triangular frame is always rigid under any condition of loading, it is reasonable to divide the frame into triangles by a diagonal member, as has been done in Fig. 16 (*b*). It will be found in drawing the stress diagram that there is no place for the member HI , for the point h coincides with the point i , and consequently the stress in the member HI is zero. By going over the lines in the stress diagram for the frame shown at (*b*), it will be found that the diagonal member GH is in tension. Equilibrium in a truss could have been maintained as well by inserting a diagonal extending between the joints HIZ and $BCGF$. If the greatest load were still maintained at BC , this diagonal member would be in compression and the member FG would be subject to no stress.

19. In the rectangular space subdivided by reversing the diagonal in this manner, the stresses in the vertical members FG and HI are changed, but the stresses GC and HZ are not altered. If, however, the space included between

the vertical members FG and HI and the horizontal members CG and HZ had been any other quadrangle instead of a rectangle, the stresses in the members CG and HZ would have been changed as well. It is an important point to remember that the reversal of a diagonal dividing a quadrangle, other than a rectangle, would change the amount of stress in each of the sides, or in each of the members enclosing the figure.

20. It was observed in drawing the stress diagram for the queen-post truss, Fig. 14, that there was no stress in the dotted vertical members. It was also found, in drawing the stress diagram for an unsymmetrically loaded queen-post truss, as shown in the frame diagram, Fig. 16 (*b*), that there was no stress in the vertical member HI , shown dotted. It is evident, therefore, that these members are useless, that the stress in each case is zero, and that the members are not needed to close the polygon of forces about any joint. In each of these cases it is also clear that the conditions of equilibrium are realized in the frame without the insertion of these members. A careful inspection of the frame diagram in each case reveals the fact that in every case where these members have been proved useless, two of the forces at the joint GHZ in Fig. 14 and HIZ in Fig. 16 (*b*) act in the same straight line, and that there is only one remaining force at the joint. In order that equilibrium in the joint can be maintained, the algebraic sum of the vertical forces or vertical components acting at a joint must equal zero, and the algebraic sum of the horizontal forces or horizontal components at any joint must likewise equal zero.

Where two opposing forces act in a straight line, the introduction of a third force at any angle to the line of action of the two forces will only tend to disturb the equilibrium and can never be introduced in such a manner that the third force or its components will produce an algebraic sum of zero. This is an important principle in graphical statics and will clearly assist the student in the analysis of intricate framed structures and the determination of the stresses in the members by the graphical method.

As it will be advisable to bear this principle in mind, it has been placed in the following concise form:

Rule.—*Where the lines of action of two opposing forces coincide and there is but one other force acting at the same point, the two opposing forces must be equal, and the third force will destroy the equilibrium of the system, unless it equals zero.*

DIAGRAMS FOR COMPLEX FRAMES

TRUSSES WITH JOINTS ACTED ON BY THREE UNKNOWN FORCES

FINK ROOF TRUSS

21. Methods of Obtaining One of Three Unknown Forces.—In analyzing the stresses in framed structures by the graphical method, joints are often encountered where three of the several stresses acting at the point are unknown. As it is impossible to determine the stress in a third unknown at a particular joint by the usual means employed in the graphical solution, when such a difficulty arises some expedient must be resorted to in order to obtain the amount of one of the unknown forces. The three methods employed to accomplish this purpose are:

1. A study of the symmetry of the frame diagram so as to determine by inspection, if possible, whether one of the unknown members or stresses does not equal some force or stress previously determined.
2. A calculation of one of the unknown forces or the stress in some adjacent member that may assist in determining one of the forces, by the theory of moments.
3. Reversing the direction of a member in the frame diagram. This method, which is known as *the solution by the reversal of the diagonal*, as it involves no calculations, is clearly graphical, surer than the first, and more expedient than the second.

These three methods will be explained in conjunction with the solution of stresses for the Fink, or Polonceau, type of roof truss shown by the frame diagram in Fig. 17.

22. Method by Symmetry.—The Fink, or Polonceau, roof truss is particularly favored by many on account of its symmetrical appearance, and from the fact that it can be




FIG. 17

readily and economically constructed. There is a difficulty, however, in analyzing the stresses, from the fact that when the joint $CDLKJI$ is attempted, the operation is immediately halted since the stresses in the members DL , LK , and KJ are unknown. Likewise, on referring to the joint $JKNZ$, the stresses in the members JK , KN , and NZ are unknown. By studying the diagram in an effort

to determine by the symmetry of the truss whether any of the unknown stresses can reasonably be supposed to have the same stress as another member—the stress in which can be determined—it is found that LM must have the same stress as HI ; this being true, and LK being the reverse of JI , necessarily sustains the same stress from the foot of the strut ML as IJ obtains from the foot of HI . With this fact in view, commence the diagram by laying out a portion of the load line from a to f , and since the reactions R_1 and R_2 are equal, on account of the loads being symmetrical, the point s will be located midway between e and f . Draw, from b , an indefinite line extending parallel with BH in the frame diagram, and, from s , a line hs extending parallel with HZ . The point of intersection will be h and the polygon of forces around the left-hand joint of the roof truss will be traced in the stress diagram from a to b to h to s , and from s upwards to the starting point a . The joints $BCIH$ and $HJJZ$ can now be laid out in the stress diagram and their respective polygons of forces obtained, thus locating the points i and j .

Now the difficult joints in the truss are encountered, but it has been suggested that ML and IH carry the same stress. Therefore, it is evident, on inspection of the frame diagram, that l and m must lie somewhere along the lines drawn from d and c parallel with DL and EM . It is also known that a line drawn downwards from j parallel with JK must contain, somewhere along its length, the point k , but on further consideration it is known that k and l must be connected by a line parallel with LK in the frame diagram, and also, which is still more important, that lk must equal, in length, ij ; then by trial, lk can be located as shown. The point m is also located and the diagram completed by drawing from m a line parallel with MN in the stress diagram, which line will pass through k and intersect a line drawn from s parallel with NZ in the frame diagram at the point n . The polygon of forces around this last joint $JKNZ$ reads in the stress diagram from j to k to n to s , and from s back to j . The figure being thus closed, the proof of the method is evident.

Since the truss is symmetrical with regard to a vertical center line and is likewise symmetrically loaded, the other half of the diagram will be the reverse of the one drawn, and the line zh in the stress diagram will be an axis of symmetry.

23. Method by Moments.—Again referring to the frame diagram, Fig. 17, it is observed that if the stress in the member NZ could be calculated, the joint $JKNZ$ would no longer contain three unknown forces and consequently could be solved by the usual graphical method.

The stress in the member NZ may be readily calculated by taking moments about the point c ; that is, by considering the truss as hinged at this point with all the loads on the rafter members tending to revolve the left-hand half of the truss in a direction opposed to the movement of the hands of a watch, while R_1 , the left-hand reaction, opposes this movement and tends to rotate the left-hand half of the truss in a direction about c agreeing with the movement of the hands of a watch. But the algebraic sum of this system of forces will not equal zero, so that the member NZ must be able to resist such a stress as to retain equilibrium of rotation for the left-hand half of the truss. The moment of the stress in the member NZ about the point c is equal to the product of its amount by the perpendicular distance between its line of action and the point in question, or 15 feet, and the amount of the stress in this member can be obtained by dividing the algebraic sum of the moments of the external forces R_1 , AB , BC , CD , DE , and EF about the point c by 15. For instance, the moments of the loads on the rafter members are as follows:

$$\text{Moment of } AB = 1,000 \times 32 = 32000 \text{ foot-pounds}$$

$$\text{Moment of } BC = 2,000 \times 24 = 48000 \text{ foot-pounds}$$

$$\text{Moment of } CD = 2,000 \times 16 = 32000 \text{ foot-pounds}$$

$$\text{Moment of } DE = 2,000 \times 8 = 16000 \text{ foot-pounds}$$

$$\text{Moment of } EF = 2,000 \times 0 = \underline{\hspace{2cm}} 0 \text{ foot-pounds}$$

$$\text{Sum of moments opposed to } R_1 = 128000 \text{ foot-pounds}$$

The moment of R_1 about the point $c = 8,000 \times 32 = 256,000$ foot-pounds. If the sum of the moments for the

loads on the rafter member is regarded as negative and the moment of R , is regarded as positive, the algebraic sum of the moments due to the external forces on one-half of the truss about the point c will equal $256,000 - 128,000$, or $128,000$ foot-pounds. This, divided by 15, equals 8,533 pounds, the stress in the member NZ .

The amount, 8,533, just obtained, may now be laid off from the point z in the stress diagram along the line parallel with the member NZ in the frame diagram and the point n thus located. Having determined the point n , the solution of the stresses around the joint $JKNZ$ is readily made. By scaling the length of the line nz in the stress diagram, which was previously drawn, it is found that the calculated amount of the stress in the member NZ agrees with that obtained by the method of symmetry.

Having obtained the stress in the member NZ , by calculation, no difficulty in drawing the stress diagram will be encountered, for by the solution of the joint $JKNZ$ the stress in the member JK is obtained. Therefore, since CI and IJ are already known, there remain around the joint $CDLKJI$ only the two unknown forces DL and LK . The diagram can now readily be completed by working around the other joints.

24. Method by Reversal of Diagonal.—This method consists in reversing the direction of a diagonal in the frame diagram, in order to determine one of the unknown forces about the joint $DEML$ or $JKNZ$, Fig. 18. The omitted member LK is shown light in the frame diagram, and is replaced by the member KM . The former member LM , shown dotted, if considered in the frame diagram, will produce a joint at KMN in unstable equilibrium and consequently the stress in this member must be zero, so that it is disregarded in drawing the stress diagram.

By omitting the useless members LK and LM , the frame diagram becomes as shown by the heavy lines and the stress diagram may be commenced. The load line and the points h , i , and j are found as usual and the stresses in the joint

$CDKJI$ may be laid out in the stress diagram by drawing a line from d parallel with DK and an intersecting line from





FIG. 18

the point j parallel with JK , the point of intersection being designated as k_0 .

The forces around the joint $JKMNZ$ may be found by first analyzing the joint $DEMK$. This joint is laid out in

the stress diagram by drawing a line from e parallel with EM and by describing from k_0 a line parallel with KM in the frame diagram. In this way m is located at the intersection of these two lines. The joint $JKMNZ$ may now be solved by drawing mn parallel with MN in the frame diagram and locating n at the intersection of the line just drawn and the line zh . The points n and m having been obtained, the omitted members LK and LM may be replaced and the reverse diagonal eliminated. The stress diagram is completed for the original truss by drawing from the point m a line ml parallel with ML in the frame diagram and extending the line jk_0 to its new intersection k_1 on the line mn , the diagram being closed by the line lk_1 , which is parallel with LK , and the extension of the line drawn from d parallel with DL in the frame diagram. It will be observed that the reversal of the diagonal was resorted to simply in order to obtain the points m and n , and consequently the stress represented by mn was not changed in any way by the reversal of the diagonal LK . The letters k_0 and k_1 are used only provisionally with the reversed diagonal KM . On replacing the diagonal LK , the letter k_0 is dropped and k_1 reverts to the original letter k .

QUADRILATERAL ROOF TRUSS

25. An interesting problem that involves the principles just described is offered by the frame diagram shown in Fig. 19 (*a*), which is the skeleton outline of a roof truss that can conveniently be used for spans of from 70 to 90 feet. The lantern, or skylight, the outline of which is shown dotted, may be of light work erected on the top of the truss, so that its weight need not be considered in proportioning the members in the frame diagram. The truss is shown with the wind acting on the left-hand side. The normal wind loads AB , BC , CD , and DE are calculated from the normal pressure on the roof slope acting on the panel area supported at each joint, while the load EF is the normal load on one-half of the panel and includes the left-hand reaction of the wind

load on the lantern, or skylight. The wind load FG is equal to the right-hand wind reaction of the skylight. The truss is considered as being constructed of steel and provided with a roller bearing at the right-hand end to allow for expansion;




FIG. 19

the other end of the truss is fixed. This condition existing, the direction of R_1 is known to be vertical; as the amount of one of the reactions must be known before the polygon of external forces can be laid out, the amount of R_1 may be

calculated by taking moments about the point c , that is, the point of application of R_1 , and regarding all of the loads as giving positive moments. Their sum is obtained by the following calculation:

Moment of $AB = 1,000 \times 0$	=	0 foot-pounds
Moment of $BC = 2,000 \times 8$	=	16 000 foot-pounds
Moment of $CD = 2,000 \times 16$	=	32 000 foot-pounds
Moment of $DE = 2,000 \times 24$	=	48 000 foot-pounds
Moment of $EF = 2,500 \times 32$	=	80 000 foot-pounds
Moment of $FG = 1,000 \times 45.666$	=	45 666 foot-pounds
Sum of positive moments	=	221 666 foot-pounds

The lever arm of R_1 is equal to the span of the truss or 71 feet, so that the amount of R_1 is equal to $221,666 \div 71 = 3,122$ foot-pounds. This result having been obtained, construct the polygon of forces shown in the stress diagram of the figure.

26. The force polygon is laid out by marking off, to scale, the forces ab , bc , cd , de , ef , and fg , then laying off upwards, from g , the amount of R_1 , locating in this way the point z . By connecting z and a , the direction and amount of R_1 is obtained; for the direction of R_1 coincides with the line az and its amount is equal to the distance, according to the scale of the diagram, from z to a . The stresses in the several members around the joint $ABHZ$ are obtained by drawing from b , in the stress diagram, the line bh parallel with BH , in the frame diagram, and intersecting this line with a horizontal line from z that is parallel with the member HZ .

The solution of the joint $BCIH$, at which two unknown forces exist, is readily made by drawing, from c , a line parallel with CI and extending from h a line parallel with the member HI , thus locating the point i . The stresses around the joints HIZ and $CDKJI$ are likewise drawn without any difficulty, but in attempting either the joint $DEMLK$ or $JKLQZ$, three unknown forces are encountered. There is no way of eliminating this difficulty by the method of symmetry, for no symmetry of the members exists in this truss. The stress in QZ or FN can be calculated by taking

moments about the joints $FGPON$ or $JKLQZ$, but as the problem can be more readily solved by reversing the diagonal LM , this method will be employed. It may be determined by inspection that the extension of the member OQ , shown dotted, is of no use when the wind acts on the left-hand portion of the structure, though this extension will come into play when the wind load acts on the right-hand portion of the truss, in which case the extension of the member LQ will be subjected to no stress, as, likewise, will be the various secondary members of the frame. Redraw and reletter the frame diagram with the diagonal reversed, as shown in (*b*), and proceed with the stress diagram by drawing from the point k , which has been previously found, the line km , parallel with the member KM in the frame diagram (*b*). This line will intersect a line drawn from e and parallel with the member EM at m_1 .

Next analyze the joint $EFNM$, as shown in the frame diagram (*b*), by drawing, from f , an indefinite horizontal line parallel with the member FN and extending, from m_1 , a line upwards parallel with the member NM , thus locating the point n . The joint $KMNQZJ$ in the frame diagram (*b*) can now be analyzed by drawing from n a line parallel with NQ . Where this line intersects the line drawn from z horizontally, or parallel with QZ , will be located the point q and the diagram for the truss may be closed by a line from g to q , which, if parallel with the member GQ , is proof that in the truss with the diagonal reversed, the diagram is correct and accurately drawn. Since the points n and q have been located in the stress diagram, the original truss with the diagonal ML , as shown in (*a*), may be drawn, and the stresses for the members LM and MN obtained by drawing from the point n a line parallel with NM in the original frame diagram. The intersection of this line with the line em_1 will locate the point m , and the length of the line nm will give the amount of the stress in the member NM . If the line nq is extended it should pass through the point l , when lq will indicate the stress in the member LQ . By extending a line from m parallel with LM

in the original diagram, until it intersects km , at l , the stress in this member may be obtained by measuring the length of the line lm , and the polygons of forces about the joints with three unknown forces, which prevented the further analysis of the truss, are completed and the stress diagram for the original truss is shown by the heavy lines. The auxiliary lines that it was necessary to draw when the diagonal was reversed are also shown in the stress diagram.

It is an interesting example and will give considerable practice for one to lay out the stress diagram for the wind on the right-hand side of the truss, considering the roller bearing still at R_1 . Likewise, lay out the stress diagram for the vertical loads, and if both diagrams close one may be reasonably sure that they have been correctly drawn.

FINK TRUSS WITH CAMBERED TIE-MEMBER

27. The Polonceau, or Fink, truss is frequently built with the lower chord of the truss cambered (raised at the center), as shown in view (a), Figs. 20 and 21. Cambering the lower chord in this manner gives greater headroom under the truss at the center, and somewhat improves its appearance; but it increases the stresses on all the members except KL , ML , and ON , and the corresponding members on the other side of the truss.

28. Diagram for Vertical Loads.—Fig. 20 (a) is a frame diagram showing the vertical loads on a Fink truss, the span of which is 80 feet, while the lower chord, or tie, is cambered from the horizontal 28 inches. The stress diagram for the vertical loads may be drawn, as shown in Fig. 20 (b), by first drawing the vertical load line af , and laying off, to some convenient scale, the loads ab , bc , cd , de , and ef designated in the frame diagram by AB , BC , CD , DE , and EF . Since the truss is symmetrically loaded, only one-half of the stress diagram need be drawn, and consequently the loads only as far as ef need be laid off on the vertical load line. The reactions R_1 and R_2 are each equal to one-half the load, or 18,000 pounds; hence, the point z is located

midway between e and f , and $z a$ represents the reaction R_1 , 18,000 pounds.

The stresses around the joint $A B K Z$ may be drawn in





FIG. 20

the stress diagram by commencing at b and drawing $b k$ parallel with $B K$, and from z , a line parallel with $K Z$, intersecting the first line at k . The polygon of forces

around this joint will then be from a to b to k to z , and from z back to a , the starting point. From the direction of these forces, the correct direction of the arrowheads in the frame diagram may be marked, and from their direction the kind of stress on the member is observed.

The next joint in the truss to be analyzed is $BCLK$. In the stress diagram begin at c and draw cl parallel with CL in the frame diagram, then from k , draw a line parallel with LK in the frame diagram, until it intersects the line drawn from c at the point l . The polygon of forces around the joint is from b to c to l to k , and from k back to b , the starting point.

Around the joint $KLMZ$, the stresses are obtained by drawing from l a line parallel with LM in the frame diagram, until it intersects the line zk at the point m . The polygon of forces around this joint is from k to l to m to z , and from z back to k , the starting point.

Difficulty will be encountered on attempting to analyze either the joint $CDONML$ or $MNQZ$, for at each of these joints there are three unknown forces or stresses. The difficulty may, however, be overcome by applying either of the three methods given in Art. 21. For instance, by reversing the diagonal NO and leaving the member OP out of consideration, a provisional point n , is located on a line dn , drawn parallel with DO . By means of n , the point p is located on the line ep , after which the diagonal NO may be replaced and the truss considered in its original form.

The remaining joints, when taken in their usual order, offer no difficulty, and the other half of the diagram need not be drawn unless it is desired to check the half just completed.

The polygon of forces that is traced in going around the joint $CDONML$ affords a good illustration of the rule, that the forces that meet at a joint must make a closed polygon in the stress diagram.

One of the peculiarities of the stress diagram, Fig. 20 (b), and one that is worthy of note, as it will materially assist in drawing the diagram, is that the triangles lkm and pon are equal and are similar to the larger one whose base is mn .

29. The wind-stress diagram may now be drawn. First the frame diagram is redrawn, and on it, as shown in Fig. 21 (*a*), are designated the wind loads acting at the several joints of the truss, in a direction normal to the slope of the roof.

The reactions R_1 and R_2 may be calculated by the principle of moments. Since the truss is securely fastened at both ends, neither end being free to move in a lateral direction, these reactions will be parallel with the action of the wind on the roof, that is, normal to the slope. The reaction R_2 may first be obtained by extending its line of direction until it intersects the extension of the left-hand rafter member at the point a' . Then by taking the center of moments at the left-hand reaction R_1 , the magnitude of the reaction R_2 may be computed.

For convenience, reduce to feet and decimals the distance from each panel point to the point of rotation R_1 ; the moments about this point will then be as follows:

$$\begin{array}{rcl} 5,625 \times 11.188 & = & 62,932.50 \text{ foot-pounds} \\ 5,625 \times 22.375 & = & 125,859.38 \text{ foot-pounds} \\ 5,625 \times 33.563 & = & 188,791.88 \text{ foot-pounds} \\ 2,813 \times 44.750 & = & 125,881.75 \text{ foot-pounds} \\ \hline \text{Total,} & & 503,465.51 \text{ foot-pounds} \end{array}$$

The distance of the center of moments of the line of action of the reaction R_2 is $44.75 + 27 = 71.75$ feet, and $503,465.51 \div 71.75 = 7,016$, the magnitude of the reaction R_2 , in pounds.

Since the sum of the wind loads is 22,501 pounds, which is equal to the sum of the reactions, the reaction due to the wind at R_1 is $22,501 - 7,016 = 15,485$ pounds.

To construct the wind-stress diagram, Fig. 21 (*b*), draw the load line from a to f parallel to the reactions and direction of the wind loads at the several joints. Then lay off on the load line the loads ab , bc , cd , de , and ef , which are, respectively, equal to the corresponding loads AB , BC , CD , DE , and EF in the frame diagram. Having located the point f , the magnitude of the reaction R_1 , represented by fz , may be

laid off upwards (the direction in which it acts), and the point z thus located; then on scaling za , it should be found





FIG 21

equal to 15,485 pounds, the reaction R_1 . The polygon of external forces will then be: from a to b to c to d to e to f to z , and from z to a , the starting point.

The joint $CDONML$ may be solved in this stress diagram in the same manner as it was solved in the vertical-load stress diagram. The analysis of stresses around the last joint $EFRQP$ in the frame diagram, is interesting, from the fact that the stress qr closes the diagram, and, if the diagram is correctly drawn, this line must be parallel to the member QR .

TABLE II

Member	Stress Due to Vertical or Dead Load	Stress Due to Wind Load	Total Stress
BK	+ 46,000	+ 34,500	+ 80,500
CL	+ 44,000	+ 34,500	+ 78,500
DO	+ 42,000	+ 34,500	+ 76,500
EP	+ 40,000	+ 34,500	+ 74,500
KL	+ 4,000	+ 5,500	+ 9,500
MN	+ 8,000	+ 11,250	+ 19,250
OP	+ 4,000	+ 5,500	+ 9,500
ZK	- 41,500	- 36,750	- 78,250
ZM	- 35,500	- 28,500	- 64,000
ZQ	- 21,000	- 11,000	- 32,000
QN	- 15,500	- 18,500	- 34,000
QP	- 21,500	- 26,000	- 47,500
FR		+ 17,000	
RQ		- 2,000	
NO	- 5,750	- 8,000	- 13,750
LM	- 5,750	- 8,000	- 13,750


Having drawn both the wind- and the vertical-load stress diagrams, the stresses in the several members in the truss may be obtained by scaling, and their magnitudes may be tabulated as in Table II.

In Table II, compression is indicated by the plus sign and tension by the minus sign.

WIND AND SNOW LOADS ON OPPOSITE SIDES**CRESCENT TRUSS OF SMALL SPAN**

30. In the solutions for determining the stresses in roof trusses, two stress diagrams have been considered: the one for the vertical load on the roof truss and the other for the wind load taken normal to the roof slope, and a combination of the stresses in the several members determined by these diagrams has been assumed to give the maximum stresses in the members throughout the truss. The assumption that the maximum stress is attained by combining the results of the full vertical-load and the wind-load diagrams is usually on the side of safety, though there are occasions when the combination of these two diagrams does not give the maximum stress in the members and the conditions as expressed by such a method can seldom exist. In the design of a large roof truss, therefore, where economy is a consideration, it is best to draw several diagrams and combine the stresses found by several combinations of these diagrams; the actual conditions as they will occur under varied wind and snow loads may then be approached. It is usual, therefore, to draw, first, the dead load exclusive of the snow load; second, a diagram of the truss including the entire snow load; third, a diagram of the wind load acting on the roof truss from both the right and the left, the different directions giving different stress diagrams if the truss is supported on rollers at one end; fourth, stress diagrams that will represent the snow load on the leeward side of the truss and the wind load acting on the windward side; that is, stress diagrams that will give the stresses in the several members of the roof truss, when one side of the truss is covered with snow and the wind blows with its maximum velocity on the other side.


This latter condition is the one that will be especially considered in this problem; that such a condition may be approached is reasonable from the fact that when the wind is blowing with its maximum velocity of 80 or 100 miles an hour,






Stress Diagram - Dead Load -


Scale: 600 lb. sq. inch



Stress Diagram - Wind Load on Left -
Wind Load on Right




(a)



(d)

Stress Diagram - Wind on Left



no snow can possibly be supported on one side of the roof truss, though a full snow load may exist on the other side.

In Fig. 22 (*a*) is shown the frame diagram of a **crescent-shaped roof truss** with the web members arranged similar to a Howe truss. The lower chord is cambered 8 feet 6 inches to comply with the conditions imposed by the architectural treatment of the interior of the building. The span of the truss is 80 feet, its total rise from the *springing line*, or level of the foot of the truss, is 25 feet, and the radii of the top and bottom chords are 44 feet 6 inches and 96 feet 5 inches, respectively. On the left-hand portion of the truss at each panel point are designated the snow loads, while on the right-hand half is shown the resultant wind pressure at the several panel points. There being no load or wind pressure at the two ends of the truss, the letters *B* and *I* are omitted and the first and last loads are termed *AC* and *HJ*, respectively.

In determining the snow loads on the left-hand portion of the truss, it might be considered that the slope of the upper chord, and consequently of the roof in the panel *AK*, is so steep as to preclude the lodgment of any snow on it. In this particular instance, however, since the walls of the building terminate in a parapet, which would be likely to cause the lodgment of considerable snow depending for its support on a portion of the chord *AK*, it was considered advisable to assume the panel load *AC* as made up of a snow load equal to 8 pounds per square foot on one-half of the chord *AK*, and of 12 pounds per square foot on one-half of the chord *CL*. Since the principals, or roof trusses, are 18 feet from center to center and the distance from panel point to panel point is 12 feet 6 inches, the vertical loads due to the snow at the several panel points may be determined by the following calculation:

Part of <i>AC</i> =	$6.25 \times 18 \times 8 =$	900
Part of <i>AC</i> =	$6.25 \times 18 \times 12 =$	1,350 2,250
<i>CD</i> =	$12.50 \times 18 \times 12 =$	2,700
<i>DE</i> =	$12.50 \times 18 \times 12 =$	2,700
<i>EF</i> =	$6.25 \times 18 \times 12 =$	1,350

In calculating the amount of the wind resultant at the several points on the right-hand side of the truss, it is advisable to calculate the pressure normal to the curve of the roof slope or the upper chord; that is, perpendicular to tangents at these points, or in the direction of the radius drawn through its point of application. These normal pressures can be calculated by Hutton's formula, or found from a table giving the values for roof slopes of different pitches. It was in this manner that the wind loads were determined in laying out the stress diagram in Fig. 22 (a). The above formula and table are given in *Loads in Structures*.

31. Determining Wind Pressure on Truss With Curved or Broken Upper Chord.—A method for determining the wind pressures at the several panel points on a truss with a curved or broken upper chord, which is usually sufficiently accurate for all practical purposes, is shown in Fig. 22 (c). It is based on the following rule:

Rule 1.—*The wind pressure normal to an inclined surface varies, approximately, as the sine of the angle that this surface makes with the horizon.*

The roof slope, in this instance, being a curved surface, a tangent drawn through the point where the wind resultant is supposed to act will represent the incline. Referring to Fig. 22 (c), the wind resultant d, d is acting at the point d , through which a tangent $d d_1$ is drawn. According to the above rule the wind pressure $d d_2$, normal to the roof, will vary with the sine of the angle a_1 . By drawing line $d_1 d_2$ parallel to $d d_2$, a right triangle $d d_1 d_2$ is produced, in which the hypotenuse $d d_1$ and the angle a_1 are given, or, if not, may be calculated as shown below. The side $d_1 d_2$ may then be found by means of the function $d_1 d_2 = \sin a_1 \times d d_1$. Assuming that the side $d d_1$ represents the wind resultant of 40 pounds per square foot and that the angle a_1 is 48° , the side $d_1 d_2 = \sin 48^\circ \times 40 = .743 \times 40 = 29.7$ pounds. By drawing $d_1 d_3$ parallel to the tangent $d d_1$, a triangle equal to $d d_1 d_2$ will be formed, in which the angle a_2 is equal to a_1 , and the side $d d_3$ is equal to $d_1 d_2$. The normal wind pressure $d d_3$ will, therefore, be

proportional to the sine of the angle a_1 . For obvious reasons, the triangle $e d p$ is similar to either of these triangles, the angle a , being equal to a_1 and a_2 . Therefore, if these angles are not known they may be found by means of the function:

$$\sin a_1 = \frac{d e}{d p} = \frac{33}{44.5} = .7415 = 47^\circ 52', \text{ or nearly } 48^\circ$$

the distance $d e$ being found from the drawing and the radius calculated, if not given, by means of the rise of 25 feet and the total length of 80 feet.

Other wind resultants are shown at the points f and h , and for the reason already given, it is obvious that the angles b , and c , are equal to b_1 and c_1 , respectively. If these angles are not known they may be found by the following rule:

Rule II.—*The sine of an angle is the quotient of the opposite side divided by the hypotenuse.*

The hypotenuse in this case is equal to the radius of the arc, and the side opposite the angle is one-half of the chord of the arc enclosed by twice the angle.

The problem may be solved graphically in the following manner: Let the line $d d_1$ represent the pressure per square foot of the wind resultant, drawn to any convenient scale. From its outer end, draw a line $d_1 d_2$ perpendicular to the extended radius $p d$; then the length of the line $d d_2$ will give the normal wind pressure per square foot, measured to the same scale. Or the line $d d_1$ may represent the total panel pressure at this place, based on a pressure of 40 pounds per square foot, when the line $d d_2$ will give the reduced pressure normal to the panel, or to the tangent representing two adjoining panels. In a similar manner, the normal pressures are found at the points f and h by laying off the lines $f f_1$ and $h h_1$ equal, in length, to $d d_1$ and drawing the lines $f_1 f_2$ and $h_1 h_2$ normal to the extended radii $p f$ and $p h$, respectively, when the lines $f f_2$ and $h h_2$ will represent the normal wind pressures at these points.

The normal pressure may also be found by means of the following proportion: $d p : d e = \text{the wind resultant } d d_1 : \text{to the normal pressure } d_2 d$. Replacing $d_2 d$ by the letter x and giving the other terms their respective values: $d p = 44.5$,

the line kz parallel with the member KZ , the intersection of the two lines being the point k . It will be necessary now to go around the joint KMZ , for around the joint $ACL MK$ there are more than two unknowns. Therefore, in the stress diagram (*b*), draw from the point k an indefinite line km parallel with KM , in the frame diagram, and from z extend a line in the direction of zm parallel with MZ , in this way locating the point m at the intersection of km and zm . The analysis of the stresses around the joint $ACL MK$ is now clear and they may be determined by drawing from c an indefinite line parallel with CL , and from m a line parallel with ML , upwards and to the left, intersecting the line drawn from c at the point l . The polygon of forces around this latter joint will then be from a to c to l to m to k and from k back to the starting point a . Each joint may, in turn, be analyzed in this manner and the diagram completed as shown.

The diagram for the dead load, exclusive of the snow load, is shown in Fig. 22 (*c*), the dead loads on the panel points being, in this instance, practically the same as the snow loads. In Fig. 22 (*d*) is designated the diagram for the wind load on the left-hand slope of the truss, neglecting the snow load, and a similar diagram for the wind load on the right-hand portion of the truss, neglecting the snow load, might be drawn.

CRESCENT TRUSS OF LARGE SPAN

33. The crescent roof truss of large span, shown in Fig. 23 (*a*), is an excellent truss for exposition buildings, car barns, and similar structures. Its elements are the top and bottom chords and the web members. While the web members are arranged entirely for utility they do not present an unpleasing appearance. The lower member of this truss is usually cambered, as shown on the drawing. Both the top and bottom can be arranged on segments of circles. The panel points may be located by means of ordinates from a top or bottom horizontal line as shown in the figure. It is proposed, in analyzing this truss, that four diagrams

The sum of the moments about the left-hand abutment equals 965,936 foot-pounds. The lever arm through which the reaction R_1 acts around the center of moments at the left-hand abutment is equal to the span, or 80 feet, and as the moment of R_1 about this point must equal the sum of the moments of the vertical and wind loads at the panel points, the value of R_1 is found by dividing 965,936 by 80, which gives 12,074.2 pounds. The stress diagram for the combined snow and wind load may now be commenced by laying out the polygon of external forces, in which way the amount and direction of the reaction R_1 will be determined.

32. In Fig. 22 (*b*) is shown the stress diagram for the truss loaded as shown in (*a*). This diagram is drawn to a scale of 600 pounds to $\frac{1}{16}$ inch. Lay off the vertical loads AC , CD , DE , and EF on the load line in the stress diagram, to scale, as shown at ac , cd , de , and ef , respectively. From f , in the stress diagram, lay off the oblique lines fg , gh , and hj representing the resultant wind pressures at the several panel points at the right-hand side of the truss. From j , extend the vertical line upwards and lay off the distance jz equal to the amount of reaction R_1 , or 12,074.2 pounds. The point z having been thus located, draw a line connecting it with the point a and by so doing determine, by the direction and the length of the line za , the amount and direction of the reaction R_1 . The polygon of external forces is now completed and includes, as in every case of graphical statics, both the loads and their several reactions. In going around the polygon of forces, following the direction from the left to the right in the frame diagram, the forces are ac , cd , de , ef , fg , gh , hj , and from j to z , and from z back to a , the starting point. This closes the polygon of external forces and the stress diagram may be completed by working around each point, conveniently commencing at the left-hand end of the truss.

Start the diagram by working around the joint AKZ , drawing from the point a , in the stress diagram, the line ak parallel with AK , in the frame diagram, and extending from z





be drawn: First, the dead-load diagram (*b*); second, the wind-load diagram (*c*); third, the snow-load diagram (*d*); fourth, a stress diagram (*e*), considering the truss as being subjected to a snow load on one side and the maximum wind load on the other.

In calculating the panel loads for the frame diagram necessary to draw the dead-load diagram shown in Fig. 23 (*b*), the weight of the principal, or roof truss, and the roof covering was considered; and in the calculation for all of the loads at the several panel points, it was assumed that the roof trusses were placed 16 feet from center to center. The dead-load diagram offers no difficulty, and as the truss is symmetrically loaded, only one-half the diagram need be drawn. The loads and reactions lie in vertical lines, so that the load line is a single straight line extending from *a* to *p* and the polygon of external forces for the dead loads is drawn from *a* to *b* to *c* to *p*, back to *a*, then to the starting point *a*. It will be found by working around the truss that at any joint there will not exist more than two unknown forces.

In drawing the wind-stress diagram (*c*), it is assumed that the right-hand end of the truss is on rollers and consequently that the reaction is vertical at this point. Since the direction of *R*, or the right-hand reaction, is known, its amount can be readily calculated by taking moments about the point *c*, or the left-hand reaction. The lever arms may be obtained by scaling the lengths of lines from the center of moments *c* perpendicular to the lines of action of the wind at each panel point. The calculation is as follows:

Moment of <i>AB</i>	=	1,600 × 0	=	0	foot-pounds
Moment of <i>BC</i>	=	3,100 × 9.8	=	30 380	foot-pounds
Moment of <i>CD</i>	=	2,600 × 19.4	=	50 440	foot-pounds
Moment of <i>DE</i>	=	2,100 × 28.6	=	60 060	foot-pounds
Moment of <i>EF</i>	=	1,600 × 37.3	=	59 680	foot-pounds
Moment of <i>FG</i>	=	1,200 × 45.5	=	54 600	foot-pounds
Moment of <i>GH</i>	=	800 × 53.5	=	42 800	foot-pounds
Moment of <i>HI</i>	=	300 × 61.5	=	18 450	foot-pounds
Sum of moments					= 316 410 foot-pounds

The leverage of the right-hand reaction, since it acts vertically, is equal to the span of the truss, or 120 feet; and $316,410 \div 120 = 2,637$ pounds, the amount of the reaction R_2 . In laying out the stress diagram, draw the load line $ab, bc, cd, de, ef, fg, gh$, and hi , being careful to designate each force in its true length and direction, as each force acts in a different direction. When the point i , which is the termination of the last wind load, has been located, the reaction R_2 can be drawn vertically and its amount, 2,637 pounds, laid off to scale, thus locating the point s . By connecting s and a the amount and direction of the left-hand reaction, which is oblique, since the end of the truss is fixed, are determined. The diagram may then be completed, when it will have the appearance shown. The reactions corresponding to this stress diagram are shown to the left and right of the truss in Fig. 23 (*f*) and (*g*).

Moment of $AB = 1,600 \times 0$	=	0 ft.-lb.
Moment of $BC = 3,100 \times 9.8$	=	30380 ft.-lb.
Moment of $CD = 2,600 \times 19.4$	=	50440 ft.-lb.
Moment of $DE = 2,100 \times 28.6$	=	60060 ft.-lb.
Moment of $EF = 1,600 \times 37.3$	=	59680 ft.-lb.
Moment of $FG = 1,200 \times 45.5$	=	54600 ft.-lb.
Moment of $GH = 800 \times 53.5$	=	42800 ft.-lb.
Moment of $HI = 300 \times 61.5$	=	18450 ft.-lb.
Moment of $I, I = 1,250 \times 60.0$	=	75000 ft.-lb.
Moment of $IJ = 2,500 \times 68.583$	=	171458 ft.-lb.
Moment of $JK = 2,500 \times 77.1667$	=	192917 ft.-lb.
Moment of $KL = 2,500 \times 85.75$	=	214375 ft.-lb.
Moment of $LM = 2,500 \times 94.333$	=	235833 ft.-lb.
Moment of $MN = 2,500 \times 102.9167$	=	257292 ft.-lb.
Moment of $NO = 2,500 \times 111.5$	=	278750 ft.-lb.
Moment of $OP = 1,250 \times 120.0$	=	150000 ft.-lb.

Sum of moments = 1892035 ft.-lb.

Dividing this sum by the span gives $1,892,035 \div 120$, or 15,767 pounds, as the right-hand vertical reaction, which is shown in Fig. 23 (*k*). The load line may now be laid out in the stress diagram as shown.



The stress diagram for the snow load, which is assumed to be 2,500 pounds on each panel, is shown in Fig. 23 (*d*). As will be observed, this diagram is similar to the dead-load diagram, except that the stresses in the different members are slightly reduced. The corresponding reactions are shown in Fig. 23 (*h*) and (*i*).

In Fig. 23 (*e*), the stress diagram is given for a wind load on the left-hand side of the truss and a snow load on the right. The snow load on the panel point *H I* will be only half of 2,500 pounds in this case, since the snow on one side of the truss only is considered. The right-hand end of the truss is assumed to be on rollers and the reaction *R*, is obtained by taking the moments about the point of support at the other end of the truss, or the point *c*. The calculations are as given on the preceding page.

The forces *ab*, *bc*, *cd*, *de*, *ef*, *fg*, *gh*, and *hi*, should be carefully laid off in the proper directions; the remaining forces *ii*, *ij*, *jk*, *kl*, *lm*, *mn*, *no*, and *op* are in a vertical direction. The reaction *R*, is now laid off vertically from *p* to *z* and a line drawn connecting *z* and *a*; this line represents the direction and magnitude of the left-hand reaction, which may be drawn in the frame diagram as shown in Fig. 23 (*j*). The reactions *R*, and *R*, shown on the frame diagram (*a*), are for the dead load, exclusive of the snow load. No difficulty will be encountered in drawing this stress diagram (*e*), as there are not more than two unknown forces at any joint.

ROOF TRUSSES WITH HORIZONTAL OR OBLIQUE THRUSTS

HAMMER-BEAM TRUSS

34. The hammer-beam roof truss, shown in Fig. 24 (*a*), is adapted to spans of from 40 to 50 feet and is much used in timber and composite construction for church roofs. It is especially applicable to the usual Gothic treatment of such buildings, for it is ornamental in form, and the several spaces into which it is divided by the members readily lend

themselves to Gothic details. This type of truss cannot be economically used unless the walls on which it rests are so buttressed or braced that they can provide a horizontal thrust, for in a truss lacking a vertical member subdividing the space P , Fig. 24 (a), it is imperative that this thrust should be provided for. If the walls are capable of resisting a vertical reaction only, the apex of the truss will tend to rise and the distortion shown in Fig. 25 will take place; that is, providing the stiffness of the joints, or the resistance of the rafter members to transverse stress at a, a is not




FIG. 25

sufficient. In view of these facts, this truss is usually adapted for the roofs of buildings, such as shown in the cross-section in Fig. 26. Here the truss spans the aisle of the church and rests on the arcades a, a at either side. The cloisters are covered by a sloped roof b, b , and their walls are usually buttressed, so that the roofs b, b provide the thrust necessary to hold the main roof truss in equilibrium. The construction is pleasing, for it is not unusual to provide a clearstory between the straight portions c, c , of the main truss, the lights and shadows obtained by this arrangement

being particularly adaptable to the architectural treatment of a Gothic edifice.

While this horizontal thrust can be calculated by the principle of moments, it is more readily determined by changing the position of some of the members in the truss on the principle of the reversal of the diagonal. It is evident that if only a vertical reaction is supplied, as at AZ , Fig. 24 (*a*), on the analysis of the joint there will be three unknowns consisting of AK , KZ , and the horizontal thrust H . The diagonal LK can be reversed and will then assume the position shown by the member BL in Fig. 24 (*b*). Likewise,




FIG. 26

MN may be reversed and assume the position of ML in (*b*). In changing the diagonals in this manner, it leaves the strut LM in Fig. 24 (*a*) acting on two members represented by the dotted lines KZ and NZ , coincident in their line of action, and it is evident that there will be no stress in the strut 1-2 shown dotted in (*b*), for, by the principles explained in Art. 20, it was shown that where the lines of action of two opposing forces coincide, the introduction of a third force will destroy the equilibrium. This member, marked LM in (*a*) and 1-2 in (*b*), may therefore be omitted from the new diagram.

According to the same reasoning AB , in Fig. 24 (a), is opposed by a direct equivalent compressive stress in AK , whose line of action coincides with the line of action of AB . When the member LK is reversed, as shown in (b), the introduction of BL in (a) tends to destroy the equilibrium and consequently its stress is zero. The new diagram is then completed, as shown, by the solid lines in Fig. 24 (b), and there remains to be determined the amounts and directions of the reactions R_1 and R_2 in order that they may be introduced in the old diagram (a).

The reciprocal stress diagram for the frame diagram shown in Fig. 24 (b) is shown in Fig. 24 (c). In laying out this diagram the load line aj is laid out as usual, but since there are three unknowns at the lower joint of the truss, the diagram must be commenced at another panel point. An inspection shows that the apex joint EFP contains only two unknown forces, and that when EP is found the joint at $DEPO$ contains only two unknowns. Therefore, it is best to commence the diagram at the apex of the truss. Draw, in the stress diagram, lines ep and fp parallel, respectively, with the members they represent in the frame diagram, thus locating the point p . Then draw the stresses for the joints $DEPO$ and $CDOM$; OM having been obtained in this manner, there will exist only two unknowns at the joint $BCML$, and this joint may be analyzed in the stress diagram. Having obtained the stress in the member BL , there exist only two unknowns at the left-hand foot of the truss. A line, therefore, drawn from l parallel with the member LZ will intersect at a point z with a horizontal line dividing the vertical load line centrally, for the truss is symmetrically loaded. The point z having thus been obtained, by connecting z and a the reaction R_1 is found in direction and amount. By completing the other half of the diagram the reaction R_2 may be obtained. It will be found, however, that under a symmetrical vertical load and where the proper oblique reactions R_1 and R_2 have been supplied, the vertical component is equal to the sum of one-half the loads on the roof truss, while the horizontal thrust may be obtained from


the stress diagram by measuring the horizontal line from the point z to its intersection with the vertical load line.

When the reactions have been obtained they may be placed in the stress diagram for the original truss, where they serve to locate the point z and then k by the line $z k$, after which no difficulty will be found in drawing this diagram, as shown in Fig. 24 (*d*).

The dotted lines shown in the frame diagram (*a*) represent members that must be substituted for the curved members, and the analysis of the substituted straight members will give the direct stress acting at the ends of the curved members. These curved members must be proportioned to withstand a bending moment equal to the direct stress in the assumed dotted member multiplied by the perpendicular distance from the line of action of the dotted member to the farthest point of the curve.

35. While it was found necessary to provide horizontal or oblique thrusts at the abutments in order to preserve equilibrium in the hammer-beam truss shown in Fig. 24 (*a*), if this truss had been provided with a vertical member dividing the upper space P , it would have been found that the truss was stable when vertical reactions alone were considered at the abutments. The frame diagram drawn with the vertical member in the upper space is shown in Fig. 24 (*e*); and the stress diagram can easily be drawn for the truss with vertical reactions alone. Before it is drawn, however, inspection will show that since all the loads and the reactions are vertical and the member $A K$ is coincident with the line of action of the reaction R_1 , there will be no stress in the member $K Z$. The truth of this assumption is substantiated by the principle stated in Art. 20.

This stress diagram, drawn to the same scale as the others, is shown in Fig. 24 (*f*). An inspection will show that the stresses in the several members have been greatly influenced, and that the truss designed with supports that offer only vertical resistance is not economical; besides, the slightest movement that might take place in the connections,



Scale $\frac{1}{16}$ inch = 500 lb.


(b)
FIG. 27

which is likely to occur when the truss is constructed of timber, will produce a sagging, which distortion will add still more to the stresses already so greatly augmented.


36. These conditions decide that it is best, for economical reasons, to provide horizontal thrusts H_1 and H_2 , shown at the foot of the truss in Fig. 27 (*a*). Before the stress diagram can be drawn for the truss, it is necessary to determine what these thrusts will be in order to produce equilibrium in the truss, when the reactions R_1 and R_2 are assumed as each being equal to one-half of the load on the truss. The framed structure furnished by the outline of the truss may be substituted by the trapezoidal frame shown by the heavy lines in Fig. 27 (*a*). This frame can be held in equilibrium by the loads W_1 and W_2 , the reactions R_1 and R_2 , and the thrusts H_1 and H_2 . The loads W_1 and W_2 can each be taken as equal to the sum of the loads CD and DE , and one-half EF , as well as one-half BC in Fig. 24 (*a*). It is reasonable to assume these loads as acting at W_1 and W_2 for the upper portion of the hammer-beam truss, that is, that portion of the truss above the horizontal member extending between the two rafter members, is practically a truss of small dimensions superimposed on the other and supported at the joints CD and GH . It is also a correct assumption to make, that one-half of the forces BC and HI are conveyed down the dotted oblique members LM and ST to the vertical members MN and SR , from the fact that the shaded triangle is isosceles and the load BC is located at the apex, so that three-eighths of the load on the truss is concentrated at each point CD and GH . Commence the stress diagram, Fig. 27 (*b*), by laying off the load line, as usual, from a to j , marking on it the loads around the truss in the order in which they occur, as from a to b to c to d , etc. Since the truss is symmetrically loaded, the stress diagram will be symmetrical and the horizontal thrusts H_1 and H_2 will lie in a line z, z bisecting the load line. Draw, therefore, from the points 1 and 2, midway between bc and hi , lines parallel with LK and TU in (*a*). The evident reason for drawing these

lines from the points 1 and 2 instead of from b and i is that in determining W_1 and W_2 only one-half of the loads BC and HI were considered. From the point z_1 , where these lines intersect, the horizontal line z_1z is drawn. These several lines, together with the portion of the load line included between 1 and 2, now form the polygon of external forces for the diagrammatical frame represented by the heavy lines and supporting W_1 and W_2 at its points of connection. The line $1z_1$ represents the amount of the oblique reaction from the load W_1 , or the stress in the member LM ; z_1z is the amount of the horizontal thrust H_1 , while z_11 is the reaction for the frame represented by the heavy lines. The reaction R_1 of the original frame shown by the dotted lines is measured by the distance z_1a and the compressive stress, or thrust, in the horizontal member represented by the heavy line in the frame diagram is equal to the horizontal thrust at the foot of the oblique member, for the principle of equilibrium must be observed and the sum of the horizontal forces must equal zero. Likewise, the algebraic sum of the vertical forces must equal zero, in consequence of which W_1 and W_2 must equal the vertical reactions at the foot of the frame. From the fact that one-half the load BC can be considered as transmitted to the left-hand end of the shaded triangle, the load AB is really increased by this amount, and the reaction R_1 of the original frame, shown dotted, is equal to W_1 plus the load AB and one-half of the load BC . The question might arise as to the correctness of taking z_1z as representing the entire horizontal thrust of the original frame, but reference to (a) shows that by considering one-half of BC as transmitted to a joint in a vertical line with CD and the other half to the joint ABL , that the moments about the point c have not been changed. When the point z_1 has been determined, the stresses for the members in the original truss can be laid out without difficulty, except when the joint $CDONM$ is to be analyzed. Here it will be found that the member ON has no stress, for the points o, n, q , and r coincide. This will undoubtedly be confusing from the fact that it was stated that the horizontal member

shown by the heavy line in the frame diagram was subject to a compressive stress equal to H_1 , but this stress is equalized when the small framed truss, superimposed on the



(a)



Stress Diagram for Wind Load.

Scale $\frac{1}{10}$ inch = 800 lb.

(b)

FIG. 28

larger, is introduced, for this truss creates a side thrust at the points of support of W_1 and W_2 equal to the horizontal compression in the member. It is, however, in an opposite direction and completely neutralizes this stress. It is also

found, in drawing the stress diagram, that there is no stress in the members NZ and RZ . There cannot be stresses in these members from vertical and symmetrical loads, but stresses will be created when the truss is subjected to an oblique wind pressure or when the truss is unsymmetrically loaded. The members NZ and RZ could not, however, be well omitted even for a vertical load, for they must be used to stiffen the truss and to provide against any slight variation that might exist between the loads on opposite sides of the truss.

The frame and stress diagrams for the wind load on this truss are shown in Fig. 28 (*a*) and (*b*). Such a truss is always constructed with ends rigidly fixed, so that the reactions from an oblique wind pressure will coincide with the direction of the forces acting on the rafter members. The amount of these reactions may be determined by the graphical method or they may be calculated by the principle of moments. By reference to Fig. 28, it will be noticed that most of the members in the frame diagram are shown dotted. These members are useless when the wind acts on the left-hand side and when the reactions act in a direction coinciding with the lines of action of the oblique wind pressure on the slope.

ROOF TRUSSES WITH MEMBERS SUBJECTED TO TRANSVERSE STRESS

THE "A" TYPE OF TRUSS

37. In Fig. 29 is shown the **A** type of roof truss, which is particularly adapted for buildings where Gothic architectural treatment is desired; it is most frequently used for high narrow buildings, such as office buildings, as an assembly hall is often required on the top floor. In order that the ceiling may be raised and a vaulted, or arched, effect obtained, it is necessary to raise the tie-member of the truss some distance above the plate line at the top of the wall. Since a member like the one shown dotted at *a*

would interfere with the cove, or vaulted, effect of the ceiling, such a member is not permissible; the member *b* must be made of heavy rolled shapes or of a compound riveted section in order that it may not only offer sufficient resistance to the direct stresses, but that it may, as well, provide the necessary transverse strength. That this member is subjected to a great transverse stress and tends to turn about the point *c* when subjected to the upward tendency of the reaction R_1 , is evident on inspection of the frame. If the foot of the member *b* and the one on the opposite side were secured to the top of a heavy masonry wall capable of resisting a horizontal thrust, these members would sustain only direct stresses, and the stresses throughout the truss would be reduced to a minimum.






FIG 20

38. In the frame diagram shown in Fig. 30 (*a*), H_1 and H_2 are readily determined by taking moments about the joints BC , CIZ and MFF , GZ . For instance, the positive moment about the left-hand joint is $1,000 \times 6 = 6,000$ foot-pounds. The negative moment about the same point is



Frame Diagram-Vertical Load



Stress Diagram-Vertical Load for
Horizontal Thrust Supplied by
Transverse Resistance of Leg
Scale 400 lb. to $\frac{1}{8}$ inch.

FIG. 30

equal to the reaction R_1 , or $5,000 \times 6 = 30,000$ foot-pounds. The difference between the positive and negative moments about the joint will then be $30,000 - 6,000 = 24,000$ foot-pounds. The leverage of the thrust H_1 is, according to the dimensions on the frame diagram, 10 feet 6 inches, so that this thrust will amount to $24,000 \div 10.5 = 2,286$ pounds.

By substituting the horizontal forces H_1 and H_2 , not only will the frame diagram be in equilibrium, but the members BZ and ZG will have no tendency to spread, and there will be no transverse stresses about the joints BC , CIZ and MFF , GZ , the two legs of the truss being subjected only to direct stress. These two necessary horizontal thrusts are introduced in the frame diagram so that the stress diagram, Fig. 30 (*b*), may be drawn without difficulty. Trusses of this character are often erected on structural steel columns, or they may be placed on the light upper walls of a building that could not offer the necessary horizontal resistance. When this construction is encountered, the members BZ and GZ must resist the tendency to spread or to revolve about their junction with the frame, by their transverse stress. But this character of stress cannot be represented in the graphical analysis of a framed structure in connection with direct stresses. Therefore, this transverse stress must be replaced by direct stresses without destroying the equilibrium of the frame or any of the joints.

39. Referring to Fig. 30 (*a*), it is evident that the member BZ will tend to revolve about the joint BC , CIZ , in the direction indicated by the dotted arrow. This rotary tendency may be resisted in two ways—either by the transverse strength of the member BZ or by the horizontal force H_1 .

The latter method must be adopted in order to analyze the frame by the method of graphical statics; by the introduction of the imaginary forces H_1 and H_2 , there is a tendency to destroy the rotary equilibrium about the joints BC , CIZ and MFF , GZ . This tendency to rotate must be overcome by the introduction of the forces CD , and FE , the amounts of which are readily calculated by taking

moments about the joints BC, CIZ and MFF, GZ ; for instance, the moment of H , about the joint BC, CIZ is equal to 2,286 multiplied by the perpendicular distance from its line of action to the point of rotation, or 10.5 feet, which equals about 24,000 foot-pounds. The lever arm with which the horizontal force CD , tends to resist this rotary tendency about the joint BC, CIZ is equal to 6 feet 11 inches, so that the amount of the force CD , is found by dividing 24,000 by 6.9167, or approximately 3,470 pounds. This force tends to produce rotation around the joint BC, CIZ in the opposite direction to that created by the thrust H ; consequently, they act in the same direction, and in order to produce translatory equilibrium a horizontal reaction equal to their sum must be introduced at BC, CIZ , which will be equal, in amount, to $2,286 + 3,470 = 5,756$. Since the truss is symmetrically loaded, similar forces must necessarily be introduced at the joints LEE, FM and FF, GZM , in order to create equilibrium in that half of the truss subjected to the horizontal thrust H . The several forces having been obtained in this manner, the frame diagram with its external forces will be as shown in Fig. 30 (*a*).

40. Commence the stress diagram by laying out the load line, which extends from a to b to c , to c to d , to d to e to e , horizontally to f , vertically to f , horizontally to g , then to h and from h to z , in a vertical direction corresponding in amount with the reaction R , to z , back to z , and from z , back to a , the starting point, this last line representing the amount of the reaction R . The polygon of external forces closes in this manner, and all the lines in the load line represent truly, in amount and direction, the forces that they represent in the frame diagram. When the load line has been completed, commence with the joint $ABZZ$, and draw, in the stress diagram, a line from b parallel with BZ in the frame diagram; where this line intersects a horizontal line drawn from z , which represents the thrusts H , and H , will be located the point z . The forces about the lower left-hand foot of the truss will then be represented in the stress diagram by the polygon extending from a to b to z to z , and from z , back to a .



In the next joint, BC, CIZ , three of the forces are known and the polygon of forces is completed by drawing from c a line parallel with ci indefinitely, and then extending the horizontal line z, z until it intersects the first line; the point of intersection will be i . The polygon of forces about this joint will read in the stress diagram from b to c , to c to i to z , and from z back to the starting point b .

The joint $IJKZ$ cannot as yet be analyzed, from the fact that there are more than two unknown forces in the system surrounding it, so that it is necessary to draw the polygon of forces for the joint CD, DJI . To analyze this joint, draw, from the point d , a line, indefinite in length, in the direction of the member DJ ; and, from i , draw a line parallel with the member IJ in the frame diagram, intersecting the first line drawn at j . The polygon of forces about this joint will then be completed and $IJKZ$ may be analyzed, thus completing one-half of the stress diagram. As the loads are symmetrically placed on the truss and the truss is symmetrical about the center line, the stress diagram for the entire truss will be balanced on the horizontal line z, i . Since the stress in the member MZ is the same as in the member $I Z$, m and i will fall at the same point.

41. The problem of determining the stresses in roof trusses of this character becomes somewhat more complicated when the wind stress diagram is considered. The principle of equalizing the bending moment by the introduction of certain forces in the frame diagram is exactly the same, however. If the frame diagram for the wind loads on the left-hand portion of the truss is as shown in Fig. 31 (*a*), the external loads acting on the truss are AB, C, C, D, D , and DE . These wind loads produce parallel reactions at R_1 and R_2 , the amounts of which may be determined by taking moments about either foot of the truss. Taking moments about the joint $ABZY$, or the point c , and considering the loads as exerting a positive moment, the calculation for obtaining their sum will be as follows, the lever arms being obtained by scaling the drawing:

Moment of AB	$= 2,000 \times 0 =$	0 foot-pounds
Moment of C_1C	$= 3,000 \times 12 =$	36 000 foot-pounds
Moment of D_1D	$= 3,000 \times 20 =$	60 000 foot-pounds
Moment of DE	$= 1,800 \times 38 =$	68 400 foot-pounds
Sum of moments		$= 164 400$ foot-pounds

The leverage of the reaction R_1 , acting parallel with the direction of the loads is 19 feet, so that its amount is $164,400 \div 19 = 8,653$ pounds. The amount of the reaction R_2 is equal to the difference between the sum of the loads and the amount of the reaction R_1 , or 1,147 pounds. Both of these reactions, though establishing equilibrium in the frame, produce, or tend to produce, rotation about the joints BC, C_1Z and MF, F_1GZ , so that rotary equilibrium is not maintained at these points.

In actual practice, these bending moments are resisted by the transverse strength of the members BZ and GZ at these points. For analytical purposes, however, it is necessary to substitute some counteracting force against this rotation at the foot of each leg. The amount and direction of these forces are readily determined by drawing the reaction diagrams, Fig. 31 (*b*) and (*c*). Before drawing the reaction diagram (*b*), an inspection of the joint $ABZV$ reveals the fact that there is a force of 2,000 pounds coincident and acting in the same straight line with the reaction of 1,147 pounds, but in the opposite direction. Under such a condition equilibrium of the joint cannot be maintained, for the force of 2,000 pounds will more than counteract the smaller force of 1,147 pounds. It is evident, then, that there is a tendency for the point c to move in a direction shown by the dotted arrows with a force equal to 853 pounds. This, then, is the force that actually tends to create bending about the joint BC, C_1Z and may be resolved into its components ab and bc , shown in the reaction diagram (*b*).

In order to analyze this force of 853 pounds, draw the line ac in the direction of R_1 and lay off, in the diagram (*b*), the amount of 853 pounds to scale, thus locating the points a and c . From c draw a line parallel with the member BZ and

from a , a horizontal line; thus it is found that the components ab and bc , acting in the directions shown, will be equal in effect to the single force ac . Of the two components just found, bc is the stress in the member BZ , while the horizontal force ab must be substituted in the frame diagram, as shown. The system of forces about the foot of the left-hand leg of the truss, which maintains equilibrium at this point, will now consist of AB , BZ , ZY , and YA .

The reaction R , must, in a similar manner, be analyzed into its components, which are opposite and equal in effect to its action on the foot of the right-hand leg of the truss. These components are shown in direction and amount in the reaction diagram (c), in which the stress in the member CZ is represented by the line cb and the horizontal thrust, or force, that it is necessary to introduce in the diagram in order to maintain equilibrium, is represented by the line ba . In this manner the system of forces necessary to create equilibrium at the lower right-hand joint of the truss is completed and consists of the forces ZG , GX , and XZ . The external forces necessary to create equilibrium in the frame and at each joint have now been introduced in the frame diagram, and the stress diagram shown in Fig. 31 (d) may be drawn. The load line is shown by the heavy line extending from the point a along the lines ab , bc , c_1c , cd , d_1d , de , ef , fg , gx , xz , zy , and ya . In this manner the polygon of forces is closed on the starting point. The stress diagram may be commenced and worked out from either end of the diagram and offers little difficulty, giving the figure designated.

In designing the truss, the stresses obtained in the vertical-load and wind-load diagrams may be combined and in this manner the maximum stress in any member is determined. Likewise, the maximum bending moment at the joints BC , CIZ and MFF , GZ must be determined and the leg of the truss proportioned for the maximum moment. In this instance the maximum bending moment at MFF , GZ occurs under the wind load and is equal to 8,653 pounds multiplied by 6, or 51,918 foot-pounds. Practically the same result

would have been obtained by multiplying the horizontal force H , by its lever arm, which gives $5,000 \times 10.5 = 52,500$ foot-pounds.

Carefully study the difference between the stresses created in the several members of the frame diagram when the horizontal forces H_1 and H_2 in Fig. 30 (*a*) are provided for by the transverse resistance of the legs at the joints BC , CI and MF , GZ , and when the necessary horizontal thrusts are supplied by the lateral resistance of a wall, or other stable abutment, as shown in Fig. 32. On comparing the stress diagrams in Figs. 30 and 32, it will be noticed that the lines bz are equal, showing that the direct stress in the members BZ and ZG is not altered by the introduction of the imaginary horizontal forces Z_1Z , BC_1 , and CD_1 in Fig. 30 (*a*). Likewise, ci remains the same, showing that the stresses in CI and FM are not altered; but the stresses in DJ and EL are greatly increased, as well as those in JK and KL . IJ and LM also have a great additional stress when the truss is held in equilibrium by the transverse resistance of BZ and ZG instead of by the horizontal thrusts ZZ_1 , in Fig. 32. The horizontal tie-member, represented by IZ , KZ and MZ , is also subjected to a great increase in stress.

TRUSSES SUPPORTED BY KNEE-BRACED COLUMNS

42. The type of truss shown in Fig. 33 is most frequently used in the construction of train sheds, rolling mills, and similar buildings. It is usually of a great span, from 80 to 100 feet, and is supported at either end on steel columns. If the connection of the column to the roof truss at a and b were hinged and no member were introduced between the column and the roof truss, it is evident that the frame would be, theoretically, in equilibrium under a vertical load, but that when a wind pressure acted on the roof, either normal to the roof slope or horizontally against the vertical surfaces of the building, the columns or posts would tend to turn about their lower ends and that when the stiffness of the joints a and b was overcome, the destruction of the structure would result.

In order to provide against this tendency to lateral motion across the building, due to the wind pressure on the roof and side, knee braces c and d must be introduced between the column and the truss. These knee braces act in unison and brace the entire structure laterally from the fact that when the wind blows against the left-hand portion of the truss, the member c will be in tension, for the angle made by the column and the horizontal member of the truss at the left-hand end will tend to distort under the wind load and form an obtuse angle; while the member d will be in compression, for the angle





FIG. 33


formed by the column and the horizontal member of the truss at the right-hand end will tend to form an acute angle. If the joints c and d made by the connection of the knee braces with the columns were considered as being hinged, the structure would tend to fail at these points, as described in connection with the joint at the top of the column. It is therefore necessary to provide, in the column, a sufficient resistance to transverse stress to take up the pull and the thrust of the knee braces c and d . But bending moments and transverse stresses cannot be represented in the stress diagrams for obtaining direct stresses, and therefore some




Frame Di




Scale 1/4 inch = 2000 lb






Load



(d)

Scale $\frac{1}{20}$ inch = 3000 lb

Wind Load



(c)



means must be introduced by which these transverse stresses are eliminated for the purpose of drawing the stress diagram. In eliminating these transverse stresses, direct stresses must be substituted, as described in Arts. 38 and 39, so that the frame will be retained in equilibrium and the stress in the members throughout the truss will not be altered.

43. In the frame diagram shown in Fig. 34 (*a*), it will be observed that the wind pressure acts normally to the slope of the oblique rafter member, and horizontally against the vertical surfaces. The oblique forces are AB , BC , CD , DE , EF , FG , GH , IJ , KL , LM , while the horizontal forces are M , N_1 , N_2 , A , HI , and JK . In order that the frame may be held in equilibrium, reactions must be provided at the foot of the columns, not only to resist the oblique forces but also to resist the horizontal forces acting on the truss. It is convenient, however, to determine these reactions separately and then to draw reaction diagrams for each end of the truss and thus obtain the resultant reactions. In order to determine the reaction acting at the foot of each column coincident with the line of action of the oblique forces and of such an amount as to balance these forces, take the moments of all the oblique forces about the foot of the left-hand column; the calculation will be as follows:

Moment of AB	$= 2,000 \times 7.66 =$	15320 foot-pounds
Moment of BC	$= 4,000 \times 15.34 =$	61360 foot-pounds
Moment of CD	$= 4,000 \times 23.02 =$	92080 foot-pounds
Moment of DE	$= 4,000 \times 30.70 =$	122800 foot-pounds
Moment of EF	$= 4,000 \times 38.38 =$	153520 foot-pounds
Moment of FG	$= 4,000 \times 46.06 =$	184240 foot-pounds
Moment of GH	$= 4,000 \times 53.74 =$	214960 foot-pounds
Moment of IJ	$= 2,000 \times 61.42 =$	122840 foot-pounds
Moment of KL	$= 2,000 \times 63.62 =$	127240 foot-pounds
Moment of LM	$= 2,000 \times 71.30 =$	142600 foot-pounds

Sum of positive moments = 1236960 foot-pounds

The reaction R_1 acts on the left-hand column foot with a lever arm equal to 98.49 feet, so that this reaction will equal, in amount, $1,236,960 \div 98.49$, or, practically, 12,500 foot-pounds.

The sum of the oblique forces acting on the truss is equal to 32,000 pounds, and consequently R_1 equals $32,000 - 12,500 = 19,500$ pounds. The horizontal forces acting on the truss tend not only to push the truss along laterally but to overturn the entire frame; that is, the forces M, N_1, N, A, HI , and JK tend to produce a rotary motion about the foot of the right-hand column that must be resisted by a pull in the left-hand column of the frame and a corresponding compression in the right-hand column.

The reactions R_1 and R_2 are horizontal and opposed to the direction of the horizontal wind pressure, but it is assumed that half of the tendency of the structure to move laterally is taken up at the foot of each column; consequently, R_1 and R_2 are equal in amount to one-half of the horizontal forces acting on the frame. The sum of these forces being 12,600 pounds, the horizontal reactions will equal 6,300 pounds. The vertical reactions R_1 and R_2 , necessary to overcome the rotary tendency of the horizontal forces M, N_1, N, A , etc., and to produce equilibrium of rotation, may be found by taking moments about the foot of the left-hand column. The calculations for these reactions are as follows:

Moment of $M, N_1 = 6,000 \times 12.04 = 72240$ foot-pounds

Moment of $N, A = 2,000 \times 17.04 = 34080$ foot-pounds

Moment of $HI = 2,300 \times 41.16 = 94668$ foot-pounds

Moment of $JK = 2,300 \times 46.16 = 106168$ foot-pounds

Sum of positive moments = 307156 foot-pounds

The lever arm of R_2 is equal to the span of the truss, or the distance from center to center of the upright columns or posts. This distance is equal to 110 feet, so that the amount of R_2 is found by dividing 307,156 by 110, which gives the reaction as equal to, in round numbers, 2,800 pounds. The reaction R_1 must necessarily equal this amount in order that the algebraic sum of the vertical forces may be equal to zero.

There exist now at each joint three forces. At the left-hand end of the truss, there are R_1, R_2 , and R_3 , while at the right-hand end of the truss there are created R_4, R_5 , and R_6 .

In each system of forces the vertical and horizontal reactions are equal, but the amounts of the oblique reactions are different. In order to obtain the resultant of these three reactions, which may be substituted in their stead, it is necessary to draw the reaction diagrams shown in Fig. 34 (*b*) and (*c*). In the diagram (*b*), ab is laid off to scale, equal to 2,800 pounds, and represents, in direction and amount, the reaction R_1 . From b , a line is drawn parallel with the reaction R_1 , and is made of such a length that it will equal to scale 19,500 pounds, thus locating the point c . From the point c , a horizontal line drawn to d truly represents the horizontal force, or reaction, R_2 , equal to 6,300 pounds. By connecting a and d , the amount and direction of the resultant of this system of forces are obtained, and the amount, on measuring, is found equal to 21,000 pounds. In consequence of the substitution of this resultant at the foot of the left-hand truss, the other forces of the system may be discarded, for this reaction is equal to them in effect on the truss. In a similar manner, the resultant reaction at the right-hand end of the truss may be obtained and will be found to equal, approximately, 19,000 pounds.

These oblique reactions can be resolved into their vertical and horizontal components, which are shown by the dotted lines in each of the reaction diagrams. The vertical components designated in each diagram by de are the amounts of direct compressive stress in the columns; that is, by measuring de in the diagram (*b*), the stress in the column M, Z is obtained, while the length of the line de , in the stress diagram (*c*), gives the amount of the stress in the column $Z O$. The horizontal component, however, in each case tends to bend the column or to turn the columns about the points c and c_1 . Before the stress diagram can be drawn, this horizontal component of the reactions must be equalized and the imaginary forces L, M , and $P O$ equal, respectively, to 14,800 and 12,300 pounds introduced in a direction opposite to that of the horizontal components ae . But these forces destroy the equilibrium of the frame diagram, so that forces must be introduced that will maintain

both rotary and translatory equilibrium. Considering each column hinged at the point of connection with the knee brace and extending in a continuous piece from its foot to its connection with the truss, it is evident that the forces L , M , and OP will have a moment about the points c and c_1 equal to their amount multiplied by the length of the columns from the foot to the points c and c_1 .

Forces applied as at N , A and MN must resist this moment created by L , M , and OP , and since they have a lever arm equal to the length of the portion of the column N , Q and $9N$, or 5 feet, the amounts of the forces necessary to be substituted at the connection of the top of the columns with the truss may be found by dividing the moments of M , L , and OP about c and c_1 by the length N , Q and $9N$. The calculation for the forces N , A and MN is therefore as follows:

Moment of L , M , about c equals $14,800 \times 12.04 = 178,192$ foot-pounds; and $178,192 \div 5 =$, in round numbers, 35,600 pounds, the amount of N , A . The moment of PO about c_1 equals $12,300 \times 12.04 = 148,092$ foot-pounds; and $148,092 \div 5 =$, in round numbers, 29,600 pounds, which equals MN . These two forces introduced on each side of the truss as N , A and MN maintain rotary equilibrium, but they destroy equilibrium of translation and, in consequence, must be opposed by an opposite and equal force so that it becomes necessary to introduce the two forces M , N , and ON . The left-hand force M , N , is equal to the sum of L , M , and N , A , while the right-hand force NO is equal to the sum of PO and MN . By the introduction of these last forces, the entire structure is in both rotary and translatory equilibrium and all the external forces acting on the truss are shown in the frame diagram.


44. The stress diagram shown in Fig. 34 (*d*) may now be commenced by first marking out the load line, which extends from a to b to c to d to e to f to g to h , horizontally to i , obliquely to j , horizontally to k , and obliquely to l to m ; mn may then be laid off horizontally, for its amount and


direction are known; no may be measured from n and the point o thus located. The point p will coincide with the point m , for the length of the line on is equal to the sum of nm and po , and since om has been laid off, the distance from m to o must equal the force op . An oblique line can be drawn from m extending indefinitely, but parallel with the resultant reaction represented by the force in the frame diagram, Fig. 34 (*c*), marked dc . In order to locate the point z , however, the line an_1 must be laid off parallel with and equal to the force N_1A in the frame diagram. Then, from n_1 , the point m_1 may be located by measuring off, to scale, the amount of the force M_1N_1 . Having located m_1 , the point l_1 is readily located by measuring from m_1 the amount of the force L_1M_1 . When l_1 has been located, a line drawn from l_1 parallel with the force, or resultant reaction, L_1Z , in the frame diagram, may be drawn, and where it intersects the oblique line mz , representing the right-hand resultant reaction, will be located the point z . The points o , m_1 , and z should lie in a vertical line; m_1z is the amount of compression in the left-hand column, and oz is the amount of compression in the right-hand column, these two compressive stresses being equal, respectively, to the vertical components of the resultant reactions shown by the vertical dotted lines in the reaction diagrams, Fig. 34 (*b*) and (*c*).

The polygon of external forces has now been completed and extends from a to b to c to d . . . to l to m to n to o to p , obliquely to z , thence along the line coincident in direction with the line of action of the left-hand reaction to l_1 ; from l_1 to m_1 to n_1 , back to a , the starting point. When the polygon of forces thus closes in a satisfactory manner, the stress diagram for the stresses in the members of the structure may be laid out. There are but two unknowns in the joint M_1N_1QZ , so that no difficulty is encountered in analyzing this joint. Likewise, the joint $ABRQ N_1$ is readily solved and the stresses around the joints $BCSR$ and $QRSTZ$ can be laid out without trouble. The next three joints, however, have three unknown forces, so that the method of symmetry must be used. By observation it can readily be seen that the

member VW in the frame diagram is subject to the same stress as the member RS , both sustaining 4,000 pounds. If VW is known, therefore, the joint $DEWV$ can readily be solved, for in the stress diagram the point v must be at such a distance from the line tu , the direction of which is known, that the line vu , when drawn in parallel with VU in the frame diagram, will intersect the line drawn from t , parallel to TU , at a point u that will be central, or midway, between the two lines dv and ew . By careful inspection in this manner, it is possible to work around the entire truss, and the finished diagram will be as shown. However, it will be found that the members shown dotted in the right-hand half of the truss are useless when the wind acts on the left-hand half of the truss. These members may therefore be neglected and the stresses obtained in the members marked 3-4, 4-5, 5-6, 6-7, 7-8, and 8-9. The last line of the stress diagram will be $9s$, and the diagram should close on the point s when $9s$ is drawn parallel with the right-hand knee brace of the frame diagram, or the member $9s$.

The analysis of this truss is the same as that shown in Fig. 35. This illustration shows not only the wind-load diagram, but also the dead-load diagram. The framework of the truss is much simpler than that in the example described, though the latter is an excellent example of the application of the principles just described.





A SERIES OF QUESTIONS

RELATING TO THE SUBJECTS
TREATED OF IN THIS VOLUME.

It will be noticed that the questions contained in the following pages are divided into sections corresponding to the sections of the text of the preceding pages, so that each section has a headline that is the same as the headline of the section to which the questions refer. No attempt should be made to answer any of the questions until the corresponding part of the text has been carefully studied.



LOADS IN STRUCTURES

EXAMINATION QUESTIONS

(1) What weight per square foot of roof surface should be allowed to provide for the weight of a steel truss the span of which is 60 feet and the rise 12 feet, the distance between trusses being 15 feet? Ans. 4.87 lb.

(2) What allowable live load should be assumed in calculating the weight on floors in: (a) hotels and apartment houses? (b) ballrooms and drill halls? (c) churches and theaters?

(3) In a warehouse used for the storage of brown sugar in barrels, the main girders support an area of floor equal to 450 square feet. If the floor construction and girders weigh 25 pounds per square foot of surface, what is the total dead and live load on each girder?

(4) Considering the wind pressure per square foot of vertical surface as 30 pounds, what will be the pressure normal to the slope, obtained from the diagram in Fig. 6, on a roof whose slope makes an angle of 55° with the horizontal?

(5) For an economically constructed country hotel, what would be considered as the proper live load to figure per square foot of surface in designing the floor systems?

(6) The outside dimensions of a rectangular cast-iron column are 12 inches and 10 inches, and the metal is $\frac{3}{4}$ inch in thickness. What is the weight of a 15-foot column having these dimensions?

(7) What is the entire live load on the floor of a church 60 feet wide and 150 feet long, figured according to the Philadelphia building laws?

(8) (a) What wind pressure would a conservative engineer assume for a vertical surface? (b) What condition is assumed and what formula is employed in determining this pressure?

(9) A steel girder supporting a portion of the floor in a theater sustains an area of 380 square feet. What will be the live load on the beam?

(10) (a) Compute the entire dead load supported by one truss for a $\frac{1}{2}$ -pitch roof, the span of the steel trusses being 60 feet. The trusses are 15 feet on centers and the roof covering is 2-inch spruce sheathing and 4-ply slag roofing. (b) What will be the total wind pressure normal to the slope, supported by one truss; the horizontal wind pressure, of 40 pounds per square foot, is considered on only one slope of the roof?

Ans. $\begin{cases} (a) 12,778.7 \text{ lb.} \\ (b) 11,923 \text{ lb.} \end{cases}$

(11) A warehouse in which baled hay is to be stored is 40 feet in width and 90 feet in length between walls. If the girders extend across the building and are placed 18 feet apart, what live load will each be required to support?

(12) Explain what you understand by an accidental load.

(13) What is the pressure, in pounds per square foot of vertical surface, when the wind is blowing at the rate of 65 miles per hour?

Ans. 16.9 lb.


(14) A load of 800 pounds is dropped a distance of 3 feet, causing the beam to deflect $\frac{1}{4}$ inch; its weight, with the dead load on it is 2,000 pounds. What static load will produce the same effect on the beam as the falling load?

Ans. 9,942 lb.

(15) What is the effective overturning pressure from the wind blowing at hurricane velocity, and exerting a pressure of 40 pounds per square foot on a cylindrical iron stack 150 feet high and 5 feet in diameter?

(16) What live load will each of the joists in a department store in New York be required to carry if the span is 15 feet and the distance between joists is 16 inches?

(17) What precautions would you observe in proportioning floors for the live load in printing houses and binderies?



PROPERTIES OF SECTIONS

EXAMINATION QUESTIONS

(1) (a) Explain, at length, what is meant by the center of gravity of a body or a system of bodies. (b) Where is the center of gravity of a plane symmetrical figure located? (c) At what point is located the center of gravity of a triangular plane figure?

(2) What is meant by the neutral axis of a beam section?

(3) Describe the mechanical method of determining the neutral axis of an irregular section.

(4) Calculate, by the principle of moments, the distance of the neutral axis $y-y$ from the upper surface of the top flange in Fig. I.

Ans. 4.11 in.

(5) What is the distance c of the built-up section in Fig. II?

Ans. 2.16 in.

(6) Determine, by the graphical method, the location of the neutral axis of the cast section shown in Fig. III.

(7) What is understood by the term moment of inertia?

(8) Explain the method of computing the approximate moment of inertia of any section by the analytical method.




FIG. I




FIG. II

(9) Write the general formula for the moment of inertia of any section.

(10) Compute the moment of inertia, with respect to the neutral axis $y-y$, of the section shown in Fig. IV. Ans. 28.731




FIG. III




FIG. IV




FIG. V

(11) Determine the moment of inertia of a rectangular beam 8 inches wide by 12 inches deep. Ans. 1,152

(12) Define section modulus:

(13) What is the moment of inertia, with respect to the neutral axis $y-y$, calculated by the general formula, of the built-up section shown in Fig. V? Ans. 5,263.276

(14) Give the formula for determining the section modulus of a rectangular beam.

(15) What is the general formula for determining the section modulus of any beam, when the moment of inertia and the location of the neutral axis are known?

(16) What is the section modulus of a $9'' \times 12''$ wooden beam? Ans. 216

(17) Determine the section modulus of a cast **T** iron having the vertical leg downwards. The width of the flange of the **T** is 3 inches and the depth of the vertical leg from the under side of the flange is $4\frac{1}{2}$ inches; the thickness of the metal is uniform and is equal to $\frac{3}{8}$ inch. Ans. 2.131

(18) A channel-shaped section of a cast-iron beam is to be used as a lintel with the two parallel sides of the channel vertical. The distance from inside face to inside face of the vertical sides of the channel is $10\frac{1}{2}$ inches, and the height of these sides from the corner is 5 inches; the thickness of the metal is $\frac{5}{8}$ inch. What is the section modulus? Ans. 7.89

(19) From Table III, determine: (a) the section modulus, on the axis 1-1, of a 12-inch 40-pound beam; (b) the section modulus on the same axis of a 15-inch 60-pound beam; (c) the section modulus on the same axis of a 20-inch 75-pound beam.

Ans. $\begin{cases} (a) & 41 \\ (b) & 71.8 \\ (c) & 126.9 \end{cases}$

(20) From Table XIII, find the least radius of gyration of two $5'' \times 3\frac{1}{2}'' \times \frac{3}{8}''$ angles, the short legs being vertical and the space between them $\frac{3}{8}$ inch. Ans. 1.02

(21) What size I beam will be required to support a uniform load of 1,000 pounds per foot over a span of 22 feet, assuming a safe unit fiber stress of 16,000 pounds?

Ans. 15-in. 42-lb. beam

(22) What will be the deflection of two channels, placed back to back and supporting a uniformly distributed load of 1,200 pounds per lineal foot, over a span of 25 feet? The channels are 15 inches deep and weigh 40 pounds per foot.

Ans. .516 in.



MATERIALS OF STRUCTURAL ENGINEERING

(PART 1)

EXAMINATION QUESTIONS

- (1) State what investigation should invariably be made before the foundations of any important structure are designed.
- (2) Describe three practical methods of determining the character of the soil at a building site.
- (3) Why should test borings in alluvial soil be made to a considerable depth?
- (4) In what localities is it positively necessary to possess accurate knowledge of the soil beneath important buildings or structures?
- (5) Describe the method of testing the bearing value of the soil at the New York State Capitol at Albany.
- (6) Show, by sketch, how you would provide means of testing the bearing capacity of soil at different points throughout an important building site.
- (7) Explain the precautions necessary in making experimental tests of the bearing capacity of foundation soils.
- (8) Name the soils usually encountered in the order of their excellence as a foundation.
- (9) Describe rock as a foundation.

- (10) What is the nature of a gravel foundation soil?
- (11) Do you consider confined dry sand a good foundation?
- (12) What are the dangers of sandy foundations?
- (13) State the character of clay as a foundation soil.
- (14) What is the load allowed, per square foot of foundation area, by the Building Laws of Chicago upon such clay as they have in that locality?
- (15) Is sand and gravel without a clay admixture as good a foundation soil as the same material with clay? Give reasons.
- (16) What ultimate bearing value for clayey soils did the tests for the State Capitol at Albany and the Congressional Library at Washington develop, and what were the working values used in those instances?
- (17) What expedient was resorted to in building the tower of the Chicago Auditorium so that the tower and building footing should have a uniform settlement?
- (18) What precautions must be observed in designing foundations whose settlement is expected and must be provided for?
- (19) How is it usually necessary to construct the foundation of heavy buildings on a compressible soil, such as clay?
- (20) What are the two usual methods of providing foundations in mud, silt, marsh, or semiliquid soils?
- (21) According to Rankin's formula, what is the unit bearing capacity of a marsh soil having a depth of 20 feet, a weight of 115 pounds per cubic foot, and an angle of repose equal to 10° ?
Ans. 3,266 lb. per sq. ft.
- (22) What is meant by quicksand?
- (23) When does quicksand become troublesome in excavating for foundation walls?

(24) Explain what precautions should be exercised in working in quicksand adjacent to foundations, and state one instance where trouble is liable to be experienced if care is not taken.

(25) Describe, at length, four methods of excavating through strata of quicksand.

(26) According to the New York Building Laws, what is the allowable unit bearing value, in tons, of: (a) soft clay? (b) firm coarse sand? (c) firm or dry loam?



MATERIALS OF STRUCTURAL ENGINEERING

(PART 2)

EXAMINATION QUESTIONS

- (1) (a) What are elements? (b) What are compounds?
- (2) (a) What is rock? (b) Into what three classes is it divided?
- (3) State the cause of fissures in rocks.
- (4) Define the terms massive, stratified, and porphyritic as applied to rock.
- (5) What is the rift of a rock?
- (6) Name four artificial or manufactured stones.
- (7) On what does the strength of masonry depend?
- (8) Explain the effect of climate on stone.
- (9) What stones are least affected by fire?
- (10) What qualities should good building stone possess?
- (11) What do you understand by a matrix?
- (12) Of what use is the microscope in examining stone?
- (13) What is the chief coloring matter in rocks?
- (14) What are the colors of granite, and how can this stone be distinguished?

- (15) Name some of the qualities of granite.
- (16) Name the qualities of good sandstone.
- (17) What three kinds of brick are usually taken from the kilns?
- (18) What substances are used in the manufacture of firebrick?
- (19) Distinguish between poor and rich concrete.
- (20) Name the advantage and disadvantage of cinder concrete?
- (21) What are fire-stones?
- (22) (a) What are the qualities necessary for good sand for mortars? (b) How is sand tested?
- (23) What cements are hydraulic?
- (24) What are the requirements of the New York building laws regarding the proportion of materials for cement mortar?
- (25) What are the advantages of cement mortar over lime mortar?
- (26) What are the various methods of inspecting building stone?
- (27) What properties are dependent on the density of rock?
- (28) State a good proportion of ingredients for stone and gravel concrete and for cinder concrete for building construction.
- (29) Give the average ultimate compressive strength, in pounds per square inch, of the following masonry materials: (a) New Hampshire granite; (b) bluestone; (c) Bedford limestone; (d) Vermont marble; (e) Philadelphia pressed bricks; (f) terra cotta.

- (30) Name the principal brands of natural-rock cements.
- (31) Name some of the principal domestic and imported Portland cements.
- (32) What are the requirements of the New York building laws in regard to the qualifications necessary for a cement to be classified as Portland?
- (33) State the proportions of materials for good cement-and-lime mortar.



MATERIALS OF STRUCTURAL ENGINEERING

(PART 3)

EXAMINATION QUESTIONS

- (1) (a) Into what three groups is wood divided? (b) Name three kinds of wood belonging to each group.
- (2) What wood is best suited to patternmaking?
- (3) Name some of the uses of: (a) black spruce; (b) red cedar; (c) cypress.
- (4) Define: (a) ultimate strength; (b) ultimate elongation.
- (5) What do you understand by modulus of rupture?
- (6) An $8'' \times 8''$ yellow-pine tie-member in a roof truss is notched 14 inches from the end to receive the rafter; what stress will be resisted by the end of the tie-member?
- (7) Give a concise description of the manufacture of iron.
- (8) (a) Name the different processes of manufacture of steel. (b) Which has the most extensive field?
- (9) What factor of safety should be used for the different materials employed in construction?
- (10) What pull will be required to break a $1\frac{1}{4}$ -inch, square, wrought-iron bar?



BEAMS AND GIRDERS

(PART 1)

EXAMINATION QUESTIONS

(1) What is: (a) a simple beam? (b) a cantilever? (c) a continuous beam?

(2) Explain what is meant by the moment of a force.

(3) How is the moment of a force usually expressed?

(4) Explain the conditions that insure equilibrium of moments.

(5) In Fig. I is shown a diagrammatical sketch of a small gib crane with a load W equal to 5,000 pounds; what will be the moment about the point c due to this weight?

Ans. 50,000 ft.-lb.




FIG. I

(6) A steel I beam projecting 7 feet beyond the center of a building wall and extending inside the center line of the wall 4 feet 6 inches is used for hoisting purposes. When the load on the outside end is 5,000 pounds,

what load on the inner end will prevent the beam from tilting? Ans. 7,778 lb.




FIG. II

(7) Explain what is understood by a reaction.

(8) What are the amounts of the reactions R_1 and R_2 ?

for a beam subjected to the conditions of loading shown in Fig. II?

$$\text{Ans. } \begin{cases} R_1, 4,240 \text{ lb.} \\ R_2, 7,760 \text{ lb.} \end{cases}$$

(9) For a distance of 8 feet from the left-hand end of a beam there is a distributed load of 12,000 pounds per running foot, and at the center of the beam is located a concentrated load of 10,300 pounds, while at a distance of 4 feet from the right-hand end of the beam there is a load of 3,600 pounds. Provided that the beam is 35 feet long, what will be the amount of the reaction at the left-hand support?

$$\text{Ans. } 90,590 \text{ lb.}$$

(10) A beam in a church choir loft is loaded as shown in Fig. III. (a) What is the direct compressive load on




FIG. III

column *a*? (b) What will be the load supported by wall *b*?

$$\text{Ans. } \begin{cases} (a) 34,194 \text{ lb.} \\ (b) 23,006 \text{ lb.} \end{cases}$$

(11) Explain what is meant by shear in a simple beam.

(12) Explain at what point the maximum shear is realized on a simple beam.

(13) A simple beam is loaded with a uniformly distributed load of 25,000 pounds; what is the maximum shear on the beam?

$$\text{Ans. } 12,500 \text{ lb.}$$

(14) Determine the maximum shear on a girder loaded as shown in Fig. IV. Ans. 23,120 lb.

(15) A uniformly distributed load of 12,000 pounds is placed on a 24-foot beam for two-thirds of the distance from the left-hand support; at distances of 9 feet




FIG. IV

and 14 feet from the right-hand support are located the concentrated loads of 4,800 pounds and 5,900 pounds, respectively. At what distance from the right-hand end of the beam does the shear change sign? Ans. 14 ft.

(16) Illustrate, with diagrams: (a) the shear on a beam uniformly loaded; (b) the shear on a simple beam loaded at the center.

(17) Describe, by means of a diagram and explanation, what is understood by bending moment.

(18) Define resisting moment.

(19) Calculate the greatest bending moment on a girder loaded as illustrated in Fig. V. Ans. 182,440 ft.-lb.




FIG. V


(20) What formulas are used for calculating the bending moment on: (a) a beam supported at both ends and uniformly loaded? (b) a beam supported at both ends and loaded with a triangular load? (c) a cantilever beam supporting a uniformly distributed load?

(21) A large plate girder in a building is required to support a uniformly distributed load of 2,500 pounds per

lineal foot, extending 18 feet each side of the center of the girder; in addition, it is required to support a load of 2,500 pounds concentrated 12 feet from one end of the girder and another load of 3,600 pounds located 26 feet from the same end. What is the greatest bending moment on the girder in foot-pounds if the span is 58 feet?

Ans. 962,707 ft.-lb.

(22) Determine, by the graphical method: (a) the amount



of the greatest bending moment, and (b) the maximum shear on the beam loaded as shown in Fig. VI.

Ans. $\begin{cases} (a) 82,987.5 \text{ ft.-lb.} \\ (b) 8,237.5 \text{ lb.} \end{cases}$

(23) It is desired to support an extraordinarily long steel I-beam girder in a building by means of an intermediate support at the center. What is the amount of the load carried by the central pier if the distance from center to center of bearings is 23 feet, and the uniformly distributed load is 1,200 pounds per lineal foot?

Ans. 34,500 lb.

(24) Determine the greatest bending moment, in inch-pounds, of the girder described in question 23.

Ans. 952,200 in.-lb.

(25) (a) Define modulus of elasticity. (b) What is the modulus of elasticity for yellow pine?

(26) A cantilever beam of 10" \times 12" yellow pine projects beyond a building wall 8 feet; what will be its greatest deflection with a load of 10,000 pounds suspended from the end?

Ans. 1.7 in.

(27) The moment of inertia of a 20-inch I beam is 1,500 and its span is 28 feet. If the beam is supported on abutments at each end, what will be its greatest deflection, in inches, with a uniformly distributed load of 1,500 pounds per lineal foot?

Ans. .47 in.

BEAMS AND GIRDERS

(PART 2)

EXAMINATION QUESTIONS

(1) What is a flitch-plate girder?

(2) Find, by formula 1, what uniformly distributed load can be safely carried by a spruce beam 10 inches wide by 12 inches deep, the span being 30 feet. The modulus of rupture of spruce is taken at 4,000 and a safety factor of 4 is used.

Ans. 5,333 $\frac{1}{3}$ lb.

(3) A hemlock beam of commercial size is required to support a uniformly distributed load of 400 pounds per lineal foot over a 15-foot span; if the width of the beam is 8 inches, what should be its depth, the modulus of rupture of hemlock being 3,500 and a factor of safety of 4 being used?

Ans. 12 in.

(4) A flitch-plate girder 14 inches deep is required to resist a bending moment of 400,000 inch-pounds; what theoretical thickness of white-pine planks will be required, the steel plate being $\frac{1}{2}$ inch thick? The modulus of elasticity for white pine is 1,000,000 and for structural steel is 29,000,000, while the safe unit stress for steel is considered as 15,000 pounds.

Ans. 4.58 in. each

(5) Describe the most efficient form of built-up beam.

(6) Describe three forms of beam hangers.

(7) Determine the approximate section modulus of a 15-inch **C** beam whose sectional area is 9.90 square inches.

Ans. 40.46

(8) What size steel I beams are necessary to support the floor of a warehouse with a total dead and live load of 200 pounds per square foot, the modulus of rupture of steel being 60,000 pounds per square inch and a factor of safety of 4 being used? The beams have a span of 22 feet and are spaced 6 feet on centers.

Ans. 15-in. 42-lb. beams

(9) What should be the minimum depth of a steel beam compared with its span?

(10) The floors of a heavy fireproof construction are composed of brick arches having a rise of 8 inches, sprung between I beams spaced 5 feet apart. The beams are tied together with tie-rods placed 4 feet apart. If the total dead and live load is 300 pounds per square foot, what size rods will be required?

Ans. $\frac{7}{8}$ -in. rods

(11) What size I beams will be required under the conditions mentioned in question 10, if the span is 25 feet and the allowable unit fiber stress is 16,000 pounds?

Ans. 18-in. 60-lb. beams

(12) Determine the dimensions of a steel bearing plate required to support the end of a 15-inch 42-pound I beam that carries a uniformly distributed load of 700 pounds per lineal foot over a span of 28 feet; the allowable unit stress is 16,000 pounds and the ends of the beam rest on piers built of brick laid in lime mortar.

Ans. $10'' \times 10'' \times \frac{5}{16}''$

(13) A concrete beam having a span of 16 feet is 20 inches wide and 24 inches deep, and has fourteen bars $\frac{1}{2}$ inch by 1 inch embedded in the bottom, the center of the bars being 2 inches from the edge of the beam. Show, by calculations, whether the beam has sufficient strength to support a load of 1,200 pounds per lineal foot, taking the safe unit compressive stress of concrete at 250 pounds, the safe tensile stress at 120 pounds per square inch, and the unit stress of the steel that may be developed before the concrete fails, at 3,000 pounds.

(14) According to formula 21, what is the area of the steel bars in a concrete beam of the Ransome system

supporting a load of 1,000 pounds per foot over a span of 14 feet? The beam is 18 inches deep and the safe unit stress of the bars is taken at 10,000 pounds.

Ans. 1.87 sq. in.

(15) Explain the principle of the Kahn system of reinforced concrete.

(16) A concrete beam reinforced with Kahn trussed bars, with a span of 16 feet, is required to support a uniformly distributed load of 2,500 pounds. According to Table V, what should be the depth of the beam?

(17) Describe, at length, the unit system of concrete steel reinforcement.

(18) Find, by formula 27, the approximate resisting moment of a concrete and steel beam of the Kahn system, having a section similar to Fig. 49 with two bars, if $b = 14$, $d = 20$, and the bars have an area of 4 square inches.

Ans. 4,063,000 in.-lb.

(19) Show, by detail drawing, the dimensions of the standard connections for a 10-inch, a 12-inch, and a 15-inch I beam.

(20) Find, by formula 24, the bending moment, in inch-pounds, of a concrete beam 14 inches wide and 18 inches deep, reinforced at the bottom with ten $\frac{3}{4}$ -inch square bars whose centers are 3 inches from the edge of the beam, c being taken to the nearest number of whole inches. The unit compressive stress on the concrete is 500 pounds and the unit tensile stress on the steel is 16,000 pounds.

Ans. 729,000 in.-lb.

(21) State six points to be observed in constructing reinforced concrete.

(22) Explain a graphical method by which the resultant bending moment is determined on a steel beam subjected to a vertical load and the transverse thrust of an arch.



BEAMS AND GIRDERS

(PART 3)

EXAMINATION QUESTIONS

(1) (a) State an advantage of the box girder over the plate girder having a single web. (b) State two disadvantages.

(2) Give a rule for determining the thickness of the web-plate in a plate girder.

(3) The reaction at the end of a plate girder is 86,000 pounds; the stiffeners are riveted to the web-plate, which is 30 inches deep, by eight $\frac{3}{4}$ -inch rivets. Taking the allowable shearing stress at 12,000 pounds: (a) what will be the thickness of the web-plate? (b) will stiffeners be required?

(4) Give two rules for the provision of stiffeners.

(5) Give the formula expressing the resistance to bending supplied by a plate girder.

(6) Give a rule for determining the net area of the flange of a plate girder.

(7) The flange of a plate girder uniformly loaded and having a span of 75 feet, consists of two $6'' \times 6'' \times \frac{5}{8}''$ angles and four $\frac{3}{8}'' \times 14''$ flange plates; $\frac{7}{8}$ -inch rivets are placed as shown in Fig. 12. Determine the length of the flange plates by the analytic method.


(8) Solve the previous question by the graphic method.

(9) (a) How should the rivets in stiffeners over abutments be spaced? (b) Give a practical rule for spacing the rivets in stiffeners between abutments.

(10) Name four methods for spacing rivets connecting flange angles with the web of a plate girder.

(11) A plate girder having a span of 45 feet and a depth of 3 feet is loaded with a uniformly distributed load of 2,000 pounds per lineal foot. Determine, by the graphic method, the pitch of the rivets through the vertical leg of the flange angle in the several panels, considering the safe strength of a rivet as 5,000 pounds. The first panel is 3 feet 6 inches, the second 4 feet, and the remainder 5 feet in length.

(12) Show all the calculations necessary in designing a plate girder to support a 13-inch brick wall weighing 130 pounds per cubic foot, over an opening 45 feet wide. Consider the load on the girder as a triangular piece of brickwork whose altitude is one-half of its base.



(13) A trussed girder having a span of 34 feet has one strut 2 feet 6 inches in length, and carries a uniformly distributed load of 1,500 pounds per lineal foot. (a) What is the stress in the tension rod? (b) What is the compression in the beam?

(14) Design a trussed beam, having two struts, to support a uniformly distributed load of 1,500 pounds per running foot; the span of the beam is 24 feet and the struts are 2 feet in length.

(15) Determine the stresses in all the members of the truss shown in the illustration.

(16) Where is counterbracing required in the panels of a Howe truss supporting a moving load?

(17) Give the frame diagram for a Pratt truss designed to carry a load of 3,000 pounds at each panel point; the span of the truss is 75 feet, the height, 12 feet 6 inches, and there are six panels. Determine the stresses in the members of the truss.

(18) Give rules for determining the stresses in the chord and web members of a Warren truss.

(19) Describe a lattice truss and explain how the loads are considered as being transmitted to the abutments.

(20) Under what conditions would it be necessary to brace a truss laterally?

(21) Mention some points to be considered in designing the splice in a tension chord member.



COLUMNS AND STRUTS

(PART 1)

EXAMINATION QUESTIONS

- (1) In what two ways do materials under compression fail?
- (2) Name four formulas in common use for calculating the strength of columns.
- (3) (a) What kinds of timber are usually employed for columns? (b) Which is preferable?
- (4) What is generally understood as a short column?
- (5) What safe load will be supported by a short spruce column 12 inches square and 8 feet long, the safe unit compressive strength of spruce being considered as 800 pounds?
Ans. 115,200 lb.
- (6) For what reason is it necessary to have formulas for calculating the strength of a column whose length exceeds ten times the width of the least side?
- (7) According to Gordon's formula, what is the safe compressive strength of a white-pine post 10 inches square and 14 feet long?
Ans. 63,700 lb.
- (8) Using the straight-line formula, find the ultimate strength of a $12'' \times 12'' \times 15'$ spruce column, if the ultimate compressive strength of the material parallel to the grain is 4,000 pounds.
Ans. 489,600 lb.
- (9) How are wooden columns protected against dry rot?
- (10) (a) What are the advantages of cast-iron columns?
(b) What are the objections to their use?

(11) Using a factor of safety of 6, find, by formula 16, the safe load of a square-bearing, hollow, cast-iron column 20 feet long, and 12 inches square outside, the thickness of the metal being 1 inch. Ans. 426,668 lb.

(12) (a) In designing cast-iron columns, what should be the least thickness of the metal? (b) Why is it advisable to have a uniform thickness throughout the casting?


(13) What are the advantages of columns of the H section?

(14) In case the bases are not square to the axis of the column, how are the columns brought to a fair bearing?

(15) In designing columns for bracket connections, what rule should be followed?

(16) In what three ways is a bracket likely to fail?

(17) What is the safe load of the bracket shown in Fig. I, allowing $\frac{1}{4}$ inch for breaking at the foot of the bracket? The



load is to be concentrated, as shown in the figure, and a factor of safety of 4 is to be used, the shearing strength being 18,000 pounds per square inch.

Ans. 47,250 lb.

(18) What is the safe shearing strength of the bracket shown in Fig. I?

Ans. 47,250 lb.

FIG I

(19) (a) When should bolt holes for beam and column connections be drilled? (b) Why?

(20) What are the indications of a good quality of cast iron?

(21) The thickness of the metal in a cast-iron cylindrical column with square ends is 1 inch; if a factor of safety of 6 is used and the length of the column is 22 feet, what

must be its outside diameter to support a load of 143 tons, using formula 16? Ans. 12 in.

(22) (a) Make a detail drawing showing all dimensions of a cast-iron cap for a wooden column supporting two $12'' \times 10''$ yellow-pine floor girders, the under story column being $10'' \times 10''$ and the upper story column $8'' \times 8''$. (b) Make a similar drawing for a cast-iron cap for a wooden column supporting two girders each composed of two 12-inch I beams placed side by side, the upper and lower columns each being 10 inches square.

(23) Design a cast-iron column connection for two 15-inch steel I beams employed as a girder and placed side by side 6 inches apart. The diameter of the column is 14 inches and the thickness of the shell $\frac{3}{4}$ inch. Give all details and dimensions.



COLUMNS AND STRUTS

(PART 2)

EXAMINATION QUESTIONS

(1) (a) What are the three classes of structural steel columns? (b) Describe each.

(2) Using Gordon's formula and a safety factor of 4, and referring to the tables, compute the safe bearing strength of a strut of a pin-connected truss, the length of the strut being 18 feet between centers of pins and its section being made up of two 8-inch 17-pound channels and two cover-plates 10 inches by $\frac{1}{2}$ inch, all of medium steel.

Ans. 195,250 lb.

(3) The medium-steel compression member of a roof truss has a section such as shown in Fig. I. Its ends are riveted to the adjacent members, its length being 20 feet; what is its safe strength according to Gordon's formula, the safety factor being 4?

Ans. 105,117 lb.

(4) What is the least factor of safety to be used with a column with hinged ends, its length being

22 feet and its least radius of gyration 2.98? Ans. 4.33

(5) Name six conditions that affect the choice of the type of column to be used.

(6) Why are steel columns the best adapted for eccentric loads?




FIG. I

(7) Calculate the stress due to the eccentric load W , on the column shown in Fig. II. Ans. 49,564 lb.

(8) If there is a center load on the column in Fig. II of 160 tons, in addition to the eccentric load, what is the maximum fiber stress produced by the loads on the column? Ans. 20,779 lb.



FIG. II

(9) How should the column be designed to meet the requirements of the stress found in example 8, if its length is 24 feet?

(10) Calculate the maximum allowable fiber stress under an eccentric load of a 12-inch 141.5-pound channel column of soft steel, 24 feet long, with hinged ends, using the straight-line formula with a factor of safety of 4. Ans. 12,110 lb.

(11) Determine, by the straight-line formula, the safe load that an interior medium-steel column with flat ends will support; the column is 18 feet long and is composed of four $6'' \times \frac{5}{8}''$ Z bars with an $8'' \times \frac{5}{8}''$ web-plate. Use a safety factor of 5. Ans. 325,136 lb.

(12) A strut in a structural-steel roof truss is composed of two $4'' \times 4'' \times \frac{5}{16}''$ angles placed back to back, securely tied together, and riveted at the ends through $\frac{3}{8}$ -inch gusset plates. Providing the nominal length of the strut is 12 feet, what safe load will it support if the material is medium steel and the straight-line formula is used for the calculation, with a safety factor of 4? Ans. 42,734 lb.

(13) Design a rigid splice connection for a heavy built-up column section composed of one $\frac{3}{4}'' \times 12''$ web-plate,

four $6'' \times 6'' \times \frac{3}{4}''$ angles, and two $\frac{1}{2}'' \times 14''$ cover-plates. The columns at the junctions are considered as being milled on the ends and no plinth plate is to be used between the ends of the columns.

(14) Make an isometric drawing of a channel-bar column with cover-plates, supporting floorbeams, and having an overhanging connection for the support of outside wall beams.

(15) Make a complete working drawing, showing all dimensions, for a **Z**-bar column with a structural steel base, heavily braced with gusset plates and angles, and having connections for heavy floor girders composed of two 15-inch 60-pound **I** beams. The secondary beams of the floor system are on a level at the top with the girders, and secondary floorbeams connect with the column on opposite sides. The distance from the base plate of the column to the under side of the floor girder is 22 feet and from the top of the floor girders to the center of the splice connection is 3 feet. The column is composed of four $6'' \times \frac{1}{2}''$ **Z** bars and a $\frac{7}{8}'' \times 10''$ web-plate. The load supported by the main girders of the floor system is 2,000 pounds per lineal foot and the distance from center to center of columns is 20 feet.



DETAILS OF CONSTRUCTION

EXAMINATION QUESTIONS

(1) How does the thickness of the plates in a riveted joint influence the size of the rivets? Why?

(2) (a) What should be the least pitch of rivets?
(b) What should be the greatest pitch in compression members?

(3) Give rules for determining the distance a rivet should be placed from the end and side of a plate.

(4) How is a riveted tension joint liable to fail?

(5) What difference exists in the method of computing the strength of riveted joints in tension and compression?

(6) What are the usual unit strains allowed on riveted work in buildings?

(7) Why is it necessary to have the longitudinal pitch of rivets less in compression than in tension joints?

(8) If the safe unit tensile strength of the plates and rivets is 15,000 pounds and $\frac{3}{4}$ -inch rivets are used in the joint shown in Fig. 20, what is its safe strength?

(9) When is a plate in: (a) ordinary bearing? (b) web bearing?

(10) Design a riveted connection for a tension member, composed of two $3'' \times 3'' \times \frac{3}{8}''$ angles, that is required to resist 28,000 pounds. Give calculations proving that your design is sufficiently strong.

(11) What are the usual unit stresses allowed for iron and steel pins in the construction of railroad bridges and buildings?

(12) How is the location and amount of the maximum bending moment on a pin obtained when some of the forces are oblique?

(13) Determine the maximum bending moment on the pin shown in Fig. 31, using the graphic method. Give diagrams and state scale used.

(14) Assuming that the members composing the joint shown in Fig. 35 may be arranged in any symmetrical order, what arrangement will produce the least bending moment on the pin?

(15) As applied to rivets, what do you understand by: (a) round heads? (b) countersunk heads? (c) flattened heads?

(16) (a) What is the maximum length of grip that is assumed to give a tight joint? (b) How should the length to be specified in ordering rivets be determined?

(17) What are the usual unit stresses allowed for pins in the different types of structures?

(18) Describe the requirements of good design for the pin or reenforcing plate of a built-up member.

GRAPHICAL ANALYSIS OF STRESSES

(PART 1)

EXAMINATION QUESTIONS

(1) (a) What is an external force? (b) What is an internal force? (c) Explain what is understood by equilibrium.

(2) (a) What is complete equilibrium? (b) What is understood by the resultant of any system of forces?

(3) Describe the fundamental principles of the relations between force and motion.

(4) Determine the amount of the resultant of the two forces in Fig. I by describing the parallelogram of forces.




FIG. I




FIG. II

(5) Determine the resultant of the several concurrent forces shown in Fig. II.

(6) Determine the horizontal and vertical components of the oblique force shown in Fig. III.

- (7) The weight of a coping stone resting on the inclined top of a wall is 1,000 pounds, the angle of inclination to the horizontal being 30° . Provided that the stone is set in cement mortar and no friction exists between the coping and wall, what force does the stone exert perpendicular to the inclined top




FIG. III

of the wall and what force does it exert parallel with the incline tending to slide it downwards?

- (8) State, by a rule, the conditions that must exist for any number of concurrent forces acting at the joint of a framed structure to be in equilibrium. Also, express the rule by an equation.

- (9) A girder 33 feet long is loaded with three concentrated loads located at distances from the left-hand end equal to 10, 15, and 21 feet, respectively. The first concentrated load is 5,000 pounds, the second 8,000 pounds, and the third 12,000 pounds. Determine by the force and equilibrium polygons the reactions R_1 and R_2 at the left- and right-hand ends, respectively.

$$\text{Ans. } \begin{cases} R_1 = 12,150 \\ R_2 = 12,850 \end{cases}$$

- (10) A girder supported at both ends, as designated in Fig. IV, is required to sustain the thrust of two oblique shores W_1 and W_2 .




FIG. IV

Determine the amount and direction of the reactions R_1 and R_2 .

$$\text{Ans. } \begin{cases} R_1 = 9,000 \\ R_2 = 7,300 \\ \text{Direction: } 33^\circ \text{ with the vertical} \end{cases}$$

- (11) A shed roof is supported on two light brick walls as shown in Fig. V. Besides supporting the vertical loads on the rafter members, as designated, the truss is required to

support an oblique load of 1,000 pounds from belting and shafting attached at the point c , the general direction of the pull being 60° with the horizontal, as shown in the figure. Determine, by the graphical method, the direction and amounts of the reactions R_1 and R_2 on the left- and right-hand walls.

$$\text{Ans. } \begin{cases} R_1 = 2,100 \\ R_2 = 1,800 \\ \text{Direction: } 7^\circ 15' \text{ with the vertical} \end{cases}$$

(12) Explain, with figures: (a) If the amount of three forces is known, how can their directions be determined? (b) How can the amounts of two unknown forces be determined when their direction and the amount and direction of the third force are known? (c) When the directions and amounts of two forces are known, how may the direction and amount of the third force be determined?




FIG. V

(13) (a) Explain, with sketch if necessary, what is understood by a frame diagram. (b) Explain, with sketch, what is meant by a stress diagram.

(14) Explain the usual notation in lettering a stress diagram.

(15) What is essentially the first step in drawing a stress diagram?

(16) Considering that the direction of R_2 is horizontal, determine, by calculation, the amounts of the reactions at R_1 and R_2 , also the direction of R_1 , for the overhanging roof shown in Fig. VI.

$$\text{Ans. } \begin{cases} R_1 = 4,750 \\ \text{Direction of } R_1 : 42^\circ 26' \\ R_2 = 3,200 \end{cases}$$

- (17) Check the results of question 16 by the graphical method.




FIG. VI

- (18) Employ the graphical method for determining the amounts of reactions R_1 , R_2 , and the direction of R_1 for the truss shown in Fig. VII. The right-hand end of the truss is supported on rollers.

$$\text{Ans. } \begin{cases} R_1 = 18,000 \\ \text{Direction of } R_1 : 7^\circ 45' \text{ with vertical} \\ R_2 = 18,375 \end{cases}$$

- (19) Describe, in detail, by means of a simple example, the method of drawing the stress diagram for a framed structure by Maxwell's method.




FIG. VII

- (20) Describe, in detail, how the stresses in the members of a frame are determined by the method of sections.

GRAPHICAL ANALYSIS OF STRESSES

(PART 2)

EXAMINATION QUESTIONS

NOTE.—In answering the questions in this Section, always lay out the frame diagram. It is preferable to use in drawing this diagram the scale of $\frac{1}{4}$ inch to the foot. In laying out the stress diagram, place this adjacent to the frame diagram and use, if possible, a tenth scale.

(1) Draw the dead-load stress diagram for the roof truss constructed and loaded as shown in Fig. I.




FIG. I

(2) The Pratt truss shown in Fig. II is considered as having the wind acting on the left-hand side and a snow load on the right-hand side. Draw the stress diagram for this type of frame with the condition of loading shown in the figure, assuming that the ends of the truss are fixed.




FIG. II




FIG. III




FIG. IV

(3) Draw the dead-load stress diagram for the truss shown in Fig. III.




FIG. V




FIG. VI

(4) Draw the wind-load diagram for the truss shown in Fig. IV, assuming that the right-hand end of the truss is supported on a roller bearing, and that the wind is acting on the left-hand slope of the roof.

(5) Draw the stress diagram for the condition of loading shown in Fig. V.

(6) Draw two stress diagrams for the conditions of loading and supports shown in Fig. VI.

(7) Draw separate diagrams of the wind and dead loads of the roof truss shown in Fig. VII.

(8) Draw the stress diagram for the wind load on the left and snow load on the right for the roof truss shown in Fig. VIII.




FIG VII

(9) Draw all the necessary stress diagrams for determining the maximum stresses in the roof truss shown in Fig. IX, and tabulate the results so that these maximum stresses may be determined.

(10) Describe, by means of sketches, as briefly as possible, the method of determining one of three unknown forces at a joint by reversing the diagonal.

(11) Calculate, by the methods of moments, the amount of stress in the center lower chord member, Fig. X.

Ans. 7,636 lb.





FIG. VIII



A KEY
TO ALL THE
QUESTIONS AND EXAMPLES
INCLUDED IN THE
EXAMINATION QUESTIONS.

It will be noticed that the Keys have been given the same section numbers as occur on the headlines of Examination Questions to which they refer. All article references refer to the Instruction Paper bearing the same section number as the Key in which it occurs, unless the title of some other Instruction Paper is given in connection with the article number.

To be of the greatest benefit, the Keys should be used sparingly. They should be used much in the same manner as a pupil would go to a teacher for instruction with regard to answering some example he was unable to solve. If used in this manner, the Keys will be of great help and assistance to the student, and will be a source of encouragement to him in studying the various papers composing the Course.



LOADS IN STRUCTURES

(1) The length of the rafter member is $\sqrt{\left(\frac{60}{2}\right)^2 + 12^2} = 32.31$ ft.; and the secant of the angle between the rafter and the horizontal is $\frac{32.31}{30} = 1.077$. Substituting in formula 2, the weight of the truss per square foot of roof surface is

$$w = \frac{.75 \times (10 + 60)}{10 \times 1.077} = 4.87 \text{ lb. Ans.}$$

- (2) (a) Hotels and apartment houses, 70 lb.
(b) Ballrooms and drill halls, 120 lb.
(c) Churches and theaters, 120 lb. See Table IV.

(3) The live load due to the barrels of brown sugar is 113 lb. per sq. ft., from Table V. Then, the total dead and live load on each girder is $450 \times 25 + 450 \times 113 = 11,250 + 50,850 = 62,100$ lb. Ans.

(4) Projecting a vertical line down from the intersection of the 55° line with the curve of normal pressure, in Fig. 6, the multiplier is found to be .98; then, $.98 \times 30 = 29.4$ lb. per sq. ft. Ans.

(5) 40 lb. per sq. ft. See Art. 6, second paragraph.

(6) The sectional area of the column is $10 \times 12 - 10.5 \times 8.5 = 120 - 89.25 = 30.75$ sq. ft. From Table I, the weight of cast iron is .26 lb. per cu. in.; hence, the weight of the column is $15 \times 12 \times 30.75 \times .26 = 1,439$ lb. Ans.

(7) The area of the floor is $60 \times 150 = 9,000$ sq. ft. From Table VI, the allowable live load to be provided for in churches is, according to the Philadelphia building laws, 100 lb. per sq. ft. Therefore, the total live load on the floor is $9,000 \times 100 = 900,000$ lb. Ans.

(8) (a) 30 to 40 lb. per sq. ft.; 30 lb. for a large area and 40 lb. for a small area.

(b) Formula 3, $p = .004V^2$ is used in determining the wind pressure, and the wind is assumed to have a velocity of 100 mi. per hr. See last paragraph in Art. 10.

(9) The live load assumed for theaters is 120 lb. per sq. ft., from Table IV; the live load on the beam is $380 \times 120 = 45,600$ lb. Ans.

(10) (a) From Table III, the weight of truss per square foot of roof surface is 4.7 lb.; from Table II, 2-in. spruce sheathing weighs 4 lb. per sq. ft. and 4-ply slag roofing weighs 4 lb. per sq. ft. Then $4.7 + 4 + 4 = 12.7$ lb. per sq. ft.

The area of the roof is $2 \times 15 \times \sqrt{30^2 + 15^2} = 2 \times 15 \times 33.54 = 1,006.2$ sq. ft.

The dead load is $1,006.2 \times 12.7 = 12,778.7$ lb. Ans.

(b) From Table VII, the wind load is 23.7 lb. per sq. ft., normal to the slope of the roof; hence, as the wind blows on only one side of the roof at one time, the wind load is $\frac{1,006.2}{2} \times 23.7 = 11,923.47$ lb. Ans.

(11) The area to be supported by one girder is $40 \times 18 = 720$ sq. ft. From Table V, the weight of baled hay is found to be 57 lb. per sq. ft. Therefore, the live load on one girder is $720 \times 57 = 41,040$ lb. Ans.

(12) See Art. 17.

(13) Substituting the values in formula 3 gives $p = .004 \times 65^2 = 16.9$ lb. Ans.

(14) The value of the constant a to be used in formula 5 is obtained by substituting the values in formula 6. Thus,

$$a = \frac{1}{1 + .489 \times \frac{2,000}{800}} = \frac{1}{2.2225} = .45$$

Substituting in formula 5, the static load that will produce the same effect as the falling load is

$$W_s = 800 \times \left(1 + \sqrt{\frac{2 \times .45 \times 36}{.25} + 1} \right) = 800 \times (1 + \sqrt{130.6}) = 9,942 \text{ lb.} \\ \text{Ans.}$$

(15) The area to be considered is the projected area, which is $150 \times 5 = 750$ sq. ft. Since the surface is cylindrical, only one-half the wind pressure is considered; hence, the pressure tending to overturn the stack is $\frac{40}{2} \times 750 = 15,000$ lb. Ans.

(16) The area supported by each joist is $15 \times \frac{16}{12} = 20$ sq. ft.

From Table VI, the live load for a department store in New York is found to be 120 lb. per sq. ft. Therefore, the live load on one joist is $120 \times 20 = 2,400$ lb. Ans.

(17) At least 250 lb Twice the static load occurring from presses, trimmers, cutters, etc. should be considered. See Art. 6.

PROPERTIES OF SECTIONS

- (1) (a) See Art. 2.
(b) and (c) See Art. 3.

(2) See Art. 4.

(3) See Art. 5.

$$(4) \quad \text{Area of flange} = 6 \times \frac{5}{8} = \frac{30}{8} = 3.750 \text{ sq. in.}$$

$$\text{Area of web} = 7 \times \frac{5}{8} = \frac{35}{8} = 4.375 \text{ sq. in.}$$

$$\text{Area of bulb end} = 1^2 \times 3.1416 = 3.142 \text{ sq. in.}$$

$$\text{Total area} = 11.267 \text{ sq. in.}$$

$$\text{Moment of flange} = 3.75 \times \frac{5}{16} = 1.17$$

$$\text{Moment of web} = 4.375 \times 4\frac{1}{8} = 18.04$$

$$\text{Moment of bulb end} = 3.1416 \times 8\frac{1}{8} = 27.09$$

$$\text{Sum of moments} = 46.30$$

The neutral axis is at a distance from the upper edge equal to $46.3 \div 11.267 = 4.11$ in. Ans.

(5) The area of a $3'' \times 3'' \times \frac{5''}{16}$ angle is 1.78 sq. in., from Table V, and the distance from the back to the neutral axis is .87 in. The moment of the angles about the upper edge of the section is $1.78 \times 2 \times .87 = 3.097$, and the moment of the web is $8 \times \frac{5}{16} \times 4 = 10$. The moment of the entire section is $3.097 + 10 = 13.097$, and the entire area is $1.78 \times 2 + 8 \times \frac{5}{16} = 3.56 + 2.5 = 6.06$ sq. in. Hence, the distance c in Fig. II of the Examination Questions is equal to $13.097 \div 6.06 = 2.16$ in. Ans.

(6) The section has been divided into the small areas a, b, c , etc., as shown in Fig. 1 (a), and the center of gravity of each area determined. These areas are laid off to scale in (b) and the points thus located on the line xy are connected with some assumed point o . In (c), the lines $x'a'', a''b'', b''c''$, etc. are laid off parallel to the corresponding




FIG. 1




FIG. 2

lines in (b); from the points x' and l'' in (c), lines are drawn parallel to the first and last lines, respectively, in the diagram at (b). A line drawn through the point s , where these lines intersect, is the neutral axis of the section, which is found, by scaling, to be $6\frac{1}{2}$ in. from the top of the section. Ans.

(7) See Art. 9.

(8) See Art. 10.

(9) $I_s = \Sigma I' = \Sigma (I + a x^2)$. Formula 2.

(10) In order to locate the neutral axis $y-y$, moments are taken about the lower edge of the section. Considering the section as being divided into three parts, as shown in Fig. 2, the moments are

$$12 \times \frac{3}{4} \times \frac{3}{8} = 3.375$$

$$2 \times 4 \times \frac{3}{4} \times 2\frac{3}{4} = 16.500$$

$$\text{Sum of moments} = 19.875$$

$$\text{Total area} = 12 \times \frac{3}{4} + 2 \times 4 \times \frac{3}{4} = 15 \text{ sq. in. } 19.875 \div 15 = 1.325 \text{ in.,}$$

the distance from the lower edge of the section to the neutral axis.

The moment of inertia of the section is obtained by formula 2, while that of each elementary section is found by formula 1. As these sections are rectangles, the moment of inertia of each, with respect to its neutral axis, is equal to $\frac{b d^3}{12}$, from Table I. Substituting this in formula 1 gives $I' = \frac{b d^3}{12} + a x^2 = \frac{\frac{3}{4} \times 4^3}{12} + \frac{3}{4} \times 4 \times 1.425^2 = 4 + 6.093 = 10.093$ for each of the upper rectangles, since the lever arm is $2 - (1.325 - .75) = 1.425$ in. $\frac{12 \times (\frac{3}{4})^3}{12} + 12 \times \frac{3}{4} \times .95^2 = .422 + 8.123 = 8.545$, for the lower rectangle, the lever arm being $1.325 - \frac{.75}{2} = .95$. Then $\Sigma I = 2 \times 10.093 + 8.545 = 28.731$. Ans.

(11) Substituting in the formula $\frac{b d^3}{12}$, from Table I, the moment of inertia of the beam is $\frac{8 \times 12^3}{12} = 1,152$. Ans.

(12) See Art. 13.

(13) First determine the moment of inertia of each section with respect to its neutral axis. For the flange plates, the moment of inertia is obtained by the formula $\frac{b d^3}{12}$, from Table I. Substituting the values, the moment of inertia of each plate is $\frac{16 \times (\frac{5}{16})^3}{12} = .041$.

From Table V, the moment of inertia of a $4'' \times 4'' \times \frac{3}{8}''$ angle is 4.36, while from Table X, the moment of inertia of the $24'' \times \frac{3}{8}''$ web-plate is found to be 432. The distance r from the center of gravity of the outside flange plate to the neutral axis of the built-up section is $12 + \frac{5}{16} + \frac{5}{32} = 12.469$ in.; for the inside flange plate $r = 12 + \frac{5}{16} = 12.156$. The distance of the center of gravity of a $4'' \times 4'' \times \frac{3}{8}''$ angle from the back is found, from Table V, to be 1.14 in., hence x for the angle is equal to $12 - 1.14 = 10.86$ in. From the same table the area of the angle 2.86 sq in. is obtained. Substituting these values in formula 2, the moment of inertia of the entire section is $I_x = 2 \times \left(.041 + \frac{5}{16} \times 16 \times 12.469^2 \right) + 2 \times \left(.041 + \frac{5}{16} \times 16 \times 12.156^2 \right) + 4 \times (4.36 + 2.86 \times 10.86^2) + 2 \times 432 = 1,554.842 + 1,477.762 + 1,366.672 + 864 = 5,263.276$. Ans.




FIG. 1

$$(14) S = \frac{b d^2}{6} \quad \text{Formula 3.}$$

$$(15) S = \frac{I}{c} \quad \text{Formula 4.}$$

(16) Substituting the values in formula 3 gives $S = \frac{9 \times 12^2}{6} = 216$.
Ans

(17) From Table I, the formula for obtaining the section modulus of a T section, such as shown in Fig 3, is $S = \frac{I}{c_1}$, but it is necessary first to obtain I and c_1 from the formulas given in the same table.

The area of the section is $A = b s + h t = 3 \times \frac{3}{8} + 12 \times \frac{3}{8} = 2.813$ sq in. The distance c_1 from the neutral axis to the back

of the section is found from the formula $c_1 = \frac{d^2 t + s^2 (b - t)}{2 A}$, Table I

Substituting the values, $c_1 = \frac{(12)^2 \times \frac{3}{8} + (\frac{3}{8})^2 \times (3 - \frac{3}{8})}{2 \times 2.813} = \frac{8.913 + .370}{5.626} = 1.65$ in. $c = d - c_1 = 4.875 - 1.65 = 3.225$ in. From the same

table, the moment of inertia of the section is

$$\begin{aligned}
 I &= \frac{t c^3 + b c_1^3 - (b - t) (c_1 - s)^3}{3} \\
 &= \frac{.375 \times 3.225^3 + 3 \times 1.65^3 - (3 - .375) (1.65 - .375)^3}{3} \\
 &= \frac{12.579 + 13.479 - 5.442}{3} = 6.872
 \end{aligned}$$

Substituting in the formula $S = \frac{I}{d - c_1}$, the section modulus of the section is $\frac{6.872}{4.875 - 1.65} = 2.131$. Ans.

(18) The area of the section, according to Table I, is

$$A = b d - h (b - t) = 5 \times 11\frac{3}{4} - 10\frac{1}{2} \left(5 - \frac{5}{8}\right) = 58.75 - 45.938 = 12.812$$

sq. in. From the same table, the distance c_1 from the back of the section to the neutral axis is found to be

$$\begin{aligned}
 \frac{2 b^3 s + h t^3}{2 A} &= \frac{2 \times 5^3 \times \frac{5}{8} + 10\frac{1}{2} \times \left(\frac{5}{8}\right)^3}{2 \times 12.812} = \frac{31.25 + 4.106}{25.624} = 1.379 \text{ in.} \\
 c &= 5 - 1.379 = 3.621 \text{ in.}
 \end{aligned}$$

The moment of inertia is

$$\begin{aligned}
 I &= \frac{2 s b^3 + h t^3}{3} - A c_1^2 = \frac{2 \times \frac{5}{8} \times 5^3 + 10\frac{1}{2} \times \left(\frac{5}{8}\right)^3}{3} - 12.812 \times 1.379^2 \\
 &= \frac{156.25 + 2.562}{3} - 24.368 = 28.569
 \end{aligned}$$

The section modulus of the section is

$$S = \frac{I}{b - c_1} = \frac{28.569}{5 - 1.379} = \frac{28.569}{3.621} = 7.89. \text{ Ans.}$$

(19) (a) Section modulus of a 12-in. 40-lb. beam, from Table III, is 41.

(b) Section modulus of a 15-in. 60-lb. beam is 71.8.

(c) Section modulus of a 20-in. 75-lb. beam is 126.9.

(20) From Table XIII, the least radius of gyration of two $5'' \times 3\frac{1}{2}'' \times \frac{3}{8}''$ angles, with the short legs vertical and spaced $\frac{3}{8}$ in. apart, is 1.02.

(21) According to Art. 21, $W = \frac{F}{\text{span}}$; then F , the coefficient of strength, is equal to the load W multiplied by the span, or $22 \times 1,000 \times 22 = 484,000$. Referring to Table III, it is found that a 15-in. 42-lb. beam, having a coefficient of strength of 628,270, will be needed to carry the load. The weight of the beam is $42 \times 22 = 924$ lb., which requires a coefficient of $924 \times 22 = 20,328$. Therefore, the total coefficient of strength required is $484,000 + 20,328 = 504,328$, and a 15-in. 42-lb. beam is amply strong.

(22) The deflection is equal to the coefficient multiplied by the cube of the span and the number of 1,000-lb units in the load. From column *N*, Table IV, the coefficient of deflection for a 15-in. 40-lb. channel supporting a uniform load is .0000022. As there are two channels, each is considered as supporting one-half of the load, or $\frac{1,200 \times 25}{2} = 15,000$ lb. Then the deflection will be

$$.0000022 \times 25^3 \times \frac{15,000}{1,000} = .516 \text{ in. Ans.}$$

MATERIALS OF STRUCTURAL ENGINEERING

(PART 1)

- (1) See Art. 1.
- (2) See Art. 1.
- (3) See last paragraph in Art 1.
- (4) See Art. 1.
- (5) See Art. 2.
- (6) Sketch from description in Art. 2.
- (7) See Art. 3.
- (8) See Art. 4.
- (9) See Art. 5.
- (10) See Art. 6.
- (11) See Art. 7.
- (12) See Art. 7.
- (13) See Art. 8.
- (14) See Art. 8.
- (15) See Art. 8 and Table I.
- (16) See Art. 8.
- (17) See Art. 8.
- (18) See Art. 8.
- (19) See Art. 8.
- (20) See Art. 9.

(21) Substituting the values in the formula $P_u = w h \left(\frac{1 + \sin \frac{\alpha}{2}}{1 - \sin \frac{\alpha}{2}} \right)$,
the bearing capacity of the soil is
 $115 \times 20 \times \left(\frac{1 + \sin 10^\circ}{1 - \sin 10^\circ} \right) = 2,300 \times 1.42 = 3,266 \text{ lb. per sq. ft.}$ Ans.

- (22) See Art. 10.
- (23) See Art. 10.
- (24) See Art. 10.
- (25) See Art. 11.
- (26) (a) 1 ton per sq. ft.
(b) 4 tons per sq. ft.
(c) 3 tons per sq. ft.

MATERIALS OF STRUCTURAL ENGINEERING

(PART 2)


- (1) (a) and (b) See Art. 2.
- (2) (a) See Art. 36.
(b) See Art. 37.
- (3) See Art. 57.
- (4) See Art. 62.
- (5) See Art. 64.
- (6) See Art. 80.
- (7) See Art. 93.
- (8) See Art. 90.
- (9) See Arts. 87 and 92.
- (10) See Arts. 87, 88, 89, and 93.
- (11) See Art. 83.
- (12) See Art. 101.
- (13) See Art. 65.
- (14) See Art. 67.
- (15) See Art. 67.
- (16) See Art. 71.
- (17) See Art. 81.
- (18) See Art. 82.
- (19) See Art. 84.
- (20) See Art. 85.
- (21) See Art. 87.

- (22) (a) and (b) See Art. 103.
- (23) See Art. 105.
- (24) See Art. 105.
- (25) See Art. 109.
- (26) See Arts 99, 100, and 101.
- (27) See Art. 59.
- (28) See Arts. 84 and 86.
- (29) (a) New Hampshire granite, 12,000 lb. per sq. in.
(b) Bluestone, 15,000 lb. per sq. in.
(c) Bedford limestone, 8,000 lb. per sq. in.
(d) Vermont marble, 10,000 lb. per sq. in.
(e) Philadelphia pressed bricks, 6,000 lb. per sq. in.
(f) Terra cotta, 5,000 lb. per sq. in.
- (30) See Art. 105.
- (31) See Art. 105.
- (32) See Art. 105.
- (33) See Art. 108.

MATERIALS OF STRUCTURAL ENGINEERING

(PART 3)

- (1) (*a* and *b*) See Art. 1.
- (2) White pine. See Art. 2.
- (3) (*a*) See Art. 2.
(*b*) See Art. 7.
(*c*) See Art. 8.
- (4) (*a* and *b*) See Art. 20.
- (5) See Art. 21.
- (6) The area resisting the shear is $8 \times 14 = 112$ sq. in. From Table I, the shearing value of yellow pine with the grain is 600 lb. per sq. in.; therefore, the resistance offered by the end of the tie is $600 \times 112 = 67,200$ lb. Ans.
- (7) See Art. 24.
- (8) (*a* and *b*) See Art. 26.
- (9) See Table IH.
- (10) The area of the bar is $1\frac{1}{4} \times 1\frac{1}{4} = 1.5625$ sq. in.; according to Table II, the ultimate tensile strength of wrought iron is 48,000 lb. per sq. in. Therefore, a tensile stress of $48,000 \times 1.5625 = 75,000$ lb. will be required to break the rod. Ans.



BEAMS AND GIRDERS

(PART 1)

(1) (a), (b), and (c). See Art. 1.

(2) See Art. 2.

(3) See Art. 5.

(4) See Art. 6.

(5) The moment about the point *c* is $5,000 \times 10 = 50,000$ ft.-lb.
Ans.

(6) The moment due to the load of 5,000 lb. is $5,000 \times 7 = 35,000$ ft.-lb. Since the sum of the moments of all the forces about any point must equal zero in order to have equilibrium, the moment of the force on the opposite end of the beam must equal 35,000 ft.-lb.; therefore, the load that will prevent the beam from tilting is $35,000 \div 4\frac{1}{2} = 7,778$ lb.
Ans.

(7) See Art. 12.

(8) Taking the moments about the left-hand support, they are:

$$10,000 \times 8 = 80000 \text{ ft.-lb.}$$

$$2,000 \times 13 = 26000 \text{ ft.-lb.}$$

$$\text{Total, } 106000 \text{ ft.-lb.}$$

Then the right-hand reaction R_2 is $106,000 \div 25 = 4,240$ lb. Ans.

The left-hand reaction R_1 is $10,000 + 2,000 - 4,240 = 7,760$ lb. Ans.

(9) Taking the right-hand reaction as the center of moments, the moments due to the loads are as follows:

$$12,000 \times 8 \times \left(35 - \frac{8}{2}\right) = 297600 \text{ ft.-lb.}$$

$$10,300 \times \frac{35}{2} = 180250 \text{ ft.-lb.}$$

$$3,600 \times 4 = 14400 \text{ ft.-lb.}$$

$$\text{Total, } 3170650 \text{ ft.-lb.}$$

The left-hand reaction is equal to $3,170,650 \div 35 = 90,590$ lb. Ans.

(10) (a) Considering the point of support b as the center of moments, the moments are

$$1,200 \times 32 \times \left(\frac{32}{2} + 8\right) = 921600 \text{ ft.-lb.}$$

$$6,000 \times (24 + 8) = 192000 \text{ ft.-lb.}$$

$$8,000 \times 8 = 64000 \text{ ft.-lb.}$$

$$600 \times 8 \times \frac{8}{2} = 19200 \text{ ft.-lb.}$$

$$\text{Total, } 1196800 \text{ ft.-lb.}$$

Therefore, the reaction a , or the compression in the column, is $1,196,800 \div 35 = 34,194$ lb. Ans.

(b) The reaction at a is $1,200 \times 32 + 6,000 + 8,000 + 600 \times 8 = 34,194 = 23,000$ lb. Ans.

(11) See Art. 19.

(12) See Art. 20.

(13) The maximum shear is equal to the reaction, or $25,000 \div 2 = 12,500$ lb. Ans.

(14) Taking the left-hand reaction as the center of moments, they are:

$$3,000 \times 5 = 15000 \text{ ft.-lb.}$$

$$2,000 \times 12 = 24000 \text{ ft.-lb.}$$

$$2,500 \times 18 = 45000 \text{ ft.-lb.}$$

$$1,500 \times 25 = 37500 \text{ ft.-lb.}$$

$$1,000 \times 33 = 52800 \text{ ft.-lb.}$$

$$1,000 \times 35 \times \frac{35}{2} = 612500 \text{ ft.-lb.}$$

$$\text{Total, } 786800 \text{ ft.-lb.}$$

Hence, R_2 is $786,800 \div 35 = 22,480$ lb., and R_1 is $3,000 + 2,000 + 2,500 + 1,500 + 1,000 + 35,000 - 22,480 = 23,120$ lb. Then, as the shear is equal to the greater reaction, the shear on this beam is 23,120 lb. Ans.

(15) Considering the center of moments at the right-hand reaction, the moments are:

$$4,800 \times 9 = 43200 \text{ ft.-lb.}$$

$$5,900 \times 14 = 82600 \text{ ft.-lb.}$$

$$12,000 \times 16 = 192000 \text{ ft.-lb.}$$

$$\text{Total, } 317800 \text{ ft.-lb.}$$

The reaction at the left-hand end of the beam is, therefore, $317,800 \div 24 = 13,242$ lb. Subtracting the uniform load up to the first concentrated load, from this reaction, gives $13,242 - \frac{12,000}{16} \times 10 = 5,742$ lb. remaining, but the concentrated load of 5,900 lb. exceeds this remainder and, consequently, the shear changes sign under this load, or 14 ft. from the right-hand end of the beam. Ans.

(16) The shear on a single beam uniformly loaded is shown in Fig. 1 (a), while that produced by a concentrated load at the center is shown at (b).




FIG. 1

(17) See Fig. 29 and Art. 23.

(18) See Art. 24.

(19) As the greatest bending moment occurs at the point where the shear changes sign, it is first necessary to locate the point of no shear. Taking the left-hand reaction as the center of moments, they are:

$$\begin{array}{rcl}
 1,000 \times 13 \times \frac{13}{2} & = & 84500 \text{ ft.-lb.} \\
 16,000 \times 5 & = & 80000 \text{ ft.-lb.} \\
 10,000 \times 13 & = & 130000 \text{ ft.-lb.} \\
 2,000 \times 17 \times 21\frac{1}{2} & = & 731000 \text{ ft.-lb.} \\
 8,000 \times 30 & = & 240000 \text{ ft.-lb.} \\
 \text{Total,} & & 1265500 \text{ ft.-lb.}
 \end{array}$$

The right-hand reaction is, therefore, $1,265,500 \div 25 = 50,620$ lb., and the left-hand reaction is $1,000 \times 13 + 16,000 + 10,000 + 2,000 \times 17 + 8,000 - 50,620 = 30,380$ lb. Subtracting the first uniform load and the first concentrated load gives $30,380 - 1,000 \times 13 + 16,000 = 1,380$ lb.; it is readily seen that the greatest bending occurs under the next concentrated load, or 10,000 lb., since this greatly exceeds the remainder of 1,380 lb. Then taking this point as the center of moments, and considering the moments to the left, they are as follows:

Positive moment, $30,380 \times 13 = 394,940$ ft.-lb.

$$\begin{array}{rcl}
 \text{Negative moments, } 1,000 \times 13 \times \frac{13}{2} & = & 84500 \text{ ft.-lb.} \\
 16,000 \times 8 & = & 128000 \text{ ft.-lb.} \\
 \text{Sum,} & & 212500 \text{ ft.-lb.}
 \end{array}$$

The greatest bending moment is equal to the algebraic sum of these moments, or $394,940 - 212,500 = 182,440$ ft.-lb. Ans.

- (20) (a) $\frac{W'}{8}$. See Table I, Case VII.
 (b) $\frac{W'}{6}$. See Table I, Case IX.
 (c) $\frac{W'}{2}$. See Table I, Case II.

(21) Assuming the concentrated loads of 2,500 lb. and 3,000 lb. to be located at distances of 12 ft. and 26 ft., respectively, from the left-hand end of the girder, and taking the center of moments at this point, they are as follows:

$$\begin{aligned} 2,500 \times 12 &= 30,000 \text{ ft.-lb.} \\ 3,000 \times 26 &= 78,000 \text{ ft.-lb.} \\ 2,500 \times 36 \times \frac{58}{2} &= 261,000 \text{ ft.-lb.} \\ \text{Total,} \quad &273,000 \text{ ft.-lb.} \end{aligned}$$

The reaction at the right-hand end is $2,733,000 \div 58 = 47,131$ lb., while the left-hand reaction is $2,500 + 3,000 + 2,500 \times 36 \div 47,131 = 49,469$ lb.

Subtracting the first concentrated load gives $49,469 - 2,500 = 46,969$ lb.; then subtract the uniformly distributed load up to the point where the second concentrated load is applied, which gives $46,969 - 2,500 \times 15 = 8,969$ lb. The concentrated load of 3,000 lb. is next subtracted, leaving a remainder of 5,969 lb. The point of no shear is, therefore, located at a point beyond the load of 3,000 lb., a distance of $\frac{5,969}{2,500} = 2.1476$ ft.; hence, the point where the shear

changes sign and the greatest bending moment exists is at a distance of $26 + 2.1476 = 28.1476$ ft. from the left-hand support. Considering this point as the center of moments and taking the moments to the right, they are.

Positive moment, $47,131 \times 58 - 28.1476 = 1,406,973.4644$ ft.-lb.


Negative moment, $2,500 \times 18.8524 \times 9.4262 = 444,266.2322$ ft.-lb.

Therefore, neglecting the decimals, the maximum bending moment is $1,406,973 - 444,266 = 962,707$ ft.-lb. Ans.


(22) (a) The loads on the beam are laid off on the load line ac , as shown in Fig. 2 (b), and lines drawn from o to the points a, b, c, d , and e . The equilibrium polygon is laid out as shown in (a), and by inspection or by measurement it is found that the greatest bending moment occurs at r , or under the load of 2,000 lb. The distance rv measures $6\frac{1}{2}$ ft., while the horizontal line H in the force polygon scales 12,000 lb.; therefore, the greatest bending moment is $12,000 \times 6\frac{1}{2} = 87,000$ ft.-lb., which is as near the correct result as it is possible to obtain by the graphical method.

(b) In the force polygon at (b), draw oz parallel to fg in the

equilibrium polygon. By scaling, az is found to equal $\frac{82\frac{3}{8}}{60}$ in., which represents 8,237.5 lb., the reaction at R_1 . This is the greater reaction, and hence is the amount of the maximum shear on the beam.



Scale $\frac{1}{16}'' = 1'$



Scale $\frac{1}{60}'' = 100 \text{ lb.}$

FIG. 2

(23) From Table II, it is found that the center reaction for a continuous beam of two spans is equal to $\frac{10}{8} w l$; substituting the values gives $\frac{10}{8} \times 1,200 \times 23 = 34,500 \text{ lb.}$ Ans.

(24) The greatest bending moment on the beam described in question 23 occurs at the center support, and from Table III it is found to equal $\frac{1}{8} w l^2$, or $\frac{1}{8} \times 1,200 \times 23 \times 23 \times 12 = 952,200$ in.-lb. Ans.

(25) (a) See Art. 39.
(b) 1,200,000 lb.

(26) The formula for the deflection in this case is found, from Table IV, to be $\frac{W l^3}{3 E I}$. The modulus of elasticity, from Art. 39, is 1,200,000 and the moment of inertia of the section, from the formula $I = \frac{b d^3}{12}$ is $I = \frac{10 \times 12^3}{12} = 1,440$. Substituting these values, the deflection is $\frac{10,000 \times (8 \times 12)^3}{3 \times 1,200,000 \times 1,440} = 1.7$ in. Ans.

(27) From Table IV, the formula for the deflection, in this case, is $\frac{5 W l^3}{384 E I}$. The modulus of elasticity of steel, according to Art. 39, is 28,000,000 to 30,000,000; taking the average, or 29,000,000, and substituting the values in the formula, the deflection is $\frac{5 \times 1,500 \times 28 \times (28 \times 12)^3}{384 \times 29,000,000 \times 1,500} = .47$ in. Ans.

BEAMS AND GIRDERS

(PART 2)

(1) See Art. 6.

(2) The section modulus is found by the formula $S = \frac{b d^3}{6}$, or $\frac{10 \times 12^3}{6} = 240$. The safe strength of the wood is $\frac{4,000}{4} = 1,000$ lb. per sq. in. Substituting these values in formula 1,

$$W = \frac{2 \times 240 \times 1,000}{3 \times 30} = 5,333\frac{1}{3} \text{ lb. Ans.}$$

(3) The safe strength of the wood is $\frac{3,500}{4} = 875$ lb. per sq. in. Substituting the values in formula 2, $S = \frac{3 \times (400 \times 15) \times 15}{2 \times 875} = 154.28$. By transposing the formula $S = \frac{b d^3}{6}$, d may be found, thus: $d = \sqrt[3]{\frac{6 S}{b}} = \sqrt[3]{\frac{6 \times 154.28}{8}} = \sqrt[3]{115.71} = 10.7+$, or about 11 in. As an 8" \times 11" timber is not a commercial size, an 8" \times 12" beam should be used. Ans.

(4) The ratio of the modulus of elasticity of the two materials is $\frac{1,000,000}{29,000,000} = \frac{1}{29}$; therefore, the safe unit stress that may be employed for white pine is $\frac{1}{29}$ of 15,000 = 517 lb. per sq. in. The bending moment M equals $S \times s$. As there are two separate beams, there are two section moduli, $\frac{b d^3}{6}$ for the wood and $\frac{b' d'^3}{6}$ for the steel plate. Substituting their sum for the value of S , $M = \frac{s b d^3}{6} + \frac{s' b' d'^3}{6}$, and transposing it is found that $b = \frac{6 M - b' s' d'^3}{s d^3}$. By substitution, b is found to equal

$$\frac{6 \times 400,000 - .5 \times 15,000 \times 14 \times 14}{517 \times 14 \times 14} = 9.17 \text{ in.}$$

Therefore, each plank should be $9.17 \div 2 = 4.58$ in. thick. Ans.

(5) See Art. 8.

(6) See Art. 12.

(7) By applying formula 4,

$$S_r = \frac{W \times L}{3.67} = 40.46. \text{ Ans.}$$

(8) The area supported by each beam is $22 \times 6 = 132$ sq. ft.; and as the load per square foot is 200 lb., the total load is $200 \times 132 = 26,400$ lb.

$$\text{The bending moment } M = \frac{26,400 \times (22 \times 12)}{8} = 871,200 \text{ in.-lb.,}$$

and the safe working value of steel is $\frac{60,000}{4} = 15,000$ lb. per sq. in.

The section modulus is therefore $\frac{871,200}{15,000} = 58.08$. From the table Properties of Standard I Beams, in *Properties of Sections*, it is found that the section modulus of a 15-in. 42-lb. I beam is 58.9; hence, this size beam should be used. Ans.

(9) See Art. 19.

(10) Transposing formula 12, $A = \frac{x w L^2}{10,000}$, and substituting the

given values, $A = \frac{4 \times 300 \times 5 \times 5}{10,000 \times 8} = \frac{3}{8} = .375$ sq. in. The area of a $\frac{3}{8}$ -in. rod, at the root of the thread, is found from the table Standard Screw Threads and Nuts, in *Details of Construction*, to be .419 sq. in. Therefore, $\frac{3}{8}$ -in. rods should be used. Ans.

(11) From formula 7, $T = \frac{3 \times 300 \times 5 \times 5}{2 \times 8} = 1,406$ lb per ft.

Assuming an 18-in. 60-lb. beam, the values of b and P are found from the table Properties of Standard I Beams, in *Properties of Sections*, to be 6.10 and 22.38, respectively. Substituting these values in formula 6,

$$s_4 = \frac{1,406 \times 6.1 \times 4 \times 4}{2 \times 22.38} = 3,066 \text{ lb per sq in. Hence, according}$$

to formula 9, $s_r = \sqrt{16,000^2 - 3,066^2} = 15,703$ lb. per sq. in.

The section modulus of an 18-in. 60-lb. beam is found from the table Properties of Standard I Beams, in *Properties of Sections*, to be 93.5. From

$$\text{formula 10, the safe vertical load } W_s = \frac{8 \times 93.5 \times 15,703}{25 \times 12} = 39,153 \text{ lb.}$$

The actual load on the beam is $300 \times 25 \times 5 = 37,500$ lb., which is less than the allowable load; therefore, the assumed size, 18-in. 60-lb. beam, is sufficiently strong. Ans.

(12) The bearing value required is equal to the reaction at the end of the beam, or $\frac{700 \times 28}{2} = 9,800$ lb. From Table IV, it is seen

that a $10'' \times 10''$ plate will give the required bearing value for a plate on brickwork laid in lime mortar.

According to the table Properties of Standard I Beams, in *Properties of Sections*, a 15-in. 42-lb. I beam has a 5.5-in. flange. Substituting

the values in formula 14, $t = .00685(10 - 5.5) \sqrt{\frac{9,800}{10 \times 10}} = .3049$.

Therefore, the thickness should be $\frac{5}{16}$ in., and, consequently, the size of the plate is 10 in. \times 10 in. \times $\frac{5}{16}$ in. Ans.

(13) The greatest bending moment is $\frac{Wl}{8} = \frac{(1,200 \times 16) \times 192}{8} = 460,800$ in.-lb. According to the formula given in Art. 39, $s_c = \frac{6M}{bd^2} = \frac{6 \times 460,800}{20 \times 24 \times 24} = 240$ lb. per sq. in.; $m = \frac{bd}{A} \times \frac{E_c}{E_s} = \frac{20 \times 24}{14 \times \frac{1}{2} \times 1} \times \frac{1,000,000}{28,000,000} = 2.45$, the values of E_c and E_s being found in Art. 39. Substituting these values in formulas 17 and 18,

$$s_t = 240 \left(\frac{1 + 2.45 - 2 \times \frac{10}{24}}{1 + 2.45 + 12 \times \frac{10^2}{24^2}} \right) = 113 \text{ lb. per sq. in., which is less than}$$

the allowable tensile stress. Also, $s_c = 240 \left(\frac{1 + 2.45 + 2 \times \frac{10}{24}}{1 + 2.45 + 12 \times \frac{10^2}{24^2}} \right) = 186$ lb. per sq. in., which is less than the allowable compressive stress of the concrete.

The total stress on the steel bars is found, from formula 19, to be $\frac{2 \times 240 \times 10 \times 20}{1 + 2.45 + 12 \times \frac{10^2}{24^2}} = 17,350$ lb.

As there are fourteen $\frac{1}{2}'' \times 1''$ bars, the sectional area of the reinforcing metal is 7 sq. in. and the unit stress is therefore $\frac{17,350}{7} = 2,479$ lb., which is well within the safe limit. The beam is therefore sufficiently strong to support its load. Ans.

(14) Substituting the given values in formula 21,

$$A = \frac{(1,000 \times 14) \times (14 \times 12)}{7 \times 18 \times 10,000} = 1.87 \text{ sq. in. Ans.}$$

(15) See Art. 44.

(16) Referring to Table V, in the column headed 16, the nearest safe load is 28 hundred pounds. Following this number in a horizontal direction to the first column at the left, it will be seen that a depth of 8 in. is required. Ans.

(17) See Art. 48.

(18) Before applying formula 27, it is necessary to determine the values of x and y . From formula 26, y is found to equal

$$\frac{15 \times 4 + 14 \times 20}{30 \times 4 + 2 \times 14 \times 20} = 8.32 \text{ in.}, \text{ and } x = d - y = 20 - 8.32 = 11.68 \text{ in.}$$

Substituting these values in formula 27,

$$\begin{aligned} M_1 &= \left(\frac{5}{8} \times 11.68 + 8.32 \right) \times 4 \times 64,000 + \frac{200 \times 14 \times 8.32^2}{8} \\ &= 4,063,000 \text{ in.-lb. Ans.} \end{aligned}$$

(19) See Fig. 28.

(20) Before applying formula 24, it will be necessary to locate the neutral axis of the beam section, which may be calculated by transposing formula 25; thus, $e = \frac{20A}{b} \left(-1 + \sqrt{1 + \frac{bd}{12A}} \right)$. Substituting the values given,

$$\begin{aligned} e &= \frac{20 \times (10 \times \frac{7}{8} \times \frac{1}{2})}{14} \times \left(-1 + \sqrt{1 + \frac{14 \times 18}{12 \times (10 \times \frac{7}{8} \times \frac{1}{2})}} \right) \\ &= 9.45 \text{ in.}, \text{ or approximately 9 in. } e_1 = \frac{5d}{6} - 9, \text{ or } \frac{5 \times 18}{6} - 9 = 6 \text{ in.} \end{aligned}$$

Substituting these values in formula 24,

$$M = \frac{1}{3} \times 500 \times 9^3 \times 14 + 16,000 \times \frac{45}{8} \times 6 = 729,000 \text{ in.-lb. Ans.}$$

(21) See Arts. 53 to 57, inclusive.

(22) See Art. 30.

BEAMS AND GIRDERS

(PART 3)

(1) (a) and (b). See Art. 2.

(2) See Art. 6.

(3) (a) The allowance to be made for one rivet hole is $\frac{3}{4} + \frac{1}{8} = \frac{7}{8}$ in. and the effective depth of the plate is $30 - \frac{7}{8} \times 8 = 23$ in.

From formula 1, the thickness of the web-plate is $t = \frac{86,000}{23 \times 12,000} = .31$ in., or $\frac{5}{16}$ in. Ans.

(b) By formula 2, the safe resistance of the plate to buckling is $b = \frac{11,000}{1 + \frac{30^2}{3,000 \times (\frac{5}{16})^2}} = 2,701$ lb. per sq. in., which is much less than

the unit shearing stress on the web-plate; hence, stiffeners are required. Ans.

(4) See Art. 10.

(5) $M_1 = A d s + \frac{s b d^3}{6}$. See Art. 11.

(6) See Art. 13.

(7) From the table Properties of Standard Angles, in *Properties of Sections*, the area of a $6'' \times 6'' \times \frac{5}{8}$ angle is found to be 7.11 sq. in. The area of each plate is $\frac{3}{8} \times 14 = 5.25$ sq. in. The diameter to be deducted for the rivet holes is $\frac{7}{8} + \frac{1}{8} = 1$ in.; therefore, the area cut from each flange plate is $\frac{3}{8} \times 1 \times 2 = .75$ sq. in., and the net area of each plate is $5.25 - .75 = 4.5$ sq. in. There are two rivets through each angle; hence, the net area of one angle is

$7.11 - (\frac{1}{2} \times 1 \times 2) = 5.86$ sq. in. The net area of the flange section is, therefore,

$$\text{Four plates } 4.5 \times 4 = 18.00 \text{ sq. in.}$$

$$\text{Two angles } 5.86 \times 2 = 11.72 \text{ sq. in.}$$

$$\text{Total, } 29.72 \text{ sq. in.}$$

Substituting the values in formula 6, the lengths of the plates are as follows:

Outside plate,

$$L_p = 75 \times \sqrt{\frac{4.5}{29.72}} = 75 \times \sqrt{.1514} = 75 \times .389 = 29.175 \text{ ft. Ans}$$

Second plate,

$$L_p = 75 \times \sqrt{\frac{9}{29.72}} = 75 \times \sqrt{.3028} = 75 \times .55 = 41.25 \text{ ft. Ans.}$$

Third plate,

$$L_p = 75 \times \sqrt{\frac{13.5}{29.72}} = 75 \times \sqrt{.4542} = 75 \times .674 = 50.55 \text{ ft. Ans}$$

Fourth plate,

$$L_p = 75 \times \sqrt{\frac{18}{29.72}} = 75 \times \sqrt{.6056} = 75 \times .778 = 58.35 \text{ ft. Ans.}$$

(8) Half the length of the girder is laid off to a scale of $\frac{1}{8}$ in. = 1 ft., as at ab in Fig 1, and the net areas of the flange angles and plates are laid off at ah , hg , gf , fe , and ed to a scale of $\frac{1}{12}$ in. = 1 sq. in.

The lines ab and ad are divided into the same number of equal parts and the parabola described as shown, from which the lengths of the flange plates are found by scaling. The outside plate is 58 ft. 4 in., the second plate, 50 ft. 6½ in.; the third plate, 41 ft. 3 in.; and the fourth plate, 29 ft. 2 in. Ans.


(9) (a) See Art 22.

(b) See Art 23.

(10) See Arts 24, 26, 27, and 28.

(11) By substituting in the formula $M = \frac{WL}{8}$, the maximum bending moment, which occurs at the center of the girder, is $M = \frac{2,000 \times 45 \times 45}{8} = 506,250$ ft.-lb. The horizontal flange stress at the center of the girder is $506,250 \div 3 = 168,750$ lb. As the strength of one rivet is 5,000 lb., the number required between the center and the end is $168,750 \div 5,000 = 33.75$, or 34 rivets. Lay out a diagrammatic elevation of one-half the girder, showing the location of the

stiffeners, and construct the parabola as shown in Fig. 2. A scale of $\frac{1}{8}$ in. = 1 ft. is used in this case. Divide the line ab into thirty-four equal spaces and from the intersections of the stiffener lines extended



and the parabola, project lines horizontally intersecting ab at $c, d, e,$ and f . Then the number of spaces between a and c , or ten, represents the number of rivets to be used in the first panel; consequently, the pitch is equal to the length of the panel divided by the number of rivets, or $42 \div 10 = 4.2$ in. In the second panel, nine rivets are required,

since there are nine spaces between c and d ; hence, the pitch is $48 \div 9 = 5.33$ in. The third panel requires nine rivets and the pitch is $60 \div 9 = 6.66$ in.; therefore, in this and the two remaining panels, the rivets will be spaced 6 in. on centers.




FIG. 2

(12) According to Art. 5, the minimum depth of the girder should be one-fifteenth of the span, or $\frac{1}{15} \times 45 = 3$ ft. The area of brickwork supported by the beam is $\frac{45 \times 4\frac{1}{2}}{2} = 506.25$ sq. ft., and the weight is $506.25 \times \frac{13}{12} \times 130 = 71,297$ lb. The bending moment, not including that produced by the weight of the girder itself, is $M = \frac{WL}{6} = \frac{71,297 \times 45}{6} = 534,728$ ft.-lb. The net flange area required is found, by formula 4, to be $A = \frac{534,728}{3 \times 15,000} = 11.883$ sq. in., assuming 15,000 lb as the safe fiber stress of the material. If the flange is composed of two $6'' \times 6'' \times \frac{3}{8}$ angles and a $13'' \times \frac{1}{2}$ flange plate, the

net area, deducting $\frac{7}{8}$ -in. holes for $\frac{3}{4}$ -in. rivets, is determined as follows: From Table V, *Properties of Sections*, the area of a $6'' \times 6'' \times \frac{3}{8}$ angle is 4.36 sq. in.; the area to be deducted from each angle for rivet holes is $\frac{7}{8} \times \frac{3}{8} \times 2 = .656$ sq. in. The area of the flange plate is $13 \times \frac{1}{2} = 6.5$ sq. in. and the amount to be deducted for rivet holes is $\frac{7}{8} \times \frac{1}{2} \times 2 = .875$ sq. in. Hence, the net flange area is $2 \times (4.36 - .656) + 6.5 - .875 = 13.033$ sq. in., which is ample.

The maximum shear is equal to the reaction, or $\frac{71,297}{2} = 35,648.5$ lb.

Assuming a $\frac{5}{16}$ -in. web-plate, which is the thinnest that may be used, the number of rivets required for the end stiffeners is determined as follows: From Table XIII, *Details of Construction*, the shearing and bearing values used for steel-riveted work in buildings are 9,000 lb. and 18,000 lb., respectively. Referring to Table XI, in the same Section, the strength of a $\frac{3}{4}$ -in. rivet in double shear at 18,000 lb. per sq. in. is 7,952 lb.; from Table XII, the bearing value of a $\frac{3}{4}$ -in. rivet, through a $\frac{5}{16}$ -in. plate, at 18,000 lb. per sq. in., is 4,219 lb., and for web bearing it is $4,219 \times 1\frac{1}{2} = 5,625$ lb.; as this is less than the shearing value, it will be used. Hence, the number of rivets required in the end stiffeners is $35,648.5 \div 5,625 = 6.3$, or 7. According to the rule given in Art. 10, stiffeners must be provided.

Applying formula 9, and assuming the stiffeners to be spaced 5 ft. apart, the pitch of the rivets in the flanges is determined as follows: The vertical shear at the end of the girder is equal to the reaction, or 35,648.5 lb.; at the first panel point the shear is equal to the reaction minus the load on the first panel, or $35,648.5 - \frac{5 \times 5}{2} \times 130 \times \frac{13}{12} = 35,648.5 - 1,760.4125 = 33,888.0875$ lb. At the second panel point, the shear is equal to the reaction minus the load on the first two panels; this is $35,648.5 - \frac{10 \times 10}{2} \times 130 \times \frac{13}{12} = 35,648.5 - 7,041.65 = 28,606.85$ lb. Similarly, the shear at the third panel point is $35,648.5 - \frac{15 \times 15}{2} \times 130 \times \frac{13}{12} = 35,648.5 - 15,843.75 = 19,804.75$ lb.

Assuming that the rivets are placed 3 in. from the back of the flange angles, the value for h , in formula 9, is $36 - 3 \times 2 = 30$ in. Substituting the above values in the formula, the following results are obtained:

$$\text{Pitch of rivets in first panel is } p = \frac{5,625 \times 30}{35,648.5} = 4.73 \text{ in.}$$

$$\text{Pitch of rivets in second panel is } p = \frac{5,625 \times 30}{33,888.0875} = 4.98 \text{ in.}$$

$$\text{Pitch of rivets in third panel is } p = \frac{5,625 \times 30}{28,606.85} = 5.89 \text{ in.}$$

Pitch of rivets in fourth panel is $p = \frac{5,625 \times 30}{19,804.75} = 8.52$ in.; hence, in this panel and the center one, the rivets will be placed 8 in. on centers. The rivets connecting the flange plate and angles should be placed 8 in. on centers.

(13) The load coming on the strut is considered as five-eighths of the entire load on the beam, or $W' = \frac{5}{8} \times 1,500 \times 34 = 31,875$ lb

(a) The length of the tension rod, from the bottom of the strut to the end of the beam, is $\sqrt{(\frac{3}{4} \times 12)^2 + (2\frac{1}{2} \times 12)^2} = 206.194$ in., and according to formula 12, the tension in the rod is $\frac{206.194}{30} \times \frac{31,875}{2} = 109,538$ lb. Ans.

(b) From formula 13, the compression in the beam is $\frac{(34 \times 12) \div 2}{30} \times \frac{31,875}{2} = 108,375$ lb. Ans.

(14) The total uniformly distributed load on the beam is $1,500 \times 24 = 36,000$ lb., and as eleven-thirtieths of the load is assumed to act directly over the strut, the total load on each strut is $\frac{11}{30} \times 36,000 = 13,200$ lb.

(a) Theoretically, the greatest stress in the rod is in the oblique portion, and its amount is $\frac{\sqrt{8^2 + 2^2}}{2} \times 13,200 = 54,424$ lb. Assuming a safe unit stress of 15,000 lb., the rod must have an area of $54,424 \div 15,000 = 3.628$ sq in. and a $2\frac{1}{4}$ -in. rod, which has an area of 3.718 sq in. at the root of the thread, will be used. If the ends are upset, a $2\frac{1}{4}$ -in. rod will be sufficient.

(b) The compression in the beam, from formula 17, is found to be $\frac{8}{2} \times 13,200 = 52,800$ lb. Assuming the beam to be composed of Georgia yellow pine, and using a factor of safety of 4, the area required to resist this stress is $\frac{52,800}{8,000} = 6.6$ sq. in., since the ultimate compressive strength of this material in end bearing is 8,000 lb. per sq. in. (from Table 1, *Materials of Structural Engineering*, Part 3). A 6" \times 6" timber is the smallest standard size that will give the required sectional area. Ans.

(15) According to the rule given in Art. 45, the stress in BG is equal to the shear in the first panel multiplied by the secant of the angle GBH . The secant of this angle is equal to $\frac{\sqrt{BH^2 + GH^2}}{BH}$
 $= \frac{\sqrt{12^2 + 10^2}}{12} = 1.3017$, and the shear in the panel AB is $10,000 - 1,250 = 8,750$ lb. Hence, the stress in BG is $8,750 \times 1.3017 = 11,390$ lb.

Stress in $CH = (10,000 - 1,250 - 2,500) \times 1.3017 = 8,136$ lb.

Stress in $DI = (10,000 - 1,250 - 2,500 - 2,500) \times 1.3017 = 4,881$ lb.

Stress in $EJ = (10,000 - 1,250 - 2,500 - 2,500 - 2,500) \times 1.3017 = 1,627$ lb.

According to Art. 46, the stresses in the vertical web members are as follows:

$$EK = 0$$

$$DJ = 2,500 \times 1\frac{1}{2} = 3,750 \text{ lb.}$$

$$CI = 2,500 \times 2\frac{1}{2} = 6,250 \text{ lb.}$$

$$BH = 2,500 \times 3\frac{1}{2} = 8,750 \text{ lb.}$$

Since AG is not really a part of the frame, it carries only the load directly over it; therefore, the stress in this member is 1,250 lb.

By the rule in Art. 47, the stresses in the chords are as follows:

$$GH = BC = 8,750 \times \tan GBH = 8,750 \times \frac{10}{12} = 7,292 \text{ lb.}$$

$$HI = CD = (8,750 + 6,250) \times \frac{10}{12} = 12,500 \text{ lb.}$$

$$IJ = DE = (8,750 + 6,250 + 3,750) \times \frac{10}{12} = 15,625 \text{ lb.}$$

$$HI = (8,750 + 6,250 + 3,750 + 1,250) \times \frac{10}{12} = 16,667 \text{ lb.}$$




FIG. 3

Theoretically, there is no stress in the chord AB , nor in the vertical web EK , but practically there would be a slight stress in each. Since the truss is symmetrically loaded, the stresses in the members in the right half of the truss are equal to those in the corresponding members in the left half.

(16) See Art 51.

(17) Fig. 3 shows the frame diagram of a Pratt truss of 75-ft. span. The stress in DI is compressive, and equal to the load at D , or 3,000 lb. One-half of this load is taken care of by each of the rods CI and EI ; hence, 1,500 lb. is transmitted to the point C , and

the stress in CH is $3,000 + 1,500 = 4,500$ lb. Similarly, the stress in BG is $3,000 + 3,000 + 1,500 = 7,500$, and the stress in AF is equal to the reaction, or 9,000 lb.

The stress in CI is equal to 1,500 multiplied by the secant of the angle CID ; in BH it is equal to 4,500 multiplied by the same value.

etc. The secant of the angle CID is $\frac{\sqrt{(12.5)^4 + (12.5)^2}}{12.5} = 1.4142$, then the stresses in the oblique web members, which are tensile, are as follows:

Stress in $CI = 1,500 \times 1.4142 = 2,121$ lb.

Stress in $BH = 4,500 \times 1.4142 = 6,364$ lb.

Stress in $AG = 7,500 \times 1.4142 = 10,607$ lb.

The stress in the chord AB is compressive and is equal to the horizontal component of the stress in AG , or $7,500 \times \tan CID = 7,500 \times 1 = 7,500$ lb. The amount of the stress in GH is the same, but it is tensile. The chord stresses may be tabulated as follows:

Stress in $AB = GH = 7,500 \times 1 = 7,500$ lb.

Stress in $BC = HI = (7,500 + 4,500) \times 1 = 12,000$ lb.

Stress in $CD = (7,500 + 4,500 + 1,500) \times 1 = 13,500$ lb.

Theoretically, there is no stress in FG . Ans.

(18) See rules under Arts. 54 and 55.

(19) See Art. 56.

(20) See Art. 58.

(21) See Arts. 61 and 63.

COLUMNS AND STRUTS

(PART 1)

(1) See Art. 4.

(2) See Arts. 7, 8, 9, and 10.

(3) (a) and (b) See Art. 11.

(4) See Art. 12.

(5) The area of the column is $12 \times 12 = 144$ sq. in. and the safe load that it may support is therefore $144 \times 800 = 115,200$ lb. Ans.

(6) See Art. 13.

(7) The length l equals $14 \times 12 = 168$ in. Substituting the known values in formula 8, the safe unit stress u , for a white pine column is found to be
$$\frac{800}{1 + \frac{168^2}{1,100 \times 10^3}} = 637 \text{ lb. per sq. in.}$$
 This quotient

multiplied by the cross-sectional area of the column, which is $10 \text{ in.} \times 10 \text{ in.}$, equals $637 \times 100 = 63,700$ lb. Ans.

(8) The length of the column is $15 \times 12 = 180$ in. and $d = 12$. Substituting these values in formula 9, $u = 4,000 - \left(\frac{4,000 \times 180}{100 \times 12} \right) = 3,400$ lb. per sq. in. This result, multiplied by the cross-sectional area of the column ($12 \text{ in.} \times 12 \text{ in.}$), equals $3,400 \times 144 = 489,600$ lb. Ans.

(9) See Art. 25.

(10) (a) See Art. 26.

(b) See Art. 27.

(11) $l = 20 \times 12 = 240$ in. and $d = 12$ in. According to Table III, the value of a for a rectangular column in square bearing equals $\frac{3}{3,200}$.

Substituting the known values in formula 16 gives $u = \frac{80,000}{1 + \frac{3 \times 240^2}{3,200 \times 12^2}} = 58,182$ lb. per sq. in. The net area of the column is $12^2 - 10^2$

= 44 sq. in., and as the factor of safety is 6, the safe load of the column equals $\frac{58,182 \times 44}{6} = 426,068$ lb. Ans.

(12) (a) and (b) See Art. 36.

(13) See Art. 38.

(14) See Art. 40.

(15) See Art. 42.

(16) See Art. 45.

(17) The area resisting shear is $(5 \times 1) + (5.5 \times 1) = 10.5$ sq. in., $\frac{1}{4}$ in. having been deducted from the vertical height of the bracket. The total safe resistance against shear equals $\frac{10.5 \times 18,000}{4} = 47,250$ lb.

From the formula in the table *Elements of Usual Sections*, in *Properties of Sections*, the distance of the neutral axis from the top of the flange is $\frac{d^2 t + s^2 (b - t)}{2 A}$. Substituting the following

values in the formula: $d = 6.5$, $t = 1$, $s = 1$, $b = 5$, and $A = 10.5$, $c_1 = \frac{(6.5^2 \times 1) + 1^2 \times (5 - 1)}{2 \times 10.5} = 2.202$ in., and $c = 6.5 - 2.202 = 4.298$

in. From the same table, the moment of inertia of the section is $I = \frac{t c^2 + b c_1^2 - (b - t)(c_1 - s)^2}{3}$, and by substitution,

$$I = \frac{(1 \times 4.298^2) + (5 \times 2.202^2) - (5 - 1) \times (2.202 - 1)^2}{3} = 41.95$$

According to formula 23, the allowable unit stress for direct compression is $s_{ca} = \frac{31,000 \times 41.95}{10 \times 4.298 \times .4} = 7,563$ lb. per sq. in. and the total safe load is $7,563 \times 10.5 = 79,412$ lb., which is greater than the shearing strength. Consequently, the safe load is 47,250 lb. Ans.

(18) The safe shearing strength of the bracket is found, as in the previous example, by multiplying the safe unit stress by the sectional area of the bracket, or $\frac{18,000}{4} \times 10.5 = 47,250$ lb. Ans.

(19) (a) and (b) See Art. 46.

(20) See Art. 47.

(21) Assuming an outside diameter of 12 in., and substituting the various values in formula 16, it is found that $u = \frac{80,000}{1 + \frac{1}{800} \times \frac{264^2}{12^2}} = 49,844$ lb. per sq. in. The factor of safety being 6, the safe load

will be $\frac{49,844}{6} = 8,307$ lb. per sq. in. The cross-sectional area of a column of the assumed diameter is $12^2 \times .7854 - 10^2 \times .7854 = 34.56$ sq. in. Therefore, the total safe load will be $8,307 \times 34.56 = 287,090$ lb. The total load to be supported is 143 tons, or 286,000 lb.; therefore, a column of the assumed size has sufficient strength to resist the applied load, and the diameter of 12 in. is satisfactory. Ans.

(22) (a) See Art. 24 and Fig. 9 (b), (c), (d), or (g).

(b) See Fig. 9 (l).

(23) See Art. 43 and Table V.



COLUMNS AND STRUTS

(PART 2)

(1) (a) and (b) See Art. 2.

(2) In Table VII, the value of r for this section is found to be 3.04. Substituting the various values in the formula $u = \frac{50,000}{1 + \frac{r^2}{18,000}}$ in

Table I, $u = \frac{50,000}{1 + \frac{216^2}{18,000 \times 3.04^2}} = 39,050$ lb. per sq. in. Multiplying

this value by the area of the section, 20 sq. in., also found in Table VII, and dividing the quotient by 4, the factor of safety, the bearing strength is found to be $\frac{39,050 \times 20}{4} = 195,250$ lb. Ans.

(3) The value of r is found from Table V to be 1.69 and the total area of the section, 13.12 sq. in. The length of the strut equals $20 \times 12 = 240$ in. Substituting these values in the formula for fixed ends, in Table I, $u = \frac{50,000}{1 + \frac{240^2}{36,000 \times 1.69^2}} = 32,047$ lb. Dividing this

value by the factor of safety, 4, the safe unit strength of the strut is found to be $\frac{32,047}{4} = 8,012$ lb., and multiplying by the area of the section, the safe strength is $8,012 \times 13.12 = 105,117$ lb. Ans.

(4) Substituting the values in formula 18, $F = 3 + .015 \times \frac{264}{2.98} = 4.33$. Ans.

(5) See Art. 3.

(6) See Art. 16.

(7) According to Table V, $S = 73.37$. Substituting the values of W , and v in formula 15, $S_c = \frac{24,000 \times 8}{73.37} = 2,616.8733$ lb. The area of the section is, according to Table V, 18.94 sq. in. Therefore, the total stress on the section is $2,616.8733 \times 18.94 = 49,564$ lb. Ans.

(8) The unit stress due to both loads may be found by the formula $s_v = \frac{W_v + W'_v}{A}$. Substituting the various values,

$$s_v = \frac{320,000 + 24,000}{18.94} = 18,162 \text{ lb.}$$

Adding this value to the unit stress found in the previous example, the total unit stress is found to be $18,162 + 2,617 = 20,779 \text{ lb.}$ Ans.

(9) Table II shows that the value of C around the axis XX varies from 1.60 to 1.75. As the column is large, 1.75 may be assumed.

According to Art. 18, $k = \frac{v}{c}$, and substituting the various values in formula 16, W_v is found to be $\frac{4}{5} \times \left(172 + \frac{12 \times 1.75 \times 8}{6} \right) = \frac{800}{5} = 160$.

Table XIV shows that a column of this section and length will sustain a load of only 80 tons; the thickness of the plate and angles must therefore be increased to $\frac{3}{4}$ in. before the column will be of sufficient strength. Ans.

(10) The length of the column $= 24 \times 12 = 288 \text{ in.}$ and r , according to Table VII, equals 4.25. Substituting these values in formula 6,

$$u = 54,000 - 225 \times \frac{288}{4.25} = 38,754 \text{ lb.}$$

With a factor of safety of 4, the allowable fiber stress for direct compression is $s_{ca} = \frac{38,754}{4} = 9,688 \text{ lb.}$

On consulting Art. 18, it is seen that s_d , which equals the allowable unit stress for combined compression and bending, is 1.25 s_{ca} ; therefore, $s_d = 9,688 \times 1.25 = 12,110 \text{ lb.}$ Ans.

(11) According to Table IX, r , for this column, is equal to 3.74 and the area $= 34.8 \text{ sq. in.}$ Substituting the values in formula 2,

$$u \text{ is equal to } 60,000 - 230 \times \frac{216}{3.74} = 46,717 \text{ lb.}$$

This value divided by the factor of safety, 5, gives the safe unit load as $\frac{46,717}{5} = 9,343 \text{ lb.,}$

which, multiplied by the area, gives the total safe load, $9,343 \times 34.8 = 325,136 \text{ lb.}$ Ans.

(12) According to Table XI in *Properties of Sections*, $r = 1.24$, and the area $= 4.8 \text{ sq. in.}$ Substituting the various values in formula 1,

$$u = 60,000 - 210 \times \frac{144}{1.24} = 35,613 \text{ lb.}$$

Dividing by the factor of safety and multiplying by the area, the safe load equals $\frac{35,613}{4} \times 4.8 = 42,734 \text{ lb.}$ Ans.

(13) Use Fig. 18 as a basis for the construction.

(14) See Fig. 30.

(15) See Fig. 27.

DETAILS OF CONSTRUCTION

- (1) See Art. 3.
- (2) (a) and (b) See Art. 9.
- (3) See Art. 10.
- (4) See Art. 13.
- (5) See Art. 24.
- (6) See Art. 25.
- (7) See Art. 24.

(8) According to Arts. 15 and 16, the safe compressive strength of the material is $15,000 \times \frac{13}{15} = 13,000$ lb., and the shearing strength of the rivets is $13,000 \times \frac{5}{6} = 10,833$ lb. The area of the section of a $\frac{3}{4}$ -in. rivet is .442 sq. in.; and the total shearing strength of the three rivets, each of which is in double shear, is $3 \times .442 \times 10,833 \times 2 = 28,729$ lb. The two outside plates are in ordinary bearing and their bearing value is $1\frac{1}{2} \times 13,000 = 19,500$ lb. (See Art. 15.) There are three rivet holes in each plate, each with a bearing area of $\frac{3}{8} \times \frac{3}{4} = .281$ sq. in.; the total bearing strength of the two plates is, therefore, $19,500 \times .275 \times 3 \times 2 = 32,175$ lb. The bearing value of the central or web-bearing plate at one rivet hole is $2 \times 13,000 = 26,000$ lb. per sq. in., and the bearing area is $\frac{3}{4} \times \frac{3}{4} = .5625$ sq. in. The total bearing strength for the three rivets is, therefore, $26,000 \times .5625 \times 3 = 43,875$ lb. The safe tensile strength of the central plate is equal to its net section multiplied by 15,000, the safe unit tensile strength of the material. The net width of the plate is $3 - \frac{7}{8} = 2\frac{1}{8}$ in., and its net area is $2\frac{1}{8} \times \frac{3}{4} = 1.594$ sq. in.; therefore, the safe strength is $1.594 \times 15,000 = 23,910$ lb. The strength of the two outside plates, calculated in the same manner, is also 23,910 lb. As the two latter

values are smaller than either the strength of the rivets or the bearing value of the plates, the safe strength of the joint is 23,910 lb. Ans.

- (9) See Art. 15.
- (10) See Arts. 22 and 24.
- (11) See Art. 28.
- (12) See Art. 32.
- (13) See Arts. 32 to 35, inclusive.
- (14) Rearrange the members and calculate the bending moments of the various combinations according to Art. 35.
- (15) (a), (b), and (c) See Art. 5.
- (16) (a) and (b) See Art. 8.
- (17) See Art. 28.
- (18) See Art. 37.

GRAPHICAL ANALYSIS OF STRESSES

(PART 1)

(1) (*a*), (*b*), and (*c*) See Art. 2.

(2) (*a*) and (*b*) See Art. 2.

(3) See Art. 4.

(4) See Fig. 1.

(5) See Fig. 2.

(6) See Fig. 3.

(7) See Fig. 4.

(8) See Arts. 16 and 17.

(9) See Fig. 5.

(10) See Fig. 6.

(11) See Fig. 7.

(12) (*a*), (*b*), and (*c*) See Art. 25.

(13) (*a*) and (*b*) See Art. 27.

(14) See Art. 29.

(15) See Art. 30.

(16) Find the sum of the moments about the upper point, as follows:

$$\begin{array}{rcl}
 500 \times 32 & = & 16000 \text{ ft.-lb.} \\
 1,000 \times 24 & = & 24000 \text{ ft.-lb.} \\
 1,000 \times 16 & = & 16000 \text{ ft.-lb.} \\
 1,000 \times 8 & = & 8000 \text{ ft.-lb.} \\
 \hline
 \text{Total} & & 64000 \text{ ft.-lb.}
 \end{array}$$

$$\text{and } R_s = \frac{64,000}{20} = 3,200 \text{ lb.}$$




FIG. 1




FIG. 2




FIG. 3




FIG. 4





FIG. 5







FIG. 7



To ascertain the amount of R_1 , the resultant of R_2 and the total load of 3,500 lb., consider 3,200 and 3,500 as the two sides of a right triangle, the hypotenuse will give the reaction R_1 , both as to magnitude and direction. The hypotenuse may be found by means of the equation, $R_1 = \sqrt{3,200^2 + 3,500^2} = 4,742$. The force of 3,500 lb. being the vertical side of the triangle, the angle between this side and the hypotenuse may be found by means of the equation $\tan x = \frac{3,200}{3,500}$ from which x is found to be $42^\circ 20'$, the inclination of R_1 from the vertical.

(17) See Fig. 8.

(18) See Fig. 9.

(19) See Art. 38.

(20) See Art. 41.

GRAPHICAL ANALYSIS OF STRESSES

(PART 2)

(1) See Fig. 1.

(2) See Fig. 2. Draw the load line, as indicated, and connect a and j , thus ascertaining the direction and amount of the reactions. To ascertain the position of the point z , calculate the amount of the reaction R_2 by taking moments about the point c . The moments of the various forces will then be:

Moment of AB	$= 1,200 \times 0$	$= 00000$ ft.-lb.
Moment of BC	$= 2,400 \times 8.7$	$= 20880$ ft.-lb.
Moment of CD	$= 2,400 \times 17.4$	$= 41760$ ft.-lb.
Moment of DE	$= 2,400 \times 26.1$	$= 62640$ ft.-lb.
Moment of EE_1	$= 1,200 \times 34.8$	$= 41760$ ft.-lb.
Moment of E_1F	$= 500 \times 30.0$	$= 15000$ ft.-lb.
Moment of FG	$= 1,000 \times 37.5$	$= 37500$ ft.-lb.
Moment of GH	$= 1,000 \times 45.0$	$= 45000$ ft.-lb.
Moment of HI	$= 1,000 \times 52.5$	$= 52500$ ft.-lb.
Moment of IJ	$= 500 \times 60.0$	$= 30000$ ft.-lb.

Total = 347040 ft.-lb.

The leverage of R_2 is found by drawing a line through the right-hand end of the truss, parallel with aj , representing the direction of R_2 , and drawing a perpendicular from the point c to this line. This perpendicular will be the leverage of R_2 and is found to measure 55.7 ft. Dividing 347,040 by 55.7 gives $R_2 = 6,230$ ft. This length measured off from j on the load line determines the position of the point z and consequently also the value of R_1 , or za . The stress diagram can now be constructed as indicated.

(3) The stress diagram may be drawn as shown in Fig. 3, no difficulty being encountered until the joint $DETSRQ$ is reached. The point w is located by drawing the polygon of forces for the joint $FGXW$; the lines el , fw , and wv may then be drawn in the




FIG. 1

proper directions, although their lengths are not known. The directions of the lines fw , wv , fs , and vs are known but their location is not determined. Draw in the dotted lines $f'u'$, $u'v'$, $f's'$, and $v'12'$, as





FIG 3






FIG. 8



(4) It is necessary to determine the reactions by drawing an equilibrium polygon, or R_1 , may be calculated as follows: The moments about the left reaction are

$$2,000 \times 7.45 = 14,900 \text{ ft.-lb.}$$

$$2,000 \times 14.91 = 29,820 \text{ ft.-lb.}$$

$$2,000 \times 22.36 = 44,720 \text{ ft.-lb.}$$

$$2,000 \times 29.81 = 59,620 \text{ ft.-lb.}$$

$$1,000 \times 37.27 = 37,270 \text{ ft.-lb.}$$

$$1,000 \times 39.51 = 39,510 \text{ ft.-lb.}$$

$$1,000 \times 46.96 = 46,960 \text{ ft.-lb.}$$

$$800 \times 16.67 = 13,336 \text{ ft.-lb.}$$

$$800 \times 21.67 = 17,336 \text{ ft.-lb.}$$

$$\text{Total moment} = 303,472 \text{ ft.-lb.}$$

Then $R_1 = 303,472 \div 80 = 3,793$ lb. Lay off the load line in the stress diagram, as shown in Fig. 4, and from h draw hz vertically, making it equal to 3,793 lb. Join z and a ; then za represents the amount and direction of the left-hand reaction. The stress diagram may be drawn without difficulty until the joint $DETSRQ$ is reached. The point w is located by drawing the polygon of forces for the joint $11GXW10$, when the lines et , fu , and wv may be drawn in their proper directions. The point s may then be located as explained in connection with Fig. 3 and the diagram completed as shown.

(5) Calculate the moments and ascertain R_1 ; then locate the point z and lay out the stress diagram in the usual manner. See Fig. 5.

(6) See Fig. 6 (a) and (b).

(7) (a) See Fig. 7 (a). Imaginary forces H_1 and H_2 must be introduced in order to counteract the rotary tendency of the member BZ about the joint BC, CIZ and the member GZ about the joint MFF, GZ . The amounts of these horizontal forces are found by taking moments about the joints BC, CIZ and MFF, GZ . The moment of AB is equal to $1,200 \times 6.5 = 7,800$ ft.-lb. Opposed to this moment is that of the reaction R_1 (one-half of the total load), which amounts to $5,900 \times 6.5 = 38,350$ ft.-lb. The difference between these moments is $38,350 - 7,800 = 30,550$ ft.-lb. and this moment must be balanced by H_1 . As the leverage of the latter is 11.26 ft., the force H_1 will be $\frac{30,550}{11.26} = 2,713$ lb. To prevent the rotary tendency of H_1 , the force CD_1 must be introduced, the amount of which is ascertained by taking moments about the joint BC, CIZ . The amount of CD_1 is then $\frac{2,713 \times 11.26}{5.6} = 5,455$ lb., and $BC_1 = 2,713 + 5,455 = 8,168$ lb. The same method is pursued in calculating the forces E, F and F, G . The necessary information is now at hand for laying out the load line and stress diagram.

(b) See Fig. 7 (b). To draw the stress diagram for the wind load, take moments about the point c as follows:

$$\text{Moment } AB = 1,800 \times 0 = 00000 \text{ ft.-lb.}$$

$$\text{Moment } C, C = 2,700 \times 13.0 = 35100 \text{ ft.-lb.}$$

$$\text{Moment } D, D = 2,700 \times 19.5 = 52650 \text{ ft.-lb.}$$

$$\text{Moment } DE = 1,400 \times 40.0 = 56000 \text{ ft.-lb.}$$

$$\text{Total} = 143750 \text{ ft.-lb.}$$








FIG. 5

The leverage of R_1 being 20 ft., the right-hand reaction R_2 = $\frac{143,750}{20} = 7,188$ lb. The sum of the loads is 8,600 lb and R_1 will therefore be equal to $8,600 - 7,188 = 1,412$ lb. The difference between the reaction R_1 and the load of 1,800 lb. at this point is 388 lb. Lay off this value in the diagram (a) as shown, and find the horizontal force required at this point. This force is found to be 450 lb. In the same manner, find the corresponding horizontal force at the other leg by constructing



Scale, 1" = 400 lb.

(a)



Scale, 1" = 400 lb.

(b)

FIG. 6

8 GRAPHICAL ANALYSIS OF STRESSES § 27

the diagram (b), from which it is found that GX equals 4,150 lb. To find the horizontal force CD , required to balance AV , take moments around the joint BC , CIZ as follows: $CD_1 = \frac{450 \times 11.26}{5.63}$







FIG. 10


$= 900 \text{ lb.}$ $BC_1 = 900 + 450 = 1,350 \text{ lb}$ In the same manner, EF is found to be $\frac{4,190 \times 11.26}{5.63} = 8,380 \text{ lb.}$, and $FG = 8,380 + 4,190 = 12,570 \text{ lb.}$ The stress diagram may now be laid out as shown.





Scale 1/8" = 500 lb

(a)

FIG





Scale, 1" = 450 lb.





(8) It is understood that the right-hand end of the truss is supported by a roller bearing; R_2 will therefore act in a vertical direction and may be calculated as shown previously by taking moments around the left-hand end of the truss. The value found for R_2 is laid off on the load line and thus z is located, after which the stress diagram is laid out in the usual manner. See Fig. 8.

(9) See Fig. 9 (*a*), (*b*), (*c*), (*d*), (*e*), and (*f*).

(10) See Art. 24.

(11) See Fig. 10. Take moments around the joint $DEMLK$.

$$\text{Moment of } AB = 1,000 \times 21 = 21\,000 \text{ ft.-lb.}$$

$$\text{Moment of } BC = 2,000 \times 14 = 28\,000 \text{ ft.-lb.}$$

$$\text{Moment of } CD = 2,000 \times 7 = 14\,000 \text{ ft.-lb.}$$

$$\text{Moment of } QZ = 1,500 \times 7 = 10\,500 \text{ ft.-lb.}$$

$$\text{Total} = 73\,500 \text{ ft.-lb.}$$

The moment of $QA = 7,500 \times 21 = 157,500$. Considering the latter moment positive and the others negative, their algebraic sum will be $157,500 - 73,500 = 84,000$ ft.-lb., which must equal the moment of LZ about the same point. As the lever arm of the latter is 11 ft. the stress in LZ must equal $\frac{84,000}{11} = 7,636$ lb.

(12) See Arts. 38, 39, and 40.

(13) See Fig. 10. The truss being symmetrically loaded, R_1 is equal to R_2 , each being one-half of the total load, or $\frac{15,000}{2} = 7,500$ lb. In laying out the load line, measure off the forces AB to GH in the usual manner. Then lay off HP , or R_2 , from h to p , pz from p to z , and zq from z to q ; the distance qa will be equal to R_1 , or QA .

INDEX

NOTE.—All items in this index refer first to the section and then to the page of the section. Thus, "Aluminum 8 9" means that aluminum will be found on page 9 of section 8.

A		<i>Sec. Page</i>				<i>Sec. Page</i>	
"A" type of truss	27	74	Beam, Finding dimensions of steel	13	23		
Accidental and suddenly applied loads	5	27	" " ultimate resisting moment of	13	1		
Acidic rocks	8	22	" hangers	13	13		
Aggregation of particles of rock	8	34	" " Tests made on	13	18		
Alabaster	8	42	" Indented	13	12		
Aluminum	8	9	" Keyed	13	11		
Amphibole and pyroxene groups of minerals	8	18	" Relation between span and depth of	13	27		
Analysis of riveted joints	25	13	" Shear in simple	12	18		
" " stresses, Graphical	26	1	Beams, Adaptability of reenforced concrete	13	47		
Angle columns, Properties of steel plate and	16	51	" and girders	12	1		
Angles, Explanation of flange	14	1	" " "	13	1		
" Maximum size of rivets in	25	3	" " "	14	1		
Application of graphical analysis	26	37	" " " Practical design of	14	52		
Arch bricks	8	43	" " " Principles of design of	14	4		
Area, Elementary	6	10	" " " Stresses in	14	4		
Areas to be deducted from riveted plates to obtain net areas	25	16	" Bending moments in simple	12	25		
Argillaceous stone	8	39	" Built-up wooden	13	9		
Arm, Power	12	7	" Connections for steel	13	30		
" Weight	12	7	" Continuous	12	37		
Ash	9	5	" Deflection of	12	40		
Assembled designs	16	44	" Details of design of wooden	13	13		
Atom, Explanation of	8	3	" Durability of reenforced concrete	13	47		
Atomic weight	8	5	" Efficiency of built-up	13	12		
Axis, The neutral	6	3	" Elements of	12	1		
B			" General notes relative to wooden	13	4		
Bars for Kahn system of concrete construction	13	66	" in heavy wooden construction	13	19		
" Spacing of lattice	16	33	" Lateral strength of	13	34		
Basalt	8	23	" Obtaining fiber stress of	13	34		
"	8	38	" " horizontal thrust of	13	35		
Bases, Column	15	38	" over equal spans, Bending moments for continuous	12	38		
Basic rocks	8	22					
Beam connections	15	49					
" Definition of	12	1					
" " " continuous	12	1					
" " " fixed	12	1					
" " " simple	12	1					

	No.	Page		No.	Page
Beams, Reinforced concrete	13	47	Bricks, Cherry	8	43
" Steel	13	21	" Soft	8	43
" Stresses in	12	17	" Strength of	8	56
" Table of efficiency of built-up wooden	13	12	Brickwork in cement mortar, Cost of	8	71
" " " formulae for deflection of	12	44	" lime mortar, Cost of	8	71
" " " maximum size of rivets in	25	8	" Strength of	8	56
" Transverse strength of steel	13	22	Buckling of web plate and distribution of stiffeners	14	7
" Wooden	13	8	Building laws, Comparison of	15	28
" steel and reinforced concrete	13	1	" regarding foundation soils	7	15
Bearing capacity of soils, Determination of	7	3	" stone, Durability of	8	19
of plates, Ordinary	25	15	" Physical properties of	8	32
plates	13	44	" Physical structure of	8	30
" for I beams and channels	13	45	" stones and masonry, Strength of	8	55
value of a pin	25	42	" Selection of	8	54
" " foundation soils	7	14	Built up beams, Efficiency of	13	12
" " riveted plates	25	24	" " girders	14	1
" " rivets on plates	25	15	" " wooden beams	13	9
" values of pin plates	25	43	" " " Efficiency of	13	12
Beech	8	7	Butt joint	25	13
Bending moment	12	23	" " with single cover-plate	25	20
" moment and shear, Graphic method of obtaining	12	32	" " " two cover-plates	25	20
" moment, Graphic method of obtaining	25	41	Button rivet heads	25	3
" moments and safe loads, Formulas for maximum	12	24	Buttonwood	9	7
" " for continuous beams over equal spans	12	38			
" " in simple beams	12	25	Calcareous rocks	8	27
" " on beams Formulas for maximum	12	30	" stones	8	40
" " on pins, Maximum	25	37	Calcite group of minerals	8	16
" stress Columns under	12	25	Calcium	8	10
" stresses	12	23	Cambered girders	14	57
" " on pins	25	35	" truss, Diagram for	27	32
Black spruce	8	2	Cantilever, Definition of	12	1
Body bricks	8	43	Caps, Column	15	21
Bracing of girders, Lateral	11	87	Carbon	8	11
Brackets, Design of cast iron	15	40	Carolina pine	9	2
" Strength of cast iron	15	44	Castings, Inspection of	15	49
Brecciated marbles	8	41	Cast iron brackets, Design of	15	40
Bricks	8	42	" " " Strength of	15	44
" Arch	8	43	" " column, Obtaining safe load per square inch of	15	29
" Body	8	43	" " columns	15	25
			" " " Design of	15	32
			" " " Dimensions of standard connections to	15	45
			" " " Formulas for	15	26
			" " " Objections to use of	15	25
			" " " Sections of	15	38

INDEX

ix

	<i>Sec.</i>	<i>Page</i>		<i>Sec.</i>	<i>Page</i>
Cedar, Red	9	3	Column caps	15	21
" White	9	3	" Conditions affecting choice		
Cement	8	63	of	16	3
" and lime mortar	8	69	" connections	15	35
" mortar	8	67	" formulas	15	7
" " Cost of brickwork			" Safe loads for steel, lat-		
in	8	71	ticed, channel	16	62
" Natural-rock	8	63	" sections, Different	16	31
" Portland	8	63	" splices and connections	16	35
Cements, Strength of	8	56	Columns and posts, Timber	15	10
Center of gravity	6	1	" " struts	15	1
" " " of a body	6	1	" " " 	16	1
" " " " an irregular			" Approximate values of		
four-sided			<i>C</i> for various	16	21
figure	6	2	" Cast-iron	15	25
" " " " parallelo-			" Classification of steel	16	1
grams	6	2	" Design of cast-iron	15	32
" " " " plane figures	6	1	" " " steel	16	31
" " " " triangles	6	2	" Dimensions of standard		
" " moments	12	2	connections to cast-		
Centric pressure on columns	13	85	iron	15	45
Chalcedonic quartz	8	15	" Fixed-end	16	3
Chalk	8	41	" Flat-end	16	3
Channel column, Safe loads for			" for power houses and		
steel, latticed	16	62	shops	16	47
" columns, Properties of			" Forms of steel	16	3
steel	16	53	" Formulas for steel	16	9
" columns with cover-			" frequently used in skele-		
plates, Safe loads for			ton building construc-		
steel	16	72	tion	16	7
" Obtaining approximate			" Hinged-end	16	2
section modulus of a	13	22	" in general	15	3
Channels, Maximum size of rivets			" Long	15	12
in	25	3	" Method of failure of long	15	5
Characteristics of foundation soil	7	4	" " " of short	15	5
" " iron and steel	9	11	" Objections to use of		
" " timber	9	1	cast-iron	15	25
Chart for safe load, Diagram	15	13	" Properties of steel chan-		
Chemical combination	8	2	nel	16	53
" elements	8	2	" Safe load for steel plate-		
" equivalent	8	5	and-angle	16	70
Chemically precipitated rocks	8	26	" Safe load for steel Z -bar	16	77
Cherry bricks	8	43	" Sections of cast-iron	15	33
Chestnut	9	6	" Short	15	11
Chlorine	8	7	" Stress in	15	3
Cinder concrete	8	46	" under bending stress	16	25
Classification of rocks	8	19	" with concentric loads	16	9
" " steel columns	16	1	" " cover-plates, Safe		
Clay	7	6	load for steel		
" rocks	8	26	plate-and-angle	16	71
Clearance	16	33	" " cover-plates, Safe		
" for tools in forming rivet			load for steel Z -		
heads	25	11	bar	16	78
" Rivet	25	4	" " eccentric loads	16	17
Color of rock	8	35	" " eccentric loads,		
Column bases	15	38	Strength of	16	18

	Ser	Page		Ser	Page
Columns with fixed ends	16	16	Continuous beams over equal spans, Reactions for	12	39
" " flat ends or fixed at one end and pin-connected at the other	16	14	Contraflexure	12	37
" " hinged ends	16	13	Coplanar and non-coplanar forces, Definition of	26	2
" " several eccentric loads	16	24	Cost of brickwork in cement mortar	8	71
Combination by weight	8	4	" " in lime mortar	8	71
Chemical	8	2	" " reinforced and other good construction, Comparison of	12	49
Common minerals	8	13	" " rubble masonry in lime mortar	8	71
Comparison of building laws	15	26	Countersunk rivet heads	25	3
Complete equilibrium	26	3	Couple	26	3
Complex frames, Diagrams for	27	40	Crescent truss of large span	27	62
Composition of forces	26	6	" " small span	27	56
Compounds, Elements and	8	1	Crucible process of steel manufacture	9	14
Computing the moment of inertia	6	11	Crushing strength of rock	7	4
Concentrated loads, Graphic diagram for several	14	27	Culm	7	13
" loads with a uniformly distributed load, Combination of	14	30	Cypress	9	4
Concentric loads, Columns with	16	9			
Concrete	8	44	D		
beams, Durability of reinforced	13	47	Dead load	5	1
" " Reinforced	13	47	" " diagram	27	19
" " Wooden, steel, and reinforced	13	1	" " on roof trusses	5	7
Cinder	8	46	Deflection	12	42
construction, Details of reinforced	13	50	of beams	12	40
" construction, Governmental regulations for reinforced	13	79	" " Formulas for	12	44
" construction, Hennebique system of	13	59	Density of stone	8	32
" construction, Ransome system of	13	57	Depth of beam, Relation between span and	13	27
" construction, Rigidity of reinforced	13	49	" " girder	14	4
" Molding the	13	81	Design of a pin	25	44
" Stone and	8	45	" " riveted joint	25	26
" Strength of	8	56	" " beams and girders, Practical	14	52
Concurrent forces, Definition of	26	2	" " beams and girders, Principles of	14	4
Conglomerate	8	25	" " cast-iron brackets	15	40
Connections, Column splices and	16	35	" " columns	15	32
" for steel beams	13	30	" " pin, Details of	25	47
Construction, Skeleton	5	31	" " steel columns	16	31
" The practice of	13	78	" " wooden beams, Details of	13	13
Continuous beam, Definition of	12	1	Designs, Assembled	16	44
beams	12	37	Details of construction	25	1
" beams over equal spans, Bending moments for	12	38	" " design of pins	25	47
			Deterioration of material	9	17
			Determination of external forces	26	46
			" " internal stresses	26	63
			" " the kind of stress	26	66
			Determining the reactions by calculations	26	47

INDEX

xi

	<i>Ser.</i>	<i>Page</i>		<i>Ser.</i>	<i>Page</i>
Determining wind pressure on truss with curved or broken upper chord	27	58	Elasticity	12	40
Diabase rocks	8	22	" Modulus of	12	41
Diagram chart for safe load . . .	15	13	Elementary area	6	10
" Dead-load	27	19	Elements and compounds	8	1
" for a combination of concentrated loads with a uniformly distributed load	14	30	" Chemical	8	2
" " a jib crane	27	5	" Gaseous	8	6
" " a small roof truss . .	27	3	" of beams	12	1
" " cambered truss	27	32	" Solid	8	8
" " vertical loads	27	50	Elongation, Ultimate	9	8
" Frame	26	41	English oak	9	5
" Wind-load	27	23	Equilibrium	26	2
" " 	27	29	" 	26	14
" " stress	27	53	" at the joints of a structure	26	15
Diagrams for complex frames . .	27	40	" Complete	26	3
" " simple frames	27	1	" of moments	12	3
" " stresses	26	41	" " the entire frame . .	26	20
" Notation for	26	44	" " translation	26	3
Diameter of rivet hole	25	2	" polygon, The force and	26	21
Diatomaceous earth	8	27	" Rotary	26	3
Dikes	8	23	" Stable	26	14
Dimensions of rivet heads	25	3	" Unstable	26	14
" of standard connections to cast-iron columns	15	45	Eruptive rocks	8	21
" of standard Z-bar columns, Properties and	16	59	Euler's and the parabolic formulas	15	30
Diorite rocks	8	22	" " " " " 	16	11
Disposition of loads, The	5	30	" formula	15	8
Dolomite or magnesian limestone	8	16	Examination of soils	7	1
Dolorite	8	23	External force, Definition of . .	26	2
Duplex hanger	13	17	" forces, Determination of	26	46
Durability of building stone . . .	8	49			
E			F		
Earth, Diatomaceous	8	27	Factor of safety	9	17
" Infusorial	8	27	" " " 	15	17
Eccentric loads, Columns with . .	16	17	" " " 	15	81
" " Columns with several	16	24	" " " for different materials	9	18
" " Formulas for	16	20	" " " for wood	13	5
" pressure on columns . .	13	85	Factors of safety	16	27
Effect of a force	26	4	" " " 	16	28
" " quarrying and finishing stone	8	52	Failure of long columns, Method of	15	5
" " the moments due to loads	12	25	" " pins, Methods of	25	83
Efficiency of built-up beams . . .	13	12	" " short columns, Method of	15	5
" " section	16	34	Feldspar group of minerals	8	15
Elastic limit	12	40	Felsite	8	22
			Fiber stress of beams, Obtaining the	13	34
			Filler, or packing piece, Explanation of	14	2
			Fink roof truss	27	40
			" truss with cambered tie-member	27	50
			Firebrick	8	44
			Fireproof floors, Weight of	5	1

	Sec.	Page		Sec.	Page
Fire-stones	8	49	Formulae for computing the area,		
Masses, Formation of	8	32	moment of inertia,		
in rocks, joints and	8	31	section modulus, and		
Fixed beam, Definition of	12	1	radius of gyration of		
" end columns	16	8	usual sections	8	23
Flange angles, Explanation of	14	1	" for deflection of beams	12	44
" plate, Explanation of	14	1	" for eccentric loads	16	20
" plates, Graphic method			" for Kahn system of re-		
of determining			inforced concrete	13	65
length of	14	20	" for maximum bending		
" Lengths of	14	17	moments and safe		
" stresses	14	13	loads	12	35
Flanges of girders	14	11	" for moment of inertia		
" Proportioning the	14	15	of standard rolled		
Flat end columns	16	3	sections	4	28
Flattened rivet heads	25	2	" for steel columns	16	9
Fitch-plate girders	13	6	" Parabolas	15	15
Floor, roof, and wind loads	5	1	Foundations soils	7	1
" Weight of fireproof	5	1	" Bearing value of	7	14
Floors, Warehouse	5	12	" Building laws		
Foot's gold	8	18	regarding	7	15
Force and equilibrium polygon, The	26	21	" Characteristics		
" Definition of	26	1	of	7	4
" " external	26	2	" Safe bearing		
" " internal	26	2	values of differ-		
" Effect of a	26	4	ent	7	14
Forces, Definition of concurrent	26	2	Foundations over mines etc	7	13
" " coplanar and			Fragmental, or elastic rocks	8	25
non-coplanar	26	2	Frame diagram	26	41
" " non-concur-			Frames, Diagrams for complex	27	40
rent	26	2	Fulcrum	12	7
" Determination of exter-			Fundamental principles of graphi-		
nal	26	46	cal analysis	26	4
" Moments of	12	1			
" Parallelogram of	26	6	G		
" Resultant of several	26	8	Gaseous elements	8	6
" The composition of	26	6	Georgia pine	9	1
" " resolution of	26	12	Girder, Definition of	12	1
" Triangle of	26	8	" Depth of	14	4
Formation and characteristics of			" Explanation of plate	14	1
rocks	8	13	Girders, Built up	14	1
Forms of steel columns	16	3	" Cambered	14	57
Formula, Euler's	15	8	" Detail design of	14	63
" for approximate weight			" Flanges of	14	11
of wooden and iron or			" Fitch plate	13	6
steel roof trusses	5	7	" I-beam	13	29
" Gordon's	16	10	" Lateral bracing of	14	87
" " or Rankin's	15	7	" Size of	13	53
" of general application			" Trussed	14	66
for beams and girders	13	1	" with concentrated loads,		
" Parabolic	15	10	Application of graphic		
" Straight line	16	11	method to	14	24
Formulas, Euler's and the para-			" with one strut	14	57
bolic	16	11	" " two struts	14	59
for cast-iron columns	15	26	" Wooden trussed	14	69
			Gneiss	8	31

	<i>Sec.</i>	<i>Page</i>		<i>Sec.</i>	<i>Page</i>
Gneiss and mica slate	8	37	Hardness of rock	8	33
Goetz hanger	13	13	Hard pine	9	1
Gold, Fool's	8	18	Hardwood	9	4
Gordon's formula	15	26	Header	13	4
" "	16	10	Heads, Rivet	25	3
" " for rectangular posts	15	12	Hematite	8	18
" or Rankin's formula	15	7	Hemlock	9	3
Grain of rock	8	35	Hennebique system of concrete construction	13	59
Granitic rocks	8	21	Hickory	9	5
Graphic diagram for several concentrated loads	14	27	Hinged-end columns	16	2
" method of determining length of flange plates	14	20	Horizontal thrust of beams, Obtaining the	13	35
" method of determining stresses	14	61	Howe roof truss	27	8
" method of obtaining bending moment	25	41	" truss	14	67
Graphical analysis, Application of	26	37	Hydrogen	8	7
" analysis, Fundamental principles of	26	4			
" analysis of stresses	26	1	I		
" " "	27	1	I-beam girders	13	29
" method of locating the neutral axis	6	7	" " Obtaining the approximate section modulus of an	13	22
" method of obtaining bending moment and shear	12	32	" beams and channels, Bearing plates for	13	45
" method of obtaining the reactions	26	55	" " Minimum spans for	13	32
" method of the parallelogram of forces	26	7	" " Properties of standard	6	28
" methods of computing moments of inertia	6	13	" " Safe loads for steel	16	66
" solutions, Scope of	26	37	" " Separators for	13	27
" statics by the method of sections	26	69	Igneous rocks, Unstratified, or	8	20
Gravel	7	5	Inches, Resisting	13	1
Gravity, Center of	6	1	Indented beam	13	12
" of a body, Center of	6	1	Infusorial earth	8	27
" " plane figures, Center of	6	1	Inspection of castings	15	49
" Specific	8	6	Intercalary beds	8	24
Greenstone	8	38	Internal force, Definition of	26	2
Gypsum	8	18	" stresses, Determination of	26	63
"	8	42	Intrusive rocks, Trappean, or	8	22
Gyrations, Radius of	6	21	Iron	8	9
			" and steel, Characteristics of	9	11
II			" Ores of	8	18
Halite, or salt	8	19	" Spathic, or siderite	8	17
Hammer-beam truss	27	65			
Hanger, Duplex	13	17	J		
" Goetz	13	13	Jaspery cryptocrystalline quartz	8	15
" Stirrup iron	13	15	Joint, Lap	25	13
" Van Dorn	13	13	Joints, Analysis of riveted	25	13
Hangers, Beam	13	13	" and fissures in rocks	8	31
" Tests made on beam	13	18	" in compression, Riveted	25	22
			" " tension	25	14
			" Packing of	25	50
			K		
			Kahn system of reenforced concrete	13	63
			Keyed beam	13	11

L		Sec.	Page			Sec.	Page
Lap joint	26	13		Loads, per square foot, Live	5	11	
Lateral bracing of girders	14	87		" Snow and wind	5	19	
" strength of beams	13	34		" The disposition of	5	30	
Lattice bars and stay-plates to be used with latticed channel bars	16	32		Locating the neutral axis, Graphical method of	6	7	
" " Spacing of	16	33		Location of neutral axis	6	3	
" truss	14	33		Locust	9	5	
Laws of motion, Newton's three	26	5		Long columns	15	12	
Length of rivets required for various grips	25	4		" " Method of failure of	15	5	
Lengths of flange plates	14	17		" leafed pine	9	1	
Lever arm of the force, Explanation of	12	2		M			
" The	12	7		Magnesian limestone, or dolomite	8	16	
Leverage of the force	12	2		Magnesium	8	10	
Lignum vitae	9	7		Magnetite	8	13	
Lime	8	62		Manganese	8	12	
" Commercial	8	63		Manufacture of steel, Processes of	9	14	
" mortar	8	65		Manufactured stones	8	42	
" " Cost of brickwork in	8	71		Maple	9	5	
" " " rubble masonry in	8	71		Marble	8	40	
Limestone, Magnesian, or dolomite	8	16		Marbles, Brecciated	8	41	
Limestones	8	40		Masonry	8	1	
Limonite	8	18		" materials, Allowable unit stresses for	8	57	
Live load	5	10		" Strength of stones and	8	53	
" loads from floor to floor, Table showing reductions of	5	31		Material Deterioration of	9	17	
" " on floors in different cities, Allowable	5	19		Materials, Factor of safety for different	9	18	
" " per square foot	5	11		" for reinforced concrete construction, Governmental regulations for	13	73	
" " Weights of merchandise for calculating	5	14		" of structural engineering	7	1	
Load, Dead	5	1		" " " engineer- ing	8	1	
" Live	5	10		" " " engineer- ing	9	1	
" on roof trusses, Dead	5	7		" Ultimate strength of	9	16	
" Static	5	12		" Weight of	5	2	
" that will break a beam, Determining the uniformly distributed	13	2		Maximum bending moments and safe loads, Formulas for	12	23	
Loads, Accidental and suddenly applied	5	27		" safe load, Obtaining the	13	36	
" Columns with concentric	16	9		" shear	12	20	
" " " eccentric	16	17		Metals, Timber, and	9	1	
" " " several eccentric	16	24		Metamorphic rocks	8	29	
" Diagram for vertical	27	50		" " Sedimentary and	8	24	
" Effect of the moments due to	12	25		Method by reversal of diagonal	27	44	
" Floor roof, and wind	5	1		" of securing posts in buildings	15	20	
" Formulas for eccentric	16	20		Methods of obtaining one of three unknown forces	27	40	
" for steel I beams, Safe	16	66		Mica group of minerals	8	17	
" in structures	5	1		Minerals, Amphibole and pyroxene groups of	8	18	
" on opposite sides, Wind and snow	27	56					

INDEX

XV

	Sec.	Page
Minerals, Calcite group of	8	16
" Common	8	13
" Feldspar group of	8	15
" Mica group of	8	17
" Orthoclase	8	15
" Plagioclase	8	15
Mixing concrete, Governmental regulations for	13	79
Mixtures	8	6
Modulus of elasticity	12	41
" " rupture of timber	9	8
" Section	6	16
" " 	13	1
Molding the concrete	13	81
Molecule, Explanation of	8	3
Moment, Bending	12	23
" of a force	26	3
" of inertia	6	10
" of inertia, Analytical method of computing the	6	11
" of inertia, Computing the	6	11
" of inertia of rectangular sections, Table of	6	40
" of inertia of standard rolled sections, Formulas for	6	23
" Resisting	6	16
" " 	12	23
" " 	13	1
Moments, Center of	12	2
" due to loads, Effect of the	12	25
" Equilibrium of	12	3
" in simple beams, Bending	12	25
" Method by	27	43
" of forces	12	1
" " inertia, Graphical methods of computing	6	13
" " inertia, Rules and formulas for	6	12
" Positive and negative	12	4
" Resultant and reactionary	12	5
Mortar, Cement	8	67
" Cement-and-lime	8	69
" Lime	8	65
Mortars	8	61
" Comparison of lime and cement	8	70
" Kinds of	8	61
" Table of strength of	8	56
Motion, Newton's three laws of	26	5
Mud, silt, marsh, or semiliquid soils	7	9

	N	Sec.	Page
Natural-rock cement		8	63
Negative moments, Positive and .		12	4
" shear, Positive and . . .		12	20
Neutral axis, Explanation of . . .		6	3
" " Graphical method of locating the		6	7
" " Locating the, by means of the prin- ciple of moments .		6	4
" " Location of		6	3
" " of a section, Finding the		6	5
" " The		6	3
" plane		6	3
" surface		6	3
Newton's three laws of motion . .		26	5
Non-concurrent forces, Definition of		26	2
Northern pine		9	1
Norway spruce		9	3
Notation for diagrams		26	44
Nuts, Standard pins and		25	48
" " screw threads and		25	49

0

Oak, English	9	5
" Red	9	4
" White	9	4
Obsidian	8	23
Oolite	8	28
Open-hearth process of steel manu- facture	9	14
Ordinary bearing of plates	25	15
Ores of iron	8	18
Organic rocks	8	27
Orthoclase minerals	8	15
Overflow sheets	8	23
Oxygen	8	6

P

Packing of joints	25	50
" piece, Explanation of filler, or	14	2
Parabolic formula	15	10
" formulas	15	15
" " Euler's and the	15	30
" " Euler's and the	16	11
Parallelogram, Center of gravity of a	6	2
" of forces	26	6
" of forces, Graphical method of the	26	7
Permanent set	12	40

	Sec	Page		Sec	Page
Phenolite	8	23	Posts in buildings, Method of		
Phosphate rocks	8	27	securing	15	20
Phosphorus	8	12	" Timber columns and	15	10
Physical properties of building			" Ultimate strength per		
stone	8	22	square inch for timber	15	18
structure of building			Potassium	8	11
stone	8	50	Power	12	7
Pin, Bearing value of a	25	42	" arm	12	7
" connections	25	32	Practice of construction	13	74
" Comparison of,			Pratt truss	14	17
with riveted			" "	27	8
connections	25	32	Pressure, Wind	5	20
" Design of a	25	44	Primary rocks	8	30
" plates	25	50	Principle of moments, Locating		
Pine, Carolina	9	2	the neutral axis by means of		
" Georgia	9	1	the	6	4
" Hard	9	1	Principles of graphical analysis,		
" Long-leaved	9	1	Fundamental	26	4
" Northern	9	1	Properties and dimensions of		
" Pitch	9	1	standard Z-bar col-		
" White	9	1	umns	16	59
Pins and nuts, Standard	25	48	" and dimensions of steel		
" Bending stresses on	25	55	Z-bar columns with		
" Calculations for shearing re-			cover plates	16	60
sistance of	25	53	" and principal dimen-		
" Details of design of	25	47	sions of standard		
" Methods of failure of	25	38	T rails	6	39
" Position of	25	47	" of heavy steel channel		
" Rivets and	25	1	columns	16	57
" Shearing values of	25	34	" of sections	6	1
Pitch of rivets	25	7	" of standard angles		
" " " in girders support-			having equal legs,		
ing concentrated			Table of	6	32
loads	14	49	" of standard angles		
" pine	9	1	having unequal legs	6	34
Plagioclase minerals	8	15	" of standard channels	6	30
Plane figures, Center of gravity of	6	1	" of standard I beams	6	28
" Neutral	6	3	" of steel channel col-		
" tree	9	7	umns	16	53
Plant deposits	8	28	" of steel plate-and-angle		
Plaster of Paris	8	42	columns	16	51
Plate-and-angle columns, Safe load			" of steel plate-and-angle		
" " " for steel	16	70	columns with cover-		
" " " columns with cov-			plates	16	52
er-plates, Safe			" of Z bars	6	36
load for steel	16	71	Proportioning the flanges	14	15
" girder, Explanation of	14	1	Pumice	8	23
Plutonic rocks	8	21	Pyroxene groups of minerals,		
Polygon, The force and equilibrium	26	21	Amphibole and	8	18
Porphyry	8	22			
Portland cement	8	63			
Position of pins	25	47			
Positive and negative moments	12	4			
" " " shear	12	20			
Posts, Gordon's formula for rect-					
angular	15	12			

	<i>Sec.</i>	<i>Page</i>		<i>Sec.</i>	<i>Page</i>
Queen-post truss	27	35	Reinforced concrete construction,		
Quicklime	8	42	Rigidity of	13	49
"	8	62	" concrete, General		
Quicksand	7	10	notes on	13	76
			" concrete, Kahn sys-		
			tem of	13	63
			" concrete, Specifica-		
			tion for	13	74
			Reenforcing bars, Johnson's		
			method of calculation of	13	54
			Regulations for reinforced con-		
			crete construction, Governmen-		
			tal	13	79
			Relation between the reactions	12	10
			Resisting inches	13	1
			" moment	6	16
			" "	12	23
			" "	13	1
			" " of a beam,		
			Finding the		
			ultimate	13	1
			Resolution of forces	26	12
			Resultant and reactionary mo-		
			ments	12	5
			" moment of several		
			stresses on pins	25	36
			" of forces	26	4
			" " several forces	26	8
			" reaction	26	4
			" stress, Obtaining the	13	36
			Rift of rock	8	35
			Rivet clearance	25	4
			" distance from end	25	11
			" heads	25	3
			" " Button	25	3
			" " Countersunk	25	3
			" " Dimensions of	25	3
			" " Flattened	25	3
			" " Round	25	3
			" hole, Diameter of	25	2
			" length, or grip	25	4
			" shank required to form one		
			rivet head, Length of	25	5
			" spacing	14	85
			" "	25	7
			" " in flange plates	14	51
			Riveted connections	25	2
			" connections, Comparison		
			of, with pin connections	25	32
			" joint, Design of a	25	26
			" joints, Analysis of	25	13
			" " in compression	25	22
			" plate, Shearing of	25	19
			" plates, Areas to be de-		
			ducted from, to obtain		
			net areas	25	16

	Sec	Page		Sec	Page
Riveted plates, Bearing value of	25	24	Rocks, Plutonic	8	21
" work, Allowable strains on	25	27	" Primary	8	36
Rivets	25	2	" Sedimentary and metamorphic	8	34
" and pins	25	1	" Silicious	8	27
" Bearing value of, on plates	25	16	" Stratified	8	19
" connecting flange angles	14	26	" Trappean, or intrusive	8	22
" with web	25	3	" Unstratified	8	19
" In angles, Maximum size of	25	3	" " or igneous	8	20
" " beams, Maximum size of	25	3	Roof, floor, and wind loads	5	1
" " channels, Maximum size of	25	3	" truss, Fink	27	60
" " compound sections	25	22	" " Howe	27	3
" " end angles or stiffeners	14	35	" " Quadrilateral	27	46
" " over abutments	25	21	" " Scissors	27	14
" " single shapes	14	35	" " with a 40-foot span	27	6
" " stiffeners between abutments	14	43	" trusses, Dead load on	5	7
" " vertical leg of flange angles, Graphic method of determining number of	14	7	" " Formula for approximate weight of wooden and iron or steel	5	7
" Pitch of	25	7	" " Table of weight of with members subjected to transverse stress	27	74
" Pitch of, in girders supporting concentrated loads	14	40	Rotary equilibrium	26	3
" Shearing strength of	25	19	Round rivet heads	25	1
" Shearing value of	25	23	Rubble masonry in lime mortar,		
" Sizes of	25	2	" Cost of	8	71
" spaced according to direct vertical shear	14	42	" Strength of	8	36
" spaced according to stress produced by bending moment	14	40	Rule for obtaining the safe load of a cast-iron column	15	23
" Spacing of	25	7	" for spacing stiffeners, Practical	14	9
Rock, Aggregation of particles of	8	34	" " thickness of web-plate	14	5
" Color of	8	35	" to determine the uniformly distributed load that will break a beam	13	2
" Crushing strength of	7	4	" to find the neutral axis of a section	6	5
" Definition of	8	19	" to find the resultant of several forces	26	8
" Grain of	8	35	" to find the stress in any chord member of a Howe truss	14	72
" Hardness of	8	33	" to find the stress in any chord member of a Warren truss	14	81
" Rift of	8	35	" to find the ultimate resisting moment of a beam	13	1
" Structure of	8	33	" to obtain the approximate section modulus of a channel	13	22
Rocks, Acidic	8	22	" to obtain the approximate section modulus of an I beam	13	22
" Basic	8	22	Rules and formulas for moments of inertia	6	12
" Calcareous	8	27	" for static computation of concrete	13	81
" Chemically precipitated	8	26			
" Classification of	8	19			
" Clay	8	26			
" Eruptive	8	21			
" Formation and characteristics of	8	19			
" Fragmental, or elastic	8	25			
" Granitic	8	21			
" Joints and fissures in	8	31			
" Metamorphic	8	29			
" Organic	8	27			
" Phosphate	8	27			

INDEX

xix

S	Sec.	Page		Sec.	Page
Safe bearing values of different foundation soils	7	14	Sedimentary and metamorphic rocks	8	24
" load, Diagram chart for . . .	15	13	" stones	8	38
" " for steel channel columns with cover-plates	16	72	Selection of building stones	8	58
" " for steel plate-and-angle columns . . .	16	70	Separators for I beams	13	27
" " for steel plate-and-angle columns with cover-plates	16	71	Shear	12	17
" " for steel Z-bar columns . . .	16	77	" Graphical method of obtaining bending moment and . . .	12	32
" " for steel Z-bar columns with cover-plates . . .	16	78	" in a simple beam	12	18
" " Obtaining the maximum	13	36	" Maximum	12	20
" loads for Kahn concrete beams	13	66	" Positive and negative	12	20
" " Formulas for maximum bending moments and	12	28	Shearing of riveted plate	25	19
" " for steel I beams . . .	16	66	" resistance of pins, Calculations for	25	33
" " for steel, latticed, channel column . . .	16	62	" strength of rivets	25	19
" " Formulas for maximum	12	30	" stresses in web-plate . . .	14	4
Safety, Factor of	15	31	" value of rivets	25	23
" " "	16	27	" values of pins	25	34
Salmon bricks	8	43	Short columns	15	11
Salt, or halite	8	19	" " Method of failure of . . .	15	5
Sand	7	6	Siderite, or spathic iron	8	17
" for mortar	8	61	Silicious rocks	8	27
Sandstones	8	25	" stones	8	36
"	8	38	Silicon	8	8
Schist	8	30	Simple beam, Definition of	12	1
Scissors roof truss	27	14	" " Shear in a	12	18
Screw threads and nuts, Standard	25	49	" beams, Bending moments in	12	25
Section, Efficiency of	16	34	Single spruce	9	3
" modulus	6	16	Size of girders	13	53
" "	13	1	" " lattice bars and stay-plates to be used with latticed channel columns	16	32
" " Explanation of . . .	6	16	Sizes of rivets	25	2
" " of a channel, Obtaining the approximate . . .	13	22	Skeleton construction	5	31
" " of an I beam, Obtaining the approximate . . .	13	22	Slate, gneiss, and mica	8	37
" Finding the neutral axis of a	6	5	Snow and wind loads	5	19
Sections of cast-iron columns . . .	15	33	" loads on opposite sides, Wind and	27	56
" of columns frequently used in skeleton building construction	16	7	Soapstone	8	39
" Properties of	6	1	Sodium	8	11
" Usual forms of	14	2	Soft bricks	8	43
			Soils, Bearing value of foundation	7	14
			" Building laws regarding foundation	7	15
			" Characteristics of foundation	7	4
			" Determination of bearing capacity of	7	3
			" Examination of	7	1
			" Foundation	7	1
			" Mud, silt, marsh, or semi-liquid	7	9
			" Safe bearing values of different foundation	7	14
			Solid elements	8	8

	Ser.	Page		Ser.	Page
Spacing of lattice bars	16	23	Steel I beams, Safe loads for	16	66
" " rivets	25	7	" manufacture, Crucible process of	9	14
" " " and bolts in angles, Standard	25	11	" " Open hearth process of	9	14
" " " and bolts in T bars, Standard	25	12	" plate-and-angle columns, Properties of	15	51
" " " and bolts in Z bars, Standard	25	14	" plate-and-angle columns, Safe load for	16	70
" " " and bolts, Standard	25	8	" plate-and-angle columns with cover plates, Properties of	16	52
" " " and bolts, Standard	25	10	" plate-and-angle columns with cover plates, Safe load for	16	71
" " tie-rods	13	37	" Processes of manufacture of reinforcement, The unit concrete	9	14
" stiffeners, Practical rule for	14	9	" Z-bar columns, Safe load for	16	77
Span and depth of beam, Relation between	13	77	" Z-bar columns, with cover plates, Properties and dimensions of	16	60
" Definition of	12	1	" Z-bar columns with cover plates, Safe load for	16	73
Spans for I beams, Minimum	13	32	Stiffeners, Buckling of web plate and distribution of	14	7
Spathe iron or alderite	8	17	" Explanation of	14	2
Specific gravity	8	8	" Practical rule for spacing	14	9
Specification for reinforced concrete	13	74	" Web-plates and	14	4
Splices and connections, Column	16	35	Stiffness	12	42
Spruce	9	2	Stirrup iron hanger	13	15
" Black	9	2	Stone and gravel concrete	8	45
" Norway	9	3	" Argillaceous	8	39
" Single	9	3	" Density of	8	32
" White	9	3	" Durability of building	8	49
Stable equilibrium	26	14	" Effect of fire on	8	52
Static computation of concrete, Rules for	13	81	" " quarrying and finishing	8	52
" load	5	12	" Physical properties of building	8	32
Stay plates to be used with latticed channel columns. Size of lattice bars and	16	32	" structure of building	8	50
Steel, and reinforced concrete beams. Wooden	13	1	Stones and masonry, Strength of	8	53
" beam, Finding the dimensions of a	13	23	" Calcareous	8	40
" beams	13	21	" Manufactured	8	42
" " Connections for	13	30	" Sedimentary	8	38
" " Transverse strength of	13	22	" Selection of building	8	58
" channel columns, Properties of heavy	16	57	" Silicious	8	36
" channel columns, Properties of	16	53	Straight line formula	15	9
" channel columns with cover plates, Safe load for	16	72	" " "	15	15
" Characteristics of iron and	9	11	" " "	16	11
" columns. Classification of	16	1	" " formulas	15	29
" " Design of	16	31	Strains on riveted work, Allowable	25	27
" " Forms of	16	3	Stratified rocks	8	19
" " Formulas for	16	9	Strength and properties of steel columns	16	50
" Definition of	9	12	" of beams, Lateral	13	31

	Sec. Page			Sec. Page	
Strength of bricks, brickwork, and			Sycamore	9	7
" " rubble	8	56	Syenite	8	37
" " cast-iron brackets . .	15	44	Symmetry, Method by	27	41
" " cements	8	56			
" " columns with eccen-			T		
tric loads	16	18	Table of allowable live loads on		
" " concrete	8	56	floors in different cities	5	19
" " mortars	8	56	" " allowable strains on		
" " stones and masonry	8	53	riveted work	25	27
" " timber	9	9	" " allowable stresses on		
" Ultimate	9	8	pins	25	33
" values of timber	9	8	" " allowable unit stresses		
Stress, Columns under bending . .	16	25	for masonry materials	8	57
" Determination of the kind			" " approximate values of		
of	26	66	C for various columns	16	21
" Effect of vertical	14	39	" " bearing plates for I		
" Explanation of transverse	6	16	beams and channels .	13	45
" in any chord member of a			" " bearing value of riveted		
Howe truss, Finding the	14	72	plates	25	24
" in any chord member of a			" " bearing values of pin		
Warren truss, Finding			plates	25	43
the	14	81	" " bending moments for		
" in columns	15	3	continuous beams . .	12	38
" Obtaining the resultant . .	13	36	" " dimensions of connec-		
" of beams, Obtaining the			tions to cast-iron col-		
fiber	13	34	umns	15	45
Stresses, Analytic method of com-			" " efficiency of built-up		
puting	14	57	wooden beams	13	12
" Bending	12	23	" " factor of safety	15	17
" Determination of inter-			" " factor of safety for dif-		
nal	26	63	ferent materials	9	18
" Diagrams for	26	41	" " factor of safety for wood	13	5
" Flange	14	13	" " factors of safety	16	28
" Graphic method of de-			" " formulas for deflection		
termining	14	61	of beams	12	44
" Graphical analysis of . .	26	1	" " formulas for maximum		
" in beams	12	7	bending moments on		
" " " and girders . .	14	4	beams	12	30
" " concrete, Allowable			" " length of rivets required		
working	13	82	for various grips . . .	25	6
" " web-plate, Shearing .	14	4	" " length of rivet shank re-		
" on pins, Bending	25	35	quired to form one		
" " " Resultant mo-			rivet head	25	5
ment of sev-			" " live loads per square foot	5	11
eral	25	36	" " maximum bending mo-		
" " " Table of allow-			ments on pins	25	37
able	25	33	" " maximum size of rivets		
" produced by live load,			in angles	25	3
Maximum	14	72	" " maximum size of rivets		
Structure of building stone, Physical	8	50	in beams	25	3
" " rock	8	33	" " maximum size of rivets		
Structures, Loads in	5	1	in channels	25	3
Suddenly applied loads, Accidental			" " minimum spans for I		
and	5	27	beams	13	32
Sulphur	8	12	" " moment of inertia of		
Surface, Neutral	6	3	rectangular sections .	6	40

	Sec. Page			Sec. Page	
Table of properties and dimensions of standard Z-bar columns	16	59	Table of safe loads for steel 1		
" " properties and dimensions of steel Z-bar columns with cover-plates	16	60	beams	16	66
" " properties and dimensions of standard T rails	6	39	" " safe loads for steel, latticed, channel columns	16	62
" " properties of heavy steel channel columns	16	67	" " shearing values of pins	25	34
" " properties of standard angles having equal legs	6	32	" " shearing value of rivets	25	23
" " properties of standard angles having unequal legs	6	34	" " size of lattice bars and stay-plates to be used with lattice channel columns	16	32
" " properties of standard channels	6	30	" " standard pins and nuts	25	48
" " properties of standard I beams	6	28	" " standard screw threads and nuts	25	49
" " properties of steel channel columns	16	53	" " standard spacing of rivets and bolts	25	8
" " properties of steel plate-and-angle columns	16	51	" " standard spacing of rivets and bolts	25	10
" " properties of steel plate-and-angle columns with cover-plates	16	62	" " standard spacing of rivets and bolts in angles	25	11
" " properties of Z bars	6	36	" " standard spacing of rivets and bolts in T bars	25	12
" " radii of gyration for two angles, having equal legs	6	42	" " standard spacing of rivets and bolts in Z bars	25	14
" " radii of gyration for two angles, having unequal legs	6	42	" " strength of bricks, brick-work, and rubble	8	54
" " reactions for continuous beams over equal spans	12	38	" " strength of building stones and masonry	8	55
" " rivet spacing	25	7	" " strength of cements	8	56
" " safe bearing values of foundation soils	7	14	" " strength of timber	9	9
" " safe load for steel channel columns with cover-plates	16	72	" " ultimate strength of materials	9	16
" " safe load for steel Z-bar columns	16	77	" " ultimate strength per square inch for timber posts	15	18
" " safe load for steel plate-and-angle columns	16	70	" " weight of materials	5	2
" " safe load for steel plate-and-angle columns with cover-plates	16	71	" " " " " " roof trusses	5	3
" " safe load for steel Z-bar columns with cover-plates	16	78	" " weights of merchandise for calculating live loads	5	14
			" " wind pressure normal to the slope of roof	5	23
			" " showing reductions of live loads from floor to floor	5	31
			Tables giving strength and properties of steel columns	16	50
			" " of bearing values of riveted plates	25	26
			" " shearing values of rivets	25	26
			Tail-beams	13	4
			Tensile strength of plates	25	20

	Sec.	Page
Testing reenforced concrete, Gov-		
ernmental regulations for	13	79
Tests made on beam hangers . . .	13	18
" Results of	16	29
Thickness of web-plate	14	5
Tie-rods, Spacing of	13	37
Timber and metals	9	1
" Characteristics of	9	1
" columns and posts	15	10
" posts, Ultimate strength		
per square inch for	15	18
" Strength values of	9	8
" Table of strength of	9	9
Trachyte	8	23
Transverse strength of steel beams	13	22
" stress, Explanation of	6	16
Trap	8	38
Trappean, or intrusive, rocks . . .	8	22
Triangle, Center of gravity of a . .	6	2
" of forces	26	8
Trimmers	13	4
Truss, "A" type of	27	74
" construction, Details of . . .	14	89
" Diagram for cambered	27	32
" Fink roof	27	40
" Hammer-beam	27	65
" Howe	14	67
" " roof	27	8
" Lattice	14	83
" of large span, Crescent	27	62
" " small span, Crescent	27	56
" Pratt	14	77
" "	27	8
" Queen-post	27	35
" Scissors roof	27	14
" Warren	14	80
" with cambered tie-member,		
Fink	27	50
" " loads on lower chord	27	25
Trussed girders	14	66
" " Wooden	14	89
Trusses, Dead load on roof	5	7
" supported by knee-braced		
columns	27	83
" with horizontal or oblique		
thrusts, Roof	27	65
" " joints acted on by		
three unknown		
forces	27	40
" " members subjected		
to transverse		
stress, Roof	27	74
U		
Ultimate elongation	9	8
" strength	9	8

	Sec.	Page
Ultimate strength per square inch		
for timber posts	15	18
" strength of materials,		
Table of	9	16
Unit concrete steel reinforcement	13	70
" stresses for masonry mate-		
rials, Allowable	8	57
Unstable equilibrium	26	11
Unstratified, or igneous rocks . .	8	20
" rocks	8	19

V

Values of C for various columns,		
Table of approximate	16	21
Van Dorn hanger	13	13
Vertical loads, Diagram for	27	50
" stress, Effect of	14	39
Vitreous quartz	8	15
Volcanic, or eruptive, rocks . . .	8	21

W

Warehouse floors	5	12
Warren truss	14	80
Web bearing	25	15
" plate, Explanation of	14	1
" " Shearing stresses in	14	4
" " Thickness of	14	5
" plates and stiffeners	14	4
Weight	12	7
" arm	12	7
" Atomic	8	5
" Combination by	8	4
" of fireproof floors	5	1
" " materials	5	2
" " roof trusses	5	9
" " wooden and iron or		
steel roof trusses,		
Formula for approxi-		
mate	5	7
Weights of merchandise for calcu-		
lating live loads	5	14
White cedar	9	3
" oak	9	4
" pine	9	1
" spruce	9	3
Whitewood	9	7
Wind and snow loads on opposite		
sides	27	56
" load diagram	27	23
" " "	27	29
" loads, Floor, roof, and	5	1
" " Snow and	5	19
" pressure	5	20
" " normal to the slope		
of roof	5	23

	<i>Sec.</i>	<i>Page</i>		<i>Sec.</i>	<i>Page</i>
Wind pressure on truss with curved or broken upper chord, Determining . . .	27	58	Wooden, steel, and reinforced concrete beams	13	1
" stress diagram	27	58	" trussed girders	14	89
Wood, Kinds of	9	1	Z		
" Factor of safety for	13	5	Z-bar columns, Properties and dimensions of	16	59
Wooden beams	13	3	" " " Safe load for steel	16	77
" " Built-up	13	9	" " " with cover-plates, Properties and dimensions of steel	16	60
" " Details of design of	13	13	" " " with cover-plates, Safe load for steel	16	78
" " General notes relative to	13	4			
" " Efficiency of built-up	13	12			
" construction, Beams in heavy	13	19			

